CONTRACT N40085-21-0009
NAVFAC SPECIFICATION
NO. 05-21-0009

FLASHING REPAIRS MCASNR AS515

AT THE

MARINE CORPS AIR STATION, NEW RIVER, NORTH CAROLINA

MARINE CORPS BASE, CAMP LEJEUNE, NORTH CAROLINA

DESIGN BY:
Gustavo De Luca, RA
Supervisor, Architectural Branch
MCBCL - Public Works División

SPECIFICATION PREPARED BY:

DESIGN BY:
Gustavo De Luca, RA
And
Kim R. Sample
MCBCL - Public Works Division

Date: 05 August 2021

SPECIFICATION APPROVED BY:

Thomas H. Burton, P.E., Director
Design Branch, Public Works Division

Ross B. Campbell, Commander, CEC, U.S. Navy
for Commander, Naval Facilities Engineering

05210009

PROJECT DESCRIPTION

The work includes the necessary repairs to avoid water intrusion into building AS515.

Areas affected by these repairs will be in compliance with applicable ATFP, fire safety, seismic, accessibility, and energy conservation (ASHRAE and LEEDS) codes and requirements upon completion of this project.

Detailed Scope Work is as follows:

1) Roof: Fix water intrusion occurring at the roof edge conditions of the lower and high roofs. Refer to drawing sheet A101:
   a) Demolish all gutters, rake conditions, downspouts, and any other related item to allow the proper installation of new roofing materials
   b) Provide new flashing, transition compatible materials, mastic, clips, gutters, downspouts, etc.
   c) Provide roof calculations demonstrating the appropriate size of gutters and downspouts
   d) Provide new downspouts at each existing location connected to rain leader booth to storm sewer system
   e) Provide new downspouts in between existing (one in between two existing) downspouts with termination elbow and splash blocks
   f) Roof spec: see section 07 52 00 MODIFIED BITUMEN 12JUNR2020
   g) Colors: comply with BEAP
2) Exterior Windows:
   a) Demolish all exterior windows, flashing, and any other related item to allow the proper installation of new window units
   b) Provide new windows, Head, Sill and Jambs flashing, transition compatible materials, sealant, etc.
   c) Window type: Match existing
   d) Window spec: see section 08 51 13 ALUMNUM WINDOWS
   e) Glazing Spec: see section 08 81 00 GLAZING
   f) Colors: comply with BEAP
3) Exterior wall penetrations:
   a) There are approximately 20 wall penetrations of various types (pipes, rectangular vents, etc.). Verify all existing conditions, locations, and quantities
   b) Remove all existing sealant or other materials found in the annular space around the penetration
   c) Install new rain hood as shown in details, fasten to existing corrugated metal wall panel system, caulk, and touch up paint as necessary

SPECIAL ACCESS

The point of contact for this project is personnel at the Air Station.

SPECIAL SCHEDULING

Other features/activities of this Base will remain in operation during the duration of the repair work. The Contractor shall conduct his operations so as to cause the least possible interference with normal operations of the facility/activity.

SPECIAL CONDITIONS / ENVIRONMENTAL

NA

HAZARDOUS MATERIALS

Asbestos and Lead abatement may be required. The contractor must perform field testing for the potential presence of these hazardous materials.

SUPERVISION

One person may fill the roles of Superintendent, Quality Control Manager, and Safety & Health Officer, if duly qualified for all three positions as defined in the project specification.

PROJECT TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

01 11 00 SUMMARY OF WORK
01 14 00 WORK RESTRICTIONS
01 20 00 PRICE AND PAYMENT PROCEDURES
01 30 00 ADMINISTRATIVE REQUIREMENTS
01 31 50 TRANSFER AND ACCEPTANCE OF MILITARY REAL PROPERTY
01 32 16 CONSTRUCTION PROGRESS DOCUMENTATION
01 33 00 SUBMITTAL PROCEDURES
01 35 29 SAFETY AND OCCUPATIONAL HEALTH REQUIREMENTS
01 42 00 SOURCES FOR REFERENCE PUBLICATIONS
01 45 10 QUALITY CONTROL
01 50 00 TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS
01 78 00 CLOSEOUT PROCEDURES
01 78 23 OPERATION AND MAINTENANCE DATA
01 78 30.00 22 GIS DATA DELIVERABLES

DIVISION 02 - EXISTING CONDITIONS

02 41 00 DEMOLITION
02 82 16 REMOVAL AND DISPOSAL OF ASBESTOS MATERIALS

DIVISION 04 - MASONRY

04 20 00 UNIT MASONRY

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 10 00 ROUGH CARPENTRY

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 21 13 BOARD AND BLOCK INSULATION
07 27 10.00 10 BUILDING AIR BARRIER SYSTEM
07 27 19.01 SELF-ADHERING AIR BARRIERS
07 27 36 SPRAY FOAM AIR BARRIERS
07 42 13 METAL WALL PANELS
07 52 00 MODIFIED BITUMINOUS MEMBRANE ROOFING
07 60 00 FLASHING AND SHEET METAL
07 92 00 JOINT SEALANTS

DIVISION 08 - OPENINGS

08 11 13 STEEL DOORS AND FRAMES
08 51 13 ALUMINUM WINDOWS
08 71 00 DOOR HARDWARE
08 81 00 GLAZING

DIVISION 09 - FINISHES

09 29 00 GYPSUM BOARD
09 90 00 PAINTS AND COATINGS

-- End of Project Table of Contents --

SECTION 01 11 00

SUMMARY OF WORK

09/08

PART 1 GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

1.1.1 Project Description

The work includes the renovation of half of Building 904 to provide the infrastructure required for the installation of an Advanced Small Arms Lethality Training (ASALT) area, a Night Vision Lab (NVL), and a shoot house. Renovation of existing modular space, enclosed areas, and Heads is required. The work also includes, structural steel, metal railings, modified membrane roofing, sprayed polyurethane insulation, steel doors and frames, wood doors, door hardware, metal wall louvers, supports for plaster & gypsum board, gypsum board, ceramic, quarry, & glass tiling, acoustical ceilings, paints & coatings, toilet compartments, and toilet accessories.

1.1.2 Location

The work shall be located at the Marine Corps Base Camp Lejeune, North Carolina, Building 904 , approximately as shown. The exact location will be indicated by the Contracting Officer.

1.2 PHASED CONSTRUCTION SCHEDULE

The work shall be completed in a single phase.

1.3 EXISTING WORK

In addition to "FAR 52.236-9, Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements":

a. Remove or alter existing work in such a manner as to prevent injury or damage to any portions of the existing work which remain.

b. Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as approved by the Contracting Officer. At the completion of operations, existing work shall be in a condition equal to or better than that which existed before new work started.

1.4 LOCATION OF UNDERGROUND FACILITIES

The Contractor will be responsible for obtaining the services of a professional utility locator to scan the construction site with electromagnetic or sonic equipment, and mark the surface of the ground where existing underground utilities are discovered. Verify the elevations of existing piping, utilities, and any type of underground obstruction not indicated or specified to be removed but indicated or discovered during scanning in locations to be traversed by piping, ducts, and other work to be installed. Verify elevations before installing new work closer than nearest manhole or other structure at which an adjustment in grade can be made.

1.4.1 Notification Prior to Excavation

Notify the Contracting Officer's Representative (COR) 48 hours prior to starting excavation work.

1.5 GOVERNMENT-FURNISHED MATERIAL AND EQUIPMENT

Government furnished materail and equipment will be indicated on drawings and i scope of work if applicable.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 14 00

WORK RESTRICTIONS

01/07

PART 1 GENERAL

1.1 SPECIAL SCHEDULING REQUIREMENTS

a. The Contractor shall comply with all special scheduling requirements as described in the attached project description.

d. Permission to interrrupt any Station roads, railroads, and/or utility service shall be requested in writing a minimum of 15 calendar days prior to the desired date of interruption.

1.2 CONTRACTOR ACCESS AND USE OF PREMISES

1.2.1 Station Regulations

Ensure that Contractor personnel employed on the Station become familiar with and obey Station regulations. Keep within the limits of the work and avenues of ingress and egress as directed. Do not enter restricted areas unless required to do so and until cleared for such entry. Wear hard hats in designated areas. The Contractor's equipment shall be conspicuously marked for identification.

1.2.2 Working Hours

Regular working hours shall be 0730-1600, Monday through Friday, excluding Government holidays.

1.2.3 Work Outside Regular Hours

Work outside regular working hours requires COR approval. Provide written request at least 15 calendar days prior to such work to allow arrangements to be made by the Government for inspecting the work in progress. During periods of darkness, the different parts of the work shall be lighted in a manner approved by the COR.

1.2.4 Occupied and Existing Buildings

The Contractor shall be working in a a portion of an existing building which is not occupied. The existing building and its contents shall be kept secure at all times.

1.2.5 Utility Cutovers and Interruptions

a. The Contractor shall coordinate a minimum of 14 calendar days prior to any planned utility cutover / interruption. Make utility cutovers and interruptions during normal working hours.

b. Ensure that new utility lines are complete, except for the

connection, before interrupting existing service.

c. Interruption to water, sanitary sewer, storm sewer, telephone service, electric service, air conditioning, heating, fire alarm, and compressed air shall be considered utility cutovers. This time limit includes time for deactivation and reactivation.

d. Operation of Station Utilities: The Contractor shall not operate nor disturb the setting of control devices in the station utilities system, including water, sewer, electrical, and steam services. The Government will operate the control devices as required for normal conduct of the work. The Contractor shall notify the Contracting Officer at least 15 days prior to such operation.

1.3 SECURITY REQUIREMENTS

Contract Clause "FAR 52.204-2, Security Requirements and Alternate II," "FAC 5252.236-9301, Special Working Conditions and Entry to Work Area," apply.

1.4 EMERGENCY UNEXPLODED ORDINNCE (UXO) RESPONSE

In the event that UXO, as defined in 40 CFR 260 is encountered during the construction activities that are deemed to be a threat to human health or the environment, Camp Lejeune Military Police and EOD professionals shall be immediately contacted to conduct an emergency response. Additionally, immediately contact the Contracting Officer if UXO is encountered. An evaluation of this scenario and procedures, with contract numbers, shall be included in the Health and Saafety Plan (HASP) for the fieldwork.

1.4.1 3R TRAINING

All Contractor personnel performing ground distubing activities must complete contractor awareness training related to recognizing UXO. This training (3R TRAINING) is available online at: http://www.lejeune.marines.mil/OfficesStaff/EnvironmentalMgmt/TrainingVideo.aspx

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 20 00

PRICE AND PAYMENT PROCEDURES

04/12

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE EP-1110-1-8	(2009) Construction Equipment Ownership and Operating Expense Schedule

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00,"Submittal Procedures."

SD-01 Preconstruction Submittals

Schedule of prices

1.3 SCHEDULE OF PRICES

1.3.1 Data Required

Within 15 calendar days of notice of award, prepare and deliver to COR a schedule of prices (construction contract). Provide a detailed breakdown of the contract price, giving quantities for each of the various kinds of work, unit prices, and extended prices therefor. Schedule of prices shall be separated by individual building numbers with subtotals for each building.

1.3.2 Schedule Instructions

Payments will not be made until the schedule of prices has been submitted to and approved by the COR. Identify the cost for site work, and include incidental work to the 5 foot line. Identify costs for the building(s), and include work out to the 5 foot line. Workout to the 5 foot line shall include construction encompassed within a theoretical line 5 feet from the face of exterior walls and shall include attendant construction, such as cooling towers, placed beyond the 5 foot line.

1.4 CONTRACT MODIFICATIONS

In conjunction with the Contract Clause "DFARS 252.236-7000, Modification Proposals-Price Breakdown," and where actual ownership and operating costs of construction equipment cannot be determined from Contractor accounting records, equipment use rates shall be based upon the applicable provisions

of the COE EP-1110-1-8.

1.5 CONTRACTOR'S PAYMENT REQUEST

1.5.1 Proper Payment Request

A proper request for payment/invoice shall comply with all requirements specified in this Section and the contract payment clauses. If any invoice does not comply with these requirements, it shall be returned with a statement of the reasons why it was not a proper invoice. A proper payment request/invoice includes the following information, completed forms, and number of copies indicated. Upon request, the Contracting Officer will furnish copies of Government forms.

a. Contractor's Monthly Estimate for Voucher (LANTNAVFACENGCOM Form 4-4330/110.

b. Payment Certification. Furnish as specified in "FAR Clause 52.232-5 (c) Payments under Fixed-Price Construction Contracts." Submit one original.

c. QC Invoice Certification. Furnish as specified in Section 01 45 10, "Quality Control." Submit one original.

1.5.1.1 Progress Payments

In addition to the requirements stated in Paragraph 1.5.1, "Proper Payment Request" above, the Contractor's request for progress payments shall include the following:

a. Updated Progress Schedule: Furnish an updated progress schedule as specified in contract clause FAR 52.236-15 "Schedules for Construction Contracts" and Section 01 32 16, "Construction Progress Documentation." Submit one copy.

1.5.1.2 Final Payments

The request for final payment is submitted after completion and acceptance of all work and all other requirements of the contract. Before submitting the final invoice the Contractor shall meet with the appropriate Government representatives to determine the final invoice amount, including the assessment of liquidated damages, if any, and to make sure the final release is complete and accurate. In addition to the requirements in Paragraph 1.5.1, "Proper Payment Request" above, the Contractor's request for final payment shall include the following:

a. A final release executed on the standard form provided by the Contracting Officer. Submit two originals with final payment request.

b. NC Tax certified statement and report for the prime and each subcontractor (FAR 52.229-7). Submit two copies.

c. As-built drawings (if applicable).

d. Warranties (if applicable).

e. O&M manuals (if applicable).

f. A release for an assignment of claims (if applicable). Submit three originals.

1.5.2 Procedures for Submitting Payment Request

a. The Contractor may submit only one invoice for payment each month as the work progresses.

b. The invoice shall be submitted through iRAPT (https://wawf.eb.mil) in accordance with the payment clause in the contract, between three calendar days before and three calendar days after the contract award date. Invoices received outside this schedule shall be returned to the Contractor unprocessed. The Contractor will have to wait until the following month to submit their next invoice.

1.6 PAYMENTS TO THE CONTRACTOR

Payments will be made on submission of a proper payment request/invoice by the Contractor.

1.6.1 Obligation of Government Payments

The obligation of the Government to make payments required under the provisions of this contract will, at the discretion of the Contracting Officer, be subject to the following:

a. Reasonable retention and/or deductions due to defects in material or workmanship; potential liquidated damages; and/or failure to comply with any other requirements of the contract.

b. Claims which the Government may have against the Contractor under or in connection with this contract; and

c. Unless otherwise adjusted, repayment to the Government upon demand for overpayments made to the Contractor.

d. Failure to provide up to date record drawings not current as stated in Contract Clause "FAC 5252.236-9310, Record Drawings"; NC State tax certified statement and report in accordance with FAR 52.229-2; labor payrolls in accordance with FAR 52.222-6; as-built drawings in accordance with Section 01 45 10, "Quality Control"; warranties and O&M manuals; and any other requirements in the contract.

1.6.2 Payment for Onsite Materials

Progress payments may be made to the contractor for materials delivered on the site under the following conditions:

a. FAR 52.232-5(b) Payments Under Fixed Price Construction Contracts.

b. Materials delivered on the site but not installed, including completed preparatory work. Materials not acceptable for payment include consumable materials such as nails, fasteners, conduits, gypsum board, glass, insulation, and wall coverings.

c. Materials to be considered for progress payment prior to installation shall be specifically and separately identified in the Contractor's estimates of work submitted for the COR's approval in accordance with Earned Value Report requirement of this contract. Requests for progress payment considerations for such items shall be supported by documents establishing their value and that the title requirements of the clause at FAR 52.232-5 have been met.

d. Materials are adequately insured and protected from theft and exposure.

e. Materials to be considered for progress payments prior to installation shall be stored in the Continental United States.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 30 00

ADMINISTRATIVE REQUIREMENTS

03/12

PART 1 GENERAL

1.1 SUBMITTALS

Submit the following in accordance with the Section 01 33 00, "Submittal Procedures."

SD-01 Preconstruction Submittals

List of contact personnel

1.2 MINIMUM INSURANCE REQUIREMENTS

Procure and maintain during the entire period of performance under this contract the following minimum insurance coverage:

a. Comprehensive general liability: $500,000 per occurrence

b. Automobile liability: $200,000 per person, $500,000 per occurrence, $20,000 per occurrence for property damage

c. Workmen's compensation as required by Federal and State workers' compensation and occupational disease laws,

d. Employer's liability coverage of $100,000, except in States where workers compensation may not be written by private carriers,

e. Others as required by State law.

1.3 ELECTRONIC MAIL (EMAIL)

a. The Contractor is required to establish and maintain electronic mail (email) capability along with the capability to open various electronic attachments in Microsoft, Adobe Acrobat, and other similar formats.

b. Within 10 days after contract award; the Contractor shall provide the Contracting Officer a single (only one) email address for the ROICC office to send communications related to this contract correspondence. The ROICC office may also use email to notify the Contractor of base access conditions when emergency conditions warrant, such as hurricanes, terrorist threats, etc.

c. Multiple email addresses are not authorized.

d. It is the Contractor's responsibility to make timely distribution of all ROICC email within its own organization, including field office(s).

e. The Contractor shall promptly notify the Contracting Officer, in

writing, of any changes to their email address.

1.4 CONTRACTOR PERSONNEL REQUIREMENTS

1.4.1 Subcontractors and Personnel

Furnish a list of contact personnel of the Contractor and subcontractors including addresses and telephone numbers for use in the event of an emergency. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

1.4.2 Identification Badges

Identification badges will be furnished without charge. Application for and use of badges will be as directed below. Immediately report instances of lost or stolen badges to the Contracting Officer. Employees are required to resubmit a complete 50 state criminal records check in order to renew their contractor badge.

1.4.3 Business Access Security Requirements

1.4.3.1 Business Access Definition

Contractor/subcontractor employees requiring installation access to MCB, Camp Lejeune or MCAS New River, N.C. must obtain a Business Access Identification Badge for that particular installation. Regularly scheduled delivery personnel, to include FEDEX, UPS, Pick-up and deliveries, should, also, follow the Business Access guidelines described below. Personnel requiring Business Access Identification Badges shall submit all documentation listed below. Badges are not required if the contracted position requires the employee to obtain a Common Access Card (CAC) which will be identified separately within the Government contract.

1.4.3.2 Installation Security Access Requirements

Contractor shall accomplish the security requirements below within 10 days after award or prior to performance under the contract.

1.4.3.3 Business Access Identification Badge Requirement

In order to obtain a Business Access Identification Badge for access to MCB, Camp Lejeune, and satellite activities, or MCAS New River, NC, all personnel providing services under this contract shall be required to present the documentation below to the following offices, as applicable:

MCB, Camp Lejeune, NC and its satellite activities. Report as follows:

1. Identification Card Center, 60 Molly Pitcher Road for badge (910-450-8444).

MCAS New River, NC. Report as follows:

1. Pass and Identification Office, Bldg AS-187 for badge (910-449-7695) and vehicle pass (910-449-5513).

1.4.3.4 Proof of Employee Citizenship or Legal Alien Status

Employers may participate in the E-verify program (1-888-464-4218, www.DHS.gov/e-verify) allowing U.S. employers to verify name, DOB, and SSN

along with immigration information for non-citizens, against federal databases in order to verify the employment eligibility of both citizens and non-citizen new hires.

1.4.3.5 Proof of Criminal Records Check

Commercial and contract employees must provide proof a complete 50 state criminal records check on an annual basis. The record check may be obtained from any of the following Internet investigative services: Kroll (former Infolink Screening Services) at www.kroll.com, Castle Branch at www.castlebranch.com, or any other investigative services company that provides records checks for all 50 states. These services also validate social security card numbers. All criminal history checks must be completed no more than 30 days prior to start date of contract. (Note: These Internet screening services are listed as possible sources for obtaining a criminal background check. The United States government and the United States Marine Corps do not endorse nor are they affiliated with any of these services).

1.4.3.6 Letter Provided By Contracting Officer Indicating Contract

Letter provided by Contracting Officer indicating contract, contract period and prime contractor. Proof of employment on a valid Government contract (e.g., a letter on company letterhead from the prime contractor including contract number and term).

1.4.3.7 Photo ID

Valid state or federal issued picture identification card. Acceptable documents include state drivers license, DMV issued photo identification, or alien registration card.

1.4.3.8 National Crime Investigation Center (NCIC) Check

Provost Marshals are authorized to conduct a national crime information center (NCIC) check of all persons entering the installation, if/where applicable, the NCIC check may include drivers's license query, wants and warrants, and criminal history.

1.4.4 Denial of Access

Installation access shall be denied if it is determined that an employee:

a. Is on the National Terrorist Watch List

b. Is illegally present in the United States.

c. Is subject to an outstanding warrant.

d. Has knowingly submitted an employment questionnaire with false or fraudulent information.

e. Has been issued a debarment order and is currently banned from military installations.

f. Is a Registered Sexual Offender.

g. Has been convicted of a felony or a drug crime within the past five years.

h. Individuals who have received a DUI/DWI in the last year may be allowed access to the installation, but will not be permitted to drive on the installation.

i. Any reason the Installation Commander deems reasonable for the good order and discipline.

1.4.5 Appeal Process

All appeals should be directed to the Base Inspector's Office for any individual that has been denied access to the Base.

1.4.6 Display of Badges

Contractors/subcontractors shall prominently display their badges on their person at all times. Upon completion/termination of this contract or an individual's employment, the Contractor shall collect and turn in to the Pass & ID Office all badges. If the Contactor fails to obtain the employee's badge, the Pass & ID Office will be notified within 24 hours. Immediately report instances of lost or stolen badges to the Contracting Officer.

1.4.7 Contractor and Subcontractor Vehicle Requirements

Each vehicle to be used in contract performance shall show the Contractor's or subcontractor's name so that it is clearly visible and shall always display a valid state license plate and safety inspection sticker. To obtain a vehicle decal, which will be valid for one year or contract period, whichever is shorter, Contractor or subcontractor vehicle operators shall provide to the Vehicle Registration Office, 60 Molly Pitcher Road (910-451-1158) or to MCAS, Building AS-187 (910-449-5513) for vehicle decal:

a. An installation sponsor request forwarded to provost Marshall office

b. A valid form of Federal or state government I.D.

c. If driving a motor vehicle, a valid driver's license, vehicle registration and proof of insurance

Upon completion/termination of this contract or an individual's employment, the Contractor shall collect and turn in to Vehicle Registration all Government vehicle decals. If any are not collected, the Contractor shall notify the Vehicle Registration Office within 24 hours.

1.4.8 Security Checks

Contractor personnel and vehicles shall only be present in locations relevant to contract performance. All Contractor personnel entering the base shall conform to all Government regulations and are subject to such checks as may be deemed necessary to ensure that violations do not occur. Employees shall not be permitted on base when such a check reveals that their presence would be detrimental to the security of the base. Subject to security regulations, the Government will allow access to an area for servicing equipment and/or performing required services. Upon request, the Contractor shall submit to the Contracting Officer questionnaires and other forms as may be required for security purposes.

1.4.9 Subcontractor Special Requirements

1.4.9.1 Asbestos Containing Material

All contract requirements related to the removal and disposal of Asbestos Containing Materials (ACM) assigned to the Private Qualified Person (PQP) shall be accomplished directly by a first tier subcontractor.

1.4.9.2 Space Temperature Control, HVAC TAB, and Apparatus Inspection

All contract requirements realted to space temperature control, HVAC TAB, and Apparatus inspection shall be accomplished directly by a first tier subcontractor.

1.4.9.3 Telecommunication and High Voltage Work

When telecommunications and high voltage work is required, all work associated with telecommunications and high voltage shall be accomplished by a first tier subcontractor. The contractor must possess a valid North Carolina Public Utility - Electrical, contractor's license and be insured to do such work in the State of North Carolina.

1.4.9.4 Paving Associated with Utility Cuts

All pavement repairs associated with utility cuts shall be completed within 14 days of completing work within paved area.

1.5 DISCLOSURE OF INFORMATION

Contactor shall comply as follows:

(a) The Contractor shall not release to anyone outside the Contractor's organization any unclassified information, regardless of medium (e.g., film, tape, document), pertaining to any part of this contract or any program related to this contact, unless -

(1) The Contracting Officer has given prior written approval; or

(2) The information is otherwise in th public domain before the date of release.

(b) Requests for approval shall identify the specific information to be released, the medium to be used, and the purpose for the release. The Contractor shall submit its request to the Contracting Officer at least 45 days before the proposed date for release.

(c) The Contractor agrees to include a similar requirement in each subcontract under this contract. Subcontractors shall submit requests for authorization to release through the prime contractor to the Contracting Officer.

1.6 SUPERVISION

Have at least one qualified supervisor capable of reading, writing, and conversing fluently in the English language on the job site during working hours. In addition, if a Quality Control (CQ) representative is required on the contract, then that individual shall also have fluent English communication skills.

NOTE: If training and experience requirements of Section 01 45 10, "Quality Control" and 01 35 29, "Safety and Occupational Health Requirements" have been met the supervisor may also serve as QC Manager.

1.7 PRECONSTRUCTION CONFERENCE

After award of the contract but prior to commencement of any work at the site, meet with the Contracting Officer to discuss and develop a mutual understanding relative to the administration of the value engineering and safety program, preparation of the schedule of prices, shop drawings, and other submittals, scheduling programming, and prosecution of the work. Major subcontractors who will engage in the work shall also attend.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 31 50

TRANSFER AND ACCEPTANCE OF MILITARY REAL PROPERTY

01/07

PART 1 GENERAL

1.1 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-11 Closeout Submittals

Interim DD-1354, Transfer & Acceptance of Military Real Property

1.2 Interim DD-1354, Transfer & Acceptance of Military Real Property

Submit Interim DD-1354 thirty (30) days prior to beneficial occupancy date (draft copy attached).

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

-- End of Section --

SECTION 01 32 16

CONSTRUCTION PROGRESS DOCUMENTATION

04/12

PART 1 GENERAL

1.1 SUBMITTALS

Submit the following in accordance with Section 01 33 00, "Submittal Procedures."

SD-01 Preconstruction Submittals

Construction schedule

Equipment delivery schedule

1.2 CONSTRUCTION SCHEDULE

Within 15 days after receipt of the Notice of Award, prepare and submit to the COR for approval a Construction Schedule in accordance with the terms in Contract Clause "FAR 52.236-15, Schedules for Construction Contracts," except as modified in this contract.

1.3 EQUIPMENT DELIVERY SCHEDULE

1.3.1 Initial Schedule

Within 30 calendar days after approval of the proposed construction schedule, submit for Contracting Officer approval a schedule showing procurement plans for materials, plant, and equipment. Submit in the format and content as prescribed by the Contracting Officer, and include as a minimum the following information:

a. Description.

b. Date of the purchase order.

c. Promised shipping date.

d. Name of the manufacturer or supplier.

e. Date delivery is expected.

f. Date the material or equipment is required, according to the current construction schedule.

1.4 NETWORK ANALYSIS SYSTEM (NAS)

The schedule shall identify as a minimum:

a. Construction time for all major systems and components;

b. Major submittals and submittal processing time; and

c. Major equipment lead time.

1.4.1 CPM Submittals and Procedures

The Contractor shall use the critical path method (CPM) to schedule and control project activities. The network analysis system shall be kept current, with changes made to reflect the actual progress and status of the construction.

1.5 UPDATED SCHEDULES

Update the construction schedule and equipment delivery schedule at monthly intervals or when schedule has been revised. Reflect any changes occurring since the last update. Submit copies of the purchase orders and confirmation of the delivery dates as directed.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 33 00

SUBMITTAL PROCEDURES

05/13

PART 1 GENERAL

1.1 SUMMARY

1.1.1 Government-Furnished Information

Submittal register will be delivered to the contractor in hard copy format. Register will have the following fields completed, to the extent that will be required by the Government during subsequent usage.

Column (c): Lists specification section in which submittal is required.

Column (d): Lists each submittal description (SD No. and type, e.g. SD-04 Drawings) required in each specification section.

Column (e): Lists one principal paragraph in specification section where a material or product is specified. This listing is only to facilitate locating submitted requirements. Do not consider entries in column (e) as limiting project requirements.

Column (f): Indicate approving authority for each submittal. The Contracting Officer is approving authority for all submittals.

1.2 DEFINITIONS

1.2.1 Submittal

Shop drawings, product data, samples, and administrative submittals presented for review and approval. Contract Clauses "FAR 52.236-5, Material and Workmanship," paragraph (b) and "FAR 52.236-21, Specifications and Drawings for Construction," paragraphs (d), (e), and (f) apply to all "submittals."

1.2.2 Types of Submittals

All submittals are classified as indicated in paragraph "Submittal Descriptions (SD)". Submittals also are grouped as follows:

a. Shop drawings: As used in this section, drawings, schedules, diagrams, and other data prepared specifically for this contract, by contractor or through contractor by way of subcontractor, manufacturer, supplier, distributor, or other lower tier contractor, to illustrate portion of work.

b. Product data: Preprinted material such as illustrations, standard schedules, performance charts, instructions, brochures, diagrams, manufacturer's descriptive literature, catalog data, and other

data to illustrate portion of work, but not prepared exclusively for this contract.

c. Samples: Physical examples of products, materials, equipment, assemblies, or workmanship that are physically identical to portion of work, illustrating portion of work or establishing standards for evaluating appearance of finished work or both.

d. Administrative submittals: Data presented for reviews and approval to ensure that administrative requirements of project are adequately met but not to ensure directly that work is in accordance with design concept and in compliance with contract documents.

1.2.3 Submittal Descriptions (SD)

SD-01 Preconstruction Submittals

Certificates of insurance
Surety bonds
List of proposed subcontractors
List of proposed products
Construction Progress Schedule
Submittal schedule
Schedule of values
Health and safety plan
Work plan
Quality control plan
Environmental protection plan

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the contractor for integrating the product or system into the project.

Drawings prepared by or for the contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-04 Samples

Physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the

project.

Field samples and mock-ups constructed on the project site establish standards by which the ensuring work can be judged. Includes assemblies or portions of assemblies which are to be incorporated into the project and those which will be removed at conclusion of the work.

SD-05 Design Data

Calculations, mix designs, analyses or other data pertaining to a part of work.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. (Testing must have been within three years of date of contract award for the project.)

Report which includes findings of a test required to be performed by the contractor on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report which includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports

Daily checklists

Final acceptance test and operational test procedure

SD-07 Certificates

Statements signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a supplier, installer or subcontractor through Contractor, the purpose of which is to further quality of orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel qualifications.

Confined space entry permits.

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and Material Safety Data sheets concerning impedances, hazards and safety precautions.

SD-09 Manufacturer's Field Reports

Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.

Factory test reports.

SD-10 Operation and Maintenance Data

Data intended to be incorporated in operations and maintenance manuals.

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

As-built drawings

Special warranties

Posted operating instructions

Training plan

1.2.4 Approving Authority

Person authorized to approve submittal.

1.2.5 Work

As used in this section, on- and off-site construction required by contract documents, including labor necessary to produce construction and materials, products, equipment, and systems incorporated or to be incorporated in such construction.

1.3 SUBMITTALS

Submit the following in accordance with the requirements of this section.

SD-11 Closeout Submittals

Submittal register

Complete Submittal Package 2 CD/DVD's

1.4 USE OF SUBMITTAL REGISTER

Prepare and maintain submittal register, as the work progresses. Use the hard copy submittal register furnished by the Government or other approved format. Do not change data which is output in columns (c), (d), (e), and (f) as delivered by government; retain data which is output in columns (a), (g), (h), and (i) as approved.

1.4.1 Submittal Register

Submit submittal register as a hard copy. Submit with quality control plan and project schedule required by Section01 45 10 Quality Control. Do not change data in columns (c), (d), (e), and (f) as delivered by the government. Verify that all submittals required for project are listed and add missing submittals. Complete the following on the register:

Column (a) Activity Number: Activity number from the project schedule.

Column (g) Contractor Submit Date: Scheduled date for approving

authority to receive submittals.

Column (h) Contractor Approval Date: Date contractor needs approval of submittal.

Column (i) Contractor Material: Date that contractor needs material delivered to contractor control.

1.4.2 Contractor Use of Submittal Register

Update the following fields in the government-furnished submittal register.

Column (b) Transmittal Number: Contractor assigned list of consecutive numbers.

Column (j) Action Code (k): Date of action used to record contractor's review when forwarding submittals to QC.

Column (l) List date of submittal transmission.

Column (q) List date approval received.

1.4.3 Approving Authority Use of Submittal Register

Update the following fields in the government-furnished submittal register.

Column (b).

Column (l) List date of submittal receipt.

Column (m) through (p).

Column (q) List date returned to contractor.

1.4.4 Contractor Action Code and Action Code

Entries used will be as follows (others may be prescribed by Transmittal Form):

NR - Not Received

AN - Approved as noted

A - Approved

RR - Disapproved, Revise, and Resubmit

1.4.5 Copies Delivered to the Government

Deliver one copy of submitted register updated by contractor to government with each invoice request.

1.4.6 Submittals reserved for Marine Corps North Carolina IPT approval

a. Section 27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEM: All submittals. Provide an information copy of all submittals to Base Telephone through the Contracting Officer. Base Telephone will coordinate their review and approval through the Marine Corps North Carolina IPT.

b. Section 33 82 00 TELECOMMUNICATIONS OUTSIDE PLANT (OSP): All submittals. Provide an information copy of all cubmittals to Base Telephone through the Contracting Officer. Base Telephone will coordinate their review and approval through the Marine Corps North Carolina IPT.

1.5 PROCEDURES FOR SUBMITTALS

1.5.1 Reviewing, Certifying, Approving Authority

QC organization shall be responsible for reviewing and certifying that submittals are in compliance with contract requirements. The Contracting Officer is the approving authority for all submittals.

1.5.2 Constraints

a. Submittals listed or specified in this contract shall conform to provisions of this section, unless explicitly stated otherwise.

b. Submittals shall be complete for each definable feature of work; components of definable feature interrelated as a system shall be submitted at same time.

c. When acceptability of a submittal is dependent on conditions, items, or materials included in separate subsequent submittals, submittal will be returned without review.

d. Approval of a separate material, product, or component does not imply approval of assembly in which item functions.

1.5.3 Scheduling

a. Coordinate scheduling, sequencing, preparing and processing of submittals with performance of work so that work will not be delayed by submittal processing. Allow for potential requirements to resubmit.

b. Except as specified otherwise, allow review period, beginning with receipt by approving authority, that includes at least 15 working days for submittals for QC manager approval and 20 working days for submittals for contracting officer approval. Period of review for submittals with contracting officer approval begins when Government receives submittal from QC organization. Period of review for each resubmittal is the same as for initial submittal.

c. For submittals requiring review by fire protection engineer, allow review period, beginning when government receives submittal from QC organization, of 45 working days for return of submittal to the contractor. Period of review for each resubmittal is the same as for initial submittal.

1.5.4 Variations

Variations from contract requirements require Government approval pursuant to contract Clause entitled "FAR 52.236-21, Specifications and Drawings for Construction" and will be considered where advantageous to government.

1.5.4.1 Considering Variations

Discussion with contracting officer prior to submission, will help ensure functional and quality requirements are met and minimize rejections and resubmittals. When contemplating a variation which results in lower cost, consider submission of the variation as a Value Engineering Change Proposal (VECP).

1.5.4.2 Proposing Variations

When proposing variation, deliver written request to the contracting officer, with documentation of the nature and features of the variation and why the variation is desirable and beneficial to government. If lower cost is a benefit, also include an estimate of the cost saving. In addition to documentation required for variation, include the submittals required for the item. Clearly mark the proposed variation in all documentation.

1.5.4.3 Warranting That Variation Are Compatible

When delivering a variation for approval, contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.5.4.4 Review Schedule Is Modified

In addition to normal submittal review period, a period of 10 working days will be allowed for consideration by the Government of submittals with variations.

1.5.5 Contractor's Responsibilities

a. Determine and verify field measurements, materials, field construction criteria; review each submittal; and check and coordinate each submittal with requirements of the work and contract documents.

b. Transmit submittals to QC organization in accordance with schedule on approved Submittal Register, and to prevent delays in the work, delays to government, or delays to separate contractors.

c. Advise contracting officer of variation, as required by paragraph entitled "Variations."

d. Correct and resubmit submittal as directed by approving authority. When resubmitting disapproved transmittals or transmittals noted for resubmittal, the contractor shall provide copy of that previously submitted transmittal including all reviewer comments for use by approving authority. Direct specific attention in writing or on resubmitted submittal, to revisions not requested by approving authority on previous submissions.

e. Furnish additional copies of submittal when requested by contracting officer, to a limit of 20 copies per submittal.

f. Complete work which must be accomplished as basis of a submittal in time to allow submittal to occur as scheduled.

g. Ensure no work has begun until submittals for that work have been returned as "approved," or "approved as noted", except to the extent that a portion of work must be accomplished as basis of submittal.

1.5.6 QC Organization Responsibilities

a. Note date on which submittal was received from contractor on each submittal.

b. Review each submittal; and check and coordinate each submittal with requirements of work and contract documents.

c. Review submittals for conformance with project design concepts and compliance with contract documents.

d. Act on submittals, determining appropriate action based on QC organization's review of submittal.

(1) When QC manager is approving authority, take appropriate action on submittal from the possible actions defined in paragraph entitled, "Actions Possible."

(2) When contracting officer is approving authority or when variation has been proposed, forward submittal to Government with certifying statement or return submittal marked "not reviewed" or "revise and resubmit" as appropriate. The QC organization's review of submittal determines appropriate action.

e. Ensure that material is clearly legible.

f. Stamp each sheet of each submittal with QC certifying statement or approving statement, except that data submitted in bound volume or on one sheet printed on two sides may be stamped on the front of the first sheet only.

(1) When approving authority is contracting officer, QC organization will certify submittals forwarded to contracting officer with the following certifying statement:

"I hereby certify that the (equipment) (material) (article) shown and marked in this submittal is that proposed to be incorporated with contract Number N40085-17-B-0056, is in compliance with the contract drawings and specification, can be installed in the allocated spaces, and is submitted for Government approval.

Certified by Submittal Reviewer _____, Date _____
(Signature when applicable)

Certified by QC manager _____, Date _____"
(Signature)

g. Sign certifying statement or approval statement. The person signing certifying statements shall be QC organization member designated in the approved QC plan. The signatures shall be in original ink. Stamped signatures are not acceptable.

h. Update submittal register as submittal actions occur and maintain the submittal register at project site until final acceptance of

all work by contracting officer.

i. Retain a copy of approved submittals at project site, including contractor's copy of approved samples.

1.5.7 Government's Responsibilities

When approving authority is contracting Officer, the Government will:

a. Note date on which submittal was received from QC manager, on each submittal for which the contracting officer is approving authority.

b. Review submittals for approval within scheduling period specified and only for conformance with project design concepts and compliance with contract documents.

c. Identify returned submittals with one of the actions defined in paragraph entitled "Actions Possible" and with markings appropriate for action indicated.

1.5.8 Actions Possible

Submittals will be returned with one of the following notations:

a. Submittals marked "not reviewed" will indicate submittal has been previously reviewed and approved, is not required , does not have evidence of being reviewed and approved by contractor, or is not complete. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed. Resubmit submittals returned for lack of review by contractor or for being incomplete, with appropriate action, coordination, or change.

b. Submittals marked "approved" "approved as submitted" authorize contractor to proceed with work covered.

c. Submittals marked "approved as noted" authorize contractor to proceed with work as noted provided contractor takes no exception to the notations.

d. Submittals marked "revise and resubmit" or "disapproved" indicate submittal is incomplete or does not comply with design concept or requirements of the contract documents and shall be resubmitted with appropriate changes. No work shall proceed for this item until resubmittal is approved.

1.6 FORMAT OF SUBMITTALS

1.6.1 Complete Submittal Package

Contractor shall make electronic copies of all submittals, including the approved transmittal sheets, and provide two (2) CD/DVD's containing all submittals for the project.

The CD/DVD's shall be marked "Complete Submittal Package - Contract # 20-0042, ASALT NVL, Building 904, MCB, CAMP LEJEUNE."

1.6.2 Transmittal Form

Transmit each submittal, except sample installations and sample panels, to

office of approving authority. Transmit submittals with transmittal form prescribed by contracting officer and standard for project. The transmittal form shall identify contractor, indicate date of submittal, and include information prescribed by transmittal form and required in paragraph entitled "Identifying Submittals." Process transmittal forms to record actions regarding sample panels and sample installations.

1.6.3 Identifying Submittals

Identify submittals, except sample panel and sample installation, with the following information permanently adhered to or noted on each separate component of each submittal and noted on transmittal form. Mark each copy of each submittal identically, with the following:

a. Project title and location.

b. Construction contract number.

c. Section number of the specification section by which submittal is required.

d. Submittal description (SD) number of each component of submittal.

e. When a resubmission, alphabetic suffix on submittal description, for example, SD-10A, to indicate resubmission.

f. Name, address, and telephone number of subcontractor, supplier, manufacturer and any other second tier contractor associated with submittal.

g. Product identification and location in project.

1.6.4 Format for Product Data

a. Present product data submittals for each section as a complete, bound volume. Include table of contents, listing page and catalog item numbers for product data.

b. Indicate, by prominent notation, each product which is being submitted; indicate specification section number and paragraph number to which it pertains.

c. Supplement product data with material prepared for project to satisfy submittal requirements for which product data does not exist. Identify this material as developed specifically for project.

1.6.5 Format for Shop Drawings

a. Shop drawings shall not be less than 8 1/2 by 11 inches nor more than 30 by 42 inches.

b. Present 8 1/2 by 11 inches sized shop drawings as part of the bound volume for submittals required by section. Present larger drawings in sets.

c. Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph entitled "Identifying Submittals."

d. Dimension drawings, except diagrams and schematic drawings; prepare drawings demonstrating interface with other trades to scale. Shop drawing dimensions shall be the same unit of measure as indicated on the contract drawings. Identify materials and products for work shown.

1.6.6 Format of Samples

a. Furnish samples in sizes below, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately same size as specified:

(1) Sample of Equipment or Device: Full size.

(2) Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11 inches.

(3) Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.

(4) Sample of Linear Devices or Materials: 10 inch length or length to be supplied, if less than 10 inches. Examples of linear devices or materials are conduit and handrails.

(5) Sample of Non-Solid Materials: Pint. Examples of non-solid materials are sand and paint.

(6) Color Selection Samples: 2 by 4 inches.

(7) Sample Panel: 4 by 4 feet.

(8) Sample Installation: 100 square feet.

b. Samples Showing Range of Variation: Where variations are unavoidable due to nature of the materials, submit sets of samples of not less than three units showing extremes and middle of range.

c. Reusable Samples: Incorporate returned samples into work only if so specified or indicated. Incorporated samples shall be in undamaged condition at time of use.

d. Recording of Sample Installation: Note and preserve the notation of area constituting sample installation but remove notation at final clean up of project.

e. When color, texture or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

1.6.7 Format of Administrative Submittals

a. When submittal includes a document which is to be used in project or become part of project record, other than as a submittal, do not apply contractor's approval stamp to document, but to a separate sheet accompanying document.

b. Operation and Maintenance Manual Data: Submit in accordance with Section 01 78 23, "Operation and Maintenance Data." Include

components required in that section and the various technical sections.

1.7 QUANTITY OF SUBMITTALS

1.7.1 Number of Copies of Product Data

a. Submit five copies of submittals of product data requiring review and approval only by the Contracting Officer. Submit three copies of submittals of product data for operation and maintenance manuals.

1.7.2 Number of Copies of Shop Drawings

Submit shop drawings in compliance with quantity requirements specified for product data.

1.7.3 Number of Samples

a. Submit two samples, or two sets of samples showing range of variation, of each required item. One approved sample or set of samples will be retained by approving authority and one will be returned to contractor.

b. Submit one sample panel. Include components listed in technical section or as directed.

c. Submit one sample installation, where directed.

d. Submit one sample of non-solid materials.

1.7.4 Number of Copies of Administrative Submittals

a. Unless otherwise specified, submit administrative submittals compliance with quantity requirements specified for product data.

b. Submit administrative submittals required under "SD-19 Operation and Maintenance Manuals" to conform to Section 01 78 23, "Operation and Maintenance Data."

1.8 FORWARDING SUBMITTALS

1.8.1 Samples and Submittals

Except as otherwise noted, submit samples and submittals to:

ROICC/OICC
Jacksonville, North Carolina Area
1005 Michael Road
Camp Lejeune, NC 28542-2521

1.8.1.1 Administrative Submittals

Submit administrative submittals for asbestos/lead removal and environmental protection plan to the Resident Officer in Charge of Construction (ROICC/OICC).

1.8.1.2 Fire Protection and Fire Alarm System Submittals

Submit fire protection and fire alarm system submittals to ROICC/OICC.

1.8.1.3 TAB Submittals

Submit to ROICC/OICC for all projects.

1.8.2 Shop Drawings, Product Data, and O&M Data

As soon as practicable after award of the contract, and before procurement or fabrication, submit shop drawings, product data and O&M Data required in the technical sections of this specification.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 20 00	SD-01 Preconstruction Submittals															
			Schedule of prices	1.3														
		01 30 00	SD-01 Preconstruction Submittals															
			List of contact personnel	1.4.1														
		01 31 50	SD-11 Closeout Submittals															
			Interim DD-1354, Transfer &	1.2														
			Acceptance of Military Real															
			Property															
		01 32 16	SD-01 Preconstruction Submittals															
			Construction schedule	1.2														
			Equipment delivery schedule	1.3														
		01 33 00	SD-11 Closeout Submittals															
			Submittal register	1.4.1														
			Complete Submittal Package	1.6.1														
		01 35 29	SD-01 Preconstruction Submittals															
			Accident Prevention Plan (APP)	1.9														
			Activity Hazard Analysis (AHA)	1.10														
			Crane Critical Lift Plan	1.9.1														
			Crane Work Plan	1.9.1														
			Crane Operators	1.7.1.4														
			SD-06 Test Reports															
			Reports	1.14														
			Accident Reports	1.14.1														
			Monthly Exposure Reports	1.14.3														
			Regulatory Citations and	1.14.4														
			Violations															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 35 29	Crane Reports	1.14.5														
			SD-07 Certificates															
			Confined Space Entry Permit	1.11														
			Certificate of Compliance	1.14.6														
		01 45 10	SD-11 Closeout Submittals															
			QC PLAN	1.6														
		01 50 00	SD-01 Preconstruction Submittals															
			Traffic Control Plan	3.4.1														
			SD-03 Product Data															
			Backflow Preventers	1.3														
			SD-06 Test Reports															
			Backflow Preventer Tests	3.5														
			SD-07 Certificates															
			Backflow Tester	1.3.1														
			Backflow Preventers	1.3														
		01 57 19	SD-06 Test Reports															
			Abrasive blasting	3.7.1														
			SD-11 Closeout Submittals															
			Solid waste disposal permit	1.4.1														
			Disposal permit for hazardous	1.4.2														
			waste															
			Environmental training	1.2														
			documentation															
			Permit to transport hazardous	1.4.3														
			waste															
			Hazardous waste certification	1.4.4														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 57 19	Environmental Plan Review	1.6.3														
			Annual Report of Products	2.1														
			Containing Recovered Materials															
		01 78 00	SD-10 Operation and Maintenance															
			Data															
			Equipment/product warranty list	1.4.1														
			SD-11 Closeout Submittals															
			Final Payroll	1.2.3														
			Sales Tax Report	1.2.3														
			As-built drawings	1.2.1														
			Record of materials	1.2.2														
			Maximo requirements	1.3														
			Complete Submittal Package	1.6														
			Equipment/product warranty tag	1.4.2														
		01 78 30.00 22	SD-11 Closeout Submittals															
			GIS Data Deliverables	1.3														
		02 41 00	SD-01 Preconstruction Submittals															
			Demolition Plan	1.2.2	G													
			Deconstruction Plan		G													
			Existing Conditions	1.11														
			SD-07 Certificates															
			Notification	1.7	G													
			SD-11 Closeout Submittals															
			Receipts															
		02 82 16	SD-06 Test Reports															
			Air sampling results	1.5.2														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		02 82 16	Pressure differential recordings	1.5.3														
			for local exhaust system															
			Clearance sampling	3.3.3.2														
			SD-07 Certificates															
			Asbestos hazard abatement plan	1.5.1														
			SD-11 Closeout Submittals															
			Asbestos Waste Shipment	1.5.4														
			Record N.C. (DHHS-HHCU) Form															
			3787															
			Daily log	1.5.5														
			North Carolina permit	1.5.6														
			Modifications to the North	1.5.7														
			Carolina permit															
			Asbestos Inspection Reporting	1.5.8														
			Form															
		04 20 00	SD-02 Shop Drawings															
			Cut CMU	3.3.4.1	G													
			SD-03 Product Data															
			Hot Weather Procedures	1.4.1	G													
			Cold Weather Procedures	1.4.2	G													
			Cement	2.2.2.2.1	G													
			Cementitious Materials	2.4.1.1	G													
			Insulation	2.6.5	G													
			SD-04 Samples															
			Concrete Masonry Units (CMU)	2.2.2.2	G													
			Admixtures for Masonry Mortar	2.4.1.3	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		04 20 00	Anchors, Ties, and Bar	2.6.2	G													
			Positioners															
			SD-08 Manufacturer’s Instructions															
			Admixtures for Masonry Mortar	2.4.1.3														
			Admixtures for Grout	2.4.2.2														
		06 10 00	SD-02 Shop Drawings															
			Nailing Strips	2.2.1	G													
			SD-06 Test Reports															
			Preservative-treated	1.4.3														
		07 21 13	SD-03 Product Data															
			Manufacturer's Standard Details	1.3	G													
			Block or Board Insulation	2.1	G													
			Vapor Retarder	2.2	G													
			Pressure Sensitive Tape	2.3	G													
			Protection Board or Coatings	1.4	G													
			Accessories	2.5	G													
			Recycled Content for Block or	2.1.3	S													
			Board Insulation															
			SD-07 Certificates															
			Block or Board Insulation	2.1	G													
			Vapor Retarder	2.2	G													
			Protection Board or Coating	2.4	G													
			Protection Board or Coating	3.4.4	G													
			Special Warranties	1.7	G													
			Special Warranties	1.7	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 21 13	Indoor Air Quality For Block Or	2.1.4	S													
			Board Insulation															
			SD-08 Manufacturer's Instructions															
			Block or Board Insulation	2.1														
			Adhesive	2.5.1														
		07 27 10.00 10	SD-02 Shop Drawings															
			Air Barrier System Shop	2.1	G													
			Drawings															
			SD-03 Product Data															
			Air Barrier System Product Data	2.1	G													
			SD-04 Samples															
			Mock-Up	3.1.2	G													
			Material Samples For Air Barrier	2.1	G													
			System															
			SD-05 Design Data															
			Design Data And Calculations	1.8	G													
			For The Air Barrier System															
			SD-06 Test Reports															
			Design Review Report	1.8	G													
			Testing and Inspection	3.1.3	G													
			SD-07 Certificates															
			Air Barrier Inspector	1.7	G													
		07 27 19.01	SD-01 Preconstruction Submittals															
			Qualifications of Manufacturer	1.7.1	G													
			Qualifications of Installer	1.7.2	G													
			SD-02 Shop Drawings															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 27 19.01	Self-adhering Air Barrier	1.4	G													
			SD-03 Product Data															
			Self-adhering Air Barrier	1.4	G													
			Primers, Adhesives, and Mastics	2.2	G													
			Safety Data Sheets	1.4.2	G													
			SD-04 Samples															
			Self-adhering Air Barrier	1.4	G													
			SD-06 Test Reports															
			Field Peel Adhesion Test	1.6	G													
			Flame Propagation of Wall	1.4.4	G													
			Assemblies															
			Flame Spread and Smoke	1.4.4	G													
			Developed Index Ratings															
			Site Inspections and Testing		G													
			SD-07 Certificates															
			Self-adhering Air Barrier	1.4	G													
			SD-08 Manufacturer's Instructions															
			Self-adhering Air Barrier	1.4	G													
			Primers, Adhesives, and Mastics	2.2	G													
		07 27 36	SD-01 Preconstruction Submittals															
			Qualification of Manufacturer	1.10.1	G													
			Qualification of Installer	1.10.2	G													
			Quality Control Plan	1.11	G													
			Safety Plan	1.11	G													
			Fire Prevention Plan	1.9.1	G													
			Respirator Plan	1.9.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 27 36	SD-02 Shop Drawings															
			Spray Foam Air Barrier	1.5														
			Foam Air Barrier System	1.11	G													
			Fire-Rated Assemblies	1.5.1	G													
			SD-03 Product Data															
			Closed Cell	2.1.2	G													
			Transition Membrane	2.2	G													
			Primers, Adhesives, and Mastics	2.3	G													
			Sealants	2.5	G													
			Safety Data Sheets	1.5.2	G													
			Thermal Barrier Materials	2.1.1	G													
			Ignition Barrier Coatings		G													
			Accessories		G													
			SD-04 Samples															
			Spray Foam Air Barrier	1.5	G													
			SD-06 Test Reports															
			Site Inspections	3.4.1	G													
			SD-07 Certificates															
			Closed cell	2.1.2	G													
			Transition Membrane	2.2	G													
			Indoor Air Quality for Spray Foam	2.1.5	G													
			Air Barrier															
			SD-08 Manufacturer's Instructions															
			SPF Handling, Storage, and	1.6.1	G													
			Spray Procedures															
			Substrate Preparation	3.2.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 27 36	Thermal Barrier	1.5.1	G													
			Ignition Barrier		G													
			Transition Membrane	2.2	G													
			Primers, Adhesives, and Mastics	2.3	G													
			SD-09 Manufacturer's Field															
			Reports															
			Core Samples	1.11														
			Daily Work Record	3.3.3														
		07 42 13	SD-01 Preconstruction Submittals															
			Qualification of Manufacturer	1.5.3	G													
			Qualification of Installation	1.5.4	G													
			Contractor															
			Warranty	1.8	G													
			SD-02 Shop Drawings															
			Installation Drawings	1.5.1.1	G													
			SD-03 Product Data															
			Wall Panels	2.2.1	G													
			Factory Color Finish	2.2.2														
			Closure Materials	1.5.5														
			Pressure Sensitive Tape	2.5.4.4														
			Sealants and Caulking	2.5.4.1														
			Galvanizing Repair Paint	1.5.3.1														
			Enamel Repair Paint	1.5.3.1														
			Accessories	1.5.5														
			Accessories	2.5														
			SD-04 Samples															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 42 13	Wall Panels	2.2.1	G													
			Fasteners	1.5.3.1	G													
			Metal Closure Strips	2.5.3	G													
			Color chart	2.2.2.5	G													
			SD-05 Design Data															
			Wind load design analysis	1.5.1.2	G													
			SD-06 Test Reports															
			Leakage Tests	3.7.2	G													
			Wind Load Tests	1.3.2	G													
			Coating	2.2.2.6	G													
			Chalking	2.2.2.6	G													
			Seismic Tests	1.3.2	G													
			SD-07 Certificates															
			Fasteners	1.5.3.1	G													
			Galvanizing Repair Paint	1.5.3.1	G													
			Enamel Repair Paint	1.5.3.1	G													
			SD-08 Manufacturer’s Instructions															
			Installation	3.3	G													
			SD-09 Manufacturer’s Field															
			Reports															
			Manufacturer's Field Reports	3.8.1	G													
			SD-11 Closeout Submittals															
			Warranty	1.8	G													
			Maintenance Instructions	1.5.6	G													
			20 year 'No Dollar Limit' warranty	1.8.1														
			for labor and material															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 52 00	SD-02 Shop Drawings															
			Roof Plan	1.4.6	G													
			Field Inspection and Existing	1.4.6														
			Conditions Report															
			SD-03 Product Data															
			Modified Bitumen Sheets	2.2	G													
			Heat Island Reduction		S													
			Asphalt	2.4														
			Fiberglass Felt	2.2	G													
			Primer	2.6	G													
			Modified Bitumen Roof Cement	2.7	G													
			Pre-Manufactured Accessories	2.10														
			Fasteners And Plates	2.9														
			G Polyisocyanurate Boards; G															
			Gutters, Downspouts, and															
			miscellaneous metal accessories															
			Warranty	1.9	G													
			SD-05 Design Data															
			Wind Uplift Calculations	1.4.5	G													
			SD-07 Certificates															
			Qualification of Manufacturer	1.4.1														
			Qualification of Applicator	1.4.2														
			Qualification of Engineer of	1.4.3														
			Record															
			Bill of Lading	1.5.1														
			Wind Uplift Resistance	1.4.5	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 52 00	Fire Resistance	1.4.4	G													
			SD-08 Manufacturer's Instructions															
			Modified Bitumen Membrane	3.3.6	G													
			Application															
			Flashing	3.3.7	G													
			Temperature Limitations for	3.2.3.1														
			Asphalt															
			Primer	2.6														
			Fasteners	2.9.1														
			Ventilating Base Sheets	3.3.4														
			Coating Application	3.3.11.2	G													
			Cold Weather Installation	1.6	G													
			SD-11 Closeout Submittals															
			Warranty	1.9														
			Information Card	3.8														
			Instructions To Government	3.7														
			Personnel															
		07 60 00	SD-02 Shop Drawings															
			Exposed Sheet Metal	2.2.1	G													
			Gutters	3.1.15	G													
			Downspouts	3.1.16	G													
			Expansion Joints	3.1.22	G													
			Gravel Stops and fascia	2.2.1	G													
			Splash Pans	3.1.19	G													
			Flashing for Roof Drains	3.1.17	G													
			Base Flashing	3.1.9	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 60 00	Counterflashing	3.1.10	G													
			Flashing at Roof Penetrations	3.1.23	G													
			and Equipment Supports															
			Reglets	2.2.10	G													
			Scuppers		G													
			Copings		G													
			Drip Edges	3.1.14	G													
			Conductor Heads	3.1.18	G													
			Open Valley Flashing		G													
			Eave Flashing	3.1.20	G													
			SD-04 Samples															
			Finish Samples for color selection		G													
			SD-08 Manufacturer’s Instructions															
			Instructions for Installation	1.4.3	G													
			Quality Control Plan	3.5	G													
			SD-10 Operation and Maintenance															
			Data															
			Cleaning and Maintenance	1.4.3	G													
		07 92 00	SD-03 Product Data															
			Sealants	2.1	G													
			Primers	2.2	G													
			Bond Breakers	2.3	G													
			Backstops	2.4	G													
			Field Adhesion	3.1	G													
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 92 00	Indoor Air Quality For Interior	2.1.1	S													
			Sealants															
			Indoor Air Quality For Interior		S													
			Floor Joint Sealants															
			Indoor Air Quality For Interior		S													
			Acoustical Sealants															
			Indoor Air Quality For Interior	2.5	S													
			Caulking															
		08 11 13	SD-02 Shop Drawings															
			Doors	2.1	G													
			Doors	2.1	G													
			Frames and Flashing		G													
			Accessories															
			Frames	2.4	G													
			SD-03 Product Data															
			Doors	2.1	G													
			Frames	2.4	G													
			Accessories															
		08 51 13	SD-02 Shop Drawings															
			Windows	2.1	G													
			Fabrication Drawings	1.6														
			SD-03 Product Data															
			Windows	2.1	G													
			Hardware	2.2.6.1	G													
			Fasteners	2.2.2	G													
			Window Performance	1.7	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		08 51 13	Thermal-Barrier Windows	2.3	G													
			Mullions	2.4	G													
			Screens		G													
			Weatherstripping	2.1.4	G													
			Accessories	2.2.6	G													
			Adhesives	2.2.3														
			Thermal Performance	1.7.4	G													
			SD-04 Samples															
			Finish Sample for color selection															
			Mock-Ups including Flashing		G													
			SD-05 Design Data															
			Structural Calculations for	2.1	G													
			Deflection															
			Design Analysis		G													
			SD-06 Test Reports															
			Minimum Condensation	1.3.4														
			Resistance Factor															
			Standard Airblast Test		G													
			Windborne-Debris-Impact	1.7.6														
			Performance															
			SD-10 Operation and Maintenance															
			Data															
			Windows	2.1	G													
		08 71 00	SD-02 Shop Drawings															
			Manufacturer's Detail Drawings	1.3	G													
			Verification of Existing Conditions	1.3	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		08 71 00	Hardware Schedule	1.5	G													
			Keying System	2.3.7	G													
			SD-03 Product Data															
			Hardware Items	2.3	G													
			SD-08 Manufacturer’s Instructions															
			Installation	3.1														
			SD-10 Operation and Maintenance															
			Data															
			Hardware Schedule	1.5	G													
			SD-11 Closeout Submittals															
			Key Bitting	1.6.1														
		08 81 00	SD-03 Product Data															
			Insulating Glass	2.3														
			Plastic Glazing															
			Glazing Accessories	1.3														
			Sealants	2.4.3.1														
			Joint Backer	2.4.4														
			SD-04 Samples															
			Insulating Glass	2.3														
			Plastic Sheet															
			Glazing Compound	2.4.2														
			Tape	2.4.6														
			Sealing Tapes	2.4.6														
			SD-07 Certificates															
			Insulating Glass	2.3														
			SD-08 Manufacturer’s Instructions															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		08 81 00	Setting and Sealing Materials	2.4														
			Glass Setting	3.2														
			SD-11 Closeout Submittals															
			Insulated Glass Units	1.7.1														
		09 29 00	SD-03 Product Data															
			Glass Mat Covered or Reinforced	2.1.2														
			Gypsum Sheathing															
			Glass Mat Covered or Reinforced	2.1.2.1														
			Gypsum Sheathing Sealant															
			Accessories	2.1.7														
			Gypsum Board	2.1.1														
			SD-07 Certificates															
			Asbestos Free Materials	2.1	G													
		09 90 00	SD-02 Shop Drawings															
			Piping Identification															
			SD-03 Product Data															
			Coating	2.1	G													
			Product Data Sheets	2.1														
			Sealant	3.2.5														
			SD-04 Samples															
			Color	2.2	G													
			Textured Wall Coating System		G													
			SD-07 Certificates															
			Indoor Air Quality for Paints and	1.5.3														
			Primers															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
AS515 REPAIRS

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		09 90 00	Indoor Air Quality for															
			Consolidated Latex Paints															
			SD-08 Manufacturer’s Instructions															
			Application Instructions	3.3.1														
			Mixing	2.1														
			Manufacturer's Safety Data	1.7.1														
			Sheets															
			SD-10 Operation and Maintenance															
			Data															
			Coatings	2.1	G													

SECTION 01 35 29

SAFETY AND OCCUPATIONAL HEALTH REQUIREMENTS

06/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z359.1	(1992; R 1999) Safety Requirements for Personal Fall Arrest Systems, Subsystems and Components

ASME INTERNATIONAL (ASME)

ASME B30.3	(1996) Construction Tower Cranes
ASME B30.5	(2000) Mobile and Locomotive Cranes
ASME B30.8	(2000) Floating Cranes and Floating Derricks
ASME B30.22	(2000) Articulating Boom Cranes

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10	(2013) Standard for Portable Fire Extinguishers
NFPA 241	(2019) Standard for Safeguarding Construction, Alteration, and Demolition Operations
NFPA 51B	(2003) Fire Prevention During Welding, Cutting, and Other Hot Work
NFPA 70	(2020) National Electrical Code
NFPA 70E	(2018; TIA 18-1; TIA 81-2) Standard for Electrical Safety in the Workplace

U. S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2014) Safety and Health Requirements Manual

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910	Occupational Safety and Health Standards
29 CFR 1910.146	Permit-required Confined Spaces
29 CFR 1910.94	Ventilation
29 CFR 1915	Confined and Enclosed Spaces and Other Dangerous Atmospheres in Shipyard Employment
29 CFR 1926	Safety and Health Regulations for Construction
29 CFR 1926.500	Fall Protection

1.2 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP)

Activity Hazard Analysis (AHA)

Crane Critical Lift Plan

Crane Work Plan

Proof of qualifications for Crane Operators

SD-06 Test Reports

Reports

Submit reports as their incidence occurs, in accordance with the requirements of the paragraph entitled, "Reports."

Accident Reports

Monthly Exposure Reports

Regulatory Citations and Violations

Crane Reports

SD-07 Certificates

Confined Space Entry Permit

Certificate of Compliance (Crane)

1.3 DEFINITIONS

a. Associate Safety Professional (ASP). An individual who is currently certified by the Board of Certified Safety Professionals.

b. Certified Construction Health & Safety Technician (CHST). An individual who is currently certified as a CHST by the Board of Certified Safety Professionals.

c. Certified Industrial Hygienist (CIH). An individual who is currently certified as a CIH by the American Board of Industrial Hygiene.

d. Certified Safety Professional (CSP). An individual who is currently certified as a CSP by the Board of Certified Safety Professionals.

e. Certified Safety Trained Supervisor (STS). An individual who is currently certified as an STS by the Board of Certified Safety Professionals.

f. Competent Person for Fall Protection. A person who is cabable of identifying hazardous or dangerous conditions in the personal fall arrest system or any component thereof, as well as their application and use with related equipment, and has the authority to take prompt corrective measures to eliminate the hazards of falling.

g. High Visibility Accident. Any mishap which may generate publicity and/or high visibility.

h. Low-slope roof. A roof having a slope less than or equal to 4 in 12 (vertical to horizontal).

i. Medical Treatment. Treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even through provided by a physician or registered personnel.

j. Multi-Employer Work Site (MEWS). A multi-employer work site, as defined by OSHA, is one in which many employers occupy the same site. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors.

k. Operating Envelope. The area surrounding any crane. Inside this "envelope" is the crane, the operator, riggers, rigging gear between the hook and the load, the load and the crane's supporting structure (ground, rail, etc.).

l. Qualified Person for Fall Protection. A person with a recognized degree or professional certifictae, extensive knowledge, training and experience in the field of fall protection who is capable of performing design, analysis, and evaluation of fall protection systems and equipment.

m. Recordable Injuries or Illnesses. Any work-related injury or illness that results in:

(1) Death, regardless of the time between the injury and death, or the length of the illness;

(2) Days away from work;

(3) Restricted work;

(4) Transfer to another job;

(5) Medical treatment beyond first aid;

(6) Loss of consciousness; or

(7) A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (1) through (6) above.

n. Site Safety and Health Officer (SSHO). The superintendent or other qualified or competent person who is responsible for the on-site safety and health required for the project.

o. Steep roof. A roof having a slope greater than 4 in 12 (vertical to horizontal).

p. "USACE" property and equipment specified in USACE EM 385-1-1 should be interpreted as Government property and equipment.

q. Weight Handling Equipment (WHE) Accident. A WHE accident occurs when any one or more of the six elements in the operating envelope fails to perform correctly during operation, including operation during maintenance or testing resulting in personnel injury or death; material or equipment damage; dropped load; derailment; two-blocking; overload; and collision, including unplanned contact between the load, crane, and/or other objects. A dropped load, derailment, two-blocking, overload and collision are considered accidents even though no material damage or injury occurs. A component failure (e.g., motor burnout, gear tooth failure, bearing failure) is not considered an accident solely due to material or equipment damage unless the component failure results in damage to other components (e.g., dropped boom, dropped load, roll over, etc.).

1.4 CONTRACTOR SAFETY SELF-EVALUATION CHECKLIST

Contracting Officer will provide a "Contractor Safety Self-Evaluation checklist" to the Contractor at the pre-construction conference. The checklist will be completed monthly by the Contractor and submitted with each request for payment voucher. An acceptable score of 90 or greater is required. Failure to submit the completed safety self-evaluation checklist or achieve a score of at least 90, will result in a retention of up to 10 percent of the voucher.

1.5 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this contract, work performed shall comply with USACE EM 385-1-1, and the following laws, ordinances, criteria, rules and regulations. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting work. Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements shall apply.

1.6 DRUG PREVENTION PROGRAM

Conduct a proactive drug and alcohol use prevention program for all workers, prime and subcontractor, on the site. Ensure that no employee uses illegal drugs or consumes alcohol during work hours. Ensure there are no employees under the influence of drugs or alcohol during work hours.

After accidents, collect blood, urine, or saliva specimens and test the injured and involved employees for the influence of drugs and alcohol. A copy of the test shall be made available to the Contracting Officer upon request.

1.7 SITE QUALIFICATIONS, DUTIES AND MEETINGS

1.7.1 Personnel Qualifications

Work performed under this contract shall meet Level 2.

1.7.1.1 Site Safety and Health Officer (SSHO)

The SSHO must meet the requirements of EM 385-1-1 section 1 and ensure that the requirements of 29 CFR 1926.16 are met for the project. Provide a Safety oversight team that includes a minimum of one (1) person at each project site to function as the Site Safety and Health Officer (SSHO). The SSHO or an equally-qualified Designated Representative/alternate shall be at the work site at all times to implement and administer the Contractor's safety program and government-accepted Accident Prevention Plan. The SSHO's training, experience, and qualifications shall be as required by EM 385-1-1 paragraph 01.A.17, entitled SITE SAFETY AND HEALTH OFFICER (SSHO), and all associated sub-paragraphs.

A Competent Person shall be provided for all of the hazards identified in the Contractor's Safety and Health Program in accordance with the accepted Accident Prevention Plan, and shall be on-site at all times when the work that presents the hazards associated with their professional expertise is being performed. Provide the credentials of the Competent Person(s) to the the Contracting Officer's Representative for acceptance. Site Safety and

1.7.1.2 Competent Person for Confined Space Entry

Provide a competent person meeting the requirements of EM 385-1-1 who is assigned in writing by the Designated Authority to assess confined spaces and who possesses demonstrated knowledge, skill and ability to:

a. Identify the structure, location, and designation of confined and permit-required confined spaces where work is done;

b. Calibrate and use testing equipment including but not limited to, oxygen indicators, combustible gas indicators, carbon monoxide indicators, and carbon dioxide indicators, and to interpret accurately the test results of that equipment;

c. Perform all required tests and inspections specified in 29 CFR 1910.146 and 29 CFR 1915 Subpart B;

d. Assess hazardous conditions including atmospheric hazards in confined space and adjacent spaces and specify the necessary protection and precautions to be taken;

e. Determine ventilation requirements for confined space entries and operations;

f. Assess hazards associated with hot work in confined and adjacent space and determine fire watch requirements; and,

g. Maintain records required.

When the work involves marine operations that handle combustible or hazardous materials, this qualified person shall be a NFPA certified marine chemist.

1.7.1.3 Competent Person for the Health Hazard Control and Respiratory Protection Program

Provide a competent person meeting the requirements of EM 385-1-1 who is:

a. Capable by education, specialized training and/or experience of anticipating, recognizing, and evaluating employee exposure to hazardous chemical, physical and biological agents in accordance with USACE EM 385-1-1, Section 6.

b. Capable of specifying necessary controls and protective actions to ensure worker health.

1.7.1.4 Crane Operators

Crane operators shall meet the requirements in USACE EM 385-1-1, Section 16 and Appendix G. In addition, for mobile cranes with Original Equipment Manufacturer (OEM) rated capacitates of 50,000 pounds or greater, crane operators shall be designated as qualified by a source that qualifies crane operators (i.e., union, a government agency, or an organization that tests and qualifies crane operators). Proof of current qualifications shall be provided.

1.7.2 Personnel Duties

1.7.2.1 Site Safety and Health Officer (SSHO)/Superintendent

a. Conduct daily safety and health inspections and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections. Safety inspection logs shall be attached to the Contractors' daily report.

b. Conduct mishap investigations and complete required reports. Maintain the OSHA Form 300 and Daily Production reports for prime and sub-contractors.

c. Maintain applicable safety reference material on the job site.

d. Attend the pre-construction conference, pre-work meetings including preparatory inspection meeting, and periodic in-progress meetings.

e. Implement and enforce accepted APPS and AHAs.

f. Maintain a safety and health deficiency tracking system that monitors outstanding deficiencies until resolution. A list of unresolved safety and health deficiencies shall be posted on the safety bulletin board.

g. Ensure sub-contractor compliance with safety and health requirements.

h. Ensure an approved "Special Permission Energized Electrical Work Permit" prior to starting any activity on energized electrical systems.

Failure to perform the above duties will result in dismissal of the superintendent and/or SSHO, and a project work stoppage. The project work stoppage will remain in effect pending approval of a suitable replacement.

1.7.2.2 Certified Safety Professional (CSP), Certified Industrial Hygienist (CIH), Associate Safety Professional (ASP), Certified Safety Trained Supervisor (STS), and/or Certified Construction Health & Safety Technician (CHST)

a. Perform safety and occupational health management, surveillance, inspections, and safety enforcement for the project.

b. Perform as the safety and occupational health "competent person" as defined by USACE EM 385-1-1.

c. Be on site whenever work or testing is being performed.

d. Conduct and document safety inspections.

e. Shall have no other duties other than safety and occupational health management, inspections, and enforcement on this contract.

If the CSP, CIH, ASP, STS, CHST is appointed as the SSHO all duties of that position shall also be performed.

1.7.3 Meetings

1.7.3.1 Preconstruction Conference

a. The Contractor will be informed, in writing, of the date of the preconstruction conference. The purpose of the preconstruction conference is for the Contractor and the Contracting Officer's representatives to become acquainted and explain the functions and operating procedures of their respective organizations and to reach mutual understanding relative to the administration of the overall project's Accident Prevention Plan (APP) before the initiation of work.

b. Contractor representatives who have a responsibility or significant role in accident prevention on the project shall attend the preconstruction conference. This includes the project superintendent, site safety and health officer, quality control supervisor, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).

c. The Contractor shall discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the contract. This list of proposed AHAs will be reviewed at the conference and an agreement will be reached between the Contractor and the Contracting Officer's representative as to which phases will require an analysis. In addition, a schedule for the preparation, submittal, review, and acceptance of AHAs shall be established to preclude project delays.

d. Deficiencies in the submitted APP will be brought to the attention of the Contractor at the preconstruction conference, and the Contractor shall revise the plan to correct deficiencies and re-submit it for

acceptance. Work shall not begin until there is an accepted APP.

e. The functions of a Preconstruction conference may take place at the Post-Awqrd Kickoff meeting for Design Build Contracts.

1.7.3.2 Weekly Safety Meetings

Conduct weekly safety meetings at the project site for all employees. The Contracting Officer will be informed of the meeting in advance and be allowed attendance. Minutes showing contract title, signatures of attendees and a list of topics discussed shall be attached to the Contractors' daily report.

1.7.3.3 Work Phase Meetings

The appropriate AHA shall be reviewed and attendance documented by the Contractor at the preparatory, initial, and follow-up phases of quality control inspection. The analysis should be used during daily inspections to ensure the implementation and effectiveness of safety and health controls.

1.8 TRAINING

1.8.1 New Employee Indoctrination

New employees (prime and sub-contractor) will be informed of specific site hazards before they begin work. Documentation of this orientation shall be kept on file at the project site.

1.8.2 Periodic Training

Provide Safety and Health Training in accordance with USACE EM 385-1-1 and the accepted APP. Ensure all required training has been accomplished for all onsite employees.

1.8.3 Training on Activity Hazard Analysis (AHA)

Prior to beginning a new phase, training will be provided to all affected employees to include a review of the AHA to be implemented.

1.9 ACCIDENT PREVENTION PLAN (APP)

The Contractor shall use a qualified person to prepare the written site-specific APP. Prepare the APP in accordance with the format and requirements of USACE EM 385-1-1 and as supplemented herein. Cover all paragraph and subparagraph elements in USACE EM 385-1-1, Appendix A, "Minimum Basic Outline for Preparation of Accident Prevention Plan". Where a paragraph or subparagraph element is not applicable to the work to be performed indicate "Not Applicable" next to the heading. Specific requirements for some of the APP elements are described below at paragraph 1.8.1. The APP shall be job-specific and shall address any unusual or unique aspects of the project or activity for which it is written. The APP shall interface with the Contractor's overall safety and health program. Any portions of the Contractor's overall safety and health program referenced in the APP shall be included in the applicable APP element and made site-specific. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the contract and the penalties for noncompliance, coordinating the work to prevent one craft

from interfering with or creating hazardous working conditions for other crafts, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out. The APP shall be signed by the person and firm (senior person) preparing the APP, the Contractor, the on-site superintendent, the designated site safety and health officer and any designated CSP and/or CIH.

Submit the APP to the Contracting Officer 15 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP. The Contracting Officer reviews and comments on the Contractor's submitted APP and accepts it when it meets the requirements of the contract provisions.

Once accepted by the Contracting Officer, the APP and attachments will be enforced as part of the contract. Disregarding the provisions of this contract or the accepted APP will be cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified.

Once work begins, changes to the accepted APP shall be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and quality control manager. Should any unforeseen hazard become evident during the performance of work, the project superintendent shall inform the Contracting Officer, both verbally and in writing, for resolution as soon as possible. In the interim, all necessary action shall be taken by the Contractor to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public, and the environment.

Copies of the accepted plan will be maintained at the resident engineer's office and at the job site. The APP shall be continuously reviewed and amended, as necessary, throughout the life of the contract. Unusual or high-hazard activities not identified in the original APP shall be incorporated in the plan as they are discovered.

1.9.1 EM 385-1-1 Contents

In addition to the requirements outlines in Appendix A of USACE EM 385-1-1, the following is required:

a. Names and qualifications (resumes including education, training, experience and certifications) of all site safety and health personnel designated to perform work on this project to include the designated site safety and health officer and other competent and qualified personnel to be used such as CSPs, CIHs, STSs, CHSTs. The duties of each position shall be specified.

b. Qualifications of competent and of qualified persons. As a minimum, competent persons shall be designated and qualifications submitted for each of the following major areas: excavation; scaffolding; fall protection; hazardous energy; confined space; health hazard recognition, evaluation and control of chemical, physical and biological agents; personal protective equipment and clothing to include selection, use and maintenance.

c. Confined Space Entry Plan. Develop a confined space entry plan in accordance with USACE EM 385-1-1, applicable OSHA standards 29 CFR 1910, 29 CFR 1915, and 29 CFR 1926, and any other federal, state and local regulatory requirements identified in this contract. Identify the qualified person's name and qualifications, training, and experience.

Delineate the qualified person's authority to direct work stoppage in the event of hazardous conditions. Include procedure for rescue by contractor personnel and the coordination with emergency responders. (If there is no confined space work, include a statement that no confined space work exists and none will be created.)

d. Health Hazard Control Program. The Contractor shall designate a competent and qualified person to establish and oversee a Health Hazard Control Program in accordance with USACE EM 385-1-1, Section 6. The program shall ensure that employees, on-site Government representatives, and others, are not adversely exposed to chemical, physical and biological agents and that necessary controls and protective actions are instituted to ensure health.

e. Crane Critical Lift Plan. Prepare and sign weight handling critical lift plans for lifts over 75 percent of capacity of the crane or hoist (or lifts over 50 percent of the capacity of a barge mounted movile crane's hoists) at any radius of lift; lifts involving more thatn one crane or hoist; lifts of personnel; and lifts involving more than rigging or operation, sensitive equipment, or unusual safety risks. The plan shall be submitted 15 calendar day6s prior to on-site work and include the requirements of USACE EM 385-1-1, paragraph 16.c.18. and the following:

(1) For lifts of personnel, the plan shall demonstrate compliance with the requirements of 29 CFR 1926.500(g).

(2) For barge mounted mobile cranes, barge stability calculations identifying barge list and trim based on anticipated loading; and load charts based on calculated list and trim. Teh amount of list and trim shall be within the crane manufacturer's requirements.

f. Alcohol and Drug Abuse Plan

(1) Describe plan for random checks and testing with pre-employment screening in accordance with the DFAR Clause subpart 252.223-7004, "Drug Free Work Force."

(2) Description of the on-site prevention program

g. Fall Protection and Prevention (FP&P) Plan. The plan shall be site specific and address all fall hazards in the work place and during different phases of construction. It shall address how to protect and prevent workers from falling to lower levels when they are exposed to fall hazards above 1.8 m (6 feet). A qualified person for fall protection shall prepare and sign the plan. The plan shall include fall protection and prevention systems, equipment and methods employed for every phase of work, responsibilities, assisted rescue self-rescue and evacuation procedures, training requirements, and monitoring methods. Fall Protection and Prevention Plan shall be revised every six months for lengthy projects, reflecting any changes during the course of construction due to changes in personnel, equipment, systems or work habits. The accepted Fall Protection and Prevention Plan shall be kept and maintained at the job site for the duration of the project. The Fall Protection Plan shall be included in the Accident Prevention Plan (APP)

h. Training Records and Requirements. List of mandatory training and certifications which are applicable to this project (e.g. explosive

actuated tools, confined space entry, fall protection, crane operation, vehicle operator, forklift operators, personal protective equipment); list of requiremetns for periodic retraining/certification; outline requirements for supervisory and employee safety meetings.

i. Occupant Protection Plan. The safety and health aspects of lead-based paint removal, prepared in accordance with Section 02 83 19.00 10 Lead Based Paint Hazard Abatement, Target Housing & Child Occupied Facilities, 02 82 33.13 20 Removal/Control and Disposal of Lead Containig Paint.

j. Lead Compliance Plan. The safety and health aspects of lead work, prepared in accordance with Section 02 83 13.00 20 Lead in Construction.

k. Asbestos Hazard Abatement Plan. The safety and health aspects of asbestos work, prepared in accordance with Section 02 2 16.00, "Engineering Control of Asbestos Containing Materials"

l. Site Safety and Health Plan. The safety and health aspects prepared in accordance with this section.

m. PCB Plan. The safety and health aspects of Polychlorinated Biphenyls work, prepared in accordance with Sections 02 84 33, "Removal and Disposal of Polychlorinated Biphenyls (PCBs) and 02 61 23, "Removal and Disposal of PCB Contaminated Soils)".

n. Site Demolition Plan. The safety and health aspects prepared in accordance with Section 02 41 00.00 40, Demolition" and referenced sources. Include engineering survey as applicable.

o. Excavation Plan. The safety and health aspects prepared in accordance with Section 3100, Earthwork.

p. Crane Work Plan. The contractor shall provide a crane work plan to the Contracting Officer for acceptance. The crane work plan shall include the specific model of each crane and a drawing identifying their locations (exact), the dimensions, wheel sizes, number of wheels, wheel spacing, tire pressure(s), number of axles, axle spacing, minimum wheel load to be exerted during operatins and maximum outrigger load to be exerted during operations. The Contractor shall allow at least 10 working days for acceptance/non-acceptance of the crane work plan. No crane operations shall begin prior to written acceptance of the crane plan by the Government. ROICC shall be the government approving authority.

1.10 ACTIVITY HAZARD ANALYSIS (AHA)

The Activity Hazard Analysis (AHA) format shall be in accordance with USACE EM 385-1-1. Submit the AHA for review at least 15 calendar days prior to the start of each phase. Format subsequent AHA as amendments to the APP. An AHA will be developed by the Contractor for every operation involving a type of work presenting hazards not experienced in previous project operations or where a new work crew or subcontractor is to perform work. The analysis must identify and evaluate hazards and outline the proposed methods and techniques for the safe completion of each phase of work. At a minimum, define activity being performed, sequence of work, specific safety and health hazards anticipated, control measures (to include personal protective equipment) to eliminate or reduce each hazard to acceptable levels, equipment to be used, inspection requirements, training

requirements for all involved, and the competent person in charge of that phase of work. For work with fall hazards, including fall hazards associated with scaffold erection and removal, identify the appropriate fall protection methods used. For work with materials handling equipment, address safeguarding measures related to materials handling equipment. For work requiring excavations, include requirements for safeguarding excavations. An activity requiring an AHA shall not proceed until the AHA has been accepted by the Contracting Officer's representative and a meeting has been conducted by the Contractor to discuss its contents with everyone engaged in the activity, including on-site Government representatives. The Contractor shall document meeting attendance at the preparatory, initial, and follow-up phases of quality control inspection. The AHA shall be continuously reviewed and, when appropriate, modified to address changing site conditions or operations. The analysis should be used during daily inspections to ensure the implementation and effectiveness of the activity's safety and health controls.

The AHA list will be reviewed periodically (at least monthly) at the Contractor supervisory safety meeting and updated as necessary when procedures, scheduling, or hazards change.

Activity hazard analyses shall be updated as necessary to provide an effective response to changing work conditions and activities. The on-site superintendent, site safety and health officer and competent persons used to develop the AHAs, including updates, shall sign and date the AHAs before they are implemented.

The activity hazard analyses shall be developed using the project schedule as the basis for the activities performed. Any activities listed on the project schedule will require an AHA. The AHAs will be developed by the contractor, supplier or subcontractor and provided t othe prime contractor for submittal to the Contracting Offficer.

1.11 DISPLAY OF SAFETY INFORMATION

Within 1 calendar days after commencement of work, erect a safety bulletin board at the job site. The following information shall be displayed on the safety bulletin board in clear view of the on-site construction personnel, maintained current, and protected against the elements and unauthorized removal:

a. Map denoting the route to the nearest emergency care facility.

b. Emergency phone numbers.

c. Copy of the most up-to-date APP.

d. Current AHA(s).

e. OSHA 300A Form.

f. OSHA Safety and Health Protection-On-The-Job Poster.
g. Confined space entry permit.
h. Hot work permit.

i. A sign indicating the number of hours worked since last lost workday accident.

j. Safety and Health Warning Posters.

1.12 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in the article "References." Maintain applicable equipment manufacturer's manuals.

1.13 EMERGENCY MEDICAL TREATMENT

Contractors will arrange for their own emergency medical treatment. Government has no responsibility to provide emergency medical treatment.

1.14 REPORTS

1.14.1 Accident Reports

a. For recordable injuries and illnesses, and property damage accidents resulting in at least $2,000 in damages, the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident, complete the Navy Contractor Significant Incident Report (CSIR) form or USACE Accident Report Form 3394 and provide the report to the Contracting Officer within 1 calendar day(s) of the accident. The Contracting Officer will provide copies of any required or special forms.

b. For a weight handling equipment accident (including rigging gear accidents) the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident, complete the WHE Accident Report (Crane and Rigging Gear) form and provide the report to the Contracting Officer within 30 calendar days of the accident. Crane operations shall not proceed until cause is determined and corrective actions have been implemented to the satisfaction of the Contracting Officer. The Contracting Officer will provide a blank copy of the accident report form.

1.14.2 Accident Notification

Notify the Contracting Officer as soon as practical, but not later than four hours, after any accident meeting the definition of Recordable Injuries or Illnesses or High Visibility Accidents, property damage equal to or greater than $2,000, or any weight handling equipment accident. Information shall include contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (to include type of construction equipment used, PPE used, etc.). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on site and Government investigation is conducted.

1.14.3 Monthly Exposure Reports

Monthly exposure reporting to the Contracting Officer is required to be attached to the monthly billing request. This report is a compilation of employee-hours worked each month for all site workers, both prime and subcontractor. The Contracting Officer will provide copies of any special forms.

1.14.4 Regulatory Citations and Violations

Contact the Contracting Officer immediately of any OSHA or other regulatory agency inspection or visit, and provide the Contracting Officer with a copy of each citation, report, and contractor response. Correct violations and citations promptly and provide written corrective actions to the Contracting Officer.

1.14.5 Crane Reports

Submit crane inspection reports required in accordance with USACE EM 385-1-1, Appendix H and as specified herein with Daily Reports of Inspections.

1.14.6 Certificate of Compliance

The Contractor shall provide a Certificate of Compliance for each crane entering an activity under this contract (see Contracting Officer for a blank certificate). Certificate shall state that the crane and rigging gear meet applicable OSHA regulations (with the Contractor citing which OSHA regulations are applicable, e.g., cranes used in construction, demolition, or maintenance shall comply with 29 CFR 1926 and USACE EM 385-1-1 section 16 and Appendix H. Certify on the Certificate of Compliance that the crane operator(s) is qualified and trained in the operation of the crane to be used. For cranes at DOD activities in foreign countries, the Contractor shall certify that the crane and rigging gear conform to the appropriate host country safety standards. The Contractor shall also certify that all of its crane operators working on the DOD activity have been trained in the proper use of all safety devices (e.g., anti-two block devices). These certifications shall be posted on the crane.

1.15 HOT WORK

Prior to performing "Hot Work" (welding, cutting, etc.) or operating other flame-producing/spark producing devices, a written permit shall be requested from the Fire Division. CONTRACTORS ARE REQUIRED TO MEET ALL CRITERIA BEFORE A PERMIT IS ISSUED. The Contractor will provide at least two (2) twenty (20) pound 4A:20 BC rated extinguishers for normal "Hot Work". All extinguishers shall be current inspection tagged, approved safety pin and tamper resistant seal. It is also mandatory to have a designated FIRE WATCH for any "Hot Work" done at this activity. The Fire Watch shall be trained in accordance with NFPA 51B and remain on-site for a minimum of 30 minutes after completion of the task or as specified on the hot work permit.

a. Oil painting materials (paint, brushes, empty paint cans, etc.), and all flammable liquids shall be removed from the facility at quitting time. All painting materials and flammable liquids shall be stored outside in a suitable metal locker or box and will require re-submittal with non-hazardous materials.

b. Accumulation of trays, paper, shavings, sawdust, boxes and other packing materials shall be removed from the facility at the close of each workday and such material disposed of in the proper containers located away from the facility.

c. The storage of combustible supplies shall be a safe distance from structures.

d. Area outside the facility undergoing work shall be cleaned of

trash, paper, or other discarded combustibles at the close of each workday.

e. All portable electric devices (saws, sanders, compressors, extension chord, lights, etc.) shall be disconnected at the close of each workday. When possible, the main electric switch in the facility shall be deactivated.

f. When starting work in the facility, Contractors shall require their personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency phone number 911. ANY FIRE, NO MATTER HOW SMALL, SHALL BE REPORTED IMMEDIATELY.

g. Obtain services from th FIRE DIVISION for "HOT WORK" within or around flammable materials (such as fuel systems, welding/cutting on fuel pipes) or confined spaces (such as sewer wet wells, manholes, vaults, etc.) that have the potential for flammable or explosive atmospheres.

PART 2 PRODUCTS

2.1 CONFINED SPACE SIGNAGE

The Contractor shall provide permanent signs integral to or securely attached to access covers for all required confined spaces. Signs wording: "DANGER--PERMIT-REQUIRED CONFINED SPACE - DO NOT ENTER -" in bold letters a minimum of 25 mm(one inch) in height and constructed to be clearly legible with all paint removed. The signal word "DANGER" shall be red and readable from 1.52 m(5 feet).

2.2 FALL PROTECTION ANCHORAGE

Fall protection anchorage, conforming to ANSI Z359.1, installed under the supervision of a qualified person in fall protection, shall be left in place for continued customer use and so identified by signage stating the capacity of the anchorage (strength and number of persons who may be tied-off to it at any one time).

PART 3 EXECUTION

3.1 CONSTRUCTION AND/OR OTHER WORK

The Contractor shall comply with USACE EM 385-1-1, NFPA 241, the APP, the AHA, Federal and/or State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard shall prevail.

3.1.1 Hazardous Material Use

Each hazardous material must receive approval prior to being brought onto the job site or prior to any other use in connection with this contract. Allow a minimum of 10 working days for processing of the request for use of a hazardous material. Any work or storage involving hazardous chemicals or materials must be done in a manner that will not expose Government or Contractor employees to any unsafe or unhealthful conditions. Adequate protective measures must be taken to prevent Government or Contractor employees from being exposed to any hazardous condition that could result from the work or storage. The Prime Contractor shall keep a complete inventory of hazardous materials brought onto the work-site. Approval by

the Contracting Officer of protective measures and storage area is required prior to the start of the work.

3.1.2 Hazardous Material Exclusions

Notwithstanding any other hazardous material used in this contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation (with the exception of radioactive material and devices used in accordance with USACE EM 385-1-1 such as nuclear density meters for compaction testing and laboratory equipment with radioactive sources) as well as materials which contain asbestos, mercury or polychlorinated biphenyls, di-isocynates, lead-based paint are prohibited. The Contracting Officer, upon written request by the Contractor, may consider exceptions to the use of any of the above excluded materials.

3.1.3 Unforeseen Hazardous Material

The design should have identified materials such as PCB, lead paint, and friable and non-friable asbestos. If additional material, not indicated, that may be hazardous to human health upon disturbance during construction operations is encountered, stop that portion of work and notify the Contracting Officer immediately. Within 14 calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification pursuant to "FAR 52.243-4, Changes" and "FAR 52.236-2, Differing Site Conditions."

3.2 PRE-OUTAGE COORDINATION MEETING

Contractors are required to apply for utility outages at least 15 days in advance. As a minimum, the request should include the location of the outage, utilities being affected, duration of outage and any necessary sketches. Special requirements for electrical outage requests are contained elsewhere in this specification section. Once approved, and prior to beginning work on the utility system requiring shut down, the Contractor shall attend a pre-outage coordination meeting with the Contracting Officer to review the scope of work and the lock-out/tag-out procedures for worker protection. No work will be performed on energized electrical circuits unless proof is provided that no other means exist.

3.3 FALL HAZARD PROTECTION AND PREVENTION

The Contractor shall establish a fall protection and prevention program, for the protection of all employees exposed to fall hazards. The program shall include company policy, identify responsibilities, education and training requirements, fall hazard identification, prevention and control measures, inspection, storage, care and maintenance of fall protection equipment and rescue and escape procedures.

3.3.1 Training

The Contractor shall institute a fall protection training program. As part of the Fall Hazard Protection and Prevention Program, the Contractor shall provide training for each employee who might be exposed to fall hazards. A competent person for fall protection shall provide the training. Training requirements shall be in accordance with USACE EM 385-1-1, section 21.A.16.

3.3.2 Fall Protection Equipment

The Contractor shall enforce use of the fall protection equipment designated for each specific work activity in the Fall Protection and Prevention Plan and/or AHA at all times when an employee is on a surface 1.8 m(6 feet) or more above lower levels. Fall protection systems such as guardrails, personnel fall arrest system, safety nets, etc., are required when working within 1.8m (6 feet) of any leading edge. In addition to the required fall protection systems, safety skiff, personal floatation devices, life rings etc., are required when working above or next to water in accordance with USACE EM 385-1-1, paragraphs 05.I. and 05.J. Personal fall arrest systems are required when working from an articulating or extendible boom, swing stages, or suspended platform. In addition, personal fall arrest systems may be required when operating other equipment such as scissor lifts if the work platform is capable of being positioned outside the wheelbase. The need for tying-off in such equipment is to prevent ejection of the employee from the equipment during raising, lowering, or travel. Fall protection must comply with 29 CFR 1926.500, Subpart M and USACE EM 385-1-1.

3.3.2.1 Personal Fall Arrest Equipment

Personal fall arrest equipment, systems, subsystems, and components shall meet ANSI Z359.1. Only a full-body harness with a shock-absorbing lanyard or self-retracting lanyard is an acceptable personal fall arrest device. Body belts may only be used as a positioning device system (for uses such as steel reinforcing assembly and in addition to an approved fall arrest system). Harnesses shall have a fall arrest attachment affixed to the body support (usually a Dorsal D-ring) and specifically designated for attachment to the rest of the system. Only locking snap hooks and carabiners shall be used. Webbing, straps, and ropes shall be made of synthetic fiber. The maximum free fall distance when using fall arrest equipment shall not exceed 1.8 m (6 feet). The total fall distance and any swinging of the worker (pendulum-like motion) that can occur during a fall shall always be taken into consideration when attaching a person to a fall arrest system.

3.3.3 Fall Protection for Roofing Work

Fall protection controls shall be implemented based on the type of roof being constructed and work being performed. The roof area to be accessed shall be evaluated for its structural integrity including weight-bearing capabilities for the projected loading.

a. Low Sloped Roofs:

(1) For work within 1.8 m (6 feet) of an edge, on low-slope roofs, personnel shall be protected from falling by use of personal fall arrest systems, guardrails, or safety nets. A safety monitoring system is not adequate fall protection and is not authorized.

(2) For work greater than 1.8 m (6 feet) from an edge, warning lines shall be erected and installed in accordance with 29 CFR 1926.500 and USACE EM 385-1-1.

b. Steep Roofs: Work on steep roofs requires a personal fall arrest system, guardrails with toe-boards, or safety nets. This requirement

also includes residential or housing type construction.

3.3.4 Safety Nets

If safety nets are used as the selected fall protection system on the project, they shall be provided at unguarded workplaces, leading edge work or when working over water, machinery, dangerous operations and or other surfaces where the use of ladders, scaffolds, catch platforms, temporary floors, fall arrest systems or restraint/positioning systems are impractical. Safety nets shall be tested immediately after installation with a drop test of 181.4 kg (400 pounds) dropped from the same elevation a person might fall, and every six months thereafter.

3.3.5 Existing Anchorage

Existing anchorages, to be used for attachment of personal fall arrest equipment, shall be certified (or re-certified) by a qualified person for fall protection in accordance with ANSI Z359.1. Exiting horizontal lifeline achorages shall be certified (or re-certified) by a registered professional engineer with experience in designing horizontal lifeline systems.

3.3.6 Horizontal Lifelines

Horizontal lifelines shall be designed, installed, certified and used under the supervision of a qualified person for fall protection as part of a complete fall arrest system which maintains a safety factor of 2 (29 CFR 1926.500).

3.3.7 Guardrail Systems

Guardrails shall consist of top and mid-rails, post and toe boards. The top edge height of standard railing must be 42 inches plus or minus 3 inches above the walking/working level. When mid-rails are used, they must be installed at a height midway between the top edge of the guardrail system and the walking/working level. Posts shall be placed no more than 8 feet apart (29 CFR 1926.500 and USACE EM 385-1-1).

3.3.8 Rescue and Evacuation Procedures

When personal fall arrest systems are used, the contracator must ensure that the mishap victim can self-rescue or can be rescued promptly should a fall occur. A Rescue and Evacuation Plan shall be prepared by the contractor and include a detailed discussion of the following: methods of rescue; methods of self-rescue; equipment used; training requirement; specialized training for the rescuers; procedures for requesting rescue and medical assistance; and transportation routes to a medical facility. The Rescue and Evaluation Plan shall be included in the Activity Hazard Analysis (AHA) for the phase of work, in the Fall Protection and Prevention (FP&P) Plan, and the Accident Prevention Plan (APP).

3.4 PERSONAL PROTECTIVE EQUIPMENT

All personnel who enter a construction site area shall wear Personal Protective Equipment (PPE) at all times as outlined in the EM 385 1-1. In addition to the requirements of the EM 385 1-1, Safety Glasses (ANSI Z87.1) and High-Visibility Apparel (ANSI 107-2004 Performance Class II, Shirt or Vest) will be worn at all times on construction sites. Hearing protection is required in noise hazard areas or when performing noise hazard tasks.

Mandatory PPE on all construction sites includes:

a. Hard Hats

b. Safety Glasses

c. High-Visibility Shirt or Vest

d. Safety-Toed Shoes or Boots

3.5 SCAFFOLDING

Employees shall be provided with a safe means of access to the work area on the scaffold. Climbing of any scaffold braces or supports not specifically designed for access is prohibited. Access to scaffold platforms greater than 6 m (20 feet) in height shall be accessed by use of a scaffold stair system. Vertical ladders commonly provided by scaffold system manufacturers shall not be used for accessing scaffold platforms greater than 6 m (20 feet) in height. The use of an adequate gate is required. Contractor shall ensure that employees are qualified to perform scaffold erection and dismantling. Do not use scaffold without the capability of supporting at least four times the maximum intended load or without appropriate fall protection as delineated in the accepted fall protection and prevention plan. Stationary scaffolds must be attached to structural building components to safeguard against tipping forward or backward. Special care shall be given to ensure scaffold systems are not overloaded. Side brackets used to extend scaffold platforms on self-supported scaffold systems for the storage of material is prohibited. The first tie-in shall be at the height equal to 4 times the width of the smallest dimension of the scaffold base. Work platforms shall be placed on mud sills. Scaffold or work platform erectors shall have fall protection during the erection and dismantling of scaffolding or work platforms that are more than six feet. Delineate fall protection requirements when working above six feet or above dangerous operations in the Fall Protection and Prevention (FP&P) Plan and Activity Hazard Analysis (AHA) for the phase of work.

3.5.1 Stilts

The use of stilts for gaining additional height in construction, renovation, repair or maintenance work is prohibited.

3.6 EQUIPMENT

3.6.1 Material Handling Equipment

a. Material handling equipment such as forklifts shall not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions.

b. The use of hooks on equipment for lifting of material must be in accordance with manufacturer's printed instructions.

c. Operators of forklifts or power industrial trucks shall be licensed in accordance with OSHA.

3.6.2 Weight Handling Equipment

a. Cranes must be equipped with:

(1) Load indicating devices (LIDs) and a boom angle or radius indicator,

(2) or load moment indicating devices (LMIs).

(3) Anti-two block prevention devices.

(4) Boom hoist hydraulic relief valve, disconnect, or shutoff (stops hoist when boom reaches a predetermined high angle).

(5) Boom length indicator (for telescoping booms).

(6) Device to prevent uncontrolled lowering of a telescoping hydraulic boom.

(7) Device to prevent uncontrolled retraction of a telescoping hydraulic boom.

b. The Contractor shall notify the Contracting Officer 15 days in advance of any cranes entering the activity so that necessary quality assurance spot checks can be coordinated. Contractor's operator shall remain with the crane during the spot check.

c. The Contractor shall comply with the crane manufacturer's specifications and limitations for erection and operation of cranes and hoists used in support of the work. Erection shall be performed under the supervision of a designated person (as defined in ASME B30.5). All testing shall be performed in accordance with the manufacturer's recommended procedures.

d. The Contractor shall comply with ASME B30.5 for mobile and locomotive cranes, ASME B30.22 for articulating boom cranes, ASME B30.3 for construction tower cranes, and ASME B30.8 for floating cranes and floating derricks.

e. The presence of Government personnel does not relieve the Contractor of an obligation to comply with all applicable safety regulations. The Government will investigate all complaints of unsafe or unhealthful working conditions received in writing from contractor employees, federal civilian employees, or military personnel.

f. Each load shall be rigged/attached independently to the hook/master-link in such a fashion that the load cannot slide or otherwise become detached. Christmas-tree lifting (multiple rigged materials) is not allowed.

g. Under no circumstance shall a Contractor make a lift at or above 90% of the cranes rated capacity in any configuration.

h. When operating in the vicinity of overhead transmission lines, operators and riggers shall be alert to this special hazard and shall follow the requirements of USACE EM 385-1-1 section 11 and ASME B30.5 or ASME B30.22 as applicable.

i. Crane suspended personnel work platforms (baskets) shall not be used unless the Contractor proves that using any other access to the work location would provide a greater hazard to the workers or is impossible. Personnel shall not be lifted with a line hoist or

friction crane.

j. A fire extinguisher having a minimum rating of 10BC and a minimum nominal capacity of 5lb of extinguishing agent shall be available at all operator stations or crane cabs. Portable fire extinguishers shall be inspected, maintained, and recharged as specified in NFPA 10, Standard for Portable Fire Extinguishers.

k. All employees shall be kept clear of loads about to be lifted and of suspended loads.

l. A weight handling equipment operator shall not leave his position at the controls while a load is suspended.

m. The Contractor shall use cribbing when performing lifts on outriggers.

n. The crane hook/block must be positioned directly over the load. Side loading of the crane is prohibited.

o. A physical barricade must be positioned to prevent personnel from entering the counterweight swing (tail swing) area of the crane.

p. A substantial and durable rating chart containing legible letters and figures shall be provided with each crane and securely mounted onto the crane cab in a location allowing easy reading by the operator while seated in the control station.

q. Certification records which include the date of inspection, signature of the person performing the inspection, and the serial number or other identifier of the crane that was inspected shall always be available for review by Contracting Officer personnel.

r. Written reports listing the load test procedures used along with any repairs or alterations performed on the crane shall be available for review by Contracting Officer personnel.

s. The Contractor shall certify that all crane operators have been trained in proper use of all safety devices (e.g. anti-two block devices).

3.6.3 Equipment and Mechanized Equipment

a. Equipment shall be operated by designated qualified operators. Proof of qualifications shall be kept on the project site for review.

b. Manufacture specifications or owner's manual for the equipment shall be on site and reviewed for additional safety precautions or requirements that are sometimes not identified by OSHA or USACE EM 385-1-1. Such additional safety precautions or requirements shall be incorporated into the AHAs.

c. Equipment and mechanized equipment shall be inspected in accordance with manufacturer's recommendations for safe operation by a competent person prior to being placed into use.

d. Daily checks or tests shall be conducted and documented on equipment and mechanized equipment by designated competent persons.

3.7 EXCAVATIONS

The competent person for excavations performed as a result of contract work shall be on-site when excavation work is being performed, and shall inspect, and document the excavations daily prior to entry by workers. The competent person must evaluate all hazards, including atmospheric, that may be associated with the work, and shall have the resources necessary to correct hazards promptly. The competent person shall perform soil classification in accordance with 29 CFR 1926.

3.7.1 Utility Locations

All underground utilities in the work area must be positively identified by a third party, independent, private utility locating company in addition to any station locating service and coordinated with the station utility department. Any markings made during the utility investigation must be maintained throughout the contract.

3.7.2 Utility Location Verification

The Contractor must physically verify underground utility locations, including utility depth, by hand digging using wood or fiberglass handled tools when any adjacent construction work is expected to come within three feet of the underground system. Digging within 2 feet of a known utility must not be performed by means of mechanical equipment; hand digging shall be used. If construction is parallel to an existing utility the utility shall be exposed by hand digging every 100 feet if parallel within 5 feet of the excavation.

3.7.3 Utilities Within and Under Concrete, Bituminous Asphalt and Other Impervious Surfaces

Utilities located within concrete slabs or pier decks, bridges, parking areas, and the like, are extremely difficult to identify. Whenever contract work involves chipping, saw cutting, or core drilling through concrete, bituminous asphalt or other impervious surfaces, the existing utility location must be coordinated with station utility departments in addition to location and depth verification by a third party, independent, private locating company. The third party, independent, private locating company shall locate utility depth by use of Ground Penetrating Radar (GPR), X-ray, bore scope, or ultrasound prior to the start of demolition and construction. Outages to isolate utility systems must be used in circumstances where utilities are unable to be positively identified. The use of historical drawings does not alleviate the contractor from meeting this requirement.

3.7.4 Shoring Systems

Trench and shoring systems must be identified in the accepted safety plan and AHA. Manufacture tabulated data and specifications or registered engineer tabulated data for shoring or benching systems shall be readily available on site for review. Job-made shoring or shielding shall have the registered professional engineer stamp, specifications, and tabulated data. Extreme care must be used when excavating near direct burial electric underground cables.

3.7.5 Trenching Machinery

Trenching machines with digging chain drives shall be operated only when

the spotters/laborers are in plain view of the operator. Operator and spotters/laborers shall be provided training on the hazards of the digging chain drives with emphasis on the distance that needs to be maintained when the digging chain is operating. Documentation of the training shall be kept on file at the project site.

3.8 ELECTRICAL

3.8.1 Conduct of Electrical Work

Underground electrical spaces must be certified safe for entry before entering to conduct work. Cables that will be cut must be positively identified and de-energized prior to performing each cut. Positive cable identification must be made prior to submitting any outage request for electrical systems. Arrangements are to be coordinated with the Contracting Officer and Station Utilities for identification. The Contracting Officer will not accept an outage request until the Contractor satisfactorily documents that the circuits have been clearly identified. Perform all high voltage cable cutting remotely using hydraulic cutting tool. When racking in or live switching of circuit breakers, no additional person other than the switch operator will be allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method. When working in energized substations, only qualified electrical workers shall be permitted to enter. When work requires Contractor to work near energized circuits as defined by the NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety shoes, insulating gloves with leather protective sleeves, fire retarding shirts, coveralls, face shields, and safety glasses. In addition, provide electrical arc flash protection for personnel as required by NFPA 70E. Insulating blankets, hearing protection, and switching suits may be required, depending on the specific job and as delineated in the Contractor's AHA.

3.8.2 Arc Flash Risk/Hazard Analysis

Contractor shall provide an Arc Flash Risk/Hazsrd Analysis in accordance with NFPA 70E for all locations where workers may be exposed to arc flash hazard (work on energized electrical equipment). The Arc Flash Risk/Hazard Analysis shall be sealed and signed by a qualified professional engineer.

3.8.3 Arc Flash Risk/Hazard Analysis Qualifications

Contractor shall engage the services of a qualified organization to provide Arc Flash Risk/Hazard Analysis of the electrial distribution system. Organization shall be independent of th aupplier, manufacturer, and installer of ht equipment. The organization shall be a first tier subcontractor. This work shall not be performed by a second tier subcontractor.

a. Submit name and qualificaitons of organization. Organization shall have been regularaly engaged in providing Arc Flash Risk/Hazard Analysis for a minimum of 5 years.

b. Submit name and qualifications of the professional engineer performing the analysis. Include a list of three comparable jobs performed by the engineer with specific names nad telephone numbers for reference.

3.8.4 Special Permission Energized Electrical Work Permit

All work on energized electrical systems, including high voltage, must have an approved "Special Permission Energized Electrical Work Permit." The results of a Arc Flash Risk/Hazard Analysis, per NFPA 70E, shall be included in the "Special Permission Energized Electrical Work Permit" request. Flame-resistant (FR) clothing and personel protective equipment (PPE) shall be rated for a minimum of 8 calories per square centimeter even if the flash hazard analysis indicates a lower value. A blank copy of the permit request is attached. An editable version may be obtained from the Contracting Officer.

3.8.5 Portable Extension Cords

Portable extension cords shall be sized in accordance with manufacturer ratings for the tool to be powered and protected from damage. All damaged extension cords shall be immediately removed from service. Portable extension cords shall meet the requirements of NFPA 70.

3.9 WORK IN CONFINED SPACES

The Contractor shall comply with the requirements in Section 06.I of USACE EM 385-1-1 and OSHA 29 CFR 1910.146. Any potential for a hazard in the confined space requires a permit system to be used.

a. Entry Procedures. Prohibit entry into a confined space by personnel for any purpose, including hot work, until the qualified person has conducted appropriate tests to ensure the confined or enclosed space is safe for the work intended and that all potential hazards are controlled or eliminated and documented. (See Section 06.I.05 of USACE EM 385-1-1 for entry procedures.) All hazards pertaining to the space shall be reviewed with each employee during review of the AHA.

b. Forced air ventilation is required for all confined space entry operations and the minimum air exchange requirements must be maintained to ensure exposure to any hazardous atmosphere is kept below its' action level.

c. Ensure the use of rescue and retrieval devices in confined spaces greater than 1.5 m (5 feet) in depth. Conform to Sections 06.I.09, 06.I.10 and 06.I.11 of USACE EM 385-1-1.

d. Sewer wet wells require continuous atmosphere monitoring with audible alarm for toxic gas detection.

e. Include training information for employees who will be involved as entrants and attendants for the work. Conform to Section 06.I.06 of USACE EM 385-1-1.

f. Daily Entry Permit. Post the permit in a conspicuous place close to the confined space entrance.

3.10 CRYSTALLINE SILICA

Grinding, abrasive blasting, and foundry operations of construction materials containing crystalline silica, shall comply with OSHA regulations, such as 29 CFR 1910.94, and USACE EM 385-1-1, Appendix C. The

Contractor shall develop and implement effective exposure control and elimination procedures to include dust control systems, engineering controls, and establishment of work area boundaries, as well as medical surveillance, training, air monitoring, and personal protective equipment.

3.11 HOUSEKEEPING

3.11.1 Clean-Up

All debris in work areas shall be cleaned up daily or more frequently if necessary. Construction debris may be temporarily located in an approved location, however garbage accumulation must be removed each day.

3.11.2 Falling Object Protection

All areas must be barricaded to safeguard employees. When working overhead, barricade the area below to prevent entry by unauthorized employees. Construction warning tape and signs shall be posted so they are clearly visible from all possible access points. When employees are working overhead all tools and equipment shall be secured so that they will not fall. When using guardrail as falling object protection, all openings shall be small enough to prevent passage of potential falling objects.

-- End of Section --

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS
11/14

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization (e.g. ASTM B564 Standard Specification for Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided.

AIR BARRIER ASSOCIATION OF AMERICA (ABAA)
1600 Boston-Providence Hwy
Walpole, MA 02081
Ph: 1-866-956-5888
Fax: 1-866-956-5819
Internet: https://www.airbarrier.org

ALUMINUM ASSOCIATION (AA)
National Headquarters
1525 Wilson Boulevard, Suite 600
Arlington, VA 22209
Ph: 703-358-2960
E-Mail: info@aluminum.org
Internet: http://www.aluminum.org

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)
1827 Walden Office Square, Suite 550
Schaumburg, IL 60173-4268
Ph: 847-303-5664
Fax: 847-303-5774
E-mail: customerservice@aamanet.org
Internet: http://www.aamanet.org

AMERICAN CONCRETE INSTITUTE (ACI)
38800 Country Club Drive
Farmington Hills, MI 48331-3439
Ph: 248-848-3700
Fax: 248-848-3701
E-mail: bkstore@concrete.org
Internet: http://www.concrete.org

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)
1330 Kemper Meadow Drive
Cincinnati, OH 45240
Ph: 513-742-2020 or 513-742-6163
Fax: 513-742-3355
E-mail: mail@acgih.org
Internet: http://www.acgih.org

AMERICAN FOREST FOUNDATION (AFF)
American Tree Farm System
2000 M Street, NW, Suite 550
Washington, DC 20036
Ph: 202-765-3660
Fax: 202-827-7924
Email: info@treefarmsystem.org
Internet: https://www.treefarmsystem.org/standards-review

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)
One East Wacker Drive, Suite 700
Chicago, IL 60601-1802
Ph: 312-670-2400
Fax: 312-670-5403
Bookstore: 800-644-2400
E-mail: aisc@ware-pak.com
Internet: http://www.aisc.org

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)
7012 South Revere Parkway, Suite 140
Centennial, CO 80112
Ph: 503-639-0651
Fax: 503-684-8928
E-mail: info@aitc-glulam.org
Internet: http://www.aitc-glulam.org

AMERICAN IRON AND STEEL INSTITUTE (AISI)
25 Massachusetts Avenue, NW Suite 800
Washington, DC 20001
Ph: 202-452-7100
Internet: http://www.steel.org

AMERICAN LUMBER STANDARDS COMMITTEE (ALSC)
P.O. Box 210
Germantown, MD 20875-0210
Ph: 301-972-1700
Fax: 301-540-8004
E-mail: alsc@alsc.org
Internet: http://www.alsc.org

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)
1899 L Street, NW,11th Floor
Washington, DC 20036
Ph: 202-293-8020
Fax: 202-293-9287
E-mail: storemanager@ansi.org
Internet: http://www.ansi.org/

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)
1801 Alexander Bell Drive
Reston, VA 20191

Ph: 703-295-6300; 800-548-2723
E-mail: member@asce.org
Internet: http://www.asce.org

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)
1801 Alexander Bell Drive
Reston, VA 20191
Ph: 703-295-6300; 800-548-2723
E-mail: member@asce.org
Internet: http://www.asce.org

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)
1791 Tullie Circle, NE
Atlanta, GA 30329
Ph: 800-527-4723 or 404-636-8400
Fax: 404-321-5478
E-mail: ashrae@ashrae.org
Internet: http://www.ashrae.org

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)
1800 East Oakton Street
Des Plaines, IL 60018
Ph: 847-699-2929
Internet: http://www.asse.org

AMERICAN WATER WORKS ASSOCIATION (AWWA)
6666 West Quincy Avenue
Denver, CO 80235-3098
Ph: 303-794-7711
E-mail: distribution@awwa.org
Internet: http://www.awwa.org

AMERICAN WELDING SOCIETY (AWS)
13301 NW 47 Ave
Miami, FL 33054

Ph: 888-WELDING, 305-824-1177, 305-826-6192
Fax: 305-826-6195
E-mail: customer.service@awspubs.com
Internet: http://www.aws.org

AMERICAN WOOD COUNCIL (AWC)
222 Catoctin Circle SE, Suite 201
Leesburg, VA 20175
Ph: 800-890-7732
Fax: 412-741-0609
E-mail: publications@awc.org
Internet: http://www.awc.org

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)
P.O. Box 361784
Birmingham, AL 35236-1784
Ph: 205-733-4077
Fax: 205-733-4075
Internet: http://www.awpa.com

APA - THE ENGINEERED WOOD ASSOCIATION (APA)
7011 South 19th St.

Tacoma, WA 98466-5333
Ph: 253-565-6600
Fax: 253-565-7265
Internet: http://www.apawood.org

ASME INTERNATIONAL (ASME)
Two Park Avenue, M/S 10E
New York, NY 10016-5990
Ph: 800-843-2763
Fax: 973-882-1717
E-mail: customercare@asme.org
Internet: http://www.asme.org

ASPHALT ROOFING MANUFACTURER'S ASSOCIATION (ARMA)
750 National Press Building
529 14th Street, NW
Washington D.C. 20045
Ph: 202-591-2450
Fax: 202-591-2445
Internet: http://www.asphaltroofing.org

ASTM INTERNATIONAL (ASTM)
100 Barr Harbor Drive, P.O. Box C700
West Conshohocken, PA 19428-2959
Ph: 877-909-2786
Internet: http://www.astm.org

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)
355 Lexington Avenue, 15th Floor
New York, NY 10017
Ph: 212-297-2122
Fax: 212-370-9047
Internet: http://www.buildershardware.com

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)
PO Box 997377, MS 0500
Sacramento, CA 95899-7377
Ph: 916-558-1784
Internet: http://www.cdph.ca.gov

CENTERS FOR DISEASE CONTROL AND PREVENTION (CDC)
1600 Clifton Road
Atlanta, GA 30333
Ph: 800-232-4636
TTY: 888-232-6348Internet: http://www.cdc.gov

CSA GROUP (CSA)
178 Rexdale Blvd.
Toronto, ON, Canada M9W 1R3
Ph: 416-747-4044
Fax: 416-747-2510
E-mail: sales@csagroup.org
Internet: http://www.csagroup.org/us/en/home

FM GLOBAL (FM)
270 Central Avenue
P.O. Box 7500
Johnston, RI 02919-4923
Ph: 877-364-6726
Fax: 401-275-3029
E-mail: servicedesk.myrisk@fmglobal.com
Internet: http://www.fmglobal.com

FOREST STEWARDSHIP COUNCIL (FSC)
212 Third Avenue North
Suite 445
Minneapolis, MN 55401
Ph: 612-353-4511
E-mail: info@us.fcs.org
Internet: https://us.fsc.org/

GLASS ASSOCIATION OF NORTH AMERICA (GANA)
800 SW Jackson St., Suite 1500
Topeka, KS 66612-1200
Ph: 785-271-0208
E-mail: gana@glasswebsite.com
Internet: http://www.glasswebsite.com

GREEN SEAL (GS)
1001 Connecticut Avenue, NW
Suite 827
Washington, DC 20036-5525
Ph: 202-872-6400
Fax: 202-872-4324
Internet: http://www.greenseal.org

GYPSUM ASSOCIATION (GA)
6525 Belcrest Road, Suite 480
Hyattsville, MD 20782
Ph: 301-277-8686
Fax: 301-277-8747
E-mail: info@gypsum.org
Internet: http://www.gypsum.org

ICC EVALUATION SERVICE, INC. (ICC-ES)
3060 Saturn Street, Suite 100
Brea, CA 92821
Ph: 800-423-6587 ext. 66546
Fax: 562-695-4694
E-mail: es@icc-es.org
Internet: http://www.icc-es.org

INSULATING GLASS MANUFACTURERS ALLIANCE (IGMA)
27 N. Wacker Dr. Suite 365
Chicago, IL 60606-2800
Ph: 613-233-1510
Fax: 613-482-9436
E-mail: enquiries@igmaonline.org
Internet: http://www.igmaonline.org

INTERNATIONAL CODE COUNCIL (ICC)
500 New Jersey Avenue, NW
6th Floor, Washington, DC 20001
Ph: 800-786-4452 or 888-422-7233
E-mail: order@iccsafe.org
Internet: www.iccsafe.org

INTERNATIONAL SAFETY EQUIPMENT ASSOCIATION (ISEA)
1901 North Moore Street
Arlington, VA 22209-1762
Ph: 703-525-1695
Fax: 703-528-2148
Internet: http://www.safetyequipment.org/

MASTER PAINTERS INSTITUTE (MPI)
2800 Ingleton Avenue
Burnaby, BC CANADA V5C 6G7
Ph: 1-888-674-8937
Fax: 1-888-211-8708
E-mail: info@paintinfo.com or techservices@mpi.net
Internet: http://www.mpi.net/

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)
1300 Sumner Avenue
Cleveland, OH 44115-2851
Ph: 216-241-7333
Fax: 216-241-0105
E-mail: mbma@mbma.com
Internet: http://www.mbma.com

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)
800 Roosevelt Road, Bldg C, Suite 312
Glen Ellyn, IL 60137
Ph: 630-942-6591
Fax: 630-790-3095
E-mail: wlewis7@cox.net(Wes Lewis,technical consultant)
Internet: http://www.naamm.org

NATIONAL FENESTRATION RATING COUNCIL (NFRC)
6305 Ivy Lane, Suite 140
Greenbelt, MD 20770
Ph: 301-589-1776
Fax: 301-589-3884
E-Mail: info@nfrc.org
Internet: http://www.nfrc.org

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
1 Batterymarch Park
Quincy, MA 02169-7471
Ph: 617-770-3000
Fax: 617-770-0700
Internet: http://www.nfpa.org

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)
6830 Raleigh LaGrange Road
PO Box 34518
Memphis, TN 38184

Ph: 901-377-1818
Store: 901-399-7563
Internet: http://www.nhla.org

NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
10255 West Higgins Road, Suite 600
Rosemont, IL 60018-5607
Ph: 866-275-6722 (866-ASK-NRCA)
Fax: 847-299-1183
E-mail: info@nrca.net
Internet: http://www.nrca.net

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)
272 Tuttle Road
Cumberland, ME 04021
Ph: 207-829-6901
Fax: 207-829-4293
E-mail: info@nelma.org
Internet: http://www.nelma.org

PROGRAMME FOR ENDORSEMENT OF FOREST CERTIFICATION (PEFC)
10, Route de l'Aeroport
Case Postale 638
1215 Geneva - Switzerland
Ph: +41 (22) 799-4540
Fax: +41 (22) 799-4550
Internet: http://www.pefc.org

REDWOOD INSPECTION SERVICE (RIS) OF THE CALIFORNIA REDWOOD ASSOCIATION (CRA)
818 Grayson Road, Suite 201
Pleasant Hill, CA 94523
Ph: 925-935-1499
Fax: 925-935-1496
E-Mail: ris@calredwood.org
Internet: http://www.redwoodinspection.com/

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)
2000 Powell Street, Suite 600
Emeryville, CA 94608
Ph: 800-326-3228
E-mail: info@SCSglobal services.com
Internet: http://www.scsglobalservices.com/

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
4201 Lafayette Center Drive
Chantilly, VA 20151-1219
Ph: 703-803-2980
Fax: 703-803-3732
Internet: http://www.smacna.org

SINGLE PLY ROOFING INDUSTRY (SPRI)
411 Waverley Oaks Road, Suite 331B
Waltham, MA 02452
Ph: 781-647-7026
Fax: 781-647-7222
E-mail: info@spri.org
Internet: http://www.spri.org

SOCIETY FOR PROTECTIVE COATINGS (SSPC)
40 24th Street, 6th Floor
Pittsburgh, PA 15222
Ph: 412-281-2331
Fax: 412-281-9992
E-mail: info@sspc.org
Internet: http://www.sspc.org

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)
21865 Copley Drive
Diamond Bar, CA 91765
Ph: 909-396-2000
E-mail: webinquiry@aqmd.gov
Internet: http://www.aqmd.gov

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)
665 Rodi Road, Suite 305
Pittsburgh, PA 15235
Ph: 412-244-0440
Fax: 412-244-9090
E-Mail: member-services@cypressinfo.org
Internet: http://www.cypressinfo.org

SOUTHERN PINE INSPECTION BUREAU (SPIB)
P.O. Box 10915
Pensacola, FL 32504-0915
Ph: 850-434-2611
Fax: 850-433-5594
Internet: http://www.spib.org

SPRAY POLYURETHANE FOAM ALLIANCE (SPFA)
3927 Old Lee Hwy. #101B
Fairfax, VA 22030
Ph: 800-523-6154
Fax: 703-222-5816
Internet: http://www.sprayfoam.org

STEEL DOOR INSTITUTE (SDI/DOOR)
30200 Detroit Road
Westlake, OH 44145
Ph: 440-899-0010
Fax: 440-892-1404
E-mail: info@steeldoor.org
Internet: http://www.steeldoor.org

SUSTAINABLE FOREST INITIATIVE (SFI)
2121 K Street NW
Suite 750
Washington, DC 20037
Ph: 202-596-3450
Fax: 202-596-3451
Internet: http://www.sfiprogram.org

THE MASONRY SOCIETY (TMS)
105 South Sunset Street, Suite Q
Longmont, CO 80501-9215
Ph: 303-939-9700
Fax: 303-541-9215

E-mail: info@masonrysociety.org
http://www.masonrysociety.org

U.S. ARMY CORPS OF ENGINEERS (USACE)
CRD-C DOCUMENTS available on Internet:
http://www.wbdg.org/ccb/browse_cat.php?c=68
Order Other Documents from:
USACE Publications Depot
Attn: CEHEC-IM-PD
2803 52nd Avenue
Hyattsville, MD 20781-1102
Ph: 301-394-0081
Fax: 301-394-0084
E-mail: pubs-army@usace.army.mil
Internet: http://www.publications.usace.army.mil/
or
http://www.hnc.usace.army.mil/Missions/Engineering/TECHINFO.aspx

U.S. DEFENSE LOGISTICS AGENCY (DLA)

Fort Belvoir, VA

Internet: http://www.dla.mil

U.S. DEPARTMENT OF DEFENSE (DOD)
Order DOD Documents from:
Room 3A750-The Pentagon
1400 Defense Pentagon
Washington, DC 20301-1400
Ph: 703-571-3343
FAX: 215-697-1462
E-mail: customerservice@ntis.gov
Internet: http://www.ntis.gov
Obtain Military Specifications, Standards and Related Publications from:
Acquisition Streamlining and Standardization Information System (ASSIST)
Department of Defense Single Stock Point (DODSSP)
Document Automation and Production Service (DAPS)
Building 4/D
700 Robbins Avenue
Philadelphia, PA 19111-5094
Ph: 215-697-6396 - for account/password issues
Internet: http://assist.daps.dla.mil/online/start/; account registration required
Obtain Unified Facilities Criteria (UFC) from:
Whole Building Design Guide (WBDG)
National Institute of Building Sciences (NIBS)
1090 Vermont Avenue NW, Suite 700
Washington, CD 20005
Ph: 202-289-7800
Fax: 202-289-1092
Internet: http://www.wbdg.org/references/docs_refs.php

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)
Ariel Rios Building
1200 Pennsylvania Avenue, N.W.
Washington, DC 20004
Ph: 202-272-0167

Internet: http://www2.epa.gov/libraries
--- Some EPA documents are available only from:
National Technical Information Service (NTIS)
5301 Shawnee Road
Alexandria, VA 22312
Ph: 703-605-6050 or 1-688-584-8332
Fax: 703-605-6900
E-mail: info@ntis.gov
Internet: http://www.ntis.gov

U.S. FEDERAL AVIATION ADMINISTRATION (FAA)
Order for sale documents from:
Superintendent of Documents
U.S. Government Printing Office (GPO)
710 North Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800
Fax: 202-512-2104
E-mail: contactcenter@gpo.gov
Internet: http://www.gpoaccess.gov
Order free documents from:
Federal Aviation Administration
Department of Transportation
800 Independence Avenue, SW
Washington, DC 20591
Ph: 1-866-835-5322
Internet: http://www.faa.gov

U.S. GENERAL SERVICES ADMINISTRATION (GSA)
General Services Administration
1275 First St. NE
Washington, DC 20417
Ph: 202-501-1231
Internet: http://www.gsaelibrary.gsa.gov/ElibMain/home.do
Obtain documents from:
Acquisition Streamlining and Standardization Information System (ASSIST)
Internet: https://assist.dla.mil/online/start/; account registration required

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)
8601 Adelphi Road
College Park, MD 20740-6001
Ph: 866-272-6272
Fax: 301-837-0483
Internet: http://www.archives.gov
Order documents from:
Superintendent of Documents
U.S.Government Printing Office (GPO)
710 North Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800
Fax: 202-512-2104
E-mail: contactcenter@gpo.gov
Internet: http://www.gpoaccess.gov

UNDERWRITERS LABORATORIES (UL)
2600 N.W. Lake Road
Camas, WA 98607-8542

Ph: 877-854-3577
E-mail: CEC.us@us.ul.com
Internet: http://www.ul.com/
UL Directories available through IHS at http://www.ihs.com

UNDERWRITERS LABORATORIES OF CANADA (ULC)
7 Underwriters Road
Toronto, ON M1R 3A9
Canada
Ph: 416.757.3611
Fax: 416.757.8727
Internet: http://canada.ul.com

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)
P.O. Box 23145
Portland, OR 97281
Ph: 503-639-0651
Fax: 503-684-8928
E-mail: info@wclib.org
Internet: http://www.wclib.org

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)
1500 SW First Ave., Suite 870
Portland, OR 97201
Ph: 503-224-3930
Fax: 503-224-3934
E-mail: info@wwpa.org
Internet: http://www.wwpa.org

PART 2 PRODUCTS

Not used

PART 3 EXECUTION

Not used

-- End of Section --

SECTION 01 45 10

QUALITY CONTROL

09/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 880	(1996) Criteria for Use in Evaluation of Testing Laboratories and Organizations for Examination and Inspection of Steel, Stainless Steel, and Related Alloys
ASTM C 1077	(1998) Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation
ASTM D 3666	(2000) Minimum Requirements for Agencies Testing and Inspecting Bituminous Paving Materials
ASTM D 3740	(1999c) Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction
ASTM E 329	(2009) Standard Specification for Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction
ASTM E 543	(1999) Evaluating Agencies that Perform Nondestructive Testing

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00, "Submittal Procedures."

SD-11 Closeout Submittals

Quality Control Plan (QC PLAN)

Submit a QC plan within 15 calendar days after receipt of Notice of Award.

1.3 INFORMATION FOR THE CONTRACTING OFFICER

Deliver the following to the Contracting Officer:

a. Combined Contractor Production Report/Contractor Quality Control Report (1 sheet): Original and 1 copy, by 10:00 AM the next work ing day after each day that work is performed;

b. QC Specialist Reports and Test Results: Originals and 1 copy, by 10:00 AM the next working day after each day that work is per formed;

c. Testing Plan and Log, 1 copy, at the end of each month;

d. QC Meeting Minutes: 1 copy, within 2 calendar days of the meeting;

e. Rework Items List: 1 copy, by the last working day of the month and;

f. QC Certifications: As required by the paragraph entitled "QC Certifications".

1.4 QC PROGRAM REQUIREMENTS

Establish and maintain a QC program as described in this section. The QC program consists of a QC Organization, a QC Plan, attending a QC Plan meet ing, attending a Coordination and Mutual Understanding Meeting, conducting QC meetings, performing three phases of control, performing submittal review, ensuring testing is performed, and preparing QC certifications and documentation necessary to provide materials, equipment, workmanship, fabrication, construction and operations which comply with the requirements of this Contract. The QC program shall cover construction operations on-site and off-site and shall be keyed to the proposed construction sequence.

1.5 QC ORGANIZATION

1.5.1 QC Manager

1.5.1.1 Duties

Provide a QC Manager at the work site to manage and implement the QC program. The QC Manager is required to attend the QC Plan meeting, attend the Coordination and Mutual Understanding Meeting, conduct the QC meetings, perform the three phases of control, perform submittal review, ensure testing is performed and prepare QC certifications and documentation required in this Contract. The QC Manager is responsible for managing and coordinating the three phases of control and documentation performed by the QC specialists. In addition to managing and implementing the QC program, the QC Manager may perform the duties of project superintendent.

1.5.1.2 Qualifications

An individual with a minimum of five years experience as a foreman, super intendent, inspector, QC Manager, project manager, or construction manager on similar size construction contracts which included the major trades that are part of this Contract.

Provide a separate QC Specialist at the work site for each of the areas of responsibilities for the following:

Electrical and Telecommunication Systems QC Specialists.

Provide ICC IBC Special Inspection Certification from the following specialist:

Telecommunictions Systems Installation Specialist, (10) years minimum experience in Telecommunication Systems Installation.

Area of responsibility:

Telecommunication Systems, all Division 27, Division 28, and Division 33 Outside Plant work.

Frequency of specialists is full time during systems installation and testing. QC Specialists are required to attend the Coordination and Mutual Understanding Meeting, QC meetings and be physically present at the construction site to perform the three phases of control and prepare documentation for each definable feature of work in their area of responsibility.

1.5.1.3 Construction Quality Management Training

In addition to the above experience and education requirements, the QC Manager shall have completed the course entitled "Construction Quality Management for Contractors." This course is periodically offered by the Navy and the Corps of Engineers. However, it is sponsered by both the AGC and the ABC of Charlotte, North Carolina. Call one of the following to sign up for the next available class:

The Army Corps of Engineers, Baltimore District;
(Offered in Baltimore, MD)
Contact: Corps of Engineers, Baltimore District
10 South Howard Street
Baltimore, MD 21201
Phone: 410-962-2323

The Associated General Contractors (AGC), Virginia Chapter
in Cooperation with the Army Corps of Engineers, Norfolk District, and
the Naval Facilities Engineering Command, Atlantic Division.
(Offered at rotating locations in Norfolk, Williamsburg, and Richmond)
Contact: AGC of Virginia
8631 Maylan Drive, Parham Park
Richmond, VA 23294
Phone: 804-346-3383

Carolinas Associated General Contractors (CACG)
Contact: CACG
1100 Euclid Avenue
Charlotte, NC 28203
Phone: 704-372-1450 (ext. 5248)

Associated Builders and Contractors (ABC), Carolinas Chapter
Contact: ABC, Carolinas Chapter
3705 Latrobe Drive
Charlotte, NC 28211
Phone: 704-367-1331
or: 877-470-4819

1.5.2 Alternate QC Manager Duties and Qualifications

Designate an alternate for the QC Manager at the work site to serve in the event of the designated QC Manager's absence. The period of absence may not exceed two weeks at one time, and not more than 30 workdays during a calendar year. The qualification requirements for the Alternate QC Manager shall be three years of experience in one of the specified positions.

1.6 QC PLAN

1.6.1 Requirements

Provide for approval by the Contracting Officer, a QC plan submitted in a 3-ring binder with pages numbered sequentially that covers, both on-site and off-site work and includes, the following:

a. A table of contents listing the major sections identified with tabs in the following order:

I. QC ORGANIZATION
II. NAMES AND QUALIFICATIONS
III. DUTIES, RESPONSIBILITY AND AUTHORITY OF QC PERSONNEL
IV. OUTSIDE ORGANIZATIONS
V. APPOINTMENT LETTERS
VI. SUBMITTAL PROCEDURES AND INITIAL SUBMITTAL REGISTER
VII. TESTING LABORATORY INFORMATION
VIII. TESTING PLAN AND LOG
IX. PROCEDURES TO COMPLETE REWORK ITEMS
X. DOCUMENTATION PROCEDURES
XI. LIST OF DEFINABLE FEATURES
XII. PROCEDURES FOR PERFORMING THE THREE PHASES OF CONTROL
XIII. PERSONNEL MATRIX
XIV. PROCEDURES FOR COMPLETION INSPECTION

b. A chart showing the QC organizational structure and its relationship to the production side of the organization.

c. Names and qualifications, in resume format, for each person in the QC organization.

d. Duties, responsibilities and authorities of each person in the QC organization.

e. A listing of outside organizations such as, architectural and consulting engineering firms that will be employed by the Contractor and a description of the services these firms will provide.

f. A letter signed by an officer of the firm appointing the QC Manager and stating that he/she is responsible for managing and implementing the QC program as described in this contract. Include in this letter the QC Manager's authority to direct the removal and replacement of non-conforming work.

g. Procedures for reviewing, approving and managing submittals. Provide the names of the persons in the QC organization authorized to review and certify submittals prior to approval.

h. Testing laboratory information required by the paragraphs entitled

"Accredited Laboratories" or "Testing Laboratory Requirements", as applicable.

i. A Testing Plan and Log that includes the tests required, referenced by the specification paragraph number requiring the test, the frequency, and the person responsible for each test.

j. Procedures to identify, record, track and complete rework items.

k. Documentation procedures, including proposed report formats.

l. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks and requires separate control requirements. As a minimum, if approved by the Contracting Officer, consider each Section of the Specifications as a definable feature of work. However, at times, there may be more than one definable feature of work in each Section of the Specifications.

m. A personnel matrix showing, for each section of the specification, who will perform and document the three phases of control, and who will perform and document the testing.

o. Procedures for Identifying and Documenting the Completion Inspection process. Include in these procedures the responsible party for punch out inspection, prefinal inspection, and final acceptance inspection.

1.6.2 Preliminary Work Authorized Prior to Approval

The only work that is authorized to proceed prior to the approval of the QC plan is mobilization of storage and office trailers and surveying.

1.6.3 Approval

Approval of the QC plan is required prior to the start of construction. The Contracting Officer reserves the right to require changes in the QC plan and operations as necessary to ensure the specified quality of work. The Contracting Officer reserves the right to interview any member of the QC organization at any time in order to verify his/her submitted qualifications.

1.6.4 Notification of Changes

Notify the Contracting Officer, in writing, of any proposed change, including changes in the QC organization personnel, a minimum of seven calendar days prior to a proposed change. Proposed changes must be approved by the Contracting Officer.

1.7 QC PLAN MEETING

Prior to submission of the QC plan, meet with the Contracting Officer to discuss the QC plan requirements of this Contract. The purpose of this meeting is to develop a mutual understanding of the QC plan requirements prior to plan development and submission.

1.8 COORDINATION AND MUTUAL UNDERSTANDING MEETING

After submission of the QC Plan, but prior to the start of construction,

meet with the Contracting Officer to discuss the QC program required by this Contract. The purpose of this meeting is to develop a mutual understanding of the QC details, including forms to be used for documentation, administration for on-site and off-site work, and the coordination of the Contractor's management, production and QC personnel with the Contracting Officer. As a minimum, the Contractor's personnel required to attend shall include the project manager, project superintendent, and QC Manager. Minutes of the meeting shall be prepared by the QC Manager and signed by both the Contractor and the Contracting Officer.

1.9 QC MEETINGS

After the start of construction, the QC Manager shall conduct weekly QC meetings at the work site with the project superintendent and QC specialists. The QC Manager shall prepare the minutes of the meeting and provide a copy to the Contracting Officer within 2 working days after the meeting. The Contracting Officer may attend these meetings. The QC Manager shall notify the Contracting Officer at least 48 hours in advance of each meet ing. As a minimum, the following shall be accomplished at each meeting:

a. Review the minutes of the previous meeting;

b. Review the schedule and the status of work:

- Work or testing accomplished since last meeting
- Rework items identified since last meeting
- Rework items completed since last meeting;

c. Review the status of submittals:

- Submittals reviewed and approved since last meeting
- Submittals required in the near future;

d. Review the work to be accomplished in the next 2 weeks and documen tation required. Schedule the three phases of control and testing:

- Establish completion dates for rework items
- Preparatory phases required
- Initial phases required
- Follow-up phases required
- Testing required
- Status of off-site work or testing
- Documentation required;

e. Resolve QC and production problems; and

f. Address items that may require revising the QC plan:

- Changes in QC organization personnel
- Changes in procedures.

1.9.1 THREE PHASES OF CONTROL

The QC Manager shall perform the three phases of control to ensure that work complies with Contract requirements. The Three Phases of Control shall adequately cover both on-site and off-site work and shall include the following for each definable features of work: A definable feature of work

is a task which is separate and distinct from other tasks and requires separate control requirements.

1.9.2 Preparatory Phase

Notify the Contracting Officer at least 48 hours in advance of each preparatory phase. Conduct the preparatory phase with the superintendent, and the foreman responsible for the definable feature. Document the results of the preparatory phase actions in the daily Contractor Quality Control Report. Perform the following prior to beginning work on each definable feature of work:

a. Review each paragraph of the applicable specification sections;

b. Review the Contract drawings;

c. Verify that appropriate shop drawings and submittals for materials and equipment have been submitted and approved. Verify receipt of approved factory test results, when required;

d. Review the testing plan and ensure that provisions have been made to provide the required QC testing;

e. Examine the work area to ensure that the required preliminary work has been completed;

f. Examine the required materials, equipment and sample work to ensure that they are on hand and conform to the approved shop drawings and submitted data;

g. Review the safety plan and appropriate activity hazard analysis to ensure that applicable safety requirements are met, and that required Material Safety Data Sheets (MSDS) are submitted; and

h. Discuss construction methods

1.9.3 Initial Phase

Notify the Contracting Officer at least 48 hours in advance of each initial phase. When construction crews are ready to start work on a definable feature of work, conduct the initial phase with the QC Specialists, the super intendent, and the foreman responsible for that definable feature of work. Observe the initial segment of the definable feature of work to ensure that the work complies with Contract requirements. Document the results of the initial phase in the daily Contractor Quality Control Report. Repeat the initial phase for each new crew to work on-site, or when acceptable levels of specified quality are not being met. Perform the following for each definable feature of work:

a. Establish the quality of workmanship required;

b. Resolve conflicts;

c. Review the Safety Plan and the appropriate activity hazard analysis to ensure that applicable safety requirements are met; and

d. Ensure that testing is performed by an approved laboratory.

1.9.4 Follow-Up Phase

Perform the following for on-going work daily, or more frequently as necessary until the completion of each definable feature of work and document in the daily Contractor Quality Control Report:

a. Ensure the work is in compliance with Contract requirements;

b. Maintain the quality of workmanship required;

c. Ensure that testing is performed by an approved laboratory; and

d. Ensure that rework items are being corrected.

1.9.5 Notification of Three Phases of Control for Off-Site Work

Notify the Contracting Officer at least two weeks prior to the start of the preparatory and initial phases.

1.10 SUBMITTAL REVIEW

Procedures for submittals are as described in Section entitled "Submittal Procedures."

1.11 TESTING

Except as stated otherwise in the specification sections, perform sampling and testing required under this Contract.

1.11.1 Testing Laboratory Requirements

Provide an independent testing laboratory or establish a laboratory quali fied to perform sampling and tests required by this Contract. When the proposed testing laboratory is not accredited by an acceptable accreditation program as described by the paragraph entitled "Accredited Laboratories", submit to the Contracting Officer for approval, certified statements signed by an official of the testing laboratory attesting that the proposed laboratory meets or conforms to the following requirements:

a. Sampling and testing shall be under the technical direction of a Registered Professional Engineer (P.E) with at least 5 years of experience in construction material testing.

b. Laboratories engaged in testing of concrete and concrete aggregates shall meet the requirements of ASTM C 1077.

c. Laboratories engaged in testing of bituminous paving materials shall meet the requirements of ASTM D 3666.

d. Laboratories engaged in testing of soil and rock, as used in engineering design and construction, shall meet the requirements of ASTM D 3740.

e. Laboratories engaged in inspection and testing of steel, stainless steel, and related alloys will be evaluated according to ASTM A 880. Laboratories shall meet the requirements of ASTM E 329.

f. Laboratories engaged in nondestructive testing (NDT) shall meet the requirements of ASTM E 543.

g. Laboratories engaged in hazardous materials testing shall meet the requirements of OSHA and EPA.

1.11.2 Accredited Laboratories

Acceptable accreditation programs are the National Institute of Standards and Technology (NIST) National Voluntary Laboratory Accreditation Program (NVLAP), the American Association of State Highway and Transportation Officials (AASHTO) program and the American Association for Laboratory Accreditation (A2LA) program. Furnish to the Contracting Officer, a copy of the Certificate of Accreditation, Scope of Accreditation and latest directory of the accrediting organization for accredited laboratories. The scope of the laboratory's accreditation shall include the test methods required by the Contract.

1.11.3 Inspection of Testing Laboratories

Prior to approval of non-accredited laboratories, the proposed testing laboratory facilities and records shall be subject to inspection by the Contracting Officer. Records subject to inspection include equipment inventory, equipment calibration dates and procedures, library of test procedures, audit and inspection reports by agencies conducting laboratory evaluations and certifications, testing and management personnel qualifications, test report forms, and the internal QC procedures.

1.11.4 Capability Check

The Contracting Officer retains the right to check laboratory equipment in the proposed laboratory and the laboratory technician's testing procedures, techniques, and other items pertinent to testing, for compliance with the standards set forth in this Contract.

1.11.5 Test Results

Cite applicable Contract requirements, tests or analytical procedures used. Provide actual results and include a statement that the item tested or analyzed conforms or fails to conform to specified requirements. Conspicuously stamp the cover sheet for each report in large red letters "CONFORMS" or "DOES NOT CONFORM" to the specification requirements, whichever is applicable. Test results shall be signed by a testing laboratory representative authorized to sign certified test reports. Furnish the signed reports, certifications, and other documentation to the Contracting Officer via the QC Manager. Furnish a summary report of field tests at the end of each month. Attach a copy of the summary report to the last daily Contractor Quality Control Report of each month.

1.12 QC CERTIFICATIONS

1.12.1 Contractor Quality Control Report Certification

Each Contractor Quality Control Report shall contain the following statement: "On behalf of the Contractor, I certify that this report is complete and correct and equipment and material used and work performed during this reporting period is in compliance with the contract drawings and specifications to the best of my knowledge, except as noted in this report".

1.12.2 Invoice Certification

Furnish a certificate to the Contracting Officer with each payment request, signed by the QC Manager, attesting that as-built drawings are current and attesting that the work for which payment is requested, including stored material, is in compliance with contract requirements.

1.12.3 Completion Certification

Upon completion of work under this Contract, the QC Manager shall furnish a certificate to the Contracting Officer attesting that "the work has been completed, inspected, tested and is in compliance with the Contract".

1.13 DOCUMENTATION

Maintain current and complete records of on-site and off-site QC program operations and activities.

1.13.1 Contractor Production Report

Reports are required for each day that work is performed and shall be attached to the Contractor Quality Control Report prepared for the same day. Account for each calendar day throughout the life of the Contract. The reporting of work shall be identified by terminology consistent with the construction schedule. Contractor Production Reports are to be prepared, signed and dated by the project superintendent and shall contain the following information:

a. Date of report, report number, name of contractor, contract number, title and location of Contract and superintendent present.

b. Weather conditions in the morning and in the afternoon including maximum and minimum temperatures.

c. A list of Contractor and subcontractor personnel on the work site, their trades, employer, work location, description of work performed and hours worked.

e. A list of job safety actions taken and safety inspections conducted. Indicate that safety requirements have been met including the results on the following:

(1) Was a job safety meeting held this date? (If YES, attach a copy of the meeting minutes.)

(2) Were there any lost time accidents this date? (If YES, attach a copy of the completed OSHA report.)

(3) Was crane/manlift/trenching/scaffold/hv electrical/high work/hazmat work done? (If YES, attach a statement or checklist showing inspection performed.)

(4) Was hazardous material/waste released into the environment? (If YES, attach a description of incident and proposed action.)

f. A list of safety actions taken today and safety inspections conducted.

g. A list of equipment/material received each day that is

incorporated into the job.

h. A list of construction and plant equipment on the work site including the number of hours used, idle and down for repair.

i. Include a "remarks" section in this report which will contain pertinent information including directions received, problems encountered during construction, work progress and delays, conflicts or errors in the drawings or specifications, field changes, safety hazards encountered, instructions given and corrective actions taken, delays encountered and a record of visitors to the work site.

1.13.2 Contractor Quality Control Report

Reports are required for each day that work is performed and for every seven consecutive calendar days of no-work and on the last day of a no-work period. Account for each calendar day throughout the life of the Contract. The reporting of work shall be identified by terminology consistent with the construction schedule. Contractor Quality Control Reports are to be prepared, signed and dated by the QC Manager and shall contain the following information:

a. Identify the control phase and the definable feature of work.

b. Results of the Preparatory Phase meetings held including the location of the definable feature of work and a list of personnel present at the meeting. Indicate in the report that for this definable feature of work, the drawings and specifications have been reviewed, submittals have been approved, materials comply with approved submittals, materials are stored properly, preliminary work was done correctly, the testing plan has been reviewed, and work methods and schedule have been discussed.

c. Results of the Initial Phase meetings held including the location of the definable feature of work and a list of personnel present at the meeting. Indicate in the report that for this definable feature of work the preliminary work was done correctly, samples have been prepared and approved, the workmanship is satisfactory, test results are acceptable, work is in compliance with the Contract, and the required testing has been performed and include a list of who performed the tests.

d. Results of the Follow-up Phase inspections held including the location of the definable feature of work. Indicate in the report for this definable feature of work that the work complies with the Contract as approved in the Initial Phase, and that required testing has been performed and include a list of who performed the tests.

e. Results of the three phases of control for off-site work, if applicable, including actions taken.

f. List the rework items identified, but not corrected by close of business.

g. List the rework items corrected from the rework items list along with the corrective action taken.

h. Include a "remarks" section in this report which will contain pertinent information including directions received, quality control problem areas, deviations from the QC plan, construction deficiencies encountered, QC meetings held, acknowledgement that as-built drawings have been updated, corrective direction given by the QC Organization and corrective action taken by the Contractor.

i. Contractor Quality Control Report certification.

1.13.3 Testing Plan and Log

As tests are performed, the QC Manager shall record on the "Testing Plan and Log" the date the test was conducted, the date the test results were forwarded to the Contracting Officer, remarks and acknowledgement that an accredited or Contracting Officer approved testing laboratory was used. Attach a copy of the updated "Testing Plan and Log" to the last daily Contractor Quality Control Report of each month.

1.13.4 Rework Items List

The QC Manager shall maintain a list of work that does not comply with the Contract, identifying what items need to be reworked, the date the item was originally discovered, and the date the item was corrected. There is no requirement to report a rework item that is corrected the same day it is discovered. Attach a copy of the "Contractor Rework Items List" to the last daily Contractor Quality Control Report of each month. The Contractor shall be responsible for including on this list items needing rework including those identified by the Contracting Officer.

1.13.5 As-Built Drawings

The QC Manager is required to review the as-built drawings required by Section 01 11 00, "Summary of Work", to ensure that as-built drawings are kept current on a daily basis and marked to show deviations which have been made from the Contract drawings. The QC Manager shall initial each deviation and each revision. Upon completion of work, the QC Manager shall furnish a certificate attesting to the accuracy of the as-built drawings prior to submission to the Contracting Officer.

1.13.6 Report Forms

The following forms, which are attached at the end of this section, are acceptable for providing the information required by the paragraph entitled "Documentation". While use of these specific formats are not required, any other format used shall contain the same information:

a. Combined Contractor Production Report and Contractor Quality Control Report (1 sheet), with separate continuation sheet

b. Testing Plan and Log

c. Rework Items List

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

SECTION 01 50 00

TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
11/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C511	(2017) Reduced-Pressure Principle Backflow Prevention Assembly

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2014) Safety and Health Requirements Manual

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Traffic Control Plan - if Applicable

SD-03 Product Data

Backflow Preventers

SD-06 Test Reports

Backflow Preventer Tests

SD-07 Certificates

Backflow Tester Certification

Backflow Preventers Certificate of Full Approval

1.3 BACKFLOW PREVENTERS CERTIFICATE

Certificate of Full Approval from FCCCHR List, University of Southern California, attesting that the design, size and make of each backflow preventer has satisfactorily passed the complete sequence of performance testing and evaluation for the respective level of approval. Certificate of provisional Approval will not be acceptable.

1.3.1 Backflow Tester Certificate

Prior to testing, submit to the Contracting Officer certification issued by

the State or local regulatory agency attesting that the backflow tester has successfully completed a certification course sponsored by the regulatory agency. Tester must not be affiliated with a company participating in other phases of this Contract.

1.3.2 Backflow Prevention Training Certificate

Submit a certificate recognized by the State or local authority that states the Contractor has completed at least 10 hours of training in backflow preventer installations. The certificate must be current.

1.4 WEATHER PROTECTION

Take necessary precautions to ensure that roof openings and other critical openings in the building are monitored carefully. Take immediate actions required to seal off such openings when rain or other detrimental weather is imminent, and at the end of each workday. Ensure that the openings are completely sealed off to protect materials and equipment in the building from damage.

1.5 DOD CONDITION OF READINESS (COR)

DOD will set the Condition of Readiness (COR) based on the weather forecast for sustained winds 50 knots (60 mph) or greater. Contact the Contracting Officer for the current COR setting.

Monitor weather conditions a minimum of twice a day and take appropriate actions according to the approved Emergency Plan in the accepted Accident Prevention Plan, EM 385-1-1 Section 01 Emergency Planning and the instructions below.

Unless otherwise directed by the Contracting Officer, comply with:

a. Condition FOUR (Sustained winds of 58 mph or greater expected within 72 hours): Normal daily jobsite cleanup and good housekeeping practices. Collect and store in piles or containers scrap lumber, waste material, and rubbish for removal and disposal at the close of each work day. Maintain the construction site including storage areas, free of accumulation of debris. Stack form lumber in neat piles less than 3.3 feet high. Remove all debris, trash, or objects that could become missile hazards. Review requirements pertaining to "Condition THREE" and continue action as necessary to attain "Condition FOUR" readiness. Contact Contracting Officer for weather and COR updates and completion of required actions.

b. Condition THREE (Sustained winds of 58 mph or greater expected within 48 hours): Maintain "Condition FOUR" requirements and commence securing operations necessary for "Condition ONE" which cannot be completed within 18 hours. Cease all routine activities which might interfere with securing operations. Commence securing and stow all gear and portable equipment. Make preparations for securing buildings. Reinforce or remove formwork and scaffolding. Secure machinery, tools, equipment, materials, or remove from the jobsite. Expend every effort to clear all missile hazards and loose equipment from general base areas. Contact Contracting Officer for weather and COR updates and completion of required actions. Review requirements pertaining to "Condition TWO" and continue action as necessary to attain "Condition THREE" readiness.

c. Condition TWO (Sustained winds of 58 mph or greater expected within 24 hours): Secure the jobsite, and leave Government premises.

d. Condition ONE. (Sustained winds of 58 mph or greater expected within 12 hours): Contractor access to the jobsite and Government premises is prohibited.

1.6 TRAILERS OR STORAGE BUILDINGS

Trailers or storage buildings will be permitted, where space is available, subject to the approval of hte Contracting Officer. The trailer or building shall be in good condition, free from visible damage, rust, and deterioration, and meet all applicable safety requirements. Trilers shall be roadworthy and comply with all appropriate State and local vehicle requirements. Failure to maintain storage trailers or buildings to these standards shall result in the removal of non-complying units at the Contractor's expense. A sign not smaller than 24 by 24 inches shall be conspicuously placed on the trailer depicting the company name, business phone number, and emergency phone number. Trailers shall be anchored to resist high winds and must meet applicable state and local standards for anchoring mobile trailers.

1.7 STORAGE AREAS

The Contract Clause entitled "FAR 52.236-10, Operations and Storage Areas" applies.

PART 2 PRODUCTS

2.1 BACKFLOW PREVENTERS

Reduced pressure principle type conforming to the applicable requirements AWWA C511.

PART 3 EXECUTION

3.1 EMPLOYEE PARKING

Construction Contract employees must park privately owned vehicles in an area designated by the Contracting Officer. Employee parking must not interfere with existing and established parking requirements of the Government installation.

3.2 AVAILABILITY AND USE OF UTILITY SERVICES

3.2.1 Temporary Utilities

a. The Contract clause related to utilities applies. Reasonable amounts of water and electricity from the nearest outlet will be provided free of charge for pursuance of work within a facility under this contract. If the nearest available outlet cannot be utilized by the Contractor because of improper voltage, insufficient current, improper pressure, incompatible connectors, etc., it shall be the responsibility of the Contractor to provide temporary utilities as required.

b. Reasonable amounts of utilities for contractor trailers and storage buildings will be made available to the Contractor, when available. The Contractor shall be responsible for providing transformers, electrical service poles and drops for electrical services, and backflow preventer

devices on connections to domestic water lines. Final taps and tie-ins to the Government utility grid will be made by the Contractor after approval by the Contracting Officer. Tap-in cost, if any, shall be the responsibility of the Contractor. Under no circumstances will taps to base fire hydrants be allowed for obtaining domestic water.

3.2.2 Energy and Utilites Conservation

The Contractor shall carefully conserve utilities furnished without charge. The Contractor, at his own expense and in a manner satisfactory to the Contracting Officer, shall install and maintain all necessary temporary connections and distribution lines and remove the same prior to final acceptance of the construction.

3.2.3 Location of Underground Utilites

Location and Protection of underground utilities shall be the responsibility of the Contractor. Where existing-to-remain piping, utilities, and underground obstructions of any type are indicted in locations to be traversed by new piping, ducts, and other excavations the elevations of the existing utilities and obstructions shall be determined before the new work is completed.

a. In addition, the Contractor will be responsible for obtaining the services of a professional utility locator prior to digging. Contractor will provide documentation that the site has been surveyed and checked for underground utilities. All utilities must be located, including but not limited to power, water, sewer, storm drains, fiber optics, T.V. cable, telephone, and intrusion detection wiring. A set of known utility drawings will be available in the ROICC office for review to assist the locator.

b. It is mandatory that the Contractor also contact the Base Telephone Office (451-2531) prior to accomplishing any digging at Camp Lejeune. A telephone office representative will assist in locating telephone lines.

c. It is mandatory that the Contractor also contact Charter Communications, cable TV service prior to accomplishing any digging at Camp Lejeune, to ensure that all buried cable lines are identified. Contact Mr. Olin Criswell at 353-8677 for assistance.

d. It is mandatory that the contractor also contact the North Carolina One-Call Center to coordinate the location of underground natural gas infrastructure. North Carolina 811, Inc. can be reached at 811 on a touch-tone phone in the state of North Carolina or toll-free at 1.800.632.4949 if calling from out of state

3.2.4 Damage to Underground Utilities

Immediate notice shall be delivered to the Contracting Officer of any damage. The Contractor shall make temporary repairs immediately, and shall provide permanent repairs as soon as practicable. For any additional work required by reason of conflict between the new and existing work, an adjustment in contract price will be made in accordance with Contract clause entitled "Differing Site Conditions", if appropriate.

3.2.5 Sanitation

Provide adequate sanitary conveniences of a type approved for the use of persons employed on the work, properly secluded from public observation, and

maintained in such a manner as required and approved by the Contracting Officer. Maintain these conveniences at all times without nuisance. Upon completion of the work, remove the conveniences from the premises, leaving the premises clean and free from nuisance. Dispose of sewage through connection to a municipal, district, or station sanitary sewage system. Where such systems are not available, use chemical toilets or comparably effective units, and periodically empty wastes into a municipal, district, or station sanitary sewage system, or remove waste to a commercial facility. Include provisions for pest control and elimination of odors.

3.3 STATION OPERATION AFFECT ON CONTRACTOR OPERATIONS

3.3.1 Restricted Access Areas

Follow guidelines identified on drawings and in scope of work.

3.4 TRAFFIC PROVISIONS

3.4.1 Maintenance of Traffic

If during the performance of work, it becomes necessary to modify vehicular traffic patterns at any locations, notify the Contracting Officer at least 15 calendar days prior to the proposed modification date, and provide a Traffic Control Plan detailing the proposed controls to traffic movement for approval. The plans shall be in accordance with State and local regulations and the MUTCD, Part VI. MAke all notifications and obtain any permits required for modification to traffic movements outside Station'a jurisdiction. Provide cones, signs, barricades, lights, or other traffic control devices and personnel required to control traffic.

3.4.2 Dust Control

Dust control methods and procedures must be approved by the Contracting Officer. Coordinate dust control methods with 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS.

3.5 REDUCED PRESSURE BACKFLOW PREVENTERS

Provide an approved reduced pressure backflow prevention assembly at each location where the Contractor taps into the Government potable water supply.

Perform backflow preventer tests using test equipment, procedures, and certification forms conforming to those outlined in the latest edition of the Manual of Cross-Connection Control published by the FCCCHR Manual. Test and tag each reduced pressure backflow preventer upon initial installation (prior to continued water use). Tag must contain the following information: make, model, serial number, dates of tests, results, maintenance performed, and signature of tester. Record test results on certification forms conforming to requirements cited earlier in this paragraph.

3.6 DUMPSTERS

Equip dumpsters with a secure cover and paint the standard installation color. Keep dumpster closed, except when being loaded with trash and debris. Empty site dumpsters at least once a week, or as needed to keep the site free of debris and trash. If necessary, provide 55 gallon trash containers painted the darker installation color to collect debris in the construction site area. For large demolitions, large dumpsters without

lids are acceptable, but must not have debris higher than the sides before emptying.

3.7 CLEANUP

Remove construction debris, waste materials, packaging material and the like from the work site daily. Any dirt or mud which is tracked onto paved or surfaced roadways must be cleaned away. Store all salvageable materials resulting from demolition activities within the fenced area described above or at the supplemental storage area. Neatly stack stored materials not in trailers, whether new or salvaged.

3.8 RESTORATION OF STORAGE AREA

Upon completion of the project remove the bulletin board, signs, barricades, haul roads, and all other temporary products from the site. After removal of trailers, materials, and equipment from within the fenced area, remove the fence. Restore areas used during the performance of the Contract to the original or better condition. Remove gravel used to traverse grassed areas and restore the area to its original condition, including top soil and seeding as necessary.

-- End of Section --

SECTION 01 57 19

TEMPORARY ENVIRONMENTAL CONTROLS

05/12

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-S-16165	(Rev E) Shielding Harnesses, Shielding Items and Shielding Enclosures for Use in the Reduction of Interference from Engine Electrical Systems
MIL-STD-461	(2015; Rev G) Requirements for the Control of Electromagnetic Interference Characteristics of Subsystems and Equipment
MIL-STD-462	(Rev D; Notice 4) Electromagnetic Interference Characteristics

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910	Occupational Safety and Health Standards
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Generators of Hazardous Waste
40 CFR 263	Transporters of Hazardous Waste
40 CFR 264	Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 265	Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 300	National Oil and Hazardous Substances Pollution Contingency Plan
49 CFR 171	General Information, Regulations, and Definitions
49 CFR 172	Hazardous Materials Tables and Hazardous Materials Communications Regulations

49 CFR 178 Shipping Container Specification

1.2 Contractor Liabilities for Environmental Protection

Contractors shall complete and provide environmental training documentation for training required by Federal, State, and local regulations.

1.3 DEFINITIONS

1.3.1 Sediment

Soil and other debris that have eroded and have been transported by runoff water or wind.

1.3.2 Solid Waste

Rubbish, debris, garbage, and other discarded solid materials, except recyclables and hazardous waste as defined in paragraph entitled "Hazardous Waste," resulting from industrial, commercial, and agricultural operations and from community activities.

1.3.3 Sanitary Wastes

Wastes characterized as domestic sanitary sewage.

1.3.4 Rubbish

Combustible and noncombustible wastes such as non-recyclable paper and cardboard, crockery, and bones.

Recyclables includes: clean paper, cardboard, glass, plastics (No. 1 & 2), metal, and cans.

Non-recyclable paper and cardboard are defined as material that has become wet or contaminated with food or other residue that render it un-acceptable for recycling.

Treated wood/lumber is defined as wood that has been stained or treated to prevent rot, or composite wood products such as OSB, pressboard furniture, etc.

Untreated wood is defined as lumber, trees, stumps, limbs, tops, and shrubs.

1.3.5 Debris

Combustible and noncombustible wastes such as ashes and waste materials resulting from construction or maintenance and repair work, (excluding organic matter) leaves, pine straw, grass and shrub clippings.

1.3.6 Chemical Wastes

This includes salts, acids, alkalies, herbicides, pesticides, and organic chemicals.

1.3.7 Garbage

Refuse and scraps resulting from preparation, cooking, dispensing, and consumption of food.

1.3.8 Hazardous Waste

Hazardous substances as defined in 40 CFR 261 or as defined by applicable State and local regulations.

1.3.9 Hazardous Materials

Hazardous materials as defined in 49 CFR 171 and listed in 49 CFR 172.

1.3.10 Landscape Features

Trees, plants, shrubs, and ground cover.

1.3.11 Lead Acid Battery Electrolyte

The electrolyte substance (liquid medium) within a battery cell.

1.3.12 Oily Waste

Petroleum products and bituminous materials.

1.3.13 Class I Ozone Depleting Substance (ODS)

Class I and Class II ODS are defined in Sections 602 (a and b) of The Clean Air Act.

1.4 SUBMITTALS

Submit the following in accordance with Section 01 33 00, "Submittal Procedures."

Environmental protection plan

SD-06 Test Reports

Abrasive blasting

waste materials - if applicable

Submit a copy of an approved laboratory analysis of materials collected as a result from abrasive blasting operations before disposing of waste materials.

SD-11 Closeout Submittals

Solid waste disposal permit

Disposal permit for hazardous waste

Environmental training documentation

Permit to transport hazardous waste

Hazardous waste certification

Environmental Plan Review

Annual Report of Products Containing Recovered Materials

1.4.1 Solid Waste Disposal Permit

Submit one copy of a State permit or license for the solid waste disposal facility. If the contract permists the use of the Base Landfill, request a letter from the Contracting Offcier authorizing permission to dump on base; submit the letter to the Base Landfill Office. In lieu of the letter a copy of the contract must be delivered to the Landfill Office for review.

1.4.2 Disposal Permit for Hazardous Waste

Submit a copy of the applicable EPA and State permits, manifests, or licenses for transportation, treatment, storage, and disposal of hazardous waste by permitted facilities.

1.4.3 Permit to Transport Hazardous Waste

Submit one copy of the EPA or State permit license, or regulation for the transporter who will ship the hazardous waste to the permitted Treatment, Storage, and Disposal (TSD) facility.

1.4.4 Hazardous Waste Certification

Submit written certification that hazardous waste turned in for disposal was generated on Government property and is identified, packaged, and labeled in accordance with 40 CFR 261, 40 CFR 262, and 40 CFR 263.

1.5 ENVIRONMENTAL PROTECTION REGULATORY REQUIREMENTS

Provide and maintain, during the life of the contract, environmental protection as defined in this Section. Plan for and provide environmental protective measures to control pollution that develops during normal construction practice. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Comply with Federal, State, and local regulations pertaining to the environment, including but not limited to water, air, solid waste, and noise pollution.

1.6 ENVIRONMENTAL PROTECTION PLAN

1.6.1 Contents of Environmental protection plan

a. Include any hazardous materials (HM) planned for use on the station shall be included in the station HM Tracking Program maintained by the Safety Department. To assist this effort, submit a list (including quantities) of HM to be brought to the station and copies of the corresponding material safety data sheets (MSDS). Submit this list to the Contracting Officer. At project completion, remove any hazardous material brought onto the station. Account for the quantity of HM brought to the station, the quantity used or expended during the job, and the leftover quantity which (1) may have additional useful life as a HM and shall be removed by the Contractor, or (2) may be a hazardous waste, which shall then be removed as specified herein.

b. The Environmental Protection Plan shall list and quantify any

Hazardous Waste (HW) to be generated during the project.

c. In accordance with station regulations, store HW near the point of generation up to a total quantity of one quart of hazardous waste or 55 gallons of hazardous waste. Move any volume exceeding these quantities to a HW permitted area within 3 days. Prior to generation of HW, contact Contracting Officer for labeling requirements for storage of hazardous wastes.

d. In accordance with station regulations, substitute materials as necessary to reduce the generation of HW and include a statement to that effect in the Environmental Plan.

e. Contact Contracting Officer for conditions in the area of the project which may be subject to special environmental procedures. Include this information in the Preconstruction Survey. Describe in the Environmental Protection Plan any permits required prior to working the area, and contingency plans in case an unexpected environmental condition is discovered.

f. Obtain permits for handling HW, and deliver completed documents to Contracting Officer for review. File the documents with the appropriate agency, and complete disposal with the approval of Contracting Officer. Deliver correspondence with the State concerning the environmental permits and completed permits to Contracting Officer.

1.6.2 Environmental Protection Plan Format

The Environmental Protection Plan shall follow the following format:

ENVIRONMENTAL PROTECTION PLAN

Contractor Organization
Address and Phone Numbers

1. Hazardous materials to be brought onto the station
2. MSDS package
3. Employee training documentation
4. HW storage plan
5. HW to be generated
6. Preconstruction survey results
7. Permitting requirements identified

1.6.3 Environmental Plan Review

Fourteen days after the environmental protection meeting, submit the proposed environmental plan for further discussion, review, and approval.

1.7 ADMINISTRATIVE REQUIREMENTS

1.7.1 Licenses and Permits

Obtain licenses and permits pursuant to "FAR 52.236-7, Permits and Responsibilities" .

For permits obtained by the Contracting Officer, whether or not required by the permit, perform inspections of the work in progress, and submit

certifications to the applicable regulatory agency, via the Contracting Officer, that the work conforms to the contract and permit requirements. The inspections and certifications shall be provided through the services of a Professional Engineer, registered in the State where the work is being performed. As a part of the quality control plan, which is required to be submitted for approval by the quality control section, provide a subitem containing the name, P.E. registration number, address, and telephone number of the professional engineer(s) who will be performing the inspections and certifications for each permit listed above.

1.8 GENERAL ENVIRONMENTAL MANAGEMENT SYSTEM AND ENVIRONMENTAL AWARENESS

The Contractor shall familiarize himself with requirements of the attached "Marine Corps Base (MCB), Camp Lejeune, Contractor Environmental Guide."

1.9 CAMP LEJEUNE SANITARY LANDFILL INFORMATION SHEET

1. Contractors may ONLY use the Camp Lejeune Sanitary Landfill for the disposal of asbestos containing materials, building products with tightly adhered lead containing paint, non-contaminated clean dirt and clean gravel. The hours of operation are 0730-1530.

2. Delivery of acceptable materials (identified above) shall be by appointment only. Appointments made by phone at 910-451-5011 or 910- 451-2946. ALL other contractor generated material shall be weighed through the Base Landfill scales before being removed from the Base. Contractors utilizing the base scales will require Contracting Officer assisted pre-registration with the Landfill Manager.

3. The Contracting Officer will register the contract via E-mail, withthe bse landfill. All haul vehicles will maintain a secure vehicle placard as a condition to utilize the scale. E-mail the contract information to the Landfill Clerk, including the name on the Prime Contractor, contract number, job name/description, completion date and whether or not any of the above materials will be delivered to the Landfill.

4. As of May 01 2014 the above supersedes any other statements/specifications pertaining to the delivery of materials to the Base Landfill.

PART 2 PRODUCTS

2.1 ANNUAL REPORT OF PRODUCTS CONTAINING RECOVERED MATERIALS

The Contractor shall submit data annually (by December 1) products used during the previous fiscal year (October 1 - September 30) as required by 6002 of the Solid Waste Disposal Act as amended by Resource Conservation and Recovery Act (RCRA). Report forms is attached to end of this section as "Appendix A."

PART 3 EXECUTION

3.1 PROTECTION OF NATURAL RESOURCES

Preserve the natural resources within the project boundaries and outside the limits of permanent work. Restore to an equivalent or improved condition upon completion of work. Confine construction activities to

within the limits of the work indicated or specified. Conform to the state permitting requirements of the Clean Water Act.

3.1.1 Land Resources

Except in areas to be cleared, do not remove, cut, deface, injure, or destroy trees or shrubs without Contracting Officer's permission. Do not fasten or attach ropes, cables, or guys to existing nearby trees for anchorages unless authorized by Contracting Officer. Where such use of attach ropes, cables, or guys is authorized, the Contractor shall be responsible for any resultant damage.

3.1.1.1 Protection of Trees

Protect existing trees which are to remain and which may be injured, bruised, defaced, or otherwise damaged by construction operations. Remove displaced rocks from uncleared areas. By approved excavation, remove trees with 30 percent or more of their root systems destroyed. Removal of trees and the procedure for removal requires approval of the Contracting Officer.

3.1.1.2 Landscape Replacement

Remove trees and other landscape features scarred or damaged by equipment operations, and replace with equivalent, undamaged trees and landscape features. Obtain Contracting Officer's approval before removal or replacement.

3.1.1.3 Temporary Construction

Remove traces of temporary construction facilities such as haul roads, work area, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other signs of construction. Grade temporary roads, parking areas, and similar temporarily used areas to conform with surrounding contours.

3.1.2 Water Resources

3.1.2.1 Stream Crossings

The Contracting Officer's approval is required before any equipment will be permitted to ford live streams.

3.1.2.2 Oily Wastes

Prevent oily or other hazardous substances from entering the ground, drainage areas, or local bodies of water. Surround all temporary fuel oil or petroleum storage tanks with a temporary earth berm of sufficient size and strength to contain the contents of the tanks in the event of leakage or spillage.

3.1.3 Fish and Wildlife Resources

Do not disturb fish and wildlife. Do not alter water flows or otherwise significantly disturb the native habitat adjacent to the project and critical to the survival of fish and wildlife, except as indicated or specified.

3.2 HISTORICAL AND ARCHAEOLOGICAL RESOURCES

Carefully protect in-place and report immediately to the Contracting

Officer historical and archaeological items or human skeletal remains discovered in the course of work. Stop work in the immediate area of the discovery until directed by the Contracting Officer to resume work. The Government retains ownership and control over historical and archaeological resources.

3.3 NOISE

Make the maximum use of low-noise emission products, as certified by the EPA. Blasting or use of explosives will not be permitted without written permission from the Contracting Officer, and then only during designated times.

3.4 RESTRICTIONS ON EQUIPMENT

3.4.1 Electromagnetic Interference Suppression

a. Electric motors must comply with MIL-STD-461 relative to radiated and conducted electromagnetic interference. A test for electromagnetic interference will not be required for motors that are identical physically and electrically to those that have previously met the requirements of MIL-STD-461. An electromagnetic interference suppression test will not be required for electric motors without commutation or sliprings having no more than one starting contact and operated at 3,600 revolutions per minute or less.

b. Equipment used by the Contractor shall comply with MIL-S-16165for internal combustion engines and MIL-STD-461 for other devices capable of producing radiated or conducted interference.

c. Conduct tests for electromagnetic interference on electric motors and Contractor's construction equipment in accordance with MIL-STD-461 and MIL-STD-462. Test location shall be reasonably free from radiated and conducted interference. Furnish testing equipment, instruments, and personnel for making the tests; a test location; and other necessary facilities.

3.4.2 Radio Transmitter Restrictions

Conform to the restrictions and procedures for the use of radio transmitting equipment, as directed. Do not use transmitters without prior approval.

3.5 CONTROL AND DISPOSAL OF SOLID WASTES

Pick up and separate solid wastes, and place in covered containers which are regularly emptied. Do not prepare or cook food on the project site. Prevent contamination of the site or other areas when handling and disposing of wastes. At project completion, leave the areas clean.

3.5.1 Disposal of Metal Paint Cans

All metal paint cans shall be taken to Building 962 for recycling. The cans shall be empty and completely dry. The cans shall be triple rinsed and stenciled "Triple Rinsed" prior to turn in. The Contractor shall give the Government 72 hours advance notice prior to turn-in. Contractor is responsible for rinsing, stenciling, crushing, and deposting in Government owned receptable, located at Building 962.

3.5.2 Disposal of Rubbish and Debris, MEtal and Dirt

Rubbish and debris shall be taken off-base for disposal, unless specifically directed otherwise below:

Metals shall be taken to the DRMO disposal area at Lot 203, as specified.

CATEGORY	CONSTRUCTION DEBRIS DISPOSAL - BASE SANITARY LANDFILL EXAMPLE/GENERAL INFORMATION FOR DEPOSIT IN THE LANDFILL
Recyclable Cardboard	Breakdown corrugated cardboard boxes and deliver to the Base Recycling Center located at Building 982. If base personnel rejects the cardboard, take cardboard for off-base disposal.
Recyclable Wood Pallets	Deliver usable pallets to the Base Recycling Center located at Building 982. If base personnel rejects the pellets, take pallets for off-base disposal.
Organic Matter	Organic matter will not be accepted at the landfill.
*****	Weigh each and every vehicle delivering debris upon entrance and exit. Cover debris.
Metals	Metals will not be accepted at the landfill. Remove metals from each and every category before delivery to landfill. (Example: Remove hardware from doors and windows.) Dispose of metal construction debris at Defense Reutilization Maintenance Office (DRMO). Aluminum, brass, copper, lead, other metal, electrical wiring, cable (cut in 3 foot or less sections)
Treated & Untreated Wood/Lumber	Treated & untreated wood/lumber will not be accepted at the landfill.
Concrete	Concrete will not be accepted at the landfill.
Construction Material	Construction material should be managed and placed in a designated area. Area shall be kept clean of debris and all material removed at the end of the project.
Solid Waste	Separate each category of solid waste to enhance recycling.
Hazardous Material	This project involves demolition, renovation/repair and/or construction activities; therefore, hazardous material (such as paints, solvents, thinners, adhesives, etc) may be used during the execution of this project. The contractor

CATEGORY	CONSTRUCTION DEBRIS DISPOSAL - BASE SANITARY LANDFILL EXAMPLE/GENERAL INFORMATION FOR DEPOSIT IN THE LANDFILL
	will be required to appropriately manage the hazardous material and provide secondary containment.
Solid Waste Report	All solid waste generated and recycled will be weighed. Contractor will report the amount of solid wasted disposed and recycled at the end of the project to EMD's Solid Waste Manager or the Pollution Prevention Manager via the OICC. Tonnage information for all materials delivered to the Base Landfill is available at the Landfill Office. Submit a written request to the Landfill Manager, specifying the desired information.
Recycling of Construction Debris	Recyclable material (ex. Scrap metal/aluminum/brass/copper/lead, and other metal) may be recycled through Defense Utilization Maintenance Office) DRMO using a 1348-1a with the following information (Proceeds for the sale of recyclable material are to go to the Qualified Recycling financial account - 17F3875 27RM 00767001 0 000027 3c 000000 06700198004). For additional information contact the Base Recycling Coordinator 910-451-4214.
Electrical Equipment	Before demolition or removal of electrical equipment from the Base - Contractor shall contact Base High Voltage Shop Supervisor at (910) 451-2790, to allow for first right of refusal of electrical equipment such as: ATS, transformers, and generators. Electrical equipment will not be accepted at landfill.

3.5.3 Disposal Off-Base

a. Provide 24-hour advance written notice to the Contracting Office of Contractor's intention to dispose of off base.

b. Disposal at sites or landfills not holding a valid State of North Carolina permit is specifically prohibited. The prohibition also applies to sites where a permit may have been applied for but not yet obtained.

c. Off-base disposal of construction debris outside the parameters of this paragraph at site without State permits and/or not in accordance with regulatory requirements shall require the Contractor at his own expense to remove, transport and relocate the debris to a State approved site. The Contractor shall also be required to pay any fines, penalties, or fees related to the illegal disposal of construction debris

3.6 CONTROL AND DISPOSAL OF HAZARDOUS WASTE

3.6.1 Hazardous Waste Generation

Handle generated hazardous waste in accordance with 40 CFR 262.

3.6.2 Hazardous Waste Disposal

Dispose of hazardous waste in accordance with Federal, State, and local regulations, especially 40 CFR 263, 40 CFR 264, and 40 CFR 265. Removal of hazardous waste from Government property shall not occur without prior notification and coordination with the Contracting officer. Transport hazardous waste by a permitted, licensed, or registered hazardous waste transported to a TSD facility. Hazardous waste shall be properly identified, packaged, and labeled in accordance with 49 CFR 172. Provide completed manifest for hazardous waste disposed of off-site to the Contracting Officer within 7 days of disposal. Hazardous waste shall not be brought onto the station.

3.6.3 Hazardous Waste Storage

Store hazardous waste in containers in accordance with 49 CFR 178. Identify hazardous waste in accordance with 40 CFR 261 and 40 CFR 262. Identify hazardous waste generated within the confines of the station by the station's EPA generator identification number.

3.6.4 Spills of Oil and Hazardous Materials

Take precautions to prevent spills of oil and hazardous material. In the event of a spill, immediately notify the Contracting Officer. Spill response shall be in accordance with 40 CFR 300 and applicable State regulations.

3.6.5 Lead-Acid Batteries

Dispose of lead-acid batteries that are not damaged or leaking at a State-approved battery recycle or at a permitted or interim status

hazardous waste TSD facility. For lead-acid batteries that are leaking or have cracked casings, dispose of the electrolyte solution using one of the following alternatives:

a. An industrial waste water treatment plant, if available and approved by the Contracting Officer for disposing of lead-acid battery electrolyte.

b. Dispose of the lead-acid battery electrolyte at a permitted or interim status hazardous waste TSD facility.

The management and disposal of waste lead-acid batteries and electrolyte shall comply with requirements for management and disposal of hazardous wastes.

3.6.6 Mercury Control

Prior to starting work, remove thermostats, switches, and other components that contain mercury. Upon removal, place items containing mercury in doubled polyethylene bags, label, and turn over to the Contracting Officer for disposal.

3.6.7 Petroleum Products

Protect against spills and evaporation during fueling and lubrication of equipment and motor vehicles. Dispose of lubricants to be discarded and excess oil.

3.7 DUST CONTROL

Keep dust down at all times, including nonworking periods. Sprinkle or treat, with dust suppressants, the soil at the site, haul roads, and other areas disturbed by operations. Dry power brooming will not be permitted. Instead, use vacuuming, wet mopping, wet sweeping, or wet power brooming. Air blowing will be permitted only for cleaning nonparticulate debris such as steel reinforcing bars. Only wet cutting will be permitted for cutting concrete blocks, concrete, and bituminous concrete. Do not shake bags of cement, concrete mortar, or plaster unnecessarily.

3.7.1 Abrasive Blasting

3.7.1.1 Blasting Operations

The use of silica sand is prohibited in abrasive blasting.

Provide tarpaulin drop cloths and windscreens to enclose abrasive blasting operations to confine and collect dust, abrasive agent, paint chips, and other debris in accordance with the requirements specified. Perform work involving removal of hazardous material in accordance with 29 CFR 1910.

3.7.1.2 Disposal Requirements

Collect dust, abrasive, paint, and other debris resulting from abrasive blasting operations and store in 55 gallon drums with watertight lids. Take a representative sample of this material, and test for EP toxicity with respect to lead, chromium, and cadmium content. The sampling and testing shall be performed in accordance with 40 CFR 261. Handle debris resulting from the abrasive blasting operations as a hazardous material, and dispose of in accordance with 40 CFR 262, 40 CFR 263, 40 CFR 264, and

40 CFR 265. Transport hazardous material by a transporter licensed and permitted for transportation of hazardous materials. Dispose of hazardous material in an EPA-approved and permitted facility specifically designated for hazardous waste disposal.

3.8 QUARANTINE FOR IMPORTED FIRE ANT (4/82)

Onslow, Jones, and Cartaret Counties and portions of Duplin and Craven Counties have been declared a generally infested area by the United States Department of Agriculture (USDA) for the imported fire ant. Compliance with the quarantine regulations established by this authority as set forth in USDA Publication 301.81 of 31 December 1992, is required for operations hereunder. Pertinent requirements of the quarantine for materials originating on the Camp Lejeune reservation, the Marine Corps Air Station (Helicopter), New River and the Marine Corps Air Station, Cherry Point, which are to be transported outside Onslow County or adjacent suppression areas, include the following:

a. Certification is required for the following articles and they shall not be moved from the reservation to any point outside Onslow County and adjacent designated areas unless accompanied by a valid inspection certificate issued by an Officer of the Plant Protection and Quarantine Program (PPQ) of the U.S. Department of Agriculture.

(1) Bulk soil

(2) Used mechanized soil-moving equipment. (Used mechanized soil-moving equipment is exempt if cleaned of loose noncompacted soil).

(3) Other products, articles, or means of conveyances, if it is determined by an inspector that they present a hazard of transporting spread of the imported fire ant and the person in possession thereof has been so notified.

b. Authorization for movement of equipment outside the imported fire and regulated area shall be obtained from USDA, Animal and Plant Health Inspection Service (APHIS), Plant Protection and Quarantine (PPQ), Box 28, Goldsboro, North Carolina, 27533-0028, Attn: Mr. William Scroggins or Mr. Frank Best, telephone (919) 735-1941. If Mr. Scroggins or Mr. Best are not available, contact Mr. Jim Kelley at (910) 815-4667, the supervisor's office in Wilmington. Requests for inspection shall be made sufficiently in advance of the date of movement to permit arrangements for the services of authorized inspectors. The equipment shall be prepared and assembled so that it may be readily inspected. Soil on or attached to equipment, supplies, and materials shall be removed by washing with water or such other means as necessary to accomplish complete removal. Resulting spoil shall be wasted as necessary and as directed.

ANNUAL REPORT OF PRODUCTS CONTAINING RECOVERED MATERIALS

Contractor shall submit data annually (By 1 December) for the following products used during the previous fiscal year (1 October - 30 September) as required by 6002 of the Solid Waste Disposal Act as ammended by Resource Conservation and Recovery Act (RCRA):

Contract Number: _____ Fiscal Year: _____

MATERIAL	UNIT	QUANTITY (CRM)	TOTAL QUANTITY
A. Insulation			
1. Loose fill	Ft3		
2. Blanket or batt	Ft2		
3. Board	Ft2		
4. Spray-in-place	m3		
5. Other			
B. Cement and Concrete	yd3		
C. Paper and Paper Products			
1. Copy Paper	Box		
2. Printing/Writing Paper	Box		
3. Corrugated and fiberboard boxes	Box		
4. Folding boxboard and cartons	Box		
5. Stationary, office papers, envelopes, and computer paper	$Amt		
6. Toilet tissue, paper towels, fasial tissue, paper napkins, doilies and industrial wipes	$Amt		
7. Brown papers and coarse papers	Box		
8. Other			

APPENDIX A

MATERIAL	DEFINITION
1. Quantity (CRM)	Quantity used containing recovered materials.
2. Total Quantity	Quantity used containing recovered materials plus quantity used not containing recovered materials.
3. Unit	Ft3 (cubic feet), Ft2 (square feet), m3 (cubic meters), yd3 (cubic yards), box (number of boxes used), $ Amt (dollar value of material used)
4. Loose-Fill Insulation	Includes, but is not limited to..."cellulose fiber, mineral fibers (fiberglass and rock wool), vermiculite, and perlite.
5. Blanket or Batt Insulation	Includes, but is not limited to... "mineral fibers (fiberglass and rock wool)."
6. Board Insulation	This category refers to sheathing, roof decking, and wood panel insulation. It includes, but is not limited to... "cellulose fiber fiberboard, perlite composite board, polyurethane, polyisocyanurate, polystyrene, phenolics, and composites."
7. Spray-in-place Insulation	Includes, but is not limited to... "foam-in-place polyurethane and polyisocyanurate, and spray-on cellulose."
8. Cement or Concrete Containing Recovered Materials, Cement, or Concrete Containing Fly Ash	
9. Copy Paper	This item refers to... "any grade of paper suitable for copying by the xerographic method."
10. Printing & Writing Paper	This item refers to... "paper designed for printing, other than newsprint, such as offset or book paper," and... "paper suitable for pen and ink, pencil, typewriter or printing."

APPENDIX A

MATERIAL	DEFINITION
11. Corrugated & Fiberboard Boxes	Corrugated boxes refer to... "boxes made of corrugated paperboard, which, in turn, is made from a fluted corrugating medium pasted to two flat sheets of paperboard (linerboard)." Fiber or fiberboard boxes refer to... "boxes made from containerboard, either solid fiber or corrugated paperboard (general term); or boxes made from solid paperboard of the same material throughout."
12. Folding Boxes and Cartons	This item refers to... "a paperboard suitable for the manufacture of folding cartons."
13. Stationery, Office Papers, Envelopes, and Manifold Business Forms	This item is considered self-explanatory, however, if questions arise refer to 40 CFR 250.4 for definitions of any of these items.
14. Toilet Tissue, Paper Towels, Facial Tissue, Paper Napkins, Doilies, and Industrial Wipes	This item is considered self-explanatory, however, if questions arise refer to 40 CFR 250.4 for definitions of any of these items.
15. Brown Papers, and Coarse Papers	Brown papers refer to... "papers usually made from unbleached kraft pulp and used for bags, sacks, wrapping paper, and so forth." Coarse papers refer to... "papers used for industrial purposes, as distinguished from those used for cultural or sanitary purposes."
16. Other	Any other type of paper not included in any of the above categories.

APPENDIX A

-- End of Section --

SECTION 01 78 00

CLOSEOUT PROCEDURES

05/13

PART 1 GENERAL

1.1 SUBMITTALS

Submit the following in accordance with Section 01 33 00, "Submittal Procedures."

SD-10, Operation and Maintenance Data

Equipment/product warranty list

Submit Data Package 1 in accordance with Section 01 78 23, "Operation and Maintenance Data."

SD-11 Closeout Submittals

Final Payroll

Sales Tax Report

As-built drawings

Record of materials

Maximo requirements

Complete Submittal Package 2 CD/DVD's

Equipment/product warranty tag

1.2 PROJECT RECORD DOCUMENTS

As-Built Drawings will be submitted as specified in 1.2.1 along with GIS Deliverables which will be created and submitted as specified in Section 01 78 30.00 22, GIS DATA DELIVERABLES.

1.2.1 As-Built Drawings

"FAC 5252.236-9310, Record Drawings." As-built drawings will be submitted in redline mark-up format.

1.2.2 As-Built Record of Materials

Furnish a record of materials.

Where several manufacturers' brands, types, or classes of the item listed have been used in the project, designate specific areas where each item was used. Designations shall be keyed to the areas and spaces depicted on the

contract drawing. Furnish the record of materials used in the following format:

MATERIALS DESIGNATION	SPECIFICATION	MANUFACTURER	MATERIALS USED (MANUFACTURER'S DESIGNATION)	WHERE USED
_____	_____	_____	_____	_____

1.2.3 Final Payroll and Sales Tax Report

Provide copy of Final Payroll and Sales Tax Report.

1.3 MAXIMO REQUIREMENTS

Submit maximo requirements as specified in Section 23 03 00.00 20.

1.4 EQUIPMENT/PRODUCT WARRANTIES

1.4.1 Equipment/Product Warranty List

Furnish to the Contracting Officer a bound and indexed notebook containing written warranties for equipment/products that have extended warranties (warranty periods exceeding the standard one-year warranty) furnished under the contract, and prepare a complete listing of such equipment/products. The equipment/products list shall state the specification section applicable to the equipment/product, duration of the warranty therefor, start date of the warranty, ending date of the warranty, and the point of contact for fulfillment of the warranty. The warranty period shall begin on the same date as project acceptance and shall continue for the full product warranty period. Execute the full list and deliver to the Contracting Officer prior to final acceptance of the facility.

1.4.2 Equipment Warranty Tags and Guarantor's Local Representative

Furnish with each warranty the name, address, and telephone number of the guarantor's representative nearest to the location where the equipment and appliances are installed. The guarantor's representative, upon request of the station representative, shall honor the warranty during the warranty period, and shall provide the services prescribed by the terms of the warranty. At the time of installation, tag each item of warranted equipment with a durable, oil- and water-resistant tag approved by the Contracting Officer. Attach tag with copper wire and spray with a clear silicone waterproof coating. Leave the date of acceptance and QC's signature blank until project is accepted for beneficial occupancy. Tag shall show the following information:

EQUIPMENT/PRODUCT WARRANTY TAG

Type of Equipment/Product _____
Warranty Period _____ From _____ To _____
Contract No. _____
Inspector's Signature _____ Date Accepted _____

Construction Contractor:
Name: _____
Address: _____
Telephone: _____

Warranty Contact: _____
Name: _____
Address: _____
Telephone: _____

STATION PERSONNEL TO PERFORM ONLY OPERATIONAL MAINTENANCE

1.5 MECHANICAL TESTING AND BALANCING

All contract requirements shall be fully completed, including all testing, prior to contract completion date. In addition, all contract requirements shall be fully completed, including testing and inspection, prior to contract completion date, except as noted otherwise.

1.6 COMPLETE SUBMITTAL PACKAGE

Contractor shall make electronic copies of all submittals, including the approved transmittal sheets, and provide two (2) CD/DVD's containing all submittals for the project.

The CD/DVD's shall be marked "Complete Submittal Package - Contract #P1601F - XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX."

1.7 CLEANUP

Leave premises "broom clean." Clean interior and exterior glass surfaces exposed to view; remove temporary labels, stains and foreign substances; polish transparent and glossy surfaces; vacuum carpeted and soft surfaces. Clean equipment and fixtures to a sanitary condition. Clean filters of operating equipment. Clean debris from roofs, gutters, downspouts and drainage systems. Sweep paved areas and rake clean landscaped areas. Remove waste and surplus materials, rubbish and construction facilities from the site.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 78 23

OPERATION AND MAINTENANCE DATA
07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E 1971	(2005) Stewardship for the Cleaning of Commercial and Institutional Buildings

1.2 SUBMISSION OF OPERATION AND MAINTENANCE DATA

Submit Operation and Maintenance (O&M) Data specifically applicable to this contract and a complete and concise depiction of the provided equipment, product, or system, stressing and enhancing the importance of system interactions, troubleshooting, and long-term preventative maintenance and operation. The subcontractors shall compile and prepare data and deliver to the Contractor prior to the training of Government personnel. The Contractor shall compile and prepare aggregate O&M data including clarifying and updating the original sequences of operation to as-built conditions. Organize and present information in sufficient detail to clearly explain O&M requirements at the system, equipment, component, and subassembly level. Include an index preceding each submittal. Submit in accordance with this section and Section 01 33 00 SUBMITTAL PROCEDURES.

1.2.1 Package Quality

Documents must be fully legible. Poor quality copies and material with hole punches obliterating the text or drawings will not be accepted.

1.2.2 Package Content

Data package content shall be as shown in the paragraph titled "Schedule of Operation and Maintenance Data Packages." Comply with the data package requirements specified in the individual technical sections, including the content of the packages and addressing each product, component, and system designated for data package submission, except as follows. Commissioned items without a specified data package requirement in the individual technical sections shall use Data Package 3.

1.2.3 Changes to Submittals

Manufacturer-originated changes or revisions to submitted data shall be furnished by the Contractor if a component of an item is so affected subsequent to acceptance of the O&M Data. Changes, additions, or revisions required by the Contracting Officer for final acceptance of submitted data, shall be submitted by the Contractor within 30 calendar days of the notification of this change requirement.

1.3 TYPES OF INFORMATION REQUIRED IN O&M DATA PACKAGES

1.3.1 Operating Instructions

Include specific instructions, procedures, and illustrations for the following phases of operation for the installed model and features of each system:

1.3.1.1 Safety Precautions

List personnel hazards and equipment or product safety precautions for all operating conditions.

1.3.1.2 Operator Prestart

Include procedures required to install, set up, and prepare each system for use.

1.3.1.3 Startup, Shutdown, and Post-Shutdown Procedures

Provide narrative description for Startup, Shutdown and Post-shutdown operating procedures including the control sequence for each procedure.

1.3.1.4 Normal Operations

Provide narrative description of Normal Operating Procedures. Include Control Diagrams with data to explain operation and control of systems and specific equipment.

1.3.1.5 Emergency Operations

Include Emergency Procedures for equipment malfunctions to permit a short period of continued operation or to shut down the equipment to prevent further damage to systems and equipment. Include Emergency Shutdown Instructions for fire, explosion, spills, or other foreseeable contingencies. Provide guidance and procedures for emergency operation of all utility systems including required valve positions, valve locations and zones or portions of systems controlled.

1.3.1.6 Operator Service Requirements

Include instructions for services to be performed by the operator such as lubrication, adjustment, inspection, and recording gage readings.

1.3.1.7 Environmental Conditions

Include a list of Environmental Conditions (temperature, humidity, and other relevant data) that are best suited for the operation of each product, component or system. Describe conditions under which the item equipment should not be allowed to run.

1.3.2 Preventive Maintenance

Include the following information for preventive and scheduled maintenance to minimize corrective maintenance and repair for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.3.2.1 Lubrication Data

Include preventative maintenance lubrication data, in addition to instructions for lubrication provided under paragraph titled "Operator Service Requirements":

a. A table showing recommended lubricants for specific temperature ranges and applications.

b. Charts with a schematic diagram of the equipment showing lubrication points, recommended types and grades of lubricants, and capacities.

c. A Lubrication Schedule showing service interval frequency.

1.3.2.2 Preventive Maintenance Plan and Schedule

Include manufacturer's schedule for routine preventive maintenance, inspections, tests and adjustments required to ensure proper and economical operation and to minimize corrective maintenance. Provide manufacturer's projection of preventive maintenance work-hours on a daily, weekly, monthly, and annual basis including craft requirements by type of craft. For periodic calibrations, provide manufacturer's specified frequency and procedures for each separate operation.

1.3.2.3 Cleaning Recommendations

Provide environmentally preferable cleaning recommendations in accordance with ASTM E 1971.

1.3.3 Corrective Maintenance (Repair)

Include manufacturer's recommended procedures and instructions for correcting problems and making repairs for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.3.3.1 Troubleshooting Guides and Diagnostic Techniques

Include step-by-step procedures to promptly isolate the cause of typical malfunctions. Describe clearly why the checkout is performed and what conditions are to be sought. Identify tests or inspections and test equipment required to determine whether parts and equipment may be reused or require replacement.

1.3.3.2 Wiring Diagrams and Control Diagrams

Wiring diagrams and control diagrams shall be point-to-point drawings of wiring and control circuits including factory-field interfaces. Provide a complete and accurate depiction of the actual job specific wiring and control work. On diagrams, number electrical and electronic wiring and pneumatic control tubing and the terminals for each type, identically to actual installation configuration and numbering.

1.3.3.3 Maintenance and Repair Procedures

Include instructions and a list of tools required to repair or restore the product or equipment to proper condition or operating standards.

1.3.3.4 Removal and Replacement Instructions

Include step-by-step procedures and a list required tools and supplies for removal, replacement, disassembly, and assembly of components, assemblies, subassemblies, accessories, and attachments. Provide tolerances, dimensions, settings and adjustments required. Instructions shall include a combination of text and illustrations.

1.3.3.5 Spare Parts and Supply Lists

Include lists of spare parts and supplies required for maintenance and repair to ensure continued service or operation without unreasonable delays. Special consideration is required for facilities at remote locations. List spare parts and supplies that have a long lead-time to obtain.

1.3.4 Corrective Maintenance Work-Hours

Include manufacturer's projection of corrective maintenance work-hours including requirements by type of craft. Corrective maintenance that requires completion or participation of the equipment manufacturer shall be identified and tabulated separately.

1.3.5 Appendices

Provide information required below and information not specified in the preceding paragraphs but pertinent to the maintenance or operation of the product or equipment. Include the following:

1.3.5.1 Product Submittal Data

Provide a copy of all SD-03 Product Data submittals required in the applicable technical sections.

1.3.5.2 Manufacturer's Instructions

Provide a copy of all SD-08 Manufacturer's Instructions submittals required in the applicable technical sections.

1.3.5.3 O&M Submittal Data

Provide a copy of all SD-10 Operation and Maintenance Data submittals required in the applicable technical sections.

1.3.5.4 Parts Identification

Provide identification and coverage for all parts of each component, assembly, subassembly, and accessory of the end items subject to replacement. Include special hardware requirements, such as requirement to use high-strength bolts and nuts. Identify parts by make, model, serial number, and source of supply to allow reordering without further identification. Provide clear and legible illustrations, drawings, and exploded views to enable easy identification of the items. When illustrations omit the part numbers and description, both the illustrations and separate listing shall show the index, reference, or key number that will cross-reference the illustrated part to the listed part. Parts shown in the listings shall be grouped by components, assemblies, and subassemblies in accordance with the manufacturer's standard practice. Parts data may cover more than one model or series of equipment,

components, assemblies, subassemblies, attachments, or accessories, such as typically shown in a master parts catalog

1.3.5.5 Warranty Information

List and explain the various warranties and clearly identify the servicing and technical precautions prescribed by the manufacturers or contract documents in order to keep warranties in force. Include warranty information for primary components such as the compressor of air conditioning system.

1.3.5.6 Personnel Training Requirements

Provide information available from the manufacturers that is needed for use in training designated personnel to properly operate and maintain the equipment and systems.

1.3.5.7 Testing Equipment and Special Tool Information

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components.

1.3.5.8 Testing and Performance Data

Include completed prefunctional checklists, functional performance test forms, and monitoring reports. Include recommended schedule for retesting and blank test forms.

1.3.5.9 Contractor Information

Provide a list that includes the name, address, and telephone number of the General Contractor and each Subcontractor who installed the product or equipment, or system. For each item, also provide the name address and telephone number of the manufacturer's representative and service organization that can provide replacements most convenient to the project site. Provide the name, address, and telephone number of the product, equipment, and system manufacturers.

1.4 TYPES OF INFORMATION REQUIRED IN CONTROLS O&M DATA PACKAGES

Include Data Package 5 and the following for control systems:

a. Narrative description on how to perform and apply all functions, features, modes, and other operations, including unoccupied operation, seasonal changeover, manual operation, and alarms. Include detailed technical manual for programming and customizing control loops and algorithms.

b. Full as-built sequence of operations.

c. Copies of all checkout tests and calibrations performed by the Contractor (not Cx tests).

1.5 SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES

Furnish the O&M data packages specified in individual technical sections. The required information for each O&M data package is as follows:

1.5.1 Data Package 1

a. Safety precautions

b. Cleaning recommendations

c. Maintenance and repair procedures

d. Warranty information

e. Contractor information

f. Spare parts and supply list

1.5.2 Data Package 2

a. Safety precautions

b. Normal operations

c. Environmental conditions

d. Lubrication data

e. Preventive maintenance plan and schedule

f. Cleaning recommendations

g. Maintenance and repair procedures

h. Removal and replacement instructions

i. Spare parts and supply list

j. Parts identification

k. Warranty information

l. Contractor information

1.5.3 Data Package 3

a. Safety precautions

b. Operator prestart

c. Startup, shutdown, and post-shutdown procedures

d. Normal operations

e. Emergency operations

f. Environmental conditions

g. Lubrication data

h. Preventive maintenance plan and schedule

i. Cleaning recommendations

j. Troubleshooting guides and diagnostic techniques

k. Wiring diagrams and control diagrams

l. Maintenance and repair procedures

m. Removal and replacement instructions

n. Spare parts and supply list

o. Product submittal data

p. O&M submittal data

q. Parts identification

r. Warranty information

s. Testing equipment and special tool information

t. Testing and performance data

u. Contractor information

1.5.4 Data Package 4

a. Safety precautions

b. Operator prestart

c. Startup, shutdown, and post-shutdown procedures

d. Normal operations

e. Emergency operations

f. Operator service requirements

g. Environmental conditions

h. Lubrication data

i. Preventive maintenance plan and schedule

j. Cleaning recommendations

k. Troubleshooting guides and diagnostic techniques

l. Wiring diagrams and control diagrams

m. Maintenance and repair procedures

n. Removal and replacement instructions

o. Spare parts and supply list

p. Corrective maintenance man-hours

q. Product submittal data

r. O&M submittal data

s. Parts identification

t. Warranty information

u. Personnel training requirements

v. Testing equipment and special tool information

w. Testing and performance data

x. Contractor information

1.5.5 Data Package 5

a. Safety precautions

b. Operator prestart

c. Start-up, shutdown, and post-shutdown procedures

d. Normal operations

e. Environmental conditions

f. Preventive maintenance plan and schedule

g. Troubleshooting guides and diagnostic techniques

h. Wiring and control diagrams

i. Maintenance and repair procedures

j. Removal and replacement instructions

k. Spare parts and supply list

l. Product submittal data

m. Manufacturer's instructions

n. O&M submittal data

o. Parts identification

p. Testing equipment and special tool information

q. Warranty information

r. Testing and performance data

s. Contractor information

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 78 30.00 22

GIS DATA DELIVERABLES

07/20

PART 1 GENERAL

1.1 OBJECTIVE

The primary objective of this section is to provide detailed specifications for collection and delivery of geospatial data commonly referred to as Geographic Information System (GIS) data. Additionally, this section shall provide guidance to ensure that all GIS data delivered is compatible and will add value to the Marine Corps Base (MCB) Camp Lejeune Installation Geospatial Information and Services (IGI&S) GEOdatabase.

Failure to comply with the specifications outlined in this document will result in non-acceptance of data deliverables.

1.1.1 Point of Contact for MCB Camp Lejeune

The Points of Contact (POC) for assistance in preparation of GIS deliverables are:

Resident Officer In Charge Of Construction
Construction Manager (CM)
1005 Michael Drive
Camp Lejeune, NC 28547-2521
(910) 451-2581

Public Works Division
GIS Data Manager
1005 Michael Road
Camp Lejeune, NC 28547-2521
(910) 451-5507 ext 3264

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00:

SD-11 Closeout Submittals

GIS Data Deliverables

1.3 GOVERNMENT GEOSPATIAL DATA AND SCHEMA

1. The IGI&S repository model schema is based on the Spatial Data Standards for Facilities, Infrastructure and Environment (SDSFIE) GEOFidelis Data Model with recurring business driven modifications and or adaptations.

   a. Data will be created and delivered by developing an ARCGIS Personal GEODatabase using ArcGIS 10.1 or higher if a higher version is being utilized by the Government at the time the deliverable is being developed.

   b. The Contractor shall verify the ArcGIS and schema version, via the CM or PM, at the commencement of this contract. All GIS DATA DELIVERABLES will be created in accordance with the current version and these specifications.

   c. The Contractor is responsible for requesting the existing GIS Data, Schema and Domain Properties by means of a Data Request

Package
(DRP). Receipt of request will include Geospatial Database table structure, schema, Domain configuration, Attribute text format, i.e., case size as well as Meta Data information.

d. The DRP should be submitted prior to the start of data collection efforts and again on an as needed basis. The Contractor shall ensure that all GIS data has been created and delivered utilizing the most up to date IGI&S GEODatabase schema.

2. Submit a request for a Geospatial DRP to the CM or the Project Manager.

a. Request to be completely filled out and include all the information as instructed on the data request form.

b. Request only GIS data and or schema for feature classes that are relevant to the contract and within the boundary of project area.

c. Utilize associated Government modified domain structure(s).

d. Attach Scope of Work, which is defined by this GIS DATA DELIVERABLES section for each project request.

e. Return the DRP to the CM or Project Manager for sponsorship and submittal to the Installation Geospatial Information & Services (IGI&S) Office.

f. Incomplete forms may delay receipt of the requested GIS data and Schema.

The following Spatial Data Standards for Facilities, Infrastructure, and Environment (SDSFIE) website may offer definitions for Feature data sets; Feature Classes and other applicable information. However, please note that specific Schema or Domain modifications are not available via this resource:

http://www.sdsfieonline.org/

1.3.1 Global Positioning System (GPS) and Spatial Reference Properties

GPS data shall be completed in accordance with the GPS Data Collection and Documentation Standards, Version 4 (or higher version if available at the time of this project) as prepared by Geographic Information Coordinating Council (GICC) Statewide Mapping Advisory Committee (SMAC) and adopted by the North Carolina Geographic Information Coordinating Council.

1. Prior to GPS efforts, ALL underground utilities are to be located utilizing a utility locating service in order to verify and obtain accurate feature locations.

2. Only bench marks included in the North Carolina Geodetic Survey Base Station Network are to be used for GPS data collection.

3. Mission planning is essential. Utilize the best Position Dilution of Precision (PDOP) values for data accuracy.

4. Utility data, as identified in paragraph "ATTRIBUTE DATA COLLECTION AND GPS REQUIREMENTS FOR SPECIFIC FEATURES" will be collected utilizing Survey Grade GPS data collection methods.

5. Infrastructure data, as identified in paragraph "ATTRIBUTE DATA COLLECTION AND GPS REQUIREMENTS FOR SPECIFIC FEATURES" will be collected utilizing Sub-Foot or better GPS data collection methods.

   a. Spatial accuracy requirements for Survey and Sub-Foot grade data collection are as follows:

      i. Sub-Foot requirements:

         1) All points shall be within + 12 inches

         2) 95 percent accuracy rate for all points.

      ii. Survey Grade requirements:

         1) All points shall be within + 1 centimeter

         2) 98 percent accuracy rate for all points

6. Make every effort to capture feature locations without using offsets. All Offsets will be noted in the Final Report for each feature.

7. Excessive offsets included in the Final Data, which will be referenced in the Final Report, will be reviewed for quality control.

   a. Resubmittal of data will be required if PDOP planning was not observed per this specification.

The following GEODatabase Coordinate Systems and Spatial Reference Properties should be utilized for Camp Lejeune:

1. Transverse Mercator (UTM) Zone 18N

   a. GRS 1980 spheroid

   b. North American Datum 1983 (NAD83) horizontal datum

   c. North American Vertical Datum 1988 (NAVD88) vertical datum.

2. Domain precision of 1000 which will result in a database accuracy of 1/1000 m

1.3.2 Demolished and Abandoned in Place (AIP) Features

Reference all Demolished and or AIP features in the data delivered. Should the current feature data class attributes and or domains not reference AIP or demolished features, the Contractor will be responsible for appropriately delivering these features by creating an associated "Demolished" or AIP feature class for all point and polyline data, i.e., CLJN.CL.WastewaterUtilitySegment.

1. Utilize a blank schema for the associated feature class.

2. Rename associated feature class and add DEMO or AIP as a prefix, i.e.,

DEMO.CLJN.CL.WastewaterUtilitySegment,
AIP.CLJN.CL.WastewaterUtilitySegment.

3. All demolished and or AIP features should provide existing spatial and non-spatial data which may be copied from existing data.

4. Update attributes appropriately to include the following:

   a. Contract Number.

   b. Drawing Number.

   c. isDemolished.

   d. dateDemolished or dateAIP.

   e. Status.

1.3.3 Creating a New Feature Class

Should a new feature class be required that is not readily available in the current GIS schema provided by the Government; the Contractor shall develop the feature class utilizing the schema consistent with the most current version of SDSFIE and document in the Final Report.

1. The Contractor shall include the following modifications (fields) to the schema structure and shall submit all information to the CM or PM for direction and final approval.

   a. Contract Number

   b. Drawing Number

1.3.4 GIS Topology Rules

All data must be created using GIS topology rules for polygons, points and lines, such as, but not limited to the following examples:

1. Polygons, Polylines and points rules; please reference illustrating topology rules in ArcGIS at www.esri.com.

2. Polygons must not have slivers.

3. All utility or infrastructure system data, which is, but is not limited to, transportation system and electrical, water, steam distribution, and wastewater collection, etc., will be created using GIS spatial connectivity rules which specify that vertex, edge and endpoints be snapped to features within the system.

4. Features will be snapped to the appropriate item.

5. Data will be created to represent the real world, for example, water, sewer, and transportations systems, etc. will be drawn and or created in the direction of flow.

6. Utility and transportation systems will be created from source to sink, etc.

7. Abandoned In Place (AIP) utility lines will be located and updated in

the current feature data set and identified as AIP in the attribute table.

1.3.5 Creation of Geographic Data Documentation (METADATA)

For each digital file delivered containing geographic information, the Contractor shall provide documentation consistent with the Federal Geographic Data Committee (FGDC) Content Standards for Digital Geospatial Metadata (CSDGM). Both 'GEOFidelis Mandatory' and 'FGDC Mandatory' fields shall be completed for each geographic data set.
The Geospatial Information & Services (IGI&S) Metadata Authoring Guide is included in the DRP package.

Metadata generation tools included in the ArcGIS suite of software (or equivalent technology) shall be used in the production of the required metadata in XML format. Regardless of the tools used for metadata creation, must ensure that the metadata is delivered in XML format and can be easily imported into the IGI&S GEODatabase. A copy of the FGDC metadata standard can be obtained on the internet at http://www.fgdc.gov or by contacting:

Federal Geographic Data Committee
590 National Center
Reston, Virginia 20192
Email: fgdc@fgdc.gov

(NOTE: The metadata should be formatted from the Government perspective, not the Contractor project perspective. Therefore such items as Point of Contact (POC) should be the POC currently associated with the data and NOT the Contractor's Project Manager. Use language and format consistent with existing metadata.)

1.3.6 New Feature Class Requirements

When developing a new feature class, the Contractor shall develop the initial structure consistent with the most current version of SDSFIE.

a. If further modifications to the database structure are required, the Contractor shall consult with the Government Project Manager for direction and final approval.

b. All new feature data classes shall be created in compliance with SDSFIE noted on the final report.

1.3.7 GIS Submittals Guidelines

All GIS Submittals will be submitted to the CM or PM and then analyzed by Government GIS personnel prior to final approval. Failure to comply with the specifications outlined in this document will result in non-acceptance of data deliverables.

1. Prior to any database development, provide the Government with a technical approach document, in PDF format, for review and approval. The Technical Approach document will describe in detail the Contractor's technical approach to designing and developing the database.

2. All attributes will be populated in accordance with the "ATTRIBUTE DATA COLLECTION AND GPS REQUIREMENTS FOR SPECIFIC FEATURES" and will be

obtained via contract specifications, plans and record drawings.

3. The Contractor may be required to conduct research, collect data and make copies of reports and studies as necessary to verify existing and/or record drawing data. Record drawing data and closed contracts can be located in the Technical Records Section in the Public Works Department.

4. Raw GPS data and collection data files will be included with every phase of delivery.

5. Actual spatial and non-spatial conditions in the field always supersede drawings. Locate and field verify all features to ensure attribute data and location is correctly recorded.

6. The Contractor shall submit a preliminary review of data at 15 to 25 percent contract completion to ensure specifications compliance.

7. Deliver digital geographic maps, GPS collection files and related data. All working text and documents and personal geodatabase will be included for review in the draft and final delivery of data.

   a. All maps of GIS DATA DELIVERABLES will be ANSI C size and include a project title, contract number, scale, legend, standard symbology, attributes, i.e., building numbers, road names, segment diameters, etc.

8. When required, provide a technical consultant to meet on site.

9. Do not deliver blank unused schema or feature class data with no attributes. Deliver only data pertinent to the contract that adds value to the GEODatabase per this section.

10. When projects are constructed in phases, deliver GIS Data at the end of each phase for all Phased Projects and Construction projects.

11. It is the Contractor's responsibility to perform quality assurance for all data and related materials required in the section prior to submitting product to the Government.

12. The data will be analyzed for discrepancies in subject content, correct format in accordance with this statement of work, and compatibility with the existing GIS system as well as all other specifications in this section.

1.3.8 Formats, Versions and Guidelines

All data deliverables will be in the following formats and/or versions.

1. GIS data will be provided in an ArcGIS 10.1 or higher if a higher version is being used by the Government at the time of this project. Verify the ArcGIS version, via the CM or PM at the commencement of this contract.

2. Microsoft Windows 10 operating system, unless otherwise approved by the Government.

3. All reports and maps will be delivered as a hard copy and in a searchable Adobe Portable Document Format (PDF).

4. All text, spreadsheet, and database files, reports and maps shall be delivered on Compact Disc read - only memory (CD-ROM) or Digital Versatile Disc read - only memory (DVD-ROM).

5. Verify required version(s) of software and schema, via the CM or PM.

6. Map submittals will accompany each geospatial deliverable.

   a. Include ANSI C map for each project/area.

   b. Data should be labeled and attributed per specification.

   c. All maps should include the date, a legend, scale, contract title, and number.

1.3.9 Final Report Requirements with additional Guidelines

Follow the following:

1. Specific procedures and list of equipment, software and versions that were utilized for the GPS data collection and creation of geospatial data.

2. Submit all GPS data files.

3. Provide the date(s) the IGI&S schema and geospatial data was received.

4. Provide steps taken to create the GEOdatabase.

5. Provide details on any offsets to include justification as to why offsets were utilized and on which features and or points offsets were used.

6. Describe all modifications to the geodatabase to include the name of all new features classes, i.e., new, demolished or AIP.

7. Provide the source that was utilized for required attributes.

   a. Include an ANSI C size copy of all design drawings that were referenced in the attribute data. This information should be included in all phases of delivery to include draft and final reviews.

   b. Provide the overall utility site plan drawing(s)with each submittal.

8. Specify Deliverable "Draft #" or "Final Submittal" when data is submitted to the CM or PM for review.

9. Provide the name and contact information for the GIS Technical Point of Contact who can answer questions regarding the data deliverable.

10. GIS DATA DELIVERABLES must be provided in a format that does not require translation or pre/post processing prior to being loaded into the IGI&S GEODatabase.

11. Provide any miscellaneous information that is deemed significant.

12. Provide the current version of the GIS DATA DELIVERABLES specification utilized for this contract submittal.

1.3.10 Ownership

All digital files, final hardcopy products, GPS raw data, source data acquired for this project, and related materials, including that furnished by the Government, will become the property of the Government and will not be issued, posted, distributed, or published by the Contractor.

Note: No endorsement of software or hardware is implied.

1.4 ATTRIBUTE DATA COLLECTION AND GPS REQUIREMENTS FOR SPECIFIC FEATURES

1.4.1 **CLJN.CL.Common**

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) and Spatial Reference Properties."

GPS and collect the following attributes:

1.4.2 **CLJN.CL.EMERGENCY_SERVICES**

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) and Spatial Reference Properties". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table, or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.RoadCenterline
The center of the road area

a) roadCategory - Major Roads/Local Roads/etc.
b) trackOrLaneCount
c) speedLimit
d) isPaved - YES / NO
e) isOneWay - Yes/ No
f) baseRoadName
g) dateConstructed
h) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
i) contractNumber
j) designDrawingNumber

1.4.3 CLJN.CL.REAL.PROPERTY

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) and Spatial Reference Properties."

GPS and collect the following attributes:

CLJN.CL.AccessControl
A structure manned or unmanned intended to control access to an area

a) assessControlIDPK - Structure ID until Field is created in schema
b) controlType
c) contractNumber
d) designDrawingNumber
e) Installation date
f) gisFeatureCollectionMethod
g) isRangeAccess Y/N
h) sdsFeatureName (Subtype of access control point/gate
i) sdsFeatureDescription

CLJN.CL.AlternativeEnergyPoint
Locations used for the production of alternative energy sources, such as wind turbines, photovoltaic, etc.

a) alternativeEnergyType - Photovoltaic, Natural Gas, etc.
b) contractNumber
c) designDrawingNumber
d) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
e) isPortable - YES / NO
f) wattage
g) operationalStatus - inservice, abandoned, etc.
h) panelType
i) sdsFeatureName
j) sdsFeatureDescription
k) wattage - Total per unit
l) hasInverter - YES / NO
m) isPartOfElectricalNetwork - YES / NO
n) photovoltaicPanelInstallation

CLJN.CL.AlternativeEnergyArea
Locations used for the production of alternative energy sources

a) operationalStatus - inservice, abandoned, etc.
b) isPortable - YES / NO
c) panelType
d) wattage - total for area
e) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
f) contractNumber
g) sdsFeatureName - Facility Number
h) hasInverter - YES / NO
i) isPartOfElectricalNetwork - YES / NO

CLJN.CL.BoatRamp
A partially submerged hard surfaced structure on a shoreline for launching or retrieving vessels or vehicles

a) boatRampIDPK - Facility Number
b) dateConstructed
c) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
d) contractNumber
e) sdsFeatureName
f) sdsFeatureDescription - Location
g) numberofLaunchLanes

CLJN.CL.Bridge
A structure used by vehicles that allows passage over or under an obstacle such as a river, chasm, mountain, road or railroad

a) isFixed - YES / NO
b) TransportationSystemType - Pedestrian, Road, Railway, etc.
c) FacilityNumber
d) verticalConstructionMaterial - Brick, Concrete, etc.
e) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
f) contractNumber
g) sdsFeatureDescription - Road Name if applicable
h) OperationalStatus - closed, operational, etc.

CLJN.CL.Building
A roofed, floored and walled structure that is completely enclosed

a) facilityNumber
b) builtDate
c) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
d) contractNumber
e) sdsFeatureDescription - General Description of Building's Purpose
f) floorCount
g) material - Exterior material such as Brick, Concrete, etc.
h) operationalStatus - inService, abandoned, etc.

CLJN.CL.BuildingFloorPlan
A linear representation of floor plans for buildings, provided in one feature per floor

a) buildingFloorLevel
b) buildingIDFK - Structure Number
c) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
d) contractNumber
e) sdsFeatureDescription Renovation Date

CLJN.CL.Disposal_RealProperty
Real property demolished structures

a) sdsFeatureDescription
b) sdsFeatureName
c) facilityNumber

d) contractNumber
e) disposalDate

CLJN.CL.DocksAndWharfs
A manmade water-land interface structure often for access to boats or ships

a) PurposeType - Fishing, Mooring, etc.
b) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
c) contractNumber
d) Facility Number - Structure Number
e) sdsFeatureDescription - Pier, boat ramp, dock, etc.
f) natureOfConstruction - concrete, earthen, steel

CLJN.CL.Fence
A freestanding structure designed to restrict or prevent movement across a boundary

a) facilityIDFK - Structure Number
b) fenceType - metal, wood, etc.
c) fenceUse - agriculture, boundary, etc.
d) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
e) contractNumber
f) sdsFeatureName - Fence or Gate
g) sdsFeatureDescription

CLJN.CL.Marina
Any facility or area for the exchange of people or materials from land to water such as a port, harbor, marina, launch area or small craft facility

a) marinaIDPK - Structure Number
b) marinaType
c) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
d) contractNumber
e) sdsFeatureName
f) createdDate - Construction Date
g) categoryOfCraftFacility - boat launch or landed, etc.

CLJN.CL.NavigationalAid
A visual or electronic device, on the ground or airborne, which provides point-to-point guidance information or position data to aircraft in flight

a) navigationalAidIDPK - Structure Number
b) navaidType - TACAN, Radar station, Beacon, etc.
c) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
d) contractNumber
e) sdsFeatureName - Type of navigational aid

CLJN.CL.PavementSectionAirfield
A pavement section is a portion of a pavement branch that differs in some aspect from other sections such that further segmentation is required to uniquely identify that section)

a) pavementSectionType - apron, roadway, etc.
b) isLighted - YES / NO
c) operationalStatus - inService, abandoned, etc.
d) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
e) builtDate
f) contractNumber
g) runwayClassification - class A, class B, rotatory, etc.
h) sdsFeatureName
i) sdsFeatureDescription - MCBCL, MCASNR, Geiger, Stone Bay, etc.

CLJN.CL.PavementSectionParkingArea
A vehicle parking area is an area used for parking vehicles not including residential streets and driveways.

a) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
b) operationalStatus - inService, abandoned, etc.
c) pavementSectionType - parking, slab, driveway, etc.
d) sdsFeatureDescription - Dumpster, Driveway, Transformer, Parking, etc.
e) sdsFeatureName - Pad, Slab, Parking, etc.
f) facilityNumber
g) builtDate
h) contractNumber
i) isLighted

CLJN.CL.PavementSectionRoadway
The surface area that comprise a road area, upon which vehicles drive and park.

a) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
b) operationalStatus - inService, abandoned, etc.
c) pavementSectionType - curb, roadway, etc.
d) facCode - Surfaced or Unsurfaced
e) divided - Yes / No
f) featureCode
g) oneWay - Yes / No
h) routeSurfaceComposition - concrete, asphalt, etc.
i) builtDate
j) contractNumber
k) isLighted - Yes / No
l) isTankTrail - Yes / No

CLJN.CL.PavementSectionSidewalk
The paved pedestrian walkway prepared to facilitate travel on foot. It may or may not be adjacent to a street/road.

a) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
b) operationalStatus - inService, abandoned, etc.
c) pavementSectionType - Sidewalks
d) sdsFeatureDescription - Named Area
e) routeSurfaceComposition - Concrete, Asphalt, etc.
f) builtDate
g) contractNumber

h) installationCode - M67001
i) isLighted - Yes / No

CLJN.CL.RailTrack
A track is the main designation for describing a physical linear portion of the network

a) contractNumber
b) facilityNumber
c) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
d) NetworkSubtype - railroadTrack, craneTrack
e) operationalStatus - inservice, abandoned, etc.
f) sdsFeatureName - Start & finish Points
g) sdsFeatureDescription - Provide Street Name Cross cover

CLJN.CL.RecreationArea
An area defined for recreational purposes

a) facilityNumber
b) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
c) contractNumber
d) sdsFeatureName - Type of recreation field
e) sdsFeatureDescription - Type of recreation feature
f) areaType - biking, boating, picnic, Hunting, etc.

CLJN.CL.RecreationTrail
A location providing physical activities which are mentally relaxing, such as running/walking, biking, or hiking

a) recreationTrailIDPK - Facility or Structure Number
b) trailType - Multi-use, horse riding, etc.
c) isPaved - YES / NO
d) dateConstructed
e) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
f) contractNumber
g) sdsFeatureName - Trail Name
h) sdsFeatureDescription - Area, Location or parallel street

CLJN.CL.StructureArea
A facility classified as other than a building or linear asset

a) facilityNumber - Structure Number
b) builtDate
c) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
d) contractNumber
e) sdsFeatureName - Name of structure according to contract
f) sdsFeatureDescription - Description of item
g) heightAboveSurfaceLevel
h) heightAboveSurfaceLevelUOM - foot, inch, meter, etc.

CLJN.CL.StructurePoint
Example: Flag poles; Point of Information Signs (POI) etc

a) facilityNumber - Structure Number
b) builtDate
c) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
d) contractNumber
e) sdsFeatureName - POI, Sign, Flagpole, bleacher, etc.
f) sdsFeatureDescription - Specific type of feature

CLJN.CL.Tower
A vertical projection, higher than its diameter, generally used for observation, storage, or electronic transmission

a) towerUseType - communication, observation, etc.
b) heightMax
c) heightUOM - foot, inch, meter, etc.
d) contractNumber
e) towerType - Observation Tower, Guard Tower, etc.
f) facilityNumber - Structure number
g) sdsFeatureDescription
h) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
i) towerMaterial - wood, concrete, steel, etc.

CLJN.CL.TrafficControlLight
A feature used to represent traffic lights

a) contractNumber
b) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
c) sdsFeatureName - Traffic Control Light, Traffic Signal control box, etc.
d) sdsFeatureDescription - Location such as streets that intersect

CLJN.CL.Wall
A linear feature used for separation of facilities, ornamental decoration, or structural reinforcement (retaining wall

a) wallType - brick, timber, stone, concrete, etc.
b) wallHeight
c) wallHeightUOM - foot, inch, meter, etc.
d) dateConstructed
e) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
f) contractNumber
g) sdsFeatureName
h) sdsFeatureDescription - Dumpster enclosure, Utility Enclosure, Blast Protection, etc.

1.4.4 CLJN.CL.REAL_PROPERTY_RESTRICTED

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) and Spatial Reference Properties." Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when

populating the feature where required.

GPS and collect the following attributes:

CLJN.CL.Well
A shaft dug or drilled into the Earth for the purpose of extracting fluids from the subsurface, collecting environmental samples, injecting fluids into the subsurface or extracting contamination or other impurities from the subsurface

a) facilityNumber - Structure Number
b) wellPurpose - extraction, injection, etc.
c) wellResource - WATER
d) operationalStatus - inservice, abandoned, etc.
e) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
f) contractNumber
g) sdsFeatureName - potable or nonpotable
h) sdsFeatureDescription - operational status source
i) ProjectID - Name of Plant this well services
j) wellType - artesian, drilled, etc.
k) operationalStatus - inservice, abandoned, removed, etc

1.4.5 CLJN.CL.COMMUNICATIONS_RESTRICTED

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System GPS and Spatial Reference Properties." Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

GPS and collect the following attributes:

CLJN.CL.CommCartographicFeatureArea
Graphic features that aid in visually associating CommAnnotation features to the appropriate communication infrastructure feature.

a) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
b) sdsFeatureName
c) sdsFeatureDescription
d) commProjectName - Contract Number
e) operationalStatus - In service, Removed, Abandon in Place, etc.

CLJN.CL.CommCartographicFeatureLine
Graphic features that aid in visually associating CommAnnotation features to the appropriate communication infrastructure feature.

a) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
b) sdsFeatureName
c) sdsFeatureDescription
d) commProjectName - Contract Number
e) operationalStatus - In service, Removed, Abandon in Place, etc.

CLJN.CL.CommCartographicFeaturePoint
Graphic features that aid in visually associating CommAnnotation features to the appropriate communication infrastructure feature.

a) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
b) sdsFeatureName
c) sdsFeatureDescription
d) commProjectName - Contract Number
e) operationalStatus - In service, Removed, Abandon in Place, etc.

CLJN.CL.CommUtilityNode
A subdivision of a communications network, particularly an asset that participates in the transmission of a signal but that is not a cable.

a) commUtilityNodeIDPK - Structure Number
b) commNodeType - connection or two or more sheaths, Devise Used to detect & measure various environmental conditions, Devise converts electrical signal in to sound, etc.
c) operatingSpectrum
d) transmissionPower
e) powerUOM
f) operationalStatus - In service, Removed, Abandon in Place, etc.
g) commProjectName - Contract Number
h) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
i) sdsFeatureName - MNS - Big Voice, MNS - Little Voice, MSN - Control Station, etc.
j) sdsFeatureDescription - MNS - Big Voice, Field Antenna, Antenna Communication, etc.

CLJN.CL.CommUtilitySegment
A subdivision of a communications network, particularly a cable for the transmission of a signal.

a) cableMaterial - Fiber Optical, PB, CU, Steel, ABS, etc.
b) cableSheathing - PE, XLPE, Cross Ply, etc.
c) availableFibers -
d) usedFibers
e) numberOfMultiModeFibers
f) numberOfPairs
g) numberOfSingleModeFibers
h) installationTypeCode - Underground, above ground, etc.
i) operationalStatus - In service, Removed, Abandon in Place, etc.
j) cableInstaller -
k) cableRoute -
l) cableCount -
m) numberOfStrands -
n) wireGauge -
o) commProjectName - Contract Number
p) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
q) sdsFeatureName - Non-direct Buried Lines, Direct Buried Lines, etc.
r) sdsFeatureDescription - communications line, etc.

CLJN.CL.UtilityFeature_cDuctBank
One or more ducts routed in parallel between two nodes.

a) networkType - A network used for the transmission of a signal.
b) networkSubType - The communication network subtype.
c) utilityFeatureType - One or more ducts routed in parallel between two nodes. (L), etc.
d) diameter
e) diameterUOM - Inches, Feet, meters, etc.
f) ductDepth
g) ductDepthUOM - Inches, Feet, meters, etc.
h) interDuctDiameter
i) interDuctDiameterUOM - Inches, Feet, meters, etc.
j) isEncased - Yes or No
k) numberOfDucts
l) numberOfInserts
m) operationalStatus - In service, Removed, Abandon in Place, etc.
n) commProjectName - Contract Number
o) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.

CLJN.CL.UtilityFeature_cManhole
An enclosed structure (manhole, or handhole)

a) utilityFeatureIDPK - MH Number - See project Manager
b) networkType - Network used for transmission of signal,
c) networkSubType - Communication network subtype
d) utilityFeatureType - Manhole, hand hole, etc.
e) cManholeType - T, R2A, L, j4, JC9C, etc.
f) cManholeMaterial - steel, plastic, aluminum, fiberglass, etc.
g) isHandhole - Yes or No
h) widthValue
i) widthUOM - Inches, Feet, meters, etc.
j) lengthValue
k) lengthUOM - Inches, Feet, meters, etc.
l) heightValue
m) heightUOM - Inches, Feet, meters, etc.
n) diameter
o) diameterUOM - Inches, Feet, meters, etc.
p) cManholeDepth
q) cManholeDepthUOM - Inches, Feet, meters, etc.
r) operationalStatus - In service, Removed, Abandon in Place, etc.
s) commProjectName - Contract Number
t) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.

CLJN.CL.UtilityFeature_cPedestal
An above-ground enclosed structure that provides access to buried plant and a place to house splices, terminals, etc.

a) networkType - A network used for the transmission of a signal.
b) networkSubType - The communication network subtype.
c) utilityFeatureType - above-ground enclosed structure that provides access to buried plant and a place to house splices, terminal, etc.

d) pedestalType - rectangular box type, etc.
e) operationalStatus - In service, Removed, Abandon in Place, etc.
f) commProjectName - Add Contract Number
g) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
h) sdsFeatureDescription

CLJN.CL.UtilityFeature_cVault
An enclosed structure in a facility used for cable entrance.

a) utilityFeatureType
b) networkType - A network used for the transmission of a signal.
c) networkSubType - The communication network subtype.
d) heightValue
e) heightUOM - Inches, Feet, meters, etc.
f) widthValue
g) widthUOM - Inches, Feet, meters, etc.
h) vaultDepth
i) vaultDepthUOM - Inches, Feet, meters, etc.
j) diameter
k) diameterUOM - Inches, Feet, meters, etc.
l) operationalStatus - In service, Removed, Abandon in Place, etc.
m) commProjectName - Contract Number
n) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
o) sdsFeatureDescription

1.4.6 CLJN.CL.UTILITIES_ELECTRICAL

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) and Spatial Reference Properties." Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

GPS and collect the following attributes:

CLJN.CL.ElecUtilNode_eExteriorLight
Exterior lighting is supplied by local distribution systems and is generally the only service for which the electric utility installs, operates and maintains utilization equipment

a) electricalUtilityNodeIDPK
b) exteriorLightType - streetLight, parkingLotLight, etc.
c) electricalNodeType - eExteriorLight
d) operationalStatus - inservice, abandoned, etc.
e) bulbType LED, INCA, etc.
f) circuitID - This available from CM or PM
g) hasSensor - YES / NO
h) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
i) contractNumber
j) dateInService
k) sdsFeatureName
l) Voltage

m) Wattage

CLJN.CL.ElecUtilNode_eGenerator
Generator is a power source for providing electricity. Generators may be primary or standby power sources

a) FacilityNumber - structure number
b) electricalNodeType - eGenerator
c) operationalStatus - inservice, abandoned, etc.
d) voltage
e) kvaRate
f) circuitID - List is available from CM or PM
g) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
h) contractNumber
i) dateInService
j) sdsFeatureName - Manufacturer
k) generatorType - Primary, backup, emergency, etc.

CLJN.CL.ElecUtilNode_eMeterPoint
A electrical meter point represents the location of the metering device

a) electricalNodeType - Description
b) operationalStatus - inservice, abandoned, etc.
c) circuitID - List is available from CM or PM
d) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
e) contractNumber
f) dateInService
g) sdsFeatureName
h) sdsFeatureDescription -
i) mountingType
j) utilityOwner
k) voltage - 208Y-120V, 480Y-277V, etc.

CLJN.CL.ElecUtilNode_eSwitch
Electrical Switches are installed at strategic locations throughout distribution feeder circuits

a) electricalNodeType
b) switchPosition - closed, open, etc.
c) operationalStatus - inservice, abandoned, etc.
d) electricalSwitchType - switches
e) circuitID - List is available from CM or PM
f) numberOfPhases single, three, two
g) switchPosition - Open, closed, etc.
h) voltage - 208Y-120V, 480Y-277V, etc.
i) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
j) contractNumber

CLJN.CL.ElecUtilNode_eTransformer
The Transformer feature class captures information about distribution and power transformers

a) electricalNodeType - Transformer
b) transformerType - stepdown, step up, etc.
c) mountingType - pool or pad

d) numberOfPhases - 1, 2, 3, etc.
e) primaryVoltage - 208Y-120V, 480Y-277V, etc.
f) secondaryVoltage - 208Y-120V, 480Y-277V, etc.
g) totalKVA
h) circuitID - List is available from CM or PM
i) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
j) contractNumber
k) sdsFeatureName - Manufacturer
l) operationalStatus - inservice, abandoned, etc.

CLJN.CL.ElecUtilNode_eVoltageRegulator
Voltage regulators vary the ac supply or source voltage to the customer to maintain the voltage within desired limits

a) electricalNodeType - VoltageRegulator
b) operationalStatus - inservice, abandoned, etc.
c) primaryVoltage - 208Y-120V, 480Y-277V, etc.
d) secondaryVoltage - 208Y-120V, 480Y-277V, etc.
e) numberOfPhases - 1, 2, 3,
f) circuitID - This available from CM or PM
g) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
h) contractNumber

CLJN.CL.UtilFeat_eSupportStructure
A structure that supports electric devices

a) utilityFeatureType - Utility, Guy, Poles, etc.
b) networkType - electrical
c) heightValue -
d) heightUOM - foot, inch, meter, etc.
e) utilityOwner
f) operationalStatus - inservice, abandoned, etc.
g) cableCircuitName - List is available from CM or PM
h) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
i) contractNumber
j) sdsFeatureName - Utility Pole, etc
k) sdsFeatureDescription - Number of circuits attached to pole

CLJN.CL.UtilFeat_eUndergroundStructure
Underground Structure is a simple junction feature that includes vaults and manholes that house and protect electrical equipment

a) utilityFeatureIDPK - Structure Number
b) utilityFeatureType - Underground, surface structure, etc
c) networkType - electrical
d) operationalStatus - inservice, abandoned, etc.
e) electricalJunctionType - Manhole, Junction Box, Handhole, etc.
f) numberOfCables -
g) rimElevation -
h) rimElevationUOM - foot, inch, meter, etc.
i) cableCircuitName - List is available from CM or PM
j) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
k) contractNumber

CLJN.CL.ElecUtilSegment
A subdivision of an electrical distribution network, particularly a line for the transmission of electricity

a) electricalSegmentType - OH Primary, UG Primary, OH Secondary, UG Secondary, etc.
b) cableMaterial - AL, copper, etc.
c) location - aboveground, underground, etc.
e) voltage - 208Y-120V, 480Y-277V, etc.
f) utilityOwner -
g) operationalStatus - inservice, abandoned, etc.
h) insulationMaterial - polyCross, none, etc.
i) conductorSize -
j) neutralSize -
k) numberOfConduct -
l) numberOfNeutral -
m) numberOfPhases - 1, 2, 3, etc.
n) circuitID - List is available from CM or PM
o) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
p) contractNumber -
q) dateInService -
r) sdsFeatureName - Electrical Distribution, exterior lighting, etc.
s) sdsFeatureDescription - Armless mount, cross arm, etc.

CLJN.CL.UtilFeat_eElecFacilitySite
Polygon feature class to define boundaries of electrical facility stations

a) utilityFeatureType - Electrical Facility station
b) operationalStatus - inservice, abandoned, etc.
c) numberOfCircuits
d) numberOfSpareBays
e) numberOfTransformers
f) voltageIn - 208Y-120V, 480Y-277V, etc.
g) utilityOwner
h) gisFeatureCollectionMethod - - CAD, Survey Grade GPS, etc.
i) contractNumber
j) equipmentInstallationDate
k) sdsFeatureDescription - Location of substation
l) facilityIDFK - structure number

1.4.7 CLJN.CL.UTILITIES_POL

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System GPS and Spatial Reference Properties." Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

GPS and collect the following attributes:

CLJN.CL.POLUtilNode_oDispenser
A fuel dispenser is a machine at a fueling station that is used to pump fuel into vehicles or AGE equipment

a) polNodeType - Fuel dispenser
b) networkSubType - automotive_diesel, jpts, etc.
c) operationalStatus - inservice, abandoned, etc.
d) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
e) contractNumber
f) dateInService
g) sdsFeatureName - Fuel Dispenser
h) sdsFeatureDescription - Type of fuel, unleaded, ethanol, diesel, etc.

CLJN.CL.UtilFeat_oPumpingFacility
A structure, typically a building, containing pumps, filters, and controls as part of a larger fuel handling system

a) utilityFeatureIDPK
b) utilityFeatureType - off-loading pumping facility
c) networkSubType automotive_diesel, jpts, etc.
d) operationalStatus - inservice, abandoned, etc.
e) gisFeatureCollectionMethod - - CAD, Survey Grade GPS, etc.
f) contractNumber
g) equipmentInstallationDate
h) sdsFeatureDescription -

1.4.8 CLJN.CL.UTILITIES_STORMWATER

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System GPS and Spatial Reference Properties." Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

GPS and collect the following attributes:

CLJN.CL.Impoundment_Stormwater
An accumulation of storm water that is impounded by a dam or weir

a) permitID - Permit Number
b) impoundmentType - minimumPool, topOfFloodControl, etc.
c) waterSurfaceElevation
d) waterSurfaceElevationUOM - foot, inch, meter, etc.
e) dateConstructed
f) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
g) contractNumber
h) operationalStatus - inservice, abandoned, etc.
i) stormwaterTreatmentType - Infiltration Basin, Constructed Wetlands, etc.
j) utilityOwner

CLJN.CL.StormwaterUtilityNode_swInlet
The location at which stormwater is collected/received into the stormwater network

a) stormwaterUtilityNodeIDPK - Structure ID
b) stormwaterNodeType - swInlet description
c) networkSubType - stormWater
d) stormwaterInletType - Inlet, Headwall, etc.

e) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
f) contractNumber
g) equipmentInstallationDate
h) sdsFeatureDescription -
i) operationalStatus inservice, abandoned, etc.

CLJN.CL.StormwaterUtilitySegment
A subdivision of a stormwater network, particularly a pipeline or drainage ditch for the transport of stormwater, between the source, holding facilities, and/or treatment facilities

a) diameter
b) diameterUOM - inch
c) pipeMaterial - cement, plastic, etc.
d) isLined - YES / NO
e) downstreamInvertElevation
f) upstreamInvertElevation
g) gisFeatureCollectionMethod - - CAD, Survey Grade GPS, etc.
h) contractNumber
i) equipmentInstallationDate
j) sdsFeatureName - Stormwater pipe, Open Ditch, etc.
k) sdsFeatureDescription
l) operationalStatus - inservice, abandoned, etc.
m) stormwaterPipeStyle
n) stormwaterSegmentType - open ditch, closed under other feature type, etc.

CLJN.CL.StorUtilNode_swManhole
A storm water manhole is an underground concrete structure with a top opening used for collecting and routing storm water runoff through underground pipes

a) stormwaterNodeType
b) stormwaterUtilityNodeIDPK - Structure Number
c) numberOfPipes
d) operationalStatus - inservice, abandoned, etc.
e) stormwaterBasinIDFK - Basin id
f) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
g) contractNumber
h) equipmentInstallationDate
i) sdsFeatureName
j) sdsFeatureDescription

1.4.9 CLJN.CL.UTILITIES_THERMAL

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System GPS and Spatial Reference Properties." Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

GPS and collect the following attributes:

CLJN.CL.GeothermalWell
A geothermal well is part of a central heating and/or cooling system

that pumps heat to or from the ground

a) geothermalWellIDPK - Well ID
b) pipeMaterial - AL, stainless_steel, etc.
c) geothermalWellCasingMaterial
d) thermalInsulationMaterial - MINERAL_FIBER, ARMAFLEX, etc.
e) geothermalWellDepth
f) geothermalWellDepthUOM - foot, inch, meter, etc.
g) downholePipeDiameter
h) downholePipeDiameterUOM - foot, inch, meter, etc.
i) hasBentoniteSeal - YES / NO
j) hasPump - YES / NO
k) operationalStatus - inservice, abandoned, etc.
l) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
m) contractNumber
n) designDrawingNumber
o) equipmentInstallationDate
p) sdsFeatureDescription - Associated Building Number
q) geothermalPipeType
r) xLocation
s) xLocationUOM - foot, inch, meter, etc.
t) yLocation
u) yLocationUOM - foot, inch, meter, etc.

CLJN.CL.TherUtilNode
The Thermal Fitting Type bend, cap, tee, etc. subclass represents the joint between two lines

a) thermalUtilityNodeIDPK
b) thermalNodeType - tFittingType bend, cap, tee, etc.
c) diameter
d) diameterUOM - foot, inch, meter, etc.
e) operationalStatus - inservice, abandoned, etc.
f) fittingType - bend, cap, tee, etc.
g) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
h) contractNumber
i) dateInService
j) sdsFeatureName
k) sdsFeatureDescription
l) depth
m) depthUOM - foot, inch, meter, etc.
n) facilityNumber
o) fittingType - bend, cap, tee, etc.
p) projectID
q) utilityOwner

CLJN.CL.TherUtilSegment
A subdivision of a thermal distribution network, particularly a pipeline for the transmission of chilled water, refrigerant, hot water, or steam

a) thermalSegmentType - tMainLine, tServiceLine
b) networkSubType
c) operationalStatus - inservice, abandoned, etc.
d) material - AL, stainless_steel, etc.
e) pipeLocation - aboveground, underground, etc.
f) diameter

g) diameterUOM - foot, inch, meter, etc.
h) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
i) contractNumber
j) dateInService
k) sdsFeatureName
l) sdsFeatureDescription
m) cathodicProtection - YES / NO
n) depth
o) depthUOM - foot, inch, meter, etc.
p) facilityNumber
q) pipeType - circular, box, etc.
r) projectID
s) utilityOwner

CLJN.CL.TherUtilNode_tProdStruc
Thermal production structures are facilities which produce steam, high-temperature water, low-temperature water, dual-temperature water or chilled water

a) thermalNodeType - facility which produce steam, etc.
b) Capacity
c) CapacityUOM - foot, inch, meter, etc.
d) operationalStatus - inservice, abandoned, etc.
e) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
f) contractNumber
g) dateInService
h) sdsFeatureName
i) sdsFeatureDescription
j) facilityNumber
k) utilityOwner

CLJN.CL.TherUtilNode_tSystemValve
A thermal system valve is a device installed in a pipeline to isolate flow

a) thermalNodeType
b) systemValveType - gate, ball, etc.
c) diameter
d) diameterUOM - foot, inch, meter, etc.
e) operationalStatus - inservice, abandoned, etc.
f) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
g) contractNumber
h) dateInService
i) depth
j) depthUOM - foot, inch, meter, etc.
k) utilityOwner
l) valveMaterial - AL, stainless_steel, etc.

CLJN.CL.UtilFeat_tUGEnclosureAccess
A point feature class for locating the access point to a thermal manhole junction

a) utilityFeatureType - SCADA, UGEnclosureAccess point, etc.
b) networkSubType - steamSupply, steamReturn, etc.
c) networktype -
d) operationalStatus - inservice, abandoned, etc.

e) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
f) contractNumber
g) diameter
h) diameterUOM - inch, feet, meter, etc.
i) sdsFeatureName - steam pit, etc.

1.4.10 CLJN.CL.UTILITIES_WASTEWATER

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System GPS and Spatial Reference Properties." Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

GPS and collect the following attributes:

CLJN.CL.UtilFeat_sPretreatmentDevice
A wastewater pretreatment device is a piece of equipment that removes contaminants before they enter the waste system, etc.

a) utilityFeatureIDPK - Structure Number
b) utilityFeatureType - Pretreatment Device see existing data
c) operationalStatus - inservice, abandoned, etc.
d) pretreatmentDeviceType - OWS, Trap, etc.
e) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
f) contractNumber
g) equipmentInstallationDate
h) sdsFeatureDescription - detailed description

CLJN.CL.UtilityFeature_sPumpStation
This is a collection of waste water Pump Station is a facility, which indications total capacity for the station

a) utilityFeatureIDPK - Structure Number
b) utilityFeaturetype - Pump station, etc.
c) networkType - wastewater network subtype….
d) numberOfPumps -
e) totalDesignCapacity -
f) designCapacityUOM -
g) totalRatedFlow
h) ratedFlowUOM - GPM, CF_SEC, etc.
i) operationalStatus - inservice, abandoned, etc.
j) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
k) contractNumber
l) equipmentInstallationDate
m) sdsFeatureName
n) sdsFeatureDescription

CLJN.CL.UtilityFeature_sSCADASensor
The SCADA sensor is a feature that is used to remotely measure the status of network components

a) utilityFeatureIDPK - Structure Number
b) utilityFeatureType - SCADA
c) networkType - wastewater

d) operationalStatus - inservice, abandoned, etc.
e) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
f) contractNumber
g) equipmentInstallationDate
h) sdsFeatureName
i) sdsFeatureDescription - Antenna Radio to Location

CLJN.CL.UtilityFeature_sSepticTank
A wastewater septic tank is a small-scale anaerobic digester and leach field designed to treat wastewater from an individual facility, and is not connected to the wastewater collection system

a) utilityFeatureIDPK - Structure Number
b) utilityFeatureType - septic tank
c) storageTankProduct - domestic wastewater
d) volume
e) volumeUOM - usGallon, cubicMeter, etc.
f) isRegulated - YES / NO
g) operationalStatus - inservice, abandoned, etc.
h) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
i) contractNumber
j) equipmentInstallationDate
k) sdsFeatureName - Septic Tank
l) sdsFeatureDescription - Location area name

CLJN.CL.WastUtilNode_sCleanOut
A clean out is an access point in a lateral used for maintenance purposes

a) wastewaterNodeType - Cleanout
b) material - PVC, etc.
c) diameter
d) diameterUOM - inch, meter, etc.
e) operationalStatus - inservice, abandoned, etc.
f) mediaID - GIS Collection Method - - CAD, Survey Grade GPS, etc.
g) contractNumber
h) utilityOwner

CLJN.CL.WastUtilNode_sFitting
The wastewater fitting that represents the join between two lines

a) fittingType - Bend, Cap, Tee, etc.
b) sdsFeatureDescription - Ben, Cap, Tee, Wye, etc.
c) diameter
d) diameterUOM - foot, inch, meter, etc.
e) operationalStatus - inservice, abandoned, etc.
f) material - PVC, precast, stainless steel, etc.
g) mediaID - GIS Collection Method - - CAD, Survey Grade GPS, etc.
h) contractNumber
i) fittingType - bend, cap, tee, etc.
j) utilityOwner

CLJN.CL.WastUtilNode_sManhole

The wastewater manhole represents an access point between two or more lines

a) wastewaterNodeType - sManhole
b) operationalStatus - inservice, abandoned, etc.
c) numberOfPipes
d) pipeMaterial - precast brick, etc.
e) diameter
f) diameterUOM - inch, etc.
g) rimElevation
h) rimElevationUOM - foot, inch, meter, etc.
i) mediaID - GIS Collection Method - - CAD, Survey Grade GPS, etc.
j) contractNumber
k) dateInService
l) sdsFeatureName - Manhole, Valve box, etc.
m) manholeMaterial - precast brick, etc.
n) utilityOwner

CLJN.CL.WastUtilNode_sPump
A wastewater pump is a piece of equipment that adds energy to a fluid being conveyed through a pipe or other closed conduit

a) facilityNumber
b) numberOfPumps
c) operationalStatus - inservice, abandoned, etc.
d) wastewaterNodeType - sPump
e) ratedFlow
f) ratedFlowUOM - GPM, CF_SEC, etc.
g) pumpHorsepower
h) contractNumber
i) dateInService
j) mediaID - GIS Collection Method - - CAD, Survey Grade GPS, etc.
k) sdsFeatureName - Wastwater Pump, Lift Station, etc.
l) utilityOwner

CLJN.CL.WastUtilNode_sSystemValve
A system valve is a facility that is fitted to a pipeline or orifice in which the closure member is either rotated or moved transversely or longitudinally in the waterway so as to control or stop the flow

a) wastewaterNodeType - sSystemValve
b) valveMaterial - stainless_steel, etc.
c) diameter
d) diameterUOM - inch, meter, etc.
e) operationalStatus - inservice, abandoned, etc.
f) valveType - gate, butterfly, check, etc.
g) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
h) contractNumber
i) dateInService
j) utilityOwner

CLJN.CL.WastUtilNode_sTreatmentPlant
A facility designed to treat wastewater using physical, chemical and/or

biological processes prior to discharge into receiving waters

a) wastewaterNodeType - facility designed to treat wastewater
b) Capacity
c) CapacityUOM - gallons, meter, etc.
d) ContractNumber
e) operationalStatus - inservice, abandoned, etc.
f) facilityNumber - Structure Number
g) mediaID - GIS Collection Method - - CAD, Survey Grade GPS, etc.
h) dateInService
i) sdsFeatureName

CLJN.CL.WastUtilSegment
Wastewater Line - A pipeline for the transport of sewage or industrial waste between the source, holding facilities, and/or treatment facilities

a) wastewaterSegmentType - Gravity, Force Main, Service etc.
b) utilityOwner - CLJN / ONWASA
c) operationalStatus - inservice, abandoned, etc.
d) pipeMaterial - PVC, VC, etc.
e) isLined - YES / NO
f) diameter
g) diameterUOM -foot, inch, meter, etc.
h) mediaID - GIS Collection Method - - CAD, Survey Grade GPS, etc.
i) contractNumber
j) dateInService
k) sdsFeatureName -
l) invertElevationDownstream
m) invertElevationUpstream
n) invertElevationUOM - foot, inch, meter, etc.
o) slope

1.4.11 CLJN.CL.UTILITIES_WATER

GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) and Spatial Reference Properties." Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

GPS and collect the following attributes:

CLJN.CL.UtilFeat_wUGEnclosureAccess
A point feature class for locating the access point to a water manhole junction

a) utilityFeatureIDPK - Manhole Number
b) numberOfPipes
c) groundElevation
d) elevationUOM - inch, foot, meter, etc.
e) operationalStatus - inservice, abandoned, etc.
f) gisFeatureCollectionMethod - CAD, Survey Grade GPS, etc.
g) contractNumber

h) equipmentInstallationDate
i) sdsFeatureName - Manhole
j) utilityFeatureType - wUGEnclosureAccess
k) waterServiceAreaIDFK - Holcomb, Hadnot Pt, Onslow Beach, etc.

CLJN.CL.WaterUtilNode_wFittingType bend, cap, tee, etc.
The water fitting class represents the joint between two lines in the water network

a) waterNodeType - fitting class represents transition between two lines
b) diameter -
c) diameterUOM - inch, meter, etc.
d) operationalStatus -inservice, abandoned, etc.
e) fittingType - reducer, bend, cap, tee, etc.
f) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
g) contractNumber
h) dateInServicen

CLJN.CL.WaterUtiNode_wHydrant
A water distribution point that enables fire fighters to attach fire hoses

a) waterNodeType - wHydrant
b) networkSubType - fireProtectionwater
c) operationalStatus - inservice, abandoned, etc.
d) connectionType - fireconnect, firehydrant
e) facilityNumber - Structure number if connection is to structure
f) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
g) contractNumber
h) dateInService

CLJN.CL.WaterUtilNode_wMeterPoint
A water meter point represents the location of the metering device

a) waterNodeType - meterPoint
b) operationalStatus - inservice, abandoned, etc.
c) projectID - area name
d) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
e) contractNumber
f) diameter
g) diameterUOM - foot, inch, meter, etc.
h) dateInService

CLJN.CL.WateUtilNode_wReliefValve
A valve used to relieve pressure

a) operationalStatus
b) sdsFeatureDescription
c) sdsFeatureName - Air Release Valve
d) contractNumber
e) dateInService
f) diameter
g) diameterUOM

h) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
i) projectID
j) utilityOwner

CLJN.CL.WaterUtilNode_wSystemValve
A valve used to regulate pressure, isolate, throttle flow, prevent backflow

a) waterNodeType - wSystemValve
b) diameter
c) diameterUOM - foot, inch, meter, etc.
d) operationalStatus - inservice, abandoned, etc.
e) valveType - gate, ball, etc.
f) projectID - MCASNR, MCBCLJN, Geiger, etc
g) mediaID - GIS Collection Method -- CAD, Survey Grade GPS, etc.
h) contractNumber
i) dateInService
j) valveType - Gate Valve, Post Indicator Valve, etc.

CLJN.CL.WaterUtilSegment
A subdivision of a water distribution network, particularly a distribution pipeline

a) networkSubType - potable water, raw water, Service, Fire etc.
b) material - PVC, Ductile Iron, Cement, etc,
c) diameter
d) diameterUOM - inch
e) utilityOwner - MBCCLJN, Onwasa, etc.
f) operationalStatus -inservice, abandoned, etc.
g) projectID
h) mediaID - GIS Collection Method /- CAD, Survey Grade GPS, etc.
i) contractNumber
j) dateInService
k) sdsFeatureName - Main, Service, Fire, AIP, Raw, etc.
l) invertElevationDownstream
m) invertElevationUpstream

CLJN.CL.WateUtilNode_wProdStructure
Water production structures are facilities which produce raw or treated water

a) waterNodeType - produce treated water, etc.
b) facilityNumber - Structure Number
c) capacity
d) capacityUOM - gallons per day, etc
e) operationalStatus - inservice, abandoned, etc.
f) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
g) contractNumber
h) dateInService
i) sdsFeatureName - Water Treatment Plant, Location
j) sdsFeatureDescription - Describe Plant purpose

CLJN.CL.WateUtilNode_wStorageStructure

Water storage structures are facilities that store large volumes of water - Water Tank)

a) facilityNumber - structure number
b) waterNodeType - water Storage Structure
c) storageTankProduct - treatedWater, rawWater, etc.
d) volume
e) volumeUOM - gallons, etc.
f) tankType - Elevated, Under Ground, Above Ground, etc.
g) operationalStatus - inservice, abandoned, etc.
h) width
i) widthUOM - foot, etc.
j) groundElevation
k) invertElevation
l) overflowElevation
m) surfaceElevation
n) elevationUOM - foot, etc.
o) projectID - Named Area of Location, Hadnot Point, etc.
p) mediaID - GIS Collection Method - CAD, Survey Grade GPS, etc.
q) contractNumber
r) dateInService
s) storageTypeProduct - Raw water or Potable Water

1.4.12 Non-Compliance

Failure to follow the specification outlined in this document will result in non-acceptance of data deliverable.

Note: Geospatial data delivery does not replace record drawing requirements.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

-- End of Section --

SECTION 02 41 00

DEMOLITION
05/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.6	(2006) Safety & Health Program Requirements for Demolition Operations - American National Standard for Construction and Demolition Operations

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2014) Safety and Health Requirements Manual

U.S. DEFENSE LOGISTICS AGENCY (DLA)

DLA 4145.25	(Jun 2000; Reaffirmed Oct 2010) Storage and Handling of Liquefied and Gaseous Compressed Gases and Their Full and Empty Cylinders http://www.aviation.dla.mil/UserWeb/aviationengineering/

U.S. DEPARTMENT OF DEFENSE (DOD)

DOD 4000.25-1-M	(2006) MILSTRIP - Military Standard Requisitioning and Issue Procedures
MIL-STD-129	(2014; Rev R; Change 1 2018; Change 2 2019) Military Marking for Shipment and Storage

U.S. FEDERAL AVIATION ADMINISTRATION (FAA)

FAA AC 70/7460-1	(2016; Rev L; Change 2) Obstruction Marking and Lighting

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61	National Emission Standards for Hazardous Air Pollutants
49 CFR 173.301	Shipment of Compressed Gases in Cylinders and Spherical Pressure Vessels

1.2 PROJECT DESCRIPTION

1.2.1 Definitions

1.2.1.1 Demolition

Demolition is the process of wrecking or taking out any load-supporting structural member of a facility together with any related handling and disposal operations.

1.2.1.2 Demolition Plan

Demolition Plan is the planned steps and processes for managing demolition activities and identifying the required sequencing activities and disposal mechanisms.

1.2.2 Demolition Plan

Prepare a Demolition Plan and submit proposed demolition, and removal procedures for approval before work is started. Include in the plan procedures for careful removal and disposition of materials specified to be salvaged, coordination with other work in progress, a disconnection schedule of utility services, and airfield lighting, a detailed description of methods and equipment to be used for each operation and of the sequence of operations. Coordinate with Waste Management Plan in accordance with Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL. Include statements affirming Contractor inspection of the existing roof deck and its suitability to perform as a safe working platform or if inspection reveals a safety hazard to workers, state provisions for securing the safety of the workers throughout the performance of the work. Provide procedures for safe conduct of the work in accordance with EM 385-1-1. Plan shall be approved by Contracting Officer prior to work beginning.

1.2.3 General Requirements

Do not begin demolition until authorization is received from the Contracting Officer. Remove rubbish and debris from the station daily project site; do not allow accumulations inside or outside the building . The work includes demolition, salvage of identified items and materials, and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Store materials that cannot be removed daily in areas specified by the Contracting Officer. In the interest of occupational safety and health, perform the work in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections.

1.3 ITEMS TO REMAIN IN PLACE

Take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the Government. Repair or replace damaged items as approved by the Contracting Officer. Coordinate the work of this section with all other work indicated. Construct and maintain shoring, bracing, and supports as required. Ensure that structural elements are not overloaded. Increase structural supports or add new supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract. Do not overload structural elements pavements to remain. Provide new supports and reinforcement for existing construction weakened by demolition, deconstruction, or removal work. Repairs, reinforcement, or structural

replacement require approval by the Contracting Officer prior to performing such work.

1.3.1 Existing Construction Limits and Protection

Do not disturb existing construction beyond the extent indicated or necessary for installation of new construction. Provide temporary shoring and bracing for support of building components to prevent settlement or other movement. Provide protective measures to control accumulation and migration of dust and dirt in all work areas. Remove snow, dust, dirt, and debris from work areas daily.

1.3.2 Weather Protection

For portions of the building to remain, protect building interior and materials and equipment from the weather at all times. Where removal of existing roofing is necessary to accomplish work, have materials and workmen ready to provide adequate and temporary covering of exposed areas.

1.3.3 Trees

Protect trees within the project site which might be damaged during demolition or deconstruction, and which are indicated to be left in place, by a 6 foot high fence. Erect and secure fence a minimum of 5 feet from the trunk of individual trees or follow the outer perimeter of branches or clumps of trees. Replace any tree designated to remain that is damaged during the work under this contract with like-kind or as approved by the Contracting Officer.

1.3.4 Utility Service

Maintain existing utilities indicated to stay in service and protect against damage during demolition and deconstruction operations. Prior to start of work, utilities serving each area of alteration or removal will be shut off by the Government and disconnected and sealed by the Contractor .

1.3.5 Facilities

Protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities. Floors, roofs, walls, columns, pilasters, and other structural components that are designed and constructed to stand without lateral support or shoring, and are determined to be in stable condition, must remain standing without additional bracing, shoring, or lateral support until demolished or deconstructed, unless directed otherwise by the Contracting Officer. Ensure that no elements determined to be unstable are left unsupported and place and secure bracing, shoring, or lateral supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract.

1.4 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.5 AVAILABILITY OF WORK AREAS

Areas in which the work is to be accomplished will be available in accordance with the following schedule:

Schedule	
Area	Date
Per COR	Per COR

1.6 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. the Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Demolition Plan; G
Deconstruction Plan; G
Existing Conditions

SD-07 Certificates

Notification; G

SD-11 Closeout Submittals

Receipts

1.7 QUALITY ASSURANCE

Submit timely notification of demolitionand renovation projects to Federal, State, regional, and local authorities in accordance with 40 CFR 61, Subpart M. Notify the Regional Office of the United States Environmental Protection Agency (USEPA) State's environmental protection agency local air pollution control district/agency and the Contracting Officer in writing 10 working days prior to the commencement of work in accordance with 40 CFR 61, Subpart M. Comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," conform to the safety requirements contained in ASSP A10.6. Comply with the Environmental Protection Agency requirements specified. Use of explosives will not be permitted.

1.7.1 Dust and Debris Control

Prevent the spread of dust and debris to occupied portions of the building on airfield pavements and avoid the creation of a nuisance or hazard in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution. Vacuum and dust the work area daily. Sweep pavements as often as necessary to control the spread of debris that may result in foreign object damage potential to aircraft.

1.8 PROTECTION

1.8.1 Traffic Control Signs

a. Where pedestrian and driver aircraft safety is endangered in the area of removal work, use traffic barricades with flashing lights. Anchor barricades in a manner to prevent displacement by wind, jet or prop blast. Notify the Contracting Officer prior to beginning such work.

Provide a minimum of 2 FAA type L-810 steady burning red obstruction lights on temporary structures (including cranes) over 100 feet, but less than 200 ft, above ground level. The use of LED based obstruction lights are not permitted. For temporary structures (including cranes) over 200 ft above ground level provide obstruction lighting in accordance with FAA AC 70/7460-1. Light construction and installation shall comply with FAA AC 70/7460-1. Lights shall be operational during periods of reduced visibility, darkness, and as directed by the Contracting Officer. Maintain the temporary services during the period of construction and remove only after permanent services have been installed and tested and are in operation.

1.8.2 Protection of Personnel

Before, during and after the demolition work continuously evaluate the condition of the structure being demolished and take immediate action to protect all personnel working in and around the project site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.9 FOREIGN OBJECT DAMAGE (FOD)

Aircraft and aircraft engines are subject to FOD from debris and waste material lying on airfield pavements. Remove all such materials that may appear on operational aircraft pavements due to the Contractor's operations. If necessary, the Contracting Officer may require the Contractor to install a temporary barricade at the Contractor's expense to control the spread of FOD potential debris. The barricade shall include a fence covered with a fabric designed to stop the spread of debris. Anchor the fence and fabric to prevent displacement by winds or jet/prop blasts. Remove barricade when no longer required.

1.10 RELOCATIONS

Perform the removal and reinstallation of relocated items as indicated with workmen skilled in the trades involved. Repair or replace items to be relocated which are damaged by the Contractor with new undamaged items as approved by the Contracting Officer.

1.11 EXISTING CONDITIONS

Before beginning any demolition or deconstruction work, survey the site and examine the drawings and specifications to determine the extent of the work. Record existing conditions in the presence of the Contracting Officer showing the condition of structures and other facilities adjacent to areas of alteration or removal. Photographs sized 4 inch will be acceptable as a record of existing conditions. Include in the record the

elevation of the top of foundation walls, finish floor elevations, possible conflicting electrical conduits, plumbing lines, alarms systems, the location and extent of existing cracks and other damage and description of surface conditions that exist prior to before starting work. It is the Contractor's responsibility to verify and document all required outages which will be required during the course of work, and to note these outages on the record document. Submit survey results.

PART 3 EXECUTION

2.1 EXISTING FACILITIES TO BE REMOVED

Inspect and evaluate existing structures onsite for reuse. Existing construction scheduled to be removed for reuse shall be disassembled. Dismantled and removed materials are to be separated, set aside, and prepared as specified, and stored or delivered to a collection point for reuse, remanufacture, recycling, or other disposal, as specified. Materials shall be designated for reuse onsite whenever possible.

2.1.1 Structures

a. Remove existing structures indicated to be removed as indicated in other constrcution documents.

b. Demolish items in a systematic manner. Demolish concrete and masonry walls in small sections. Remove items with suitable methods as approved by the Contracting Officer.

c. Locate demolition equipment throughout the structure and remove materials so as to not impose excessive loads to supporting walls, floors, or framing.

2.1.2 Utilities and Related Equipment

2.1.2.1 General Requirements

Do not interrupt existing utilities serving occupied or used facilities, except when authorized in writing by the Contracting Officer. Do not interrupt existing utilities serving facilities occupied and used by the Government except when approved in writing and then only after temporary utility services have been approved and provided. Do not begin demolition or deconstruction work until all utility disconnections have been made. Shut off and cap utilities for future use, as indicated.

2.1.2.2 Disconnecting Existing Utilities

Remove existing utilities, as indicated uncovered by work and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Contracting Officer. When utility lines are encountered but are not indicated on the drawings, notify the Contracting Officer prior to further work in that area. Remove meters and related equipment and deliver to a location on the station in accordance with instructions of the Contracting Officer.

2.1.3 Roofing

Partially remove existing roof system and associated components as indicated. Remove existing roofing system to effect the connections with new flashing or roofing. Cut existing felts membrane cap sheet, wood

blocking, and insulation along straight lines. Partially remove roofing system, wood blocking, and insulation without damaging the roof deck. Sequence work to minimize building exposure between demolition or deconstruction and new roof materials installation.

2.1.3.1 Temporary Roofing

Install temporary roofing and flashing as necessary to maintain a watertight condition throughout the course of the work. Remove temporary work prior to installation of permanent roof system materials unless approved otherwise by the Contracting Officer. Make provisions for worker safety during demolition, deconstruction, and installation of new materials as described in paragraphs entitled "Statements" and "Regulatory and Safety Requirements."

2.1.3.2 Reroofing

When removing the existing roofing system from the roof deck, remove only as much roofing as can be recovered by the end of the work day, unless approved otherwise by the Contracting Officer. Do not attempt to open the roof covering system in threatening weather. Reseal all openings prior to suspension of work the same day.

2.1.4 Masonry

Sawcut and remove masonry so as to prevent damage to surfaces to remain, to removed materials being salvaged and to facilitate the installation of new work. Where new masonry adjoins existing, the new work shall abut or tie into the existing construction as indicated specified for the new work. Provide square, straight edges and corners where existing masonry adjoins new work and other locations.

2.1.5 Concrete

Saw concrete along straight lines to a depth of a minimum 2 inch. Make each cut in walls perpendicular to the face and in alignment with the cut in the opposite face. Break out the remainder of the concrete provided that the broken area is concealed in the finished work, and the remaining concrete is sound. At locations where the broken face cannot be concealed, grind smooth or saw cut entirely through the concrete.

2.1.6 Structural Steel

Do not disturb, protect as necessary,and protect from the weather.

2.1.7 Miscellaneous Metal

Demolish as indicated.

2.1.8 Carpentry

Demolish as indicated.

2.1.9 Acoustic Ceiling Tile

Partially remove, neatly stack, and only re-install the undamaged acoustic ceiling tiles.

2.1.10 Airfield Lighting

Do not disturb, protect as necessary, except as indicated.

2.1.11 Patching

Where removals leave holes and damaged surfaces exposed in the finished work, patch and repair these holes and damaged surfaces to match adjacent finished surfaces, using on-site materials when available. Where new work is to be applied to existing surfaces, perform removals and patching in a manner to produce surfaces suitable for receiving new work. Finished surfaces of patched area shall be flush with the adjacent existing surface and shall match the existing adjacent surface as closely as possible as to texture and finish. Patching shall be as specified and indicated, and shall include:

a. Concrete and Masonry: Completely fill holes and depressions, caused by previous physical damage or left as a result of removals in existing masonry walls to remain, with an approved masonry patching material, applied in accordance with the manufacturer's printed instructions.

b. Where existing partitions have been affected by the SOW , patch to match existing.

c. Patch acoustic lay-in ceiling where partitions have been affected by the SOW, patch to match existing.

2.1.12 Air Conditioning Equipment

Disconnect and re-connect all affected air conditioning, refrigeration, and other equipment containing refrigerants without releasing chlorofluorocarbon refrigerants to the atmosphere in accordance with the Clean Air Act Amendment of 1990.

2.1.13 Locksets on Swinging Doors

Remove all locksets from all swinging doors indicated to be removed and disposed of. Deliver the locksets and related items to a designated location for receipt by the Contracting Officer after removal.

2.1.14 Mechanical Equipment and Fixtures

Disconnect mechanical hardware at the nearest connection to existing services to remain, unless otherwise noted. Disconnect mechanical equipment and fixtures at fittings. Do not remove/disconnect equipment and fixtures until approved.

2.1.14.1 Piping

Disconnect piping at unions, flanges and valves, and fittings as required to reduce the pipe into straight lengths for practical storage. Store salvaged piping according to size and type. If the piping that remains can become pressurized due to upstream valve failure, end caps, blind flanges, or other types of plugs or fittings with a pressure gage and bleed valve shall be attached to the open end of the pipe to ensure positive leak control. Carefully dismantle piping that previously contained gas, gasoline, oil, or other dangerous fluids, with precautions taken to prevent injury to persons and property. Store piping outdoors until all fumes and residues are removed. Box prefabricated supports, hangers, plates, valves,

and specialty items according to size and type. Wrap sprinkler heads individually in plastic bags before boxing. Classify piping not designated for salvage, or not reusable, as scrap metal.

2.1.14.2 Ducts

Remove affected duct to allow the proper installation of the new exterior wall system. Re-connect using the existing items or replace with new.

2.1.15 Electrical Equipment and Fixtures

Salvage motors, motor controllers, and operating and control equipment that are attached to the driven equipment. Salvage wiring systems and components. Box loose items and tag for identification. Disconnect primary, secondary, control, communication, and signal circuits at the point of attachment to their distribution system.

2.1.15.1 Fixtures

Remove and salvage electrical fixtures. Reconnect in the same place.

2.1.15.2 Electrical Devices

Remove and salvage switches, switchgear, transformers, conductors including wire and nonmetallic sheathed and flexible armored cable, regulators, meters, instruments, plates, circuit breakers, panelboards, outlet boxes, and similar items. Box and tag these items for identification according to type and size.

2.1.15.3 Wiring Ducts or Troughs

Remove and salvage wiring ducts or troughs. Dismantle plug-in ducts and wiring troughs into unit lengths. Remove plug-in or disconnecting devices from the busway and store separately.

2.1.15.4 Conduit and Miscellaneous Items

Salvage conduit except where embedded in concrete or masonry. Consider corroded, bent, or damaged conduit as scrap metal. Sort straight and undamaged lengths of conduit according to size and type. Classify supports, knobs, tubes, cleats, and straps as debris to be removed and disposed.

2.1.16 Items With Unique/Regulated Disposal Requirements

Remove and dispose of items with unique or regulated disposal requirements in the manner dictated by law or in the most environmentally responsible manner.

2.2 DISPOSITION OF MATERIAL

2.2.1 Title to Materials

Except for salvaged items specified in related Sections, and for materials or equipment scheduled for salvage, all materials and equipment removed and not reused or salvaged, shall become the property of the Contractor and shall be removed from Government property. Title to materials resulting from demolition and deconstruction, and materials and equipment to be removed, is vested in the Contractor upon approval by the Contracting Officer of the Contractor's demolition, deconstruction, and removal

procedures, and authorization by the Contracting Officer to begin demolition and deconstruction. The Government will not be responsible for the condition or loss of, or damage to, such property after contract award. Showing for sale or selling materials and equipment on site is prohibited.

2.2.2 Transportation Guidance

Ship all ODS containers in accordance with MIL-STD-129, DLA 4145.25 (also referenced one of the following: Army Regulation 700-68, Naval Supply Instruction 4440.128C, Marine Corps Order 10330.2C, and Air Force Regulation 67-12), 49 CFR 173.301, and DOD 4000.25-1-M.

2.2.3 Unsalvageable and Non-Recyclable Material

Dispose of unsalvageable and non-recyclable noncombustible material off-Base. 2.3 CLEANUP

Remove debris and rubbish from basement and similar excavations. Remove and transport the debris in a manner that prevents spillage on streets or adjacent areas. Apply local regulations regarding hauling and disposal.

2.4 DISPOSAL OF REMOVED MATERIALS

2.4.1 Regulation of Removed Materials

Dispose of debris, rubbish, scrap, and other nonsalvageable materials resulting from removal operations with all applicable federal, state and local regulations as contractually specified in the Waste Management Plan. Storage of removed materials on the project site is prohibited.

2.4.2 Burning on Government Property

Burning of materials removed from demolished and deconstructed structures will not be permitted on Government property

2.4.3 Removal from Government Property

Transport waste materials removed from demolished and deconstructed structures, except waste soil, from Government property for legal disposal. Dispose of waste soil as directed.

2.5 REUSE OF SALVAGED ITEMS

Recondition salvaged materials and equipment designated for reuse before installation. Replace items damaged during removal and salvage operations or restore them as necessary to usable condition.

-- End of Section --

SECTION 02 82 16

REMOVAL AND DISPOSAL OF ASBESTOS MATERIALS (CAMP LEJEUNE COMPLEX)

03/10

SECTION 02 82 16

REMOVAL AND DISPOSAL OF ASBESTOS MATERIALS
(CAMP LEJEUNE COMPLEX)

03/10

PART 1 GENERAL

1.1 APPLICABLE NORTH CAROLINA LAW

North Carolina State General Statues 130A, Article 19-444-452 and 10A North Carolina Administrative Chapter (NCAC) 41C .0600 through .0611.

1.1.1 N.C. (DHHS-HHCU) Asbestos Accreditation

All personnel involved in asbestos removal shall be currently accredited for asbestos removal by N.C. (DHHS-HHCU). An application for accreditation may be requested from the State of North Carolina, Health Hazards Control Unit, Department of Health and Human Services, Division of Public Health,; 1912 Mail Service Center, Raleigh, NC 27699-1912; (919) 707-5950. Out of State accreditation will not be accepted.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z88.2	(1992) Respiratory Protection

ASTM INTERNATIONAL (ASTM)

ASTM C 732	(1995) Aging Effects of Artificial Weathering on Latex Sealants
ASTM D 1331	(1989; R 1995) Surface and Interfacial Tension of Solutions of Surface-Active Agents
ASTM E 84	(2000a) Surface Burning Characteristics of Building Materials
ASTM E96/E96M	(2016) Standard Test Methods for Water Vapor Transmission of Materials
ASTM E 119	(1998) Fire Tests of Building Construction and Materials
ASTM E 736	(1992) Cohesion/Adhesion of Sprayed Fire-Resistive Materials Applied to Structural Members
ASTM E 1368	(1997) Visual Inspection of Asbestos Abatement Projects

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.103	Respiratory Protection
29 CFR 1926.59	Hazard Communication
29 CFR 1926.1101	Asbestos
40 CFR 61, SUBPART A	General Provisions
40 CFR 61, SUBPART M	National Emission Standard for Hazardous Air Pollutants

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 560/5-85-024	(1985) Guidance for Controlling Asbestos Containing Materials in Buildings
EPA SW-846	(Third Edition; Update IV) Test Methods for Evaluating Solid Waste: Physical/Chemical Methods

UNDERWRITERS LABORATORIES (UL)

UL 586	(1996; Rev thru Aug 1999) High-Efficiency, Particulate, Air Filter Units

1.3 DEFINITIONS

1.3.1 Asbestos Containing Material (ACM)

All building materials that have more than 1% of chrysotile, amosite, crocidolite, tremolite, anthopyhlite, or any other form of asbestos in the serpentine or anthobole class.

1.3.2 Action Level/Permissive Exposure Limit (PEL)

An airborne concentration of asbestos fibers, in the breathing zone of a worker equaling 0.1 fibers per cubic centimeter of air calculated as an 8-hour time weighted average.

1.3.3 Amended Water

Water containing a wetting agent or surfactant with a surface tension of 29 dynes per square centimeter when tested in accordance with ASTM D 1331 shall be utilized. In the event where wetting operations are suspended due to freezing temperatues, the operator or abatement contractor shall record the temperature on Form DHHS 3787..

1.3.4 Area Sampling

Sampling of asbestos fiber concentrations within the asbestos control area and outside the asbestos control area which approximates the concentrations of asbestos in the theoretical breathing zone but is not actually collected in the breathing zone of an employee.

1.3.5 Asbestos

The term asbestos includes chrysotile, amosite, crocidolite, tremolite, anthophyllite, and actinolite and any of these minerals that has been chemically treated or altered. Materials are considered to contain asbestos if the asbestos content is more than 1% of the material by area.

1.3.6 Asbestos Control Area

That area where asbestos removal operations are performed which is isolated by physical boundaries which assist in the prevention of the uncontrolled release of asbestos dust, fibers, or debris. Two examples of an asbestos control area are: a full containment and a "glovebag."

1.3.7 Asbestos Fibers

Those fibers having an aspect ratio of at least 3:1 and longer than 5 micrometers as determined by National Institute for Occupational Safety and Health (NIOSH) Method 7400.

1.3.8 Asbestos Permissible Exposure Limit

0.1 fibers per cubic centimeter of air as an 8-hour time weighted average as defined by 29 CFR 1926.1101 or other federal legislation having legal jurisdiction for the protection of workers health.

1.3.9 Background

Normal airborne asbestos concentration in an area similar to the asbestos abatement area but in an uncontaminated (with asbestos) state.

1.3.10 Contractor

The Contractor is that individual, or entity under contract to the Navy to perform the herein listed work.

1.3.11 Encapsulants

Specific materials in various forms used to chemically entrap asbestos fibers in various configurations to prevent these fibers from becoming airborne. There are four types of encapsulants as follows which must comply with performance requirements as specified herein.

a. Removal Encapsulant (can be used as a wetting agent)

b. Bridging Encapsulant (used to provide a tough, durable surface coating to asbestos containing material)

c. Penetrating Encapsulant (used to penetrate the asbestos containing material down to substrate, encapsulating all asbestos fibers)

d. Lock-Down Encapsulant (used to seal off or "lock-down" minute asbestos fibers left on surfaces from which asbestos containing material has been removed)

1.3.12 Friable Asbestos Material

Material that contains more than 1% asbestos by area and that can be crumbled, pulverized, or reduced to powder by hand pressure when dry.

1.3.13 Full Containment

Those engineering control techniques described in 29 CFR 1926.1101 for major asbestos removal, renovation and demolition operations.

1.3.14 Glovebag Technique

Those asbestos removal and control techniques put forth in 29 CFR 1926.1101.

1.3.15 HEPA Filter Equipment

High efficiency particulate air (HEPA) filtered vacuum and/or exhaust ventilation equipment with a filter system capable of collecting and retaining asbestos fibers. Filters shall retain 99.97 percent of particles 0.3 microns or larger as indicated in UL 586.

1.3.16 Navy Industrial Hygienist (NIH)

That industrial hygienist employed by the Navy to monitor, sample, and/or inspect the work separate from the original construction contract. The NIH can be either a Federal civil servant or a private consultant as determined by the Navy. In some instances the NIH shall perform assigned duties vicariously through a trained subordinate but only with the specific consent of the Contracting Officer.

1.3.17 Nonfriable Asbestos Material

Material that contains asbestos in which the fibers have been temporarily locked in by a bonding agent, coating, binder, or other material so that the asbestos is well bound and will not normally release asbestos fibers during any appropriate use, handling, storage or transportation. It is understood that asbestos fibers will be released under other conditions such as demolition or removal.

1.3.18 PCM - Phased Contrast Microscopy

A method of analyzing air samples for fibers using a light microscope.

1.3.19 PLM - Polarized Light Microscopy

A method of analyzing bulk samples for asbestos in which the sample is illuminated with polarized light (light which vibrates in only one plane) and viewed under a light microscope.

1.3.20 Personal Sampling

Air sampling to determine asbestos fiber concentrations within the breathing zone of a specific employee, performed in accordance with 29 CFR 1926.1101.

1.3.21 Supervising Air Monitor (SAM)

That supervising air monitor hired by the Contractor to perform the herein listed industrial hygiene tasks. In some instances, the SAM can perform this role vicariously through a trained subordinate, but only with the specific consent of the Contracting Officer. Under N.C. Statue, the SAM must make a site visit on any project exceeding 10 days and once every 30 days thereafter.

1.3.22 TEM

Refers to Transmission Electron Microscopy (TEM). Technique whereby a beam of electrons is transmitted through an ultra think specimen, interacting with the specimen as it passes through. An image is formed from the interaction of the electrons transmitted through the specimen; the image is magnified and focused onto an imaging device, such as a fluorescent screen, on a layer of photographic film, or to be detected by a sensor such as a CCB camera.

1.3.23 Time Weighted Average (TWA)

The TWA is an 8-hour time weighted average airborne concentration of asbestos fibers. At least three full shift samples per person are required to establish that person's TWA exposure.

1.3.24 Wetting Agent

That specific agent used to reduce airborne asbestos levels by physically bonding asbestos fibers to material to be removed. An equivalent wetting agent must have a surface tension of at least 29 dynes per square centimeter as tested in accordance with ASTM D 1331. In the event where wetting operations are suspended due to freezing temperatures, the operator or abatement contractor shall record the temperature on Form DHHS 3787.

1.3.25 Project Design Survey

The Project Design Survey is used to provide information to the Project Designer for prepping abatement plans and specifications. Destructive testing is required for a Project Design Survey in order to identify suspect materials. The presence of asbestos in suspect materials are confirmed in a Project Design Survey. A Project Design Survey is required prior to any building renovation or demolition project.

1.4 REQUIREMENTS

1.4.1 Description of Work

The work covered by this section includes the handling of asbestos containing materials which are encountered during repair, construction and demolition projects and describes some of the resultant procedures and equipment required to protect workers and occupants of the building or area, or both, from contact with airborne asbestos fibers. The work also includes the disposal of the generated asbestos containing materials. The asbestos work includes the demolition and removal of asbestos containing material located in identified areas in Part 6. Under normal conditions non-friable or chemically bound materials containing asbestos would not be considered hazardous; however, this material will release airborne asbestos fibers during demolition and removal and therefore must be handled in accordance with North Carolina Regulations.

1.4.2 N. C. (DHHS-HHCU) North Carolina Department of Health and Human Services - Health Hazards Control Unit

Obtain necessary permits in conjunction with asbestos removal, hauling, and disposition, and furnish timely notification of such actions required by federal, state, regional, and local authorities. A permit is only required when you will be abating more than 260 linear feet, 160 square feet, or 35

cubic feet of an asbestos-containing building material. Also, if mechanical means of removing non-friable asbestos is utilized the contractor will need to provide permit. Notify the N.C. (DHHS-HHCU) and the Contracting Officer in writing 10 days prior to the commencement of work. Submit a copy of the permit to the Contracting Officer.

1.4.2.1 N.C. (DHHS-HHCU) mailing address is:

Health Hazards Control Unit
N.C. Department of Health and Human Services
Division of Public Health
1912 Mail Service Center
Raleigh, NC 27699-1912
Phone: (919) 733-0820

1.4.2.2 Changes in Work

Changes in Work which affect items on the attached form shall be covered by an amended form submitted to the same address.

1.4.3 Safety and Health Compliance

In addition to detailed requirements of this specification, comply with those applicable laws, ordinances, criteria, rules, and regulations of federal, state, regional, and local authorities regarding handling, storing, transporting, and disposing of asbestos waste materials. Comply with the applicable requirements of the current issue of 29 CFR 1926.1101, 40 CFR 61, SUBPART A, 40 CFR 61, SUBPART M. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting the work. Where the requirements of this specification, applicable laws, rules, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirement as defined by the Contracting Officer shall apply.

1.4.4 Respiratory Protection Program

Establish and implement a respirator program as required by ANSI Z88.2 and 29 CFR 1910.103.

1.4.5 Supervising Air Monitor (SAM)

Conduct personal area/environmental air sampling and training under the direction of a North Carolina accredited supervising air monitor. For the purpose of this contract, the Contractor shall retain the services of a SAM to perform the Contractor's industrial hygiene tasks.

1.5 SUBMITTALS

Submit 4 copies of the following in accordance with Section 01 33 00.05 20, "Construction Submittal Procedures."

SD-06 Test Reports

Air sampling results

Pressure differential recordings for local exhaust system

Clearance sampling

SD-07 Certificates

Asbestos hazard abatement plan (Abatement Design)

SD-11 Closeout Submittals

Asbestos Waste Shipment Record N.C. (DHHS-HHCU) Form 3787

Daily log

North Carolina permit

Modifications to the North Carolina permit

Asbestos Inspection Reporting Form

Closeout submittals shall be submitted within 60 days of asbestos activity completion.

1.5.1 Asbestos Hazard Abatement Plan (NC Abatement Design)

An asbestos abatement design shall be prepared by a N.C. accredited asbestos abatement designer for each individually permitted removal of more than 260 linear feet, 160 square feet, or 35 cubic feet of regulated asbestos containing materials. The plan shall be prepared, signed, and sealed, including accreditation number and date, by an accredited abatement designer. The respirator program and air monitoring strategies portion of this plan shall be prepared by the supervising air monitor. Such plan shall include but not be limited to the precise personal protective equipment to be used, the location of asbestos control areas including clean and dirty areas, buffer zones, showers, storage areas, change rooms, removal method, interface of trades involved in the construction, sequencing of asbestos related work, disposal plan, type of wetting agent and asbestos sealer to be used, locations of local exhaust equipment, planned air monitoring strategies, and a detailed description of the method to be employed in order to control pollution. The plan shall also include (both fire and medical emergency) response plans. The Contractor and designer shall meet with the Contracting Officer prior to beginning work, to discuss in detail the asbestos plan, including work procedures and safety precautions. The plan will be enforced as if an addition to the specification. Any changes required in the specification as a result of the plan shall be identified specifically in the plan. The plan shall comply with all federal and state requirements and this specification, and shall serve as the North Carolina Abatement Design. Submit a copy of plan to the Contracting Officer.

1.5.2 Air Sampling Results

Complete fiber counting and provide results to the SAM for review within 16 hours. Notify the Contracting Officer immediately of any airborne levels of asbestos fibers in excess of the acceptable limits. Submit sampling results to the Contracting Officer and the affected Contractor employees within 3 working days, signed by the employee performing air sampling, the employee that analyzed the sample, and the SAM.

1.5.3 Pressure Differential Recordings for Local Exhaust System

Provide a local exhaust system that creates a negative pressure of at least 0.02 inches of water relative to the pressure external of the enclosure and operate it continuously, 24 hours a day, until the enclosure of the asbestos control area is removed. Provide continuous 24-hour per day monitoring of the pressure differential with a pressure differential automatic recording instrument. Submit pressure differential recordings for each work day to the SAM for review and to the Contracting Officer within 24 hours from the end of each work day. Notify the Contractor and the Contracting Officer immediately of any variance in the pressure differential which could cause adjacent unsealed areas to have asbestos fiber concentrations in excess of 0.01 fibers per cubic centimeter or background whichever is higher. In no circumstance shall levels exceed 0.1 fibers per cubic centimeter.

1.5.4 Asbestos Waste Shipment Record N.C. (DHHS-HHCU) Form 3787

Record and report, to the Contracting Officer, the amount of asbestos containing material removed and released for disposal. Deliver the report for the previous day at the beginning of each day shift with amounts of material removed during the previous day reported in linear feet or square feet as described initially in this specification and in cubic feet for the amount of asbestos containing material released for disposal. Use "Asbestos Waste Shipment Record N.C. (DHHS-HHCU) Form 3787 for this report. A copy of the (DHHS-HHCU) Form 3787 must accompany any asbestos waste shipment to the Base sanitary landfill.

1.5.5 Daily Log

A daily log documenting work practices, sample locations, and all other asbestos related job conditions shall be maintained, by the testing lab and be available for Government examination throughout the course of work. At the completion of testing, a copy of this log shall be immediately delivered to the Government.

1.5.6 North Carolina Permit

Submit one copy of the North Carolina Permit before beginning abatement activities to the Contracting Officer.

1.5.7 Modifications to the North Carolina Permit

Submit a copy of all permit modifications to the Contracting Officer. These must be received before they become effective. The Contractor is responsible for proper permit modification notification to the State. Modifications may be delivered to the Contracts Office or transmitted by facsimile to (910) 411-5899.

1.5.8 Asbestos Inspection Reporting Form

This Asbestos Inspection Reporting Form is included at the end of this section and shows the homogeneous areas involved with this project. The Contractor shall mark the line "confirmed ACM from this HA:" as either "Abated" or "Managed in Place." Abated shall be defined as removed. If an HA is partially abated, approximate the percentage of asbestos removed and mark in the comments area. Provide any other descriptive data, such as rooms/areas removed or rooms/areas where asbestos not removed. The intent of this requirement is to report "as built" conditions. The Contractor is

not required to perform any additional asbestos surveys or inspections as a result of this paragraph. Include this report with drawing of abated areas with other closeout documentation.

1.6 PRE-ABATEMENT MEETING

The Contractor and designer shall meet with the Contracting Officer prior to beginning work, to discuss in detail the asbestos plan, including work procedures and safety precautions.

1.7 ASBESTOS INSPECTION REPORTING FORM AND ASBESTOS SAMPLE REPORTING FORM

These two forms are included at the end of this section for informational purposes. They do not define or modify the scope of work.

PART 2 PRODUCTS

2.1 ENCAPSULANTS

Shall conform to current USEPA requirements, shall contain no toxic or hazardous substances as defined in 29 CFR 1926.59, and shall conform to the following performance requirements. Use of encapsulants is generally restricted to the surface of the temporary enclosure and to areas that are not to be refinished such as attics and crawlspaces. The proposed use of encapsulants shall be included in the abatement design.

2.1.1 Removal Encapsulants

Requirement	Test Standard
Flame Spread - 25, Smoke Emission - 50	ASTM E 84
Life Expectancy - 20 years	ASTM C 732, Accelerated Aging Test
Permeability - Minimum 0.4 perms	ASTM E96/E96M

2.1.2 Lock-down Encapsulant

Requirement	Test Standard
Flame Spread - 25, Smoke Emission - 50	ASTM E 84
Life Expectancy - 20 years	ASTM C 732 Accelerated Aging Test
Permeability - Minimum 0.4 perms	ASTM E96/E96M
Fire Resistance - Negligible affect on fire resistance rating over 3 hour test (Tested with fireproofing over encapsulant applied directly to steel member)	ASTM E 119
Bond Strength - 100 pounds of force/ foot (Tests compatibility with	ASTM E 736

Requirement	Test Standard
cementitious and fibrous fire-proofing)	

2.1.3 Plastic Sheet

Plastic sheet, polyethylene, 6 mil minimum thickness, unless otherwise specified, in sizes to minimize the frequency of joints. All asbestos material or debris will be at least double bagged or wrapped in two layers of 6 mil poly sheeting.

2.1.4 Tape

Capable of sealing joints of adjacent sheets or plastic sheets and for attachment of plastic sheet to finished or unfinished surfaces of dissimilar materials and capable of adhering under dry and wet conditions, including use of amended water.

2.1.5 Disposal Bags

Bags shall be a minimum of 6 mil thick polyethylene. Affix a warning and Department of Transportation (DOT) label to each bag or use bags with the approved warnings and DOT labeling preprinted on the bag.

2.1.6 Warning Labels

Provide labels conforming to 29 CFR 1926.1101 of sufficient size to be clearly legible, displaying the following legend:

DANGER
CONTAINS ASBESTOS FIBERS
AVOID CREATING DUST
CANCER AND LUNG DISEASE HAZARD
BREATHING ASBESTOS DUST MAY
CAUSE SERIOUS BODILY HARM

PART 3 EXECUTION

3.1 DISPOSAL SITE

CAMP LEJEUNE SANITARY LANDFILL
982 PINEY GREEN ROAD
CAMP LEJEUNE, NC 28542
(910) 451-5011

Base Sanitary Landfill shall be used for disposal of all asbestos waste. The Base Sanitary Landfill is approved and is available for use by the Contractor providing the following requirements are satisfied:

a. The Contracting Officer must be informed at least five working days in advance of the anticipated delivery date of the asbestos material to the Landfill. On larger projects, the notification should be accompanied by a cubic yard estimate of the anticipated volume, updated weekly if the disposal period extends for more than one week. The Government will be responsible for digging the trenches and covering the debris at the end of the working day. Debris will not be accepted before 8:00 AM or after 10:00 AM, except in an emergency situation.

b. Asbestos will be accepted only if adequately wet and double bagged in heavy-duty 6 mil plastic bags which are clearly marked "Asbestos." If a Contractor desires to handle the asbestos in a manner other than double-bagged, written application, along with a description of the proposed deviation, must be submitted to the OICC and Landfill Manager for approval.

c. Asbestos insulated piping with the asbestos insulation intact will be accepted if the following requirements are met:

1. The pipe is cut in eight foot or shorter lengths

2. Each section of pipe is double wrapped, sealed, and labeled as asbestos.

3. All pipe is palletized on a 7/8-inch, 4- by 8-foot sheet of plywood. The whole pallet is banded with a minimum of three 1-inch wide metal bands with the coupling on top and wrapped with 6-mil plastic. The pallet is not higher than 3-inches.

d. All asbestos, except palletized pipe will be off loaded and placed in the trench pipe hand.

e. Asbestos disposal is restricted to one designated location in the Landfill and the landfill operators must be informed of and direct each delivery. Asbestos shall be disposed of from 0800 to 1000 hours daily, except holidays and weekends. Trucks hauling asbestos must be properly covered with tarpaulins or equivalent. Trucks not covered properly must be parked until the Contracting Officer approves corrective actions.

f. The Contractor will ensure asbestos contaminated material delivered to the Base Sanitary Landfill contain no free liquids. Free liquids are defined as material which fails the EPA SW-846 free liquids test.

g. The Contractor will include all asbestos waste shipment records (DHHS-HHCU Form 3787) that are filled out completely with the correct information, to the project manager after abatement job is completed.

3.2 EQUIPMENT

Make available to the Contracting Officer or the Contracting Officer's Representative, two complete sets of personal protective equipment as required herein for entry to the asbestos control area at all times for inspection of the asbestos control area. Provide equivalent training to the Contracting Officer or a designated representative as provided to Contractor employees in the use of the required personal protective equipment. Provide manufacturer's certificate of compliance for all equipment required to contain airborne asbestos fibers.

3.2.1 Respirators

Comply with 29 CFR 1926.1101.

3.3 WORK PROCEDURE

Remove all friable and non-friable ACM in accordance with all Federal, State, and local Marine Corps regulations. Ensure that the asbestos abatement plan is followed throughout all aspects of the abatement process.

3.3.1 Furnishings

Furniture and equipment will be removed from the area of work by either the Government or the contractor before asbestos work begins. Refer to RFP documents for additional information.

3.3.2 Pipe Insulation

Pipe may be removed with the asbestos insulation in place by wrapping the entire length of pipe and associated insulation with double thickness 6 mil plastic secured with duct tape. Mechanically cutting of asbestos containing insulation is prohibited. When using the "candy-stripe" method the abatement contractor must use glovebag operations to establish an "asbestos free" area to cut the pipe into appropriate lengths. Cut piping simultaneously into lengths suitable for transportation to disposal area, but no greater than 8 feet in length. Continuously wet the cutting site during the process. As soon as a length of pipe is completely cut loose, cover exposed ends with double thickness 6 mil plastic secured with duct tape. If the pipe is to remain in service, the removed pipe must be replaced in accordance with this Specification, with a pipe of the same size that is removed.

3.3.2.1 Attic Insulation

In those buildings indicated on the drawings, attic insulation consisting of any combination of blown-in or batt fiberglass or rockwool material, has been contaminated with asbestos materials, and is to be removed as contaminated asbestos material. The insulation material shall be wet with a fine mist of amended water. The material shall be placed immediately in double thickness 6 mil plastic bags for disposal as asbestos waste.

3.3.2.2 Contaminated Soil

In those buildings so indicated on the drawings, asbestos materials are located in the building crawl spaces and deterioration of the asbestos material has resulted in contamination of the soil under the building. Under the indicated area of these buildings, asbestos material and 2 inches of soil shall be removed and one sheet of plastic, 6 mils thick, spread over the area with seams lapped a minimum of 4 inches. Sand shall be placed a minimum of 2 inches thick over the plastic. Removal shall occur just prior to clean-up operations. All debris in the crawl space shall be disposed of with the soil as asbestos materials. Workers shall be equipped with respirators and protective clothing during the removal of soil and debris.

3.3.2.3 Non-Organic Bound (NOB) Asbestos Materials

These kind of materials include floor tile, mastic, caulking, roofing material, and other non-friable material. Materials are to be adequately wet before removal and double bagged with a 6 mil poly bag. Ensure that bags have been labeled properly before they are taken to the Base Landfill.

3.3.3 Air Sampling

Sampling of airborne concentrations of asbestos fibers shall be performed in accordance with 29 CFR 1926.1101 and as specified herein. Sampling performed in accordance with 29 CFR 1926.1101 shall be performed by the SAM. Sampling performed for environmental and quality control reasons shall be performed by the SAM. Unless otherwise specified, use NIOSH Method 7400 for sampling and analysis. Monitoring may be duplicated by the Government at the discretion of the Contracting Officer. If the air sampling results obtained by the Government differ from those results obtained by the Contractor, the Government results shall prevail.

3.3.3.1 Sampling During Asbestos Work

The SAM shall provide personal and area sampling as indicated in 29 CFR 1926.1101 and governing environmental regulations. Thereafter, provided the same type of work is being performed, provide area sampling at least once every work shift close to the work inside the containment, outside the clean room entrance to the containment, and at the exhaust opening of the local exhaust system. Also, where an enclosure is not provided, conduct area monitoring of airborne asbestos fibers during the work shift at the designated limits of the asbestos work area at such frequency as recommended by the SAM and conduct personal samples of each worker engaged in asbestos handling (removal, disposal, transport and other associated work). If the quantity of airborne asbestos fibers monitored at the breathing zone of the workers or designated limits at any time exceeds background or 0.01 fibers per cubic centimeter whichever is lesser outside of the containment area, stop work, evacuate personnel in adjacent areas or provide personnel with approved protective equipment at the discretion of the Contracting Officer. This sampling may be duplicated by the government at the discretion of the Contracting Officer. If the air sampling results obtained by the government differ from those obtained by the Contractor, the government results shall prevail. If adjacent areas are contaminated as determined by the Contracting Officer, clean the contaminated areas, monitor, and visually inspect the area as specified herein.If sampling outside the containment shows airborne levels have exceeded background or 0.01 fibers per cubic centimeter, whichever is greater, stop all work, correct the condition(s) causing the increase, and notify the Contracting Officer immediately. In areas where the construction of a containment is not required, after initial TWAs are established and provided the same type of work is being performed, provide sampling at the designated limits of the asbestos work area at such frequency as recommended by the SAM. Where glovebag methods are used, perform personal and area air sampling at locations and frequencies thatwill accurately characterize the evolving airborne asbestos levels.

3.3.3.2 Sampling After Final Clean-Up (Clearance Sampling) For All Areas Unless Noted Otherwise

Provide area sampling of asbestos fibers using aggressive air sampling techniques as defined in the EPA 560/5-85-024 and establish an air borne asbestos concentration of less than 70 structures per square millimeter after final clean-up but before removal of the containment or the asbestos work control area. After final cleanup and the asbestos control area is

dry but prior to clearance sampling, the SAM shall perform a visual inspection, in accordance with ASTM E 1368, to insure that the asbestos control and work area is free of any accumulations of dirt, dust, or debris. Use transmission electron microscopy (TEM) to analyze clearance samples and report the results in accordance with current NIOSH criteria. The asbestos fiber counts from these samples shall be less than 70 structures per square millimeter or be not greater than the background, whichever is greater. Should any of the final samples indicate a higher value, the Contractor shall take appropriate actions to re-clean the area and shall repeat the sampling and TEM analysis at the Contractor's expense.

3.3.3.3 Sampling After Final Clean-Up (Clearance Sampling)

Refer to PART 6 Asbestos Reports for sampling areas. Provide area sampling of asbestos fibers using aggressive air sampling techniques as defined in the EPA 560/5-85-024 and establish an air borne asbestos concentration of less than 0.01 fibers per cubic centimeter after final clean-up but before removal of the containment or the asbestos work control area. After final cleanup and the asbestos control area is dry but prior to clearance sampling, the SAM shall perform a visual inspection, in accordance with ASTM E 1368, to insure that the asbestos control and work area is free of any accumulations of dirt, dust, or debris. Should any of the final samples indicate a higher value, the Contractor shall take appropriate actions to re-clean the area and shall repeat the sampling and analysis at the Contractor's expense.

3.3.4 Lock Down

Prior to removal of plastic barriers and after pre-clearance clean up of gross contamination, a visual inspection by the SAM, of all areas affected by the removal of the asbestos contaminated materials for any visible fibers, shall be conducted and approved by the SAM. A post removal (lock down) encapsulant shall then be spray applied to ceiling, walls, floors and other areas exposed in the removal area. The exposed area shall include but not be limited to plastic barriers, furnishings and articles to be discarded as well as dirty change room, air locks for bag removal and decon chambers.

3.3.5 Site Inspection

While performing asbestos removal work, the Contractor shall be subject to on-site inspection by the Contracting Officer who may be assisted by or represented by safety or industrial hygiene personnel. If the work is found to be in violation of this specification, the Contracting Officer or his representative will issue a stop work order to be in effect immediately and until the violation is resolved. Standby time required to resolve the violation shall be at the Contractor's expense.

3.4 CLEAN-UP AND DISPOSAL

3.4.1 Housekeeping

Essential parts of asbestos dust control are housekeeping and clean-up procedures. Maintain surfaces of the asbestos control area free of accumulations of asbestos fibers. Give meticulous attention to restricting the spread of dust and debris; keep waste from being distributed over the general area. Use HEPA filtered vacuum cleaners. Do not blow down the space with compressed air. When asbestos removal is complete, all asbestos waste is removed from the work-site, final clean-up is completed, and final

air sampling results are reported, the SAM will certify the area as safe and the Conrracting Officer will approve the abatement completion, before the signs can be removed. After final clean-up and acceptable airborne concentrations are attained but before the HEPA unit is turned off and the containment removed, remove all pre-filters on the building HVAC system and provide new pre-filters. Dispose of filters as asbestos-contaminated materials. Reestablish HVAC mechanical, and electrical systems in proper work ing order. The Contracting Officer will visually inspect all surfaces within the containment for residual material or accumulated dust or debris. The Contractor shall re-clean all areas showing dust or residual materials. If re-cleaning is required, air sample and establish an acceptable asbestos airborne concentration after re-cleaning. The SAM will provide written certification that the work area is safe within all standards as referenced within this contract before unrestricted entry is permitted. The Government shall have the option to perform monitoring to certify the areas are safe before entry is permitted.

3.4.2 Title to Materials

All materials resulting from demolition work, except as specified otherwise, shall become the property of the Contractor and shall be disposed of as specified in applicable local, state, and Federal regulations and herein. All building materials that are cross contaminated must be disposed of as an ACM at Base Landfill.

3.4.3 Disposal of Asbestos

3.4.3.1 Procedure for Disposal

Collect asbestos waste, asbestos contaminated water, scrap, debris, bags, containers, equipment, and asbestos contaminated clothing which may produce airborne concentrations of asbestos fibers and place in sealed fiberproof, waterproof, non-returnable containers (e.g. double plastic bags 6 mils thick, cartons, drums or cans). Wastes within the containers must be wetted to insure the security of the material in case of container breeching. Affix a warning and Department of Transportation (DOT) label to each bag or use at least 6 mil thick bags with the approved warnings and DOT labeling preprinted on the bag. For temporary storage, store sealed impermeable bags in asbestos waste drums or skids. An area for interim storage of asbestos waste-containing drums or skids will be assigned by the Contracting Officer or his authorized representative. Procedure for haul ing and disposal shall comply with 40 CFR 61, SUBPART M, state, regional, and local standards.

3.4.3.2 Disposal Material Shall Contain No Free Liquid

The Contractor will ensure asbestos contaminated material delivered to the Base Sanitary Landfill contain no free liquids. Free liquids are defined as material which fails the EPA SW-846 Free Liquids Test.

3.4.3.2.1 Appendix

Refer to Asbestos Report of Building # AS515 - MCB Camp Lejeune; dated Monday, July 26, 2021

-- End of Section --

ASBESTOS INSPECTION REPORT of:

Building # AS515

MCB CAMP LEJEUNE

Print Date

Monday, July 26, 2021

INSPECTION SUMMARY

BLDG #: **AS515** ***YEAR BUILT:*** **1963**

OCCUPANT: **MAINTENANCE HANGAR** ***ASBESTOS MANAGER: 910-451-5837***

BUILDING COMMENTS:

HAZ RANK 2B/YELLOW [AH NOV2012]
ACM GASKET MATERIAL DEBRIS, "A" WING NW MECH ROOM. SIGNIFICANT TRANSITE PANELS THROUGHOUT HANGAR BAY.

NOV2012
PVS. ACM REMAINS, ACM GASKET DEBRIS SHOULD BE CLEAN-ED UP

DEC09
ADDL SAMPLING, PVS. ACM REMAINS, ACM INCLUDES:
FLOOR TILE MASTIC
GASKET MATERIAL DEBRIS
TRANSITE PANEL MATERIAL

MAY07
BUILT-UP ROOFING NON ACM RUBBER/EPMD
TRANSITE PANELS IDENTIFIED IN HANGAR BAY

NOV02
ROOFING REMAINS INACCESSIBLE FOR SAMPLING, ASSUME ACM TARS AND SEALANTS

INSPECT SEP99 (CAPE)
NON FRIABLE ACM IDENTIFIED INCLUDES:
BUILT-UP ROOFING (ASUMED)

NOTIFICATION OF ACM IN BUILDING

NOTICE: The following asbestos-containing materials have been identified in this structure. Refer to survey findings for additional information or contact the Asbestos Program Manager. Please note ACM that is intact and undisturbed is not considered a significant health hazard to building occupants.

Friable ACM(s) identified

DESCRIPTION	*LOCATION*	*Date*	*Quantity*
No friable ACM records found in database			

Non-friable ACM(s) identified

DESCRIPTION	*LOCATION*	*Date*	*Quantity*
TRANSITE PANEL MATERIAL	SOUTH CENTRAL HANGAR BAY, EXTERIOR SOUTH CEILING AT DOORS, AND PERIMETER WALLS (OVER SECOND FLOOR)	5/15/2007	23,310 SF
GASKET MATERIAL	FIRST FLOOR A WING, NORTHEAST MECHANICAL GROUND DEBRIS. SOURCE UNKNOWN, ADDITIONAL GASKETS POSSIBLE THROUGHOUT	12/17/2009	1 SF
RESIDUAL MASTIC	STAIRWELLS, CLOSETS, AREAS WITH PREVIOUS ORIGINAL 12" TILES REMOVED (SEE ALSO HM31)	12/17/2009	40 SF

12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	NORTH SECOND FLOOR OFFICES AND CORRIDORS THROUGHOUT	12/17/2009	14,500	SF
TRANSITE PANEL MATERIAL	SOUTH CENTRAL HANGAR BAY, EXTERIOR SOUTH CEILING AT DOORS, AND PERIMETER WALLS (OVER SECOND FLOOR)	12/17/2009	23,310	SF
TRANSITE PANEL MATERIAL	SOUTH CENTRAL HANGAR BAY, EXTERIOR SOUTH CEILING AT DOORS, AND PERIMETER WALLS (OVER SECOND FLOOR)	11/27/2012	23,310	SF
GASKET MATERIAL	FIRST FLOOR A WING, NORTHEAST MECHANICAL GROUND DEBRIS. SOURCE UNKNOWN, ADDITIONAL GASKETS POSSIBLE THROUGHOUT	11/27/2012	1	SF
RESIDUAL MASTIC	STAIRWELLS, CLOSETS, AREAS WITH PREVIOUS ORIGINAL 12" TILES REMOVED (SEE ALSO HM31)	11/27/2012	40	SF
TRANSITE PANEL MATERIAL	SOUTH CENTRAL HANGAR BAY, EXTERIOR SOUTH CEILING AT DOORS, AND PERIMETER WALLS (OVER SECOND FLOOR)	8/26/2014	23,310	SF
12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	NORTH SECOND FLOOR OFFICES AND CORRIDORS THROUGHOUT	8/26/2014	14,500	SF
GASKET MATERIAL	FIRST FLOOR A WING, NORTHEAST MECHANICAL GROUND DEBRIS. SOURCE UNKNOWN, ADDITIONAL GASKETS POSSIBLE THROUGHOUT	8/26/2014	1	SF
RESIDUAL MASTIC	STAIRWELLS, CLOSETS, AREAS WITH PREVIOUS ORIGINAL 12" TILES REMOVED (SEE ALSO HM31)	8/26/2014	40	SF

Tested Non ACM or REMOVED Materials

DESCRIPTION	*LOCATION*	*Date*
INTERIOR CAULKING,	SECOND FLOOR CORRIDORS, INTERIOR HANGAR SIDE WINDOWS	9/23/1999
MISCELLANEOUS SEALANT	CABLE AND CONDUIT WALL PENETRATIONS THROUGHOUT	5/15/2007
JOINT MATERIAL	CEILINGS AND WALLS THROUGHOUT FIRST AND SECOND FLOOR RESTROOMS AND UTILITY SPACES (SEE ALSO HM02, 03)	5/15/2007
DUCT SEALANT, GRAY	FIRST FLOOR OVERHEAD HVAC DUCTS THROUGHOUT	9/23/1999
12" BEIGE FLOOR TILE AND ADHESIVE	FIRST FLOOR A WING, NORTHWEST OFFICE AREA (REPLACEMENT PATCHING)	5/15/2007

BLACK VINYL BASE AND ADHESIVE, 4"	SECOND FLOOR B WING, NORTH CENTER OFFICE	9/23/1999
WINDOW GLAZING MATERIAL	SECOND FLOOR CORRIDORS, INTERIOR HANGAR SIDE WINDOWS	9/23/1999
DRYWALL AND JOINT MATERIAL	SECOND FLOOR WALLS THROUGHOUT EXCEPT STAIRWELLS; FIRST FLOOR ENTRY FOYERS	9/23/1999
BUILT-UP ROOFING	ROOFING SYSTEM, MAIN COVERING	9/23/1999
DRYWALL AND JOINT MATERIAL	CEILINGS THROUGHOUT FIRST AND SECOND FLOOR RESTROOMS AND UTILITY SPACES (SEE ALSO HM21)	9/23/1999
FLEXIBLE DUCT CONNECTOR(S)	FIRST FLOOR MECHANICAL/ AIR HANDLER ROOMS THROUGHOUT	9/23/1999
12" GRAY FLOOR TILE AND ADHESIVE	SECOND FLOOR A, B, C WINGS OFFICES AND WORK SPACES	9/23/1999
2'x4' CEILING TILE,	FIRST FLOOR STAIRWELLS; SECOND FLOOR STAIRWELLS AND OFFICES THROUGHOUT	9/23/1999
GRAY VINYL BASE AND ADHESIVE, 4"	FIRST FLOOR NORTHEAST AND NORTHWEST MECHANICAL ROOMS; SECOND FLOOR THROUGHOUT OFFICES AND CORRIDORS	9/23/1999
INTERIOR CAULKING,	INTERIOR FIBERGLASS PIPE INSULATION AT THROUGH WALL PENETRATIONS	12/17/2009
EXTERIOR CAULKING,	METAL DOORS THROUGHOUT	12/17/2009
CONCRETE EXPANSION JOINT MATERIAL	HANGAR SLAB PERIMETER AND CENTER EXPANSION JOINTS THROUGHOUT	12/17/2009
FIBERGLASS INSULATION SEALANT	PIPING AND HVAC DUCT WORK THROUGHOUT	12/17/2009
ROOFING SEALANT, BLACK	LOWER ROOF, PATCHING AND POCKETS ON WHITE MEMBRANE	8/26/2014
ROOF FLASHING/SEALER MATERIAL	BUCKET FOR PATCHING, UPPER B ROOF (PATCHES THROUGHOUT)	8/26/2014
PITCH POCKET TAR	UPPER ROOF AT FRAMING AND PENETRATION	8/26/2014
ROOFING SEALANT, GRAY	UPPER ROOF, PATCHING AND POCKETS ON WHITE MEMBRANE	8/26/2014
BUILT-UP ROOFING	ROOFING SYSTEM, MAIN COVERING	11/7/2002
12" GRAY FLOOR TILE AND ADHESIVE	SECOND FLOOR A, B, C WINGS OFFICES AND WORK SPACES	5/15/2007
DRYWALL AND JOINT MATERIAL	SECOND FLOOR WALLS THROUGHOUT EXCEPT STAIRWELLS; FIRST FLOOR ENTRY FOYERS	12/17/2009
JOINT MATERIAL	SECOND FLOOR WALLS AND CEILINGS THROUGHOUT EXCEPT STAIRWELLS; FIRST FLOOR ENTRY FOYERS (SEE ALSO HM02, 03)	12/17/2009

HEALTH ASPECTS:	ACM only presents a health hazard when asbestos fibers are airborne and inhaled. Avoid disturbance which will release fibers. The presence of asbestos does not constitute a health hazard.
CONDITIONS TO AVOID:	Do not disturb or cause damage to ACM. Do not sand, grind or abrade materials or cause damage with any type of equipment.
REPORTS OF DAMAGE:	Report any damage, dust or debris that may come from ACM or suspect ACM, or any change in the condition of materials, or accidental disturbance to the Asbestos Program Manager.
RESPONSE ACTION:	Corrective action initiated to minimize fiber release and protect personnel.
INSPECTION:	ACM will be inspected periodically to evaluate any changes in condition.
RECORDKEEPING:	The Camp Lejeune Asbestos Program Manager maintains a copy of the survey for the building.

CAMP LEJEUNE Asbestos Program Manager: **Phone: (910) 451-5837**

SAMPLES COLLECTED

Sample	HA	Description	Sample Date	Sample Location	Chr (%)	Amo (%)	Oth (%)
AS515-01-01	01	12" GRAY FLOOR TILE AND ADHESIVE	9/23/1999	2ND FL A WING; SW	0	0	0
AS515-0101QC	01	12" GRAY FLOOR TILE AND ADHESIVE	9/23/1999	2ND FL A WING; SW OFFICE	0	0	0
AS515-01-02	01	12" GRAY FLOOR TILE AND ADHESIVE	9/23/1999	2ND FL B WING, CNTR SOUTH HALL	0	0	0
AS515-01-03	01	12" GRAY FLOOR TILE AND ADHESIVE	9/23/1999	2ND FL C WING; SE OFFICE	0	0	0
AS515-01-30	01	12" GRAY FLOOR TILE AND ADHESIVE	5/15/2007	1ST FL B WING, NORTH CNTR OFFICE CLOSET	0	0	0
AS515-01-31	01	12" GRAY FLOOR TILE AND ADHESIVE	5/15/2007	2ND FL A WING; SW STAIRWELL	0	0	0
AS515-01-32	01	12" GRAY FLOOR TILE AND ADHESIVE	5/15/2007	2ND FL A WING; NW HALLWAY	0	0	0
AS515-01-33	01	12" GRAY FLOOR TILE AND ADHESIVE	5/15/2007	2ND FL A WING; NORTH CNTR LG. OFFICE	0	0	0
AS515-01-34	01	12" GRAY FLOOR TILE AND ADHESIVE	5/15/2007	2ND FL A WING; EAST HALL AT B WING	0	0	0
AS515-02-01	02	DRYWALL AND JOINT MATERIAL WALLS	9/23/1999	2ND FL A WING; NORTH CNTR OFFICE	0	0	0
AS515-02-02	02	DRYWALL AND JOINT MATERIAL WALLS	9/23/1999	2ND FL B WING; SE OFFICE	0	0	0
AS515-02-03	02	DRYWALL AND JOINT MATERIAL WALLS	9/23/1999	2ND FL C WING; SOUTH CNTR HALL	0	0	0
AS515-02-40	02	DRYWALL AND JOINT MATERIAL WALLS	12/17/2009	1ST FL C WING; SE ENTRY FOYER	0	0	0
AS515-02-41	02	DRYWALL AND JOINT MATERIAL WALLS	12/17/2009	2ND FL A WING; SW HALL	0	0	0
AS515-02-42	02	DRYWALL AND JOINT MATERIAL WALLS	12/17/2009	2ND FL A WING; NW HALL	0	0	0
AS515-02-43	02	DRYWALL AND JOINT MATERIAL WALLS	12/17/2009	2ND FL A WING; CNTR HALL	0	0	0
AS515-02-44	02	DRYWALL AND JOINT MATERIAL WALLS	12/17/2009	2ND FL B WING; NW FEMALE HEAD	0	0	0
AS515-03-01	03	DRYWALL AND JOINT MATERIAL CEILINGS	9/23/1999	2ND FL A WING; NE RESTROOM	0	0	0

Sample	HA	Description		Sample Date	Sample Location	Chr (%)	Amo (%)	Oth (%)
AS515-03-02	03	DRYWALL AND JOINT MATERIAL	CEILINGS	9/23/1999	1ST FL B WING; WEST RESTROOM	0	0	0
AS515-03-03	03	DRYWALL AND JOINT MATERIAL	CEILINGS	9/23/1999	1ST FL B WING; WEST RESTROOM	0	0	0
AS515-04-01	04	2'x4' CEILING TILE,	FISSURED	9/23/1999	2ND FL A WING; WEST CNTR OFFICE	0	0	0
AS515-0401QC	04	2'x4' CEILING TILE,	FISSURED	9/23/1999	2ND FL A WING; WEST CNTR OFFICE	0	0	0
AS515-04-02	04	2'x4' CEILING TILE,	FISSURED	9/23/1999	2ND FL B WING; SOUTH CNTR HALL	0	0	0
AS515-04-03	04	2'x4' CEILING TILE,	FISSURED	9/23/1999	1ST FL C WING; SE STAIRWELL	0	0	0
AS515-05-01	05	GRAY VINYL BASE AND ADHESIVE, 4"		9/23/1999	2ND FL A WING; SW OFFICE	0	0	0
AS515-05-02	05	GRAY VINYL BASE AND ADHESIVE, 4"		9/23/1999	2ND FL B WING; NORTH CNTR OFFICE	0	0	0
AS515-05-03	05	GRAY VINYL BASE AND ADHESIVE, 4"		9/23/1999	2ND FL C WING; SOUTH CNTR HALL	0	0	0
AS515-06-01	06	BLACK VINYL BASE AND ADHESIVE, 4"		9/23/1999	2ND FL B WING, NORTH CNTR OFFICE	0	0	0
AS515-06-02	06	BLACK VINYL BASE AND ADHESIVE, 4"		9/23/1999	2ND FL B WING, NORTH CNTR OFFICE	0	0	0
AS515-06-03	06	BLACK VINYL BASE AND ADHESIVE, 4"		9/23/1999	2ND FL B WING, NORTH CNTR OFFICE	0	0	0
AS515-07-01	07	WINDOW GLAZING MATERIAL	GRAY	9/23/1999	2ND FL A WING; NE WINDOW	0	0	0
AS515-0701QC	07	WINDOW GLAZING MATERIAL	GRAY	9/23/1999	2ND FL A WING; NE HALL WINDOW	0	0	0
AS515-07-02	07	WINDOW GLAZING MATERIAL	GRAY	9/23/1999	2ND FL B WING; SE HALL WINDOW	0	0	0
AS515-07-03	07	WINDOW GLAZING MATERIAL	GRAY	9/23/1999	2ND FL C WING; SOUTH CNTR HALL WINDOW	0	0	0
AS515-08-01	08	INTERIOR CAULKING,	GRAY	9/23/1999	2ND FL A WING; NW HALL WINDOW	0	0	0
AS515-08-02	08	INTERIOR CAULKING,	GRAY	9/23/1999	2ND FL A WING; NORTH CNTR HALL WINDOW	0	0	0
AS515-08-03	08	INTERIOR CAULKING,	GRAY	9/23/1999	2ND FL C WING; NE HALL WINDOW	0	0	0

Sample	HA	Description		Sample Date	Sample Location	Chr (%)	Amo (%)	Oth (%)
AS515-09-01	09	DUCT SEALANT, GRAY		9/23/1999	1ST FL A WING; SW MECH AREA	0	0	0
AS515-09-02	09	DUCT SEALANT, GRAY		9/23/1999	1ST FL B WING; NE MECH AREA	0	0	0
AS515-09-03	09	DUCT SEALANT, GRAY		9/23/1999	1ST FL C WING; SE MECH AREA	0	0	0
AS515-20-30	20	MISCELLANEOUS SEALANT	RED FIRESTOP	5/15/2007	HANGAR AREA C; NW WALL	0	0	0
AS515-21-30	21	JOINT MATERIAL		5/15/2007	1ST FL B WING; NORTH CNTR ENTRY	0	0	0
AS515-21-40	21	JOINT MATERIAL		12/17/2009	1ST FL C WING; NW MENS HEAD CEILING	0	0	0
AS515-21-41	21	JOINT MATERIAL		12/17/2009	1ST FL B WING; NORTH CNTR WEST OFFICE WALL	0	0	0
AS515-21-42	21	JOINT MATERIAL		12/17/2009	1ST FL B WING; WEST OFFICE WALL	0	0	0
AS515-21-43	21	JOINT MATERIAL		12/17/2009	2ND FL A WING; NE FEMALE HEAD CEILING	0	0	0
AS515-21-44	21	JOINT MATERIAL		12/17/2009	2ND FL B WING; CNTR HALL DEBRIS	0	0	0
AS515-21-45	21	JOINT MATERIAL		12/17/2009	2ND FL B WING; NE OFFICE WALL	0	0	0
AS515-21-46	21	JOINT MATERIAL		12/17/2009	2ND FL C WING; NW FEMALE HEAD CEILING	0	0	0
AS515-21-47	21	JOINT MATERIAL		12/17/2009	2ND FL C WING; EAST CNTR OFFICE WALL	0	0	0
AS515-21-48	21	JOINT MATERIAL		12/17/2009	2ND FL C WING; SE STAIR WALL	0	0	0
AS515-22-30	22	12" BEIGE FLOOR TILE AND ADHESIVE	w/GREEN SPECS	5/15/2007	1ST FL A WING, NW OFFICE CLOSET	0	0	0
AS515-23-00	23	TRANSITE PANEL MATERIAL	GRAY	5/15/2007	N/A	9	9	9
AS515-23-00ri09	23	TRANSITE PANEL MATERIAL	GRAY	12/17/2009	N/A	9	9	9
AS515-23-00ri12	23	TRANSITE PANEL MATERIAL	GRAY	11/27/2012	N/A	9	9	9
AS515-23-00ri14	23	TRANSITE PANEL MATERIAL	GRAY	8/26/2014	N/A	9	9	9

Sample	HA	Description	Sample Date	Sample Location	Chr (%)	Amo (%)	Oth (%)
AS515-30-40	30	EXTERIOR CAULKING, WHITE	12/17/2009	C WING, SE ENTRY	0	0	0
AS515-30-41	30	EXTERIOR CAULKING, WHITE	12/17/2009	B WING, WEST OFFICE TO HANGAR	0	0	0
AS515-30-42	30	EXTERIOR CAULKING, WHITE	12/17/2009	A WING, NE STAIRWELL ENTRY	0	0	0
AS515-30-43	30	EXTERIOR CAULKING, WHITE	12/17/2009	C WING, NW STAIRWELL ENTRY	0	0	0
AS515-30-44	30	EXTERIOR CAULKING, WHITE	12/17/2009	A WING, NW ENTRY	0	0	0
AS515-31-00ri14	31	12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	8/26/2014	N/A	9	9	9
AS515-31-40	31	12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	12/17/2009	1ST FL C WING; NE OFFICE	0	0	0
AS515-31-41	31	12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	12/17/2009	2ND FL A WING; SW HALL	0	0	0
AS515-31-42	31	12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	12/17/2009	2ND FL A WING; CNTR MAIN HALL	3	0	0
AS515-31-43	31	12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	12/17/2009	2ND FL B WING; WEST END HALL	3	0	0
AS515-31-44	31	12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	12/17/2009	2ND FL C WING; NORTH CNTR OFFICE	5	0	0
AS515-31-45	31	12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	12/17/2009	2ND FL C WING; SE HALL	3	0	0
AS515-31-45tem	31	12" WHITE w/ GRAY FLOOR TILE AND ADHESIVE	12/17/2009	2ND FL C WING; SE HALL	0	0	0
AS515-32-40	32	CONCRETE EXPANSION JOINT MATERIAL	12/17/2009	C WING HANGAR BAY, NORTH CNTR	0	0	0
AS515-32-41	32	CONCRETE EXPANSION JOINT MATERIAL	12/17/2009	B WING HANGAR BAY, NORTH CNTR	0	0	0
AS515-32-42	32	CONCRETE EXPANSION JOINT MATERIAL	12/17/2009	A WING HANGAR BAY, SW	0	0	0
AS515-33-40	33	FIBERGLASS INSULATION SEALANT	12/17/2009	B WING, NE MECH RM	0	0	0

Sample	HA	Description		Sample Date	Sample Location	Chr (%)	Amo (%)	Oth (%)
AS515-33-41	33	FIBERGLASS INSULATION SEALANT		12/17/2009	A WING, NE MECH RM	0	0	0
AS515-34-40	34	INTERIOR CAULKING,	WHITE, RUBBERY	12/17/2009	B WING, NE MECH RM	0	0	0
AS515-35-00ri12	35	GASKET MATERIAL	GRAY	11/27/2012	N/A	9	9	9
AS515-35-00ri14	35	GASKET MATERIAL	GRAY	8/26/2014	N/A	9	9	9
AS515-35-40	35	GASKET MATERIAL	GRAY	12/17/2009	A WING, NE MECH RM, SW CORNER	3	0	0
AS515-36-00ri12	36	RESIDUAL MASTIC	BLACK	11/27/2012	N/A	9	9	9
AS515-36-00ri14	36	RESIDUAL MASTIC	BLACK	8/26/2014	N/A	9	9	9
AS515-36-40	36	RESIDUAL MASTIC	BLACK	12/17/2009	2ND FL C WING; NW STAIRWELL	5	0	0
AS515-40-30	40	ROOFING SEALANT, BLACK		8/26/2014	A ROOF, LOWER	0	0	0
AS515-40-31	40	ROOFING SEALANT, BLACK		8/26/2014	C ROOF, LOWER	0	0	0
AS515-41-30	41	ROOFING SEALANT, GRAY		8/26/2014	C ROOF, UPPER	0	0	0
AS515-41-31	41	ROOFING SEALANT, GRAY		8/26/2014	A ROOF, UPPER	0	0	0
AS515-42-30	42	ROOF FLASHING/SEALER MATERIAL	BLACK	8/26/2014	B ROOF, UPPER	0	0	0
AS515-43-30	43	PITCH POCKET TAR	BLACK	8/26/2014	A ROOF, UPPER	0	0	0

PREVIOUS ACM [HM23] HAS BEEN REMOVED.



AN ASBESTOS NOTIFICATION
CR CONCRETE
ELECTRICAL PANEL
IP INFORMATION PACKET
MR MECHANICAL ROOM
NAX NOT ACCESSIBLE
OVHD OVERHEAD

SAMPLE LEGEND ID

01-01 (+,-)
SAMPLE IDENTIFICATION
POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS
HOMOGENOUS MATERIAL

BUILDING AS515
FIRST FLOOR "A"

12.5' 0' 12.5' 25' 50'

N



ACM LEGEND

GASKET MATERIAL (DEBRIS) [HM35]

REVISIONS

SYM.	DESCRIPTION	DATE	APPROVED

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
AS515-01A
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 1 OF 6

PREVIOUS ACM [HM23] HAS BEEN REMOVED.



CR CONCRETE
HT HARD TILE
MR MECHANICAL ROOM
[HM] HOMOGENOUS MATERIAL NUMBER

SAMPLE LEGEND ID

01-01 (+,-)

SAMPLE IDENTIFICATION

POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS

HOMOGENOUS MATERIAL

BUILDING AS515
FIRST FLOOR "B"

12.5' 0' 12.5' 25' 50'

N



REVISIONS

SYM	DESCRIPTION	DATE	APPROVED

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

2014 ASBESTOS INSPECTION
AS515-01B
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 2 OF 6

PREVIOUS ACM [HM23] HAS BEEN REMOVED.



CR CONCRETE
HT HARD TILE
NAX NOT ACCESSIBLE

SAMPLE LEGEND ID

01-01 (+,-)

SAMPLE IDENTIFICATION

POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS

HOMOGENOUS MATERIAL

BUILDING AS515
FIRST FLOOR "C"

12.5' 0' 12.5' 25' 50'

N



REVISIONS

SYM	DESCRIPTION	DATE	APPROVED

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
AS515-01C
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 3 OF 6





C CARPET
CR CONCRETE
HT HARD TILE
[HM] HOMOGENOUS MATERIAL NUMBER

SAMPLE LEGEND ID

01-01 (+,-)
- SAMPLE IDENTIFICATION
- POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS
- HOMOGENOUS MATERIAL

BUILDING AS515
SECOND FLOOR "A"

12.5' 0' 12.5' 25' 50'

N

ACM LEGEND

- MASTIC UNDER 12" WHITE WITH GRAY FLOOR TILE [HM31]
- TRANSITE PANEL MATERIAL, CEILING [HM23]
- TRANSITE PANEL MATERIAL, WALLS [HM23]

REVISIONS

SYM	DESCRIPTION	DATE	APPROVED

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
AS515-02A
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 4 OF 6



C CARPET
HT HARD TILE
[HM] HOMOGENOUS MATERIAL NUMBER

SAMPLE LEGEND ID

01-01 (+,-)
- SAMPLE IDENTIFICATION
- POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS
- HOMOGENOUS MATERIAL

BUILDING AS515
SECOND FLOOR "B"

12.5' 0' 12.5' 25' 50'

N



ACM LEGEND

- MASTIC UNDER 12" WHITE WITH GRAY FLOOR TILE [HM31]
- TRANSITE PANEL MATERIAL, CEILING [HM23]
- TRANSITE PANEL MATERIAL, WALLS [HM23]

SYM	DESCRIPTION	DATE	APPROVED

REVISIONS

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
AS515-02B
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 5 OF 6





Ⓒ CARPET
HT HARD TILE
[HM] HOMOGENOUS MATERIAL NUMBER
NAX NOT ACCESSIBLE

SAMPLE LEGEND ID

01-01 (+,-)
- SAMPLE IDENTIFICATION
- POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS
- HOMOGENOUS MATERIAL

BUILDING AS515
SECOND FLOOR "C"

12.5' 0' 12.5' 25' 50'

N

ACM LEGEND

- MASTIC UNDER 12" WHITE WITH GRAY FLOOR TILE [HM31 36]
- TRANSITE PANEL MATERIAL, CEILING [HM23]
- TRANSITE PANEL MATERIAL, WALLS [HM23]

REVISIONS

SYM.	DESCRIPTION	DATE	APPROVED

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
AS515-02C
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 6 OF 6





BUILDING AS515
ROOF "A"



SAMPLE LEGEND ID



SYM.	DESCRIPTION	DATE	APPROVED

REVISIONS

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
AS515-RA
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 1 OF 6

PREVIOUS ACM [HM23] HAS BEEN REMOVED.



SAMPLE LEGEND ID

01-01 (+,-)

SAMPLE IDENTIFICATION

POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS

HOMOGENOUS MATERIAL

BUILDING AS515
ROOF "B"

12.5' 0' 12.5' 25' 50'

N



SYM.	DESCRIPTION	DATE	APPROVED

REVISIONS

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

2014 ASBESTOS INSPECTION
AS515-RB
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 2 OF 6





BUILDING AS515
ROOF "C"

12.5' 0' 12.5' 25' 50'

SAMPLE LEGEND ID

01-01 (+,-)

- SAMPLE IDENTIFICATION
- POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS
- HOMOGENOUS MATERIAL

SYM.	DESCRIPTION	DATE	APPROVED

REVISIONS

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
AS515-RC
MCB CAMP LEJEUNE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: AUGUST 2014
SHEET 1 OF 6

SECTION 04 20 00

UNIT MASONRY
11/15

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 216.1	(2014) Code Requirements for Determining Fire Resistance of Concrete and Masonry Construction Assemblies
ACI 318	(2014; Errata 1-2 2014; Errata 3-5 2015; Errata 6 2016; Errata 7-9 2017) Building Code Requirements for Structural Concrete (ACI 318-14) and Commentary (ACI 318R-14)
ACI SP-66	(2004) ACI Detailing Manual

ASTM INTERNATIONAL (ASTM)

ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A167	(2011) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A185/A185M	(2007) Standard Specification for Steel Welded Wire Reinforcement, Plain, for Concrete
ASTM A641/A641M	(2019) Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire
ASTM A653/A653M	(2020) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A951/A951M	(2011) Standard Specification for Steel Wire for Masonry Joint Reinforcement
ASTM A1008/A1008M	(2020) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable

ASTM A1064/A1064M	(2017) Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM B370	(2012; R 2019) Standard Specification for Copper Sheet and Strip for Building Construction
ASTM C90	(2016) Standard Specification for Loadbearing Concrete Masonry Units
ASTM C129	(2017) Standard Specification for Nonloadbearing Concrete Masonry Units
ASTM C207	(2018) Standard Specification for Hydrated Lime for Masonry Purposes
ASTM C270	(2019) Standard Specification for Mortar for Unit Masonry
ASTM C476	(2020) Standard Specification for Grout for Masonry
ASTM C494/C494M	(2019) Standard Specification for Chemical Admixtures for Concrete
ASTM C641	(2017) Standard Test Method for Iron Staining Materials in Lightweight Concrete Aggregates
ASTM C780	(2020) Standard Test Method for Preconstruction and Construction Evaluation of Mortars for Plain and Reinforced Unit Masonry
ASTM C1019	(2019) Standard Test Method for Sampling and Testing Grout
ASTM C1384	(2012a) Standard Specification for Admixtures for Masonry Mortars
ASTM C1611/C1611M	(2014) Standard Test Method for Slump Flow of Self-Consolidating Concrete

THE MASONRY SOCIETY (TMS)

TMS MSJC	(2016) Masonry Standard Joint Committee's (MSJC) Book - Building Code Requirements and Specification for Masonry Structures, Containing TMS 402/ACI 530/ASCE 5, TMS 602/ACI 530.1/ASCE 6, and Companion Commentaries

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control

approval. Submit non-G submittals to the Government for their record. the Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Cut CMU Drawings; G

SD-03 Product Data

Hot Weather Procedures; G

Cold Weather Procedures; G

Concrete Masonry Units (CMU; G

Cement; G

Cementitious Materials; G

Insulation; G

SD-04 Samples

Concrete Masonry Units (CMU); G

Admixtures for Masonry Mortar; G

Anchors, Ties, and Bar Positioners; G

SD-08 Manufacturer's Instructions

Admixtures for Masonry Mortar

Admixtures for Grout

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver, store, handle, and protect material to avoid chipping, breakage, and contact with soil or contaminating material. Store and prepare materials in already disturbed areas to minimize project site disturbance and size of project site.

1.3.1 Masonry Units

Cover and protect masonry units from precipitation. Conform to handling and storage requirements of TMS MSJC.

a. Pack prefaced concrete masonry units in the manufacturer's standard paper cartons, trays, or shrink wrapped pallets with a divider between each unit. Do not stack pallets. Do not remove units from cartons until cartons are placed on scaffolds or in the location where units are to be laid.

b. Mark prefabricated lintels on top sides to show either the lintel schedule number or the number and size of top and bottom bars.

1.3.2 Reinforcement, Anchors, and Ties

Store steel reinforcing bars, coated anchors, ties, and joint reinforcement above the ground. Maintain steel reinforcing bars and uncoated ties free of loose mill scale and loose rust.

1.3.3 Cementitious Materials, Sand and Aggregates

Deliver cementitious and other packaged materials in unopened containers, plainly marked and labeled with manufacturers' names and brands. Store cementitious material in dry, weathertight enclosures or completely cover. Handle cementitious materials in a manner that will prevent the inclusion of foreign materials and damage by water or dampness. Store sand and aggregates in a manner to prevent contamination and segregation.

1.4 PROJECT/SITE CONDITIONS

Conform to TMS MSJC for hot and cold weather masonry erection.

1.4.1 Hot Weather Procedures

When ambient air temperature exceeds 100 degrees F, or exceeds 90 degrees F and the wind velocity is greater than 8 mph, comply with TMS MSJC Article 1.8 D for: preparation prior to conducting masonry work; construction while masonry work is in progress; and protection for newly completed masonry.

1.4.2 Cold Weather Procedures

When ambient temperature is below 40 degrees F, comply with TMS MSJC Article 1.8 C for: preparation prior to conducting masonry work; construction while masonry work is in progress; and protection for newly completed masonry.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

2.1.1 Design - Specified Compressive Strength of Masonry

The specified compressive strength of masonry, f'm, is as indicated for each type of masonry. .

2.1.2 Performance - Verify Masonry Compressive Strength

Verify specified compressive strength of masonry using the "Unit Strength Method" of TMS MSJC. Submit calculations and certifications of unit and mortar strength.

Verify specified compressive strength of masonry using the "Prism Test Method" of TMS MSJC when the "Unit Strength Method" cannot be used. Submit test results.

2.2 MANUFACTURED UNITS

2.2.1 General Requirements

Do not change the source of materials, which will affect the appearance of the finished work, after the work has started except with Contracting Officer's approval. Submit test reports from an approved independent laboratory. Certify test reports on a previously tested material as the same materials as that proposed for use in this project. Submit certificates of compliance stating that the materials meet the specified requirements.

2.2.2 Concrete Units

2.2.2.1 Aggregates

Test lightweight aggregates, and blends of lightweight and heavier aggregates in proportions used in producing the units, for stain-producing iron compounds in accordance with ASTM C641,visual classification method. Do not incorporate aggregates for which the iron stain deposited on the filter paper exceeds the "light stain" classification.

Use industrial waste by-products (air-cooled slag, cinders, or bottom ash), ground waste glass and concrete, granulated slag, and expanded slag in aggregates.

2.2.2.2 Concrete Masonry Units (CMU)

2.2.2.2.1 Cement

Use only cement that has a low alkali content and is of one brand.

2.2.2.2.2 Size

Provide units with specified dimension to match existing conditions.

2.2.2.2.3 Surfaces

Provide units with exposed surfaces that are smooth and of uniform texture to match existing.

2.2.2.2.4 Weather Exposure

Provide concrete masonry units with water-repellant admixture added during manufacture where units will be exposed to weather.

2.2.2.2.5 Unit Types

a. Hollow Load-Bearing Units: ASTM C90, normal weight. Provide load-bearing units for exterior walls, load-bearing walls, and shear walls.

b. Hollow Non-Load-Bearing Units: ASTM C129, normal weight. Load-bearing units may be provided in lieu of non-load-bearing units.

c. Solid Load-Bearing Units: ASTM C90, lightweight normal weight units. Provide solid units as indicated.

2.2.2.2.6 Jamb Units

Provide jamb units of the shapes and sizes to conform with wall units. Solid units may be incorporated in the masonry work where necessary to fill out at corners, gable slopes, and elsewhere as approved.

Provide sash jamb units with a 3/4 by 3/4 inch groove near the center at end of each unit.

2.2.2.3 Fire-Rated Concrete Masonry Units

For indicated fire-rated construction, provide concrete masonry units of minimum equivalent thickness for the fire rating indicated and the corresponding type of aggregates indicated in TABLE I. Units containing more than one of the aggregates listed in TABLE I will be rated by linear interpolation based on the percent by dry-rodded volume of each aggregate used in manufacturing the units.

TABLE I
FIRE-RATED CONCRETE MASONRY UNITS

Aggregate Type	Minimum Equivalent Thickness for Fire-Resistance Rating, inch						
	1/2 hour	3/4 hour	1 hour	1-1/2 hour	2 hours	3 hours	4 hours
Calcareous or siliceous gravel (other than limestone)	2.0	2.4	2.8	3.6	4.2	5.3	6.2
Limestone, cinders, or air-cooled slag	1.9	2.3	2.7	3.4	4.0	5.0	5.9
Expanded clay, expanded shale, or expanded slate	1.8	2.2	2.6	3.3	3.6	4.4	5.1
Expanded slag or pumice	1.5	1.9	2.1	2.7	3.2	4.0	4.7

Determine equivalent thickness in accordance with ACI 216.1. Where walls are to receive plaster or be faced with brick, or otherwise form an assembly; include the thickness of plaster or brick or other material in the assembly in determining the equivalent thickness. Submit calculation results.

2.2.3 Precast Concrete Units

2.2.3.1 General

a. Provide precast concrete lintels and splashblocks that are factory-made units in a plant regularly engaged in producing precast concrete units. Unless otherwise indicated, provide precast concrete with minimum 4,000psi compressive strength using 1/2 inch to No. 4 nominal-size coarse aggregate, and with reinforcement required for handling of the units. Maintain minimum clearance of 3/4 inch between reinforcement and faces of units.

b. Unless precast-concrete items have been subjected during manufacture to saturated-steam pressure of at least 120 psi for at least 5 hours, either damp-cure for 24 hours or steam-cure and then age under cover for 28 days or longer. In precast concrete members weighing over 80 pounds provide built-in loops of galvanized wire or other approved provisions for lifting and anchoring.

c. Fabricate units with beds and joints at right angles to the face, with sharp true arises and with drip grooves on the underside where units overhang walls. Form exposed-to-view surfaces free of surface voids, spalls, cracks, and chipped or broken edges and with uniform appearance and color. Unless otherwise specified, provide units with a smooth dense finish.

d. Prior to installation, wet and inspect each unit for crazing. Items showing evidence of dusting, spalling, crazing, or having surfaces treated with a protective coating will be rejected.

e. Submit specified factory certificates.

f. Provide cast stone units that comply with ASTM C1364.

2.2.3.2 Precast Concrete Lintels

Provide precast concrete lintels, unless otherwise shown, of a thickness equal to the wall and reinforced with minimum two No. 4 bars for the full length. Provide top and bottom bars for lintels over 36 inches in length. Provide at least 8 inches bearing at each end. Label the top of lintels and clearly mark each lintel to show location in the structure. Design reinforced lintels in conformance with ACI 318 for flexural and shear strength, using concrete with a minimum 28 day compressive strength of 4,000 psi. Limit lintel deflection due to dead plus live load to L/600 or 0.3 inches.

2.3 EQUIPMENT

2.3.1 Vibrators

Maintain at least one spare vibrator on site at all times.

2.3.2 Grout Pumps

Pumping through aluminum tubes is not permitted.

2.4 MATERIALS

2.4.1 Mortar Materials

2.4.1.1 Cementitious Materials

Provide cementitious materials that conform to those permitted by ASTM C270.

2.4.1.2 Hydrated Lime and Alternates

Provide lime that conforms to one of the materials permitted by ASTM C207 for use in combination with portland cement, hydraulic cement, and blended hydraulic cement. Do not use lime in combination with masonry cement or mortar cement.

2.4.1.3 Admixtures for Masonry Mortar

In cold weather, use a non-chloride based accelerating admixture that conforms to ASTM C1384, unless Type III portland cement is used in the mortar.

In showers and kitchens, use mortar that contains a water-repellent admixture that conforms to ASTM C1384. Provide a water-repellent admixture, conforming to ASTM C1384 and of the same brand and manufacturer as the block's integral water-repellent, in the mortar used to place concrete masonry units that have an integral water-repellent admixture.

2.4.1.4 Aggregate and Water

Provide aggregate (sand) and water that conform to materials permitted by ASTM C270.

2.4.2 Grout and Ready-Mix Grout Materials

2.4.2.1 Cementitious Materials for Grout

Provide cementitious materials that conform to those permitted by ASTM C476.

2.4.2.2 Admixtures for Grout

Water-reducing admixtures that conform to ASTM C494/C494M Type F or G and viscosity-modifying admixtures that conform to ASTM C494/C494M Type S are permitted for use in grout. Other admixtures require approval by the Contracting Officer.

In cold weather, a non-chloride based accelerating admixture may be used subject to approval by the Contracting Officer; use accelerating admixture that is non-corrosive and conforms to ASTM C494/C494M, Type C.

2.4.2.3 Aggregate and Water

Provide fine and coarse aggregates and water that conform to materials permitted by ASTM C476.

2.5 MORTAR AND GROUT MIXES

2.5.1 Mortar Mix

a. Provide mortar Type M unless specified otherwise herein.

b. Use ASTM C270 Type M cement-lime mortar or mortar cement mortar for seismic-force-resisting elements indicated.c. For field-batched mortar, measure component materials by volume. Use measuring boxes for materials that do not come in packages, such as sand, for consistent batching. Mix cementitious materials and aggregates between 3 and 5 minutes in a mechanical batch mixer with a sufficient amount of water to produce a workable consistency. Do not hand mix mortar unless approved by the Contracting Officer. Maintain workability of mortar by remixing or retempering. Discard mortar that has begun to stiffen or is not used within 2-1/2 hours after initial mixing.

d. For preblended mortar, follow manufacturer's mixing instructions.

2.5.2 Grout and Ready Mix Grout Mix

Use grout that conforms to ASTM C476, finecoarse. Use conventional grout with a slump between 8 and 11 inches. Use self-consolidating grout with slump flow of 24 to 30 inches and a visual stability index (VSI) not greater than 1. Provide minimum grout strength of 3,000 psi in 28 days, as tested in accordance with ASTM C1019. Do not change proportions and do not use materials with different physical or chemical characteristics in grout for the work unless additional evidence is furnished that grout meets the specified requirements. Use ready-mixed grout that conforms to ASTM C476.

2.6 ACCESSORIES

2.6.1 Grout Barriers

Grout barriers for vertical cores that consist of fine mesh wire, fiberglass, or expanded metal.

2.6.2 Anchors, Ties, and Bar Positioners

2.6.2.1 General

a. Fabricate anchors and ties without drips or crimps. Size anchors and ties to provide a minimum of 5/8 inch mortar cover from each face of masonry.

b. Fabricate steel wire anchors and ties shall from wire conforming to ASTM A1064/A1064M and hot-dip galvanize in accordance with ASTM A153/A153M.

c. Fabricate joint reinforcement in conformance with ASTM A951/A951M. Hot dip galvanize joint reinforcement in exterior walls and in interior walls exposed to moist environment in conformance with ASTM A153/A153M. Galvanize joint reinforcement in other interior walls in conformance with ASTM A641/A641M; coordinate with paragraph JOINT REINFORCEMENT below.

d. Fabricate sheet metal anchors and ties in conformance with ASTM A1008/A1008M. Hot dip galvanize sheet metal anchors and ties in exterior walls and in interior walls exposed to moist environment in compliance with ASTM A153/A153M Class B. Galvanize sheet metal anchors and ties in other interior walls in compliance with ASTM A653/A653M, Coating Designation G60.

e. Submit two anchors, ties and bar positioners of each type used, as samples.

2.6.2.2 Wire Mesh Anchors

Provide wire mesh anchors of 1/4 inch mesh galvanized hardware cloth, conforming to ASTM A185/A185M, with length not less than 12 inches, at intersections of interior non-bearing masonry walls.

2.6.2.3 Wall Ties for Multi-Wythe Masonry Construction

Provide rectangular-shaped wall ties, fabricated of hot-dipped galvanized W1.7 diameter steel wire. Provide rectangular wall ties no less than 4 inches wide.

Provide adjustable type wall ties, if approved for use, that consist of two essentially U-shaped elements fabricated of minimum W2.8 diameter steel wire or pintle type ties that are inserted to eyes of horizontal joint reinforcement, hot-dip galvanized. Provide adjustable ties with double pintle legs and allows a maximum offset of 1-1/4 inch between each element of the tie and maximum distance between connecting parts no more than 1/16 inch. Form the pintle and eye elements shall be formed so that both can be in the same plane. Wall ties may also be of a continuous type conforming to paragraph JOINT REINFORCEMENT.

2.6.2.4 Veneer Anchor Screws

Provide screws for attachment of veneer anchors to cold-formed steel framing members of size No. 12 or as required by design to provide the needed pullout load capacity but not less than No. 12. Provide length of screws such that the screws penetrate the holding member by not less than 5/8 inch.

2.6.3 Clay Masonry Expansion-Joint Materials

Provide backer rod and sealant, adequate to accommodate joint compression and extension equal to 50 percent of the width of the joint. Provide the backer rod of compressible rod stock of closed cell polyethylene foam, polyurethane foam, butyl rubber foam, or other flexible, nonabsorptive material as recommended by the sealant manufacturer. Provide sealant in conformance with Section 07 92 00 JOINT SEALANTS with a maximum volatile organic compound (VOC) content of 600 grams/liter.

Submit one piece of each type of material used.

2.6.4 Through Wall Flashing and Weeps

2.6.4.1 General

Provide coated copper, copper or stainless steel sheet, self-adhesive rubberized sheet, or reinforced membrane sheet flashing except that flashing indicated to terminate in reglets shall be metal or coated-metal flashing and except that the material shall be one which is not adversely affected by dampproofing material. Coordiante with spec section FLASHING AND SHEET METAL 07 60 00.

2.6.4.2 Coated-Copper Flashing

Provide 7 ounce, electrolytic copper sheet, uniformly coated on both sides with acidproof, alkaliproof, asphalt impregnated kraft paper or polyethylene sheets.

2.6.4.3 Copper or Stainless Steel Flashing

Provide copper sheet, complying with ASTM B370, minimum 16 ounce weight; or stainless steel, ASTM A167, Type 304 or 316, 0.015 inch thick, No. 2D finish.

2.6.4.4 Reinforced Membrane Flashing

Provide polyester film core with a reinforcing fiberglass scrim bonded to one side. Provide membrane that is impervious to moisture, flexible, is not affected by caustic alkalis, and after being exposed for not less than 1/2 hour to a temperature of 32 degrees F, shows no cracking when, at that temperature, it is bent 180 degrees over a 1/16 inch diameter mandrel and

then bent at the same point over the same size mandrel in the opposite direction 360 degrees.

2.6.4.5 Rubberized Flashing

Provide self-adhesive rubberized asphalt sheet flashing consisting of 32-mil thick pliable and highly adhesive rubberized asphalt compound bonded completely and integrally to 8-mil thick, high density, cross-laminated polyethylene film to produce an overall thickness of 40 mils. Provide rubberized, asphalt-based mastic and surface conditioner that are each approved by flashing manufacturer for use with flashing material.

2.6.4.6 Weep Ventilators

Provide weep ventilators that are prefabricated from stainless steel or plastic. Provide inserts with grill or louver-type openings designed to allow the passage of moisture from cavities and to prevent the entrance of insects, and with a rectangular closure strip to prevent mortar droppings from clogging the opening. Provide ventilators with compressible flanges to fit in a standard 3/8 inch wide mortar joint and with height equal to the nominal height of the unit.

2.6.4.7 Single-Wythe Exterior Wall CMU Flashing System

In single-wythe exterior CMU walls, provide a system of CMU cell flashing pans and interlocking CMU web covers made from UV-resistant, high-density polyethylene. For exterior CMU walls, provide a flashing/weep system in open cores that do not receive grout. Cell flashing pans are to have integral weep spouts built into mortar bed joints that extend into the cell to prevent clogging with mortar.

2.6.4.8 Metal Drip Edge

Provide stainless steel drip edge, 15-mil thick, hemmed edges, with down-turned drip at the outside edge and upturned dam at the inside edge for use with membrane flashings.

2.6.5 RIGID BOARD-TYPE INSULATION

Provide rigid board-type insulation as specified in Section 07 21 13 BOARD AND BLOCK INSULATION.

PART 3 EXECUTION

3.1 EXAMINATION

Prior to start of work, verify the applicable conditions as set forth in TMS MSJC, inspection.

3.2 PREPARATION

3.2.1 Stains

Protect exposed surfaces from mortar and other stains. When mortar joints are tooled, remove mortar from exposed surfaces with fiber brushes and wooden paddles. Protect base of walls from splash stains by covering adjacent ground with sand, sawdust, or polyethylene.

3.2.2 Loads

Do not apply uniform loads for at least 12 hours or concentrated loads for at least 72 hours after masonry is constructed. Provide temporary bracing as required.

3.2.3 Concrete Surfaces

Where masonry is to be placed, clean concrete of laitance, dust, dirt, oil, organic matter, or other foreign materials and slightly roughen to provide a surface texture with a depth of at least 1/8 inch. Sandblast, if necessary, to remove laitance from pores and to expose the aggregate.

3.2.4 Shelf Angles

Adjust shelf angles as required to keep the masonry level and at the proper elevation.

3.2.5 Bracing

Provide bracing and scaffolding necessary for masonry work. Design bracing to resist wind pressure as required by OSHA and local codes and submit bracing calculations, sealed by a registered professional engineer. Do not remove bracing in less than 10 days.

3.3 ERECTION

3.3.1 General

a. Coordinate masonry work with the work of other trades to accommodate built-in items and to avoid cutting and patching. Lay masonry units to match existing conditions. Lay facing courses level with back-up courses, unless the use of adjustable ties has been approved in which case the tolerances is plus or minus 1/2 inch. Adjust each unit to its final position while mortar is still soft and has plastic consistency.

b. Remove and clean units that have been disturbed after the mortar has stiffened, and relay with fresh mortar. Keep air spaces, cavities, chases, expansion joints, and spaces to be grouted free from mortar and other debris. Select units to be used in exposed masonry surfaces from those having the least amount of chipped edges or other imperfections detracting from the appearance of the finished work.

c. When necessary to temporarily discontinue the work, step (rack) back the masonry for joining when work resumes. Toothing may be used only when specifically approved by the Contracting Officer. Before resuming work, remove loose mortar and thoroughly clean the exposed joint. Cover the top of walls subjected to rain or snow with nonstaining waterproof covering or membrane when work is not in process. Extend the covering a minimum of 610 mm 2 feet down on each side of the wall and hold securely in place.

d. Ensure that units being laid and surfaces to receive units are free of water film and frost. Lay solid units in a nonfurrowed full bed of mortar. Bevel mortar for veneer wythes and slope down toward the cavity side. Shove units into place so that the vertical joints are tight. Completely fill vertical joints between solid units with mortar, except where indicated at control, expansion, and isolation joints. Place hollow units so that mortar extends to the depth of the

face shell at heads and beds, unless otherwise indicated. Mortar will be permitted to protrude up to 1/2 inch into the space or cells to be grouted. Provide means to prevent mortar from dropping into the space below or clean grout spaces prior to grouting.

e. In multi-wythe construction with collar joints no more than 3/4 inch wide, bring up the inner wythe not more than 16 inches ahead of the outer wythe. Fill collar joints with mortar during the laying of the facing wythe, and filling shall not lag the laying of the facing wythe by back-buttering each unit as it is laid.

3.3.1.1 Jointing

Tool mortar joints when the mortar is thumbprint hard. Tool horizontal joints after tooling vertical joints. Brush mortar joints to remove loose and excess mortar.

3.3.1.1.1 Tooled Joints

Tool mortar joints in exposed exterior and interior masonry surfaces to match existing, using a jointer that is slightly larger than the joint width so that complete contact is made along the edges of the unit. Perform tooling so that the mortar is compressed and the joint surface is sealed. Use a jointer of sufficient length to obtain a straight and true mortar joint. No exterior joints are to be left un-tooled.

3.3.1.1.2 Flush Joints

Flush cut mortar joints in concealed masonry surfaces and joints at electrical outlet boxes in wet areas. Finish flush cut joints by cutting off the mortar flush with the face of the wall. Point joints in unparged masonry walls below grade tight. For architectural units, such as fluted units, completely fill both the head and bed joints and flush cut.

3.3.1.1.3 Door and Window Frame Joints

On the exposed interior side of exterior frames, joints between frames and abutting masonry walls shall be raked to a depth of 3/8 inch. On the exterior side of exterior frames, joints between frames and abutting masonry walls shall be raked to a depth of 3/8 inch.

3.3.1.1.4 Joint Widths

a. Construct brick masonry with mortar joint widths equal to the difference between the specified and nominal dimensions of the unit, within tolerances permitted by TMS MSJC.

b. Provide 3/8 inch wide mortar joints in concrete masonry, except for prefaced concrete masonry units.

c. Provide 3/8 inch wide mortar joints on unfaced side of prefaced concrete masonry units and not less than 3/16 inch nor more than 1/4 inch wide on prefaced side.

d. Maintain mortar joint widths within tolerances permitted by TMS MSJC

3.3.1.2 Cutting and Fitting

Use full units of the proper size wherever possible, in lieu of cut units.

Locate cut units where they would have the least impact on the architectural aesthetic goals of the facility. Perform cutting and fitting, including that required to accommodate the work of others, by masonry mechanics using power masonry saws. Concrete masonry units may be wet or dry cut. Before being placed in the work, dry wet-cut units to the same surface-dry appearance as uncut units being laid in the wall. Provide cut edges that are clean, true and sharp.

a. Carefully make openings in the masonry so that wall plates, cover plates or escutcheons required by the installation will completely conceal the openings and will have bottoms parallel with the masonry bed joints. Provide reinforced masonry lintels above openings over 12 inches wide for pipes, ducts, cable trays, and other wall penetrations, unless steel sleeves are used.

b. Do not reduce masonry units in size by more than one-third in height and one-half in length. Do not locate cut products at ends of walls, corners, and other openings.

3.3.1.3 Unfinished Work

Rack back unfinished work for joining with new work. Toothing may be resorted to only when specifically approved by the Contracting Officer. Remove loose mortar and thoroughly clean the exposed joints before laying new work.

3.3.1.4 Control Joints

Provide control joints in concrete masonry as indicated. Construct by raking out mortar within the head joint or using special control-joint units or using sash jamb units with control joint key or using open end stretcher units placed with the closed end at the joint in accordance with the details shown on the Drawings. Form a continuous vertical joint at control joint locations, including through bond beams, by utilizing half blocks in alternating courses on each side of the joint. Interrupt the control joint key in courses containing continuous bond beam reinforcement. Do not interrupt the horizontal reinforcement and grout at the control joint. Interrupt the horizontal reinforcement and grout in bond beams at the control joint except in bond beams at the floor and roof diaphragms.

Where mortar was placed in the joint, rake both faces of the control joints to a depth of 3/4 inch. Install backer rod and sealant on both faces in accordance with Section 07 92 00 JOINT SEALANTS.

3.3.2 Anchored Veneer Construction

a. Construct exterior masonry wythes to the thickness indicated on the drawings. Provide air space behind the masonry veneer to match existing. Provide means to ensure that the cavity space and flashings are kept clean of mortar droppings and other loose debris. Maintain chases and raked-out joints free from mortar and debris.

b. Place masonry in pattern to match existing.

c. For veneer over stud framing, do not install veneer until the exterior sheathing, moisture barrier, veneer anchors and flashing have been installed on the backing. Take extreme care to avoid damage to the moisture barrier and flashing during construction of the masonry

veneer. Repair or replace portions of the moisture barrier and flashing that are damaged prior to completion of the veneer. Provide a continuous cavity as indicated.

d. For veneer with a masonry backup wythe, lay up both the inner and the outer wythes together except when adjustable joint reinforcement assemblies are approved for use. When both wythes are not brought up together, install through-wall flashings with the exterior wythe, securing the top edge of the flashing with a termination bar and sealant, or protect flashings that are installed with the interior wythe from damage until they are fully enclosed in the wall.

e. Provide anchors (ties) to connect the veneer to its backing in sufficient quantity to comply with the following requirements: maximum wall area per anchor {tie) of 40 psf. Provide additional anchors around openings larger than 16 inch in either direction. Space anchors around perimeter of opening at a maximum of 24 inches on center. Place anchors within 12 inches of openings. Anchors with drips are not permitted.

f. With solid units, embed anchors in mortar joint and extend into the veneer a minimum of 1-1/2 inch, with at least 5/8 inch mortar cover to the outside face.

g. With hollow units, embed anchors in mortar or grout and extend into the veneer a minimum of 1-1/2 inch, with at least 5/8 inch mortar or grout cover to outside face.

3.3.3 Composite Walls

Tie masonry wythes together with joint reinforcement or with unit wall ties. Embed wall ties at least 1-1/2 inch into mortar of solid units and at least 1/2 inch into the mortar of the outer face shell of hollow units. Provide at least one tie every 2.67 square feet for wire size W1.7 and at least one tie every 4.50 square feet for wire size W2.8. Space ties at a maximum of 36 inches horizontally and 24 inches vertically. Do not cross expansion joints or control joints with ties. Fill collar joints between masonry facing and masonry backup solidly with grout.

3.3.4 Reinforced, Single Wythe Concrete Masonry Units Walls

3.3.4.1 Concrete Masonry Unit Placement

a. Fully bed units used to form piers, pilasters, columns, starting courses on footings, solid foundation walls, lintels, and beams, and where cells are to be filled with grout in mortar under both face shells and webs. Provide mortar beds under both face shells for other units. Mortar head joints for a distance in from the face of the unit not less than the thickness of the face shell.

b. Solidly grout foundation walls below grade.

c. Stiffen double walls at wall-mounted plumbing fixtures by use of strap anchors, two above each fixture and two below each fixture, located to avoid pipe runs, and extending from center to center of each wall within the double wall. Adequately reinforce walls and partitions for support of wall-hung plumbing fixtures when chair carriers are not specified.

d. Submit drawings showing elevations of walls exposed to view and indicating the location of all cut CMU products.

3.3.4.2 Preparation for Reinforcement

Lay units in such a manner as to preserve the unobstructed vertical continuity of cores to be grouted. Remove mortar protrusions extending 1/2 inch or more into cells before placing grout. Position reinforcing bars accurately as indicated before placing grout. Where vertical reinforcement occurs, fill cores solid with grout in accordance with paragraph PLACING GROUT in this Section.

3.3.5 ANCHORAGE

3.3.5.1 Anchorage to Concrete

Anchorage of masonry to the face of concrete columns, beams, or walls shall be with dovetail anchors spaced not over 16 inches on centers vertically and 24 inches on center horizontally.

3.3.5.2 Anchorage to Structural Steel

Masonry shall be anchored to vertical structural steel framing with adjustable steel wire anchors spaced not over 16 inches on centers vertically, and if applicable, not over 24 inches on centers horizontally.

3.3.6 Lintels

3.3.6.1 Masonry Lintels

Construct masonry lintels with lintel units filled solid with grout in all courses and reinforced with a minimum of two No. 4 bars in the bottom course unless otherwise indicated. Extend lintel reinforcement beyond each side of masonry opening 40 bar diameters or 24 inches, whichever is greater. Support reinforcing bars in place prior to grouting and locate 1/2 inch above the bottom inside surface of the lintel unit.

3.3.6.2 Precast Concrete and Steel Lintels

Provide precast concrete and steel lintels as shown on the Drawings. Set lintels in a full bed of mortar with faces plumb and true. Provide steel and precast lintels with a minimum bearing length of 8 inches unless otherwise indicated. In partially grouted masonry, provide fully grouted units under the full lintel bearing length, unless otherwise indicated.

3.4 INSTALLATION

3.4.1 Bar Reinforcement Installation

3.4.1.1 Preparation

Submit detail drawings showing bar splice locations. Identify bent bars on a bending diagram and reference and locate such bars on the drawings. Show wall dimensions, bar clearances, and wall openings. Utilize bending details that conform to the requirements of ACI SP-66. No approval will be given to the shop drawings until the Contractor certifies that all openings, including those for mechanical and electrical service, are shown. If, during construction, additional masonry openings are required, resubmit the approved shop drawings with the additional openings shown

along with the proposed changes. Clearly highlight location of these additional openings. Provide wall elevation drawings with minimum scale of 1/4 inch per foot. Submit drawings including plans, elevations, and details of wall reinforcement; details of reinforcing bars at corners and wall intersections; offsets; tops, bottoms, and ends of walls; control and expansion joints; lintels; and wall openings.

Clean reinforcement of loose, flaky rust, scale, grease, mortar, grout, and other coatings that might destroy or reduce its bond prior to placing grout. Do not use bars with kinks or bends not shown on the approved shop drawings. Place reinforcement prior to grouting. Unless otherwise indicated, extend vertical wall reinforcement to within 2 inches of tops of walls.

3.4.1.2 Positioning Bars

a. Accurately place vertical bars within the cells at the positions indicated on the drawings. A minimum clearance of 1/2 inch shall be maintained between the bars and masonry units. Provide minimum clearance between parallel bars of 1/2 inch between the bars and masonry units for coarse grout and a minimum clearance of 1/4 inch between the bars and masonry units for fine grout. Provide minimum clearance between parallel bars of 1 inch or one diameter of the reinforcement, whichever is greater. Vertical reinforcement may be held in place using bar positioners located near the ends of each bar and at intermediate intervals of not more than 192 diameters of the reinforcement or by other means to prevent displacement beyond permitted tolerances. As masonry work progresses, secure vertical reinforcement to prevent displacement beyond allowable tolerances.

b. Wire column and pilaster lateral ties in position around the vertical reinforcing bars. Place lateral ties in contact with the vertical reinforcement and do not place in horizontal mortar bed joints.

c. Position horizontal reinforcing bars as indicated. Stagger splices in adjacent horizontal bars, unless otherwise indicated.

d. Form splices by lapping bars as indicated. Do not cut, bend or eliminate reinforcing bars. Foundation dowel bars may be field-bent when permitted by TMS MSJC.

3.4.1.3 Splices of Bar Reinforcement

Lap splice reinforcing bars as indicated. When used, provide welded or mechanical connections that develop at least 125 percent of the specified yield strength of the reinforcement.

3.4.2 Placing Grout

3.4.2.1 General

Fill cells containing reinforcing bars with grout. Solidly grout hollow masonry units in walls or partitions supporting plumbing, heating, or other mechanical fixtures, voids at door and window jambs, and other indicated spaces. Solidly grout cells under lintel bearings on each side of openings for full height of openings. Solidly grout walls below grade, lintels, and bond beams. Units other than open end units may require grouting each course to preclude voids in the units.

Discard site-mixed grout that is not placed within 1-1/2 hours after water is first added to the batch or when the specified slump is not met without adding water after initial mixing. Discard ready-mixed grout that does not meet the specified slump without adding water other than water that was added at the time of initial discharge. Allow sufficient time between grout lifts to preclude displacement or cracking of face shells of masonry units. Provide a grout shear key between lifts when grouting is delayed and the lower lift loses plasticity. If blowouts, flowouts, misalignment, or cracking of face shells should occur during construction, tear down the wall and rebuild.

3.4.2.2 Vertical Grout Barriers for Multi-Wythe Composite Walls

In multi-wythe composite walls, provide grout barriers in the collar join not more than 30 feet apart, or as required, to limit the horizontal flow of grout for each pour.

3.4.2.3 Horizontal Grout Barriers

Embed horizontal grout barriers in mortar below cells of hollow units receiving grout.

3.4.2.4 Grout Holes and Cleanouts

3.4.2.4.1 Grout Holes

Provide grouting holes in slabs, spandrel beams, and other in-place overhead construction. Locate holes over vertical reinforcing bars or as required to facilitate grout fill in bond beams. Provide additional openings spaced not more than 16 inches on centers where grouting of hollow unit masonry is indicated. Fom such openings not less than 4 inches in diameter or 3 by 4 inches in horizontal dimensions. Upon completion of grouting operations, plug and finish grouting holes to match surrounding surfaces.

3.4.2.4.2 Cleanouts for Hollow Unit Masonry Construction

For hollow masonry units. provide cleanout holes at the bottom of every grout pour in cores containing vertical reinforcement when the height of the grout pour exceeds 5 feet 4 inches. Where all cells are to be grouted, construct cleanout courses using bond beam units in an inverted position to permit cleaning of all cells. Provide cleanout holes at a maximum spacing of 32 inches where all cells are to be filled with grout.

Establish a new series of cleanouts if grouting operations are stopped for more than 4 hours. Provide cleanouts not less than 3 by 3 inch by cutting openings in one face shell. Manufacturer's standard cutout units may be used at the Contractor's option. Do not cleanout holes until masonry work, reinforcement, and final cleaning of the grout spaces have been completed and inspected. For walls which will be exposed to view, close cleanout holes in an approved manner to match surrounding masonry.

3.4.2.4.3 Cleanouts for Multi-Wythe Composite Masonry Construction

Provide cleanouts for construction of walls that incorporate a grout filled cavity between solid masonry wythes, provide cleanouts at the bottom of every pour by omitting every other masonry unit from one wythe. Establish a new series of cleanouts if grouting operations are stopped for more than 4 hours. Do not plug cleanout holes until masonry work, reinforcement, and

final cleaning of the grout spaces have been completed and inspected. For walls which will be exposed to view, close cleanout holes in an approved manner to match surrounding masonry.

3.4.2.5 Grout Placement

A grout pour is the total height of masonry to be grouted prior to erection of additional masonry. A grout lift is an increment of grout placement within a grout pour. A grout pour is filled by one or more lifts of grout.

a. Lay masonry to the top of a pour permitted by TMS MSJC Table 7, based on the size of the grout space and the type of grout. Prior to grouting, remove masonry protrusions that extend 1/2 inch or more into cells or spaces to be grouted. Provide grout holes and cleanouts in accordance with paragraph GROUT HOLES AND CLEANOUTS above when the grout pour height exceeds 5 feet 4 inches. Hold reinforcement, bolts, and embedded connections rigidly in position before grouting is started. Do not prewet concrete masonry units.

b. Place grout using a hand bucket, concrete hopper, or grout pump to fill the grout space without segregation of aggregate. Operate grout pumps to produce a continuous stream of grout without air pockets, segregation, or contamination.

c. If the masonry has cured at least 4 hours, grout slump is maintained between 10 to 11 inches, and no intermediate reinforced bond beams are placed between the top and bottom of the pour height, place conventional grout in lifts not exceeding 12 feet 8 inches. For the same curing and slump conditions but with intermediate bond beams, limit conventional grout lift to the bottom of the lowest bond beam that is more than 5 feet 4 inches above the bottom of the lift, but do not exceed 12 feet 8 inches. If masonry has not cured at least 4 hours or grout slump is not maintained between 10 to 11 inches, place conventional grout in lifts not exceeding 5 feet 4 inches.

d. Consolidate conventional grout lift and reconsolidate after initial settlement before placing next lift. For grout pours that are 12 inches or less in height, consolidate and reconsolidate grout by mechanical vibration or puddling. For grout pours that are greater than 12 inches in height, consolidate and reconsolidate grout by mechanical vibration. Apply vibrators at uniformly spaced points not further apart than the visible effectiveness of the machine. Limit duration of vibration to time necessary to produce satisfactory consolidation without causing segregation. If previous lift is not permitted to set, dip vibrator into previous lift. Do not insert vibrators into lower lifts that are in a semi-solidified state. If lower lift sets prior to placement of subsequent lift, form a grout key by terminating grout a minimum of 1-1/2 inch below a mortar joint. Vibrate each vertical cell containing reinforcement in partially grouted masonry. Do not form grout keys within beams.

e. If the masonry has cured 4 hours, place self-consolidating grout (SCG) in lifts not exceeding the pour height. If masonry has not cured for at least 4 hours, place SCG in lifts not exceeding 5 feet 4 inches. Do not mechanically consolidate self-consolidating grout. Place self-consolidating grout in accordance with manufacturer's recommendations.

f. Upon completion of each day's grouting, remove waste materials and

debris from the equipment, and dispose of outside the masonry.

3.4.3 Bond Beams

Reinforce and grout bond beams as indicated and as described in paragraphs above. Install grout barriers under bond beam units to retain the grout as required, unless wall is fully grouted or solid bottom units are used. For high lift grouting in partially grouted masonry, provide grout retaining material on the top of bond beams to prevent upward flow of grout. Ensure that reinforcement is continuous, including around corners, except through control joints or expansion joints, unless otherwise indicated.

3.4.4 Flashing and Weeps

a. Install through-wall flashing at obstructions in the cavity and where indicated on Drawings. Ensure continuity of the flashing at laps and inside and outside corners by splicing in a manner approved by the flashing manufacturer. Ensure that the top edge of the flashing is sealed by turning the flashing 1/2 inch into the mortar bed joint of backup masonry attaching a termination bar and applying compatible sealant at the top edge of the termination bar lapping a minimum of 6 inches under the weather resistive barrier securing the sheet metal flashing into a reglet cast into the concrete backup. Terminate the horizontal leg of the flashing by extending the sheet metal 1/2 inch beyond the outside face of masonry and turning downward with a hemmed drip terminating the fabric flashing 1/2 inch short of the outside face of masonry and adhering the flashing to a sheet metal drip edge extending the fabric flashing beyond the outside face of masonry and, when construction is complete, cutting the flashing flush with the face of masonry. Provide sealant below the drip edge of through-wall flashing.

b. Wherever through-wall flashing occurs, provide weep holes to drain flashing to exterior at acceptable locations as indicated. Provide weeps of open head jointsweep ventilators. Locate weeps not more than 24 inches on centers in mortar joints of the exterior wythe directly on the horizontal leg of through-wall flashing over foundations, bond beams, and any other horizontal interruptions of the cavity. Place weep holes perfectly horizontal or slightly canted downward to encourage water drainage outward and not inward. Other methods may be used for providing weeps when spacing is reduced to 16 inches on center and approved by the Contracting Officer. Maintain weeps free of mortar and other obstructions.

c. Install single-wythe CMU flashing system in bed joints of CMU walls where CMU cells are open. Install CMU cell pans with upturned edges located below face shells and webs of CMUs above and with weep spouts aligned with face of wall on the exterior side. Install CMU web covers so that they cover upturned edges of CMU cell pans at CMU webs and extend from face shell to face shell.

3.5 APPLICATION

3.5.1 Insulation

Insulate cavity walls (multi-wythe noncomposite masonry walls), where shown, by installing board-type insulation on the cavity side of the inner wythe. Apply board type insulation directly to the masonry or thru-wall flashing with adhesive. Neatly fit insulation between obstructions without

impaling insulation on ties or anchors. Apply insulation in parallel courses with vertical joints breaking midway over the course below and in moderate contact with adjoining units without forcing. Cut to fit neatly against adjoining surfaces. Tape or seal the joints between the boards.

3.5.2 Interface with Other Products

3.5.2.1 Built-In Items

Fill spaces around built-in items with mortar. Point openings around flush-mount electrical outlet boxes in wet locations with mortar. Embed anchors, ties, wall plugs, accessories, flashing, pipe sleeves and other items required to be built-in as the masonry work progresses. Fully embed anchors, ties and joint reinforcement in the mortar. Fill cells receiving anchor bolts and cells of the first course below bearing plates with grout, unless otherwise indicated.

3.5.2.2 Door and Window Frame Joints

On the exposed interior and exterior sides of exterior frames, rake joints between frames and abutting masonry walls to a depth of 3/8 inch.

3.5.3 Tolerances

Lay masonry plumb, true to line, with courses level within the tolerances of TMS MSJC, Article 3.3 F.

3.6 FIELD QUALITY CONTROL

3.6.1 Tests

3.6.1.1 Field Testing of Mortar

For each required mortar test, provide a minimum of three mortar samples. Perform initial mortar testing prior to construction for comparison purposes during construction.

Prepare and test mortar samples for mortar aggregate ratio in accordance with ASTM C780 Appendix A4. Prepare and test mortar compressive strength specimens in accordance with ASTM C780 Appendix A6.

3.6.1.2 Field Testing of Grout

a. For each required grout property to be evaluated, provide a minimum of three specimens.

b. Sample and test conventional and self-conslidating grout for compressive strength and temperature in accordance with ASTM C1019.

c. Evaluate slump in conventional grout in accordance with ASTM C1019.

d. Evaluate slump flow and visual stability index of self-consolidating grout in accordance with ASTM C1611/C1611M.

3.7 POINTING AND CLEANING

After mortar joints have attained their initial set, but prior to hardening, completely remove mortar and grout daubs and splashings from masonry-unit surfaces that will be exposed or painted. Before completion

of the work, rake out defects in joints of masonry to be exposed or painted, fill with mortar, and tool to match existing joints. Immediately after grout work is completed, remove scum and stains that have percolated through the masonry work using a low pressure stream of water and a stiff bristled brush. Do not clean masonry surfaces, other than removing excess surface mortar, until mortar in joints has hardened. Leave masonry surfaces clean, free of mortar daubs, dirt, stain, and discoloration, including scum from cleaning operations, and with tight mortar joints throughout. Do not use metal tools and metal brushes for cleaning.

3.7.1 Dry-Brushing Concrete Masonry

Dry brush exposed concrete masonry surfaces at the end of each day's work and after any required pointing, using stiff-fiber bristled brushes.

3.8 PROTECTION

Protect facing materials against staining. Cover top of walls with nonstaining waterproof covering or membrane to protect from moisture intrusion when work is not in progress. Continue covering the top of the unfinished walls until the wall is waterproofed with a complete roof or parapet system. Extend covering a minimum of 2 feet down on each side of the wall and hold securely in place. Before starting or resuming work, clean top surface of masonry in place of loose mortar and foreign material.

-- End of Section --

SECTION 06 10 00

ROUGH CARPENTRY
08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN FOREST FOUNDATION (AFF)

ATFS STANDARDS	(2015) American Tree Farm System Standards of Sustainability 2015-2020

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)

AITC 111	(2005) Recommended Practice for Protection of Structural Glued Laminated Timber During Transit, Storage and Erection

AMERICAN LUMBER STANDARDS COMMITTEE (ALSC)

ALSC PS 20	(2015) American Softwood Lumber Standard

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2015) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B18.5.2.1M	(2006; R 2011) Metric Round Head Short Square Neck Bolts
ASME B18.5.2.2M	(1982; R 2010) Metric Round Head Square Neck Bolts
ASME B18.6.1	(2016) Wood Screws (Inch Series)

AMERICAN WOOD COUNCIL (AWC)

AWC WFCM	(2012) Wood Frame Construction Manual for One- and Two-Family Dwellings

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)

AWPA BOOK	(2015) AWPA Book of Standards
AWPA M2	(2019) Standard for the Inspection of Preservative Treated Wood Products for Industrial Use

AWPA M6	(2013) Brands Used on Preservative Treated Materials
AWPA P5	(2015) Standard for Waterborne Preservatives
AWPA P18	(2014) Nonpressure Preservatives
AWPA U1	(2020) Use Category System: User Specification for Treated Wood

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

APA E445	(2002) Performance Standards and Qualification Policy for Structural-Use Panels (APA PRP-108)
APA EWS R540	(2013) Builder Tips: Proper Storage and Handling of Glulam Beams
APA F405	(19) Product Guide: Performance Rated Panels
APA L870	(2010) Voluntary Product Standard, PS 1-09, Structural Plywood
APA S350	(2014) PS 2-10, Performance Standard for Wood-Based Structural-Use Panels

ASTM INTERNATIONAL (ASTM)

ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2014; E 2017) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM D198	(2015) Standard Test Methods of Static Tests of Lumber in Structural Sizes
ASTM D696	(2016) Standard Test Method for Coefficient of Linear Thermal Expansion of Plastics Between -30 degrees C and 30 degrees C With a Vitreous Silica Dilatometer
ASTM D1435	(2013) Standard Practice for Outdoor Weathering of Plastics
ASTM D1972	(1997; R 2005) Standard Practice for Generic Marking of Plastic Products
ASTM D2344/D2344M	(2016) Standard Test Method for Short-Beam Strength of Polymer Matrix Composite Materials and Their Laminates
ASTM D6108	(2013) Standard Test Method for

	Compressive Properties of Plastic Lumber and Shapes
ASTM D6109	(2013) Standard Test Methods for Flexural Properties of Unreinforced and Reinforced Plastic Lumber and Related Products
ASTM D6111	(2013a) Standard Test Method for Bulk Density and Specific Gravity of Plastic Lumber and Shapes by Displacement
ASTM D6112	(2013) Compressive and Flexural Creep and Creep-Rupture of Plastic Lumber and Shapes
ASTM D6117	(2016) Standard Test Methods for Mechanical Fasteners in Plastic Lumber and Shapes
ASTM F547	(2017) Standard Terminology of Nails for Use with Wood and Wood-Base Materials
ASTM F1667	(2018a) Standard Specification for Driven Fasteners: Nails, Spikes, and Staples

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

CSA GROUP (CSA)

CSA Z809-08	(R2013) Sustainable Forest Management

FM GLOBAL (FM)

FM 4435	(2013) Roof Perimeter Flashing

FOREST STEWARDSHIP COUNCIL (FSC)

FSC STD 01 001	(2015) Principles and Criteria for Forest Stewardship

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)

NHLA Rules	(2015) Rules for the Measurement & Inspection of Hardwood & Cypress

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)

NELMA Grading Rules	(2013) Standard Grading Rules for Northeastern Lumber

PROGRAMME FOR ENDORSEMENT OF FOREST CERTIFICATION (PEFC)

PEFC ST 2002:2013	(2015) PEFC International Standard Chain of Custody of Forest Based Products Requirements

REDWOOD INSPECTION SERVICE (RIS) OF THE CALIFORNIA REDWOOD ASSOCIATION (CRA)

RIS Grade Use	(1998) Redwood Lumber Grades and Uses

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2017) Adhesive and Sealant Applications

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)

SCMA Spec	(1986; Supple. No. 1, Aug 1993) Standard Specifications for Grades of Southern Cypress

SOUTHERN PINE INSPECTION BUREAU (SPIB)

SPIB 1003	(2014) Standard Grading Rules for Southern Pine Lumber

SUSTAINABLE FOREST INITIATIVE (SFI)

SFI 2015-2019	(2015) Standards, Rules for Label Use, Procedures and Guidance

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-1923	(Rev A; Notice 3) Shield, Expansion (Lag, Machine and Externally Threaded Wedge Bolt Anchors)
CID A-A-1924	(Rev A; Notice 3) Shield, Expansion (Self Drilling Tubular Expansion Shell Bolt Anchors
CID A-A-1925	(Rev A; Notice 3) Shield Expansion (Nail Anchors)

UNDERWRITERS LABORATORIES (UL)

UL 2818	(2013) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)

WCLIB 17	(2015) Standard Grading Rules

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)

WWPA G-5	(2017) Western Lumber Grading Rules

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. the Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Wood Blocking, Nailers and Nailing Strips; G

SD-06 Test Reports

Preservative-treated Lumber and Plywood

1.3 DELIVERY AND STORAGE

Deliver materials to the site in an undamaged condition. Store, protect, handle, and install prefabricated structural elements in accordance with manufacturer's instructions and as specified. Store materials off the ground to provide proper ventilation, with drainage to avoid standing water, and protection against ground moisture and dampness. Store materials with a moisture barrier at both the ground level and as a cover forming a well ventilated enclosure. Store wood I-beams and glue-laminated beams and joists on edge. Adhere to requirements for stacking, lifting, bracing, cutting, notching, and special fastening requirements. Handle and store laminated timber in accordance with AITC 111 or APA EWS R540. Do not use materials that have visible moisture or biological growth. Remove defective and damaged materials and provide new materials. Store separated reusable wood waste convenient to cutting station and area of work.

1.4 GRADING AND MARKING

1.4.1 Lumber

Mark each piece of framing and board lumber or each bundle of small pieces of lumber with the grade mark of a recognized association or independent inspection agency. Such association or agency must be certified by the Board of Review, American Lumber Standards Committee, to grade the species used. Surfaces that are to be exposed to view must not bear grademarks, stamps, or any type of identifying mark. Hammer marking will be permitted on timbers when all surfaces will be exposed to view.

1.4.2 Plywood

Mark each sheet with the mark of a recognized association or independent inspection agency that maintains continuing control over the quality of the plywood. The mark must identify the plywood by species group or span rating, exposure durability classification, grade, and compliance with APA L870. Surfaces that are to be exposed to view must not bear grademarks or other types of identifying marks.

1.4.3 Preservative-Treated Lumber and Plywood

The Contractor is responsible for the quality of treated wood products.

Each treated piece must be inspected in accordance with AWPA M2 and permanently marked or branded, by the producer, in accordance with AWPA M6. The Contractor must provide Contracting Officer's Representative (COR) with the inspection report of an approved independent inspection agency that offered products comply with applicable AWPA Standards. The appropriate Quality Mark on each piece will be accepted, in lieu of inspection reports, as evidence of compliance with applicable AWPA treatment standards.

1.4.4 Hardboard, Gypsum Board, and Fiberboard

Mark each sheet or bundle to identify the standard under which the material is produced and the producer.

1.4.5 Plastic Lumber

Label plastic products to be incorporated into the project in accordance with ASTM D1972, or provide product data indicating polymeric information in the Operation and Maintenance Manual.

a. Type 1: Polyethylene Terephthalate (PET, PETE).
b. Type 2: High Density Polyethylene (HDPE).
c. Type 3: Vinyl (Polyvinyl Chloride or PVC).
d. Type 4: Low Density Polyethylene (LDPE).
e. Type 5: Polypropylene (PP).
f. Type 6: Polystyrene (PS).
g. Type 7: Other. Use of this code indicates that the package in question. is made with a resin other than the six listed above, or is made of more than one resin listed above, and used in a multi-layer combination.

1.5 SIZES AND SURFACING

ALSC PS 20 for dressed sizes of yard and structural lumber. Lumber must be surfaced four sides. Size references, unless otherwise specified, are nominal sizes, and actual sizes must be within manufacturing tolerances allowed by the standard under which the product is produced. Other measurements are IP or SI standard.

1.6 MOISTURE CONTENT

Air-dry or kiln-dry lumber. Kiln-dry treated lumber after treatment. Maximum moisture content of wood products must be as follows at the time of delivery to the job site:

a. Moisture content must be in accordance with standard under which the product is produced

1.7 PRESERVATIVE TREATMENT

Treat wood products with waterborne wood preservatives conforming to AWPA P5. Pressure treatment of wood products must conform to the requirements of AWPA BOOK Use Category System Standards U1 and T1. Pressure-treated wood products must not contain arsenic, chromium, or other agents classified as carcinogenic, probably carcinogenic, or possibly carcinogenic to humans (compounds in Groups 1, 2A, or 2B) by the International Agency for Research on Cancer (IARC), Lyon, France. Pressure-treated wood products must not exceed the limits of the U.S. EPA's Toxic Characteristic Leaching Procedure (TCLP), and must not be classified as hazardous waste. Submit certification from treating plant stating chemicals and process used and

net amount of preservatives retained are in conformance with specified standards. In accordance with AWPA U1 provide non-copper preservative treatment such as EL2, PTI or SBX,DOT for products in direct contact with sheet metal.

a. 0.25 pcf intended for above ground use.

b. All wood must be air or kiln dried after treatment. Specific treatments must be verified by the report of an approved independent inspection agency, or the AWPA Quality Mark on each piece. Minimize cutting and avoid breathing sawdust. Brush coat areas that are cut or drilled after treatment with either the same preservative used in the treatment or with a 2 percent copper naphthenate solution. All lumber and woodwork must be preservative treated. Plastic lumber must not be preservative treated. The following items must be preservative treated:

(1) Nailers, edge strips, crickets, curbs, and cants for roof decks.

1.7.1 Existing Structures

Use borate, permathrin, or a sodium silicate wood mineralization process to treat wood. Use borate for interior applications only.

1.7.2 New Construction

Use a boron-based preservative conforming to AWPA P18, sodium silicate wood mineralization process, or Ammoniacal Copper Quaternary Compound to treat wood. Use boron-based preservatives for above-ground applications only.

1.8 QUALITY ASSURANCE

1.8.1 Drawing Requirements

Do not proceed with modifications until the submittal has been approved.

1.8.2 Humidity Requirements

Sequence work to minimize use of temporary HVAC to dry out building and control humidity.

1.8.3 Plastic Lumber Performance

Plastic lumber intended for use in exterior applications must have no fading or discoloration and no change in dimensional stability as tested in accordance with ASTM D1435 for a period of 5 years.

1.9 ENVIRONMENTAL REQUIREMENTS

During and immediately after installation of treated wood, engineered wood products, and laminated wood products at interior spaces, provide temporary ventilation.

1.10 CERTIFICATIONS

1.10.1 Certified Wood Grades

Provide certificates of grade from the grading agency on graded but unmarked lumber or plywood attesting that materials meet the grade requirements specified herein.

1.10.2 Certified Sustainably Harvested Wood

Provide wood certified as sustainably harvested by FSC STD 01 001, ATFS STANDARDS, CSA Z809-08, SFI 2015-2019, or other third party program certified by PEFC ST 2002:2013. Provide a letter of Certification of Sustainably Harvested Wood signed by the wood supplier. Identify certifying organization and their third party program name and indicate compliance with chain-of-custody program requirements. Submit sustainable wood certification data; identify each certified product on a line item basis. Submit copies of invoices bearing certification numbers.

1.10.3 Indoor Air Quality Certifications

Submit required indoor air quality certifications in one submittal package.

1.10.3.1 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Virgin Lumber

Lumber fabricated from old growth timber is not permitted. Avoid companies who buy, sell, or use old growth timber in their operations, when possible. Provide certified sustainably harvested virgin lumber.

2.1.2 Plastic Lumber

HDPE lumber must contain a minimum of 90 percent total recycled content. Mixed plastics and cellulose lumber must contain a minimum of 100 percent total recovered materials content, with a minimum of 50 percent post-consumer recycled content. HDPE/fiberglass lumber must contain a minimum of 95 percent total recovered materials content with a minimum of 75 percent post-consumer recycled content. Other mixed resin lumber must contain a minimum of 95 percent total recovered materials content with a minimum of 50 percent post-consumer recycled content. Provide data identifying percentage of recycled content for plastic lumber.

2.1.2.1 Shear Parallel to Length

Maximum 1,000 psi in accordance with ASTM D2344/D2344M.

2.1.2.2 Density

ASTM D6111.

2.1.2.3 Compressive Strength

a. Secant Modulus: Minimum 70,000 psi in accordance with ASTM D6108.

b. Stress at 3 percent strain: Minimum 1,500 psi in accordance with ASTM D6108.

c. Compression Parallel to Grain: Minimum 3,000 psi in accordance with ASTM D6112.

d. Compression Perpendicular to Grain: Minimum 1,000 psi in accordance with ASTM D6112.

2.1.2.4 Flexural Strength

Minimum 2,000 psi in accordance with ASTM D6109.

2.1.2.5 Tensile Strength

Minimum 1,250 psi in accordance with ASTM D198.

2.1.2.6 Coefficient of Thermal Expansion

Maximum 0.000080 in/in/degree F in accordance with ASTM D696.

2.1.2.7 Screw Withdrawal

350 lbs in accordance with ASTM D6117.

2.1.2.8 Nail Withdrawal

150 lbs in accordance with ASTM D6117.

]2.2 LUMBER

2.2.1 Framing Lumber

Framing lumber such as studs, plates, caps, collar beams, cant strips, bucks, sleepers, nailing strips, and nailers and board lumber such as subflooring and wall and roof sheathing must be one of the species listed in the table below. Minimum grade of species must be as listed. Provide certified sustainably harvested framing lumber.

Table of Grades for Framing and Board Lumber			
Grading Rules	Species	Framing	Board Lumber
WWPA G-5 standard grading rules	Aspen, Douglas Fir-Larch, Douglas Fir South, Engelmann Spruce-Lodgepole Pine, Engelmann Spruce, Hem-Fir, Idaho White Pine, Lodgepole Pine, Mountain Hemlock, Mountain Hemlock-Hem-Fir, Ponderosa Pine-Sugar Pine, Ponderosa Pine-Lodgepole Pine, Subalpine Fir, White Woods, Western Woods, Western Cedars, Western Hemlock	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	All Species: No. 3 Common
WCLIB 17 standard grading rules	Douglas Fir-Larch, Hem-Fir, Mountain Hemlock, Sitka Spruce, Western Cedars, Western Hemlock	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	All Species: Standard

Table of Grades for Framing and Board Lumber			
Grading Rules	Species	Framing	Board Lumber
SPIB 1003 standard grading rules	Southern Pine	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	No. 2 Boards
SCMA Spec standard specifications	Cypress	No. 2 Common	No. 2 Common
NELMA Grading Rules standard grading rules	Balsam Fir, Eastern Hemlock-Tamarack, Eastern Spruce, Eastern White Pine, Northern Pine, Northern Pine-Cedar	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	All Species: No. 3 Common except Standard for Eastern White and Northern Pine
RIS Grade Use standard specifications	Redwood	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	Construction Heart

Table of Grades for Framing and Board Lumber			
Grading Rules	Species	Framing	Board Lumber
NHLA Rules rules for the measurement and inspection of hardwood and cypress lumber	Cypress	No. 2 Dimension	No. 2 Common

2.3 PLYWOOD, STRUCTURAL-USE, AND ORIENTED STRAND BOARD (OSB) PANELS

APA L870, APA S350, APA E445, and APA F405 respectively.

2.4 OTHER MATERIALS

2.4.1 Roof Decking

Roof decking must be commercial grade.

2.4.2 Miscellaneous Wood Members

2.4.2.1 Nonstress Graded Members

Members must include bridging, corner bracing, furring, grounds, and nailing strips. Members must be in accordance with TABLE I for the species used. Sizes must be as follows unless otherwise shown:

Member	Size inch
Bridging	1 x 3 or 1 x 4 for use between members 2 x 12 and smaller; 2 x 4 for use between members larger than 2 x 12.
Corner bracing	1 x 4.
Furring	1 x 2 3
Grounds	Plaster thickness by 38.
Nailing strips	1 x 3 or 1 x 4 when used as shingle base or interior finish, otherwise 2 inch stock.

2.4.2.2 Blocking

Blocking must be standard or number 2 grade.

2.4.3 Adhesives

Comply with applicable regulations regarding toxic and hazardous materials

and as specified. Provide non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide aerosol adhesives used on the interior of the building meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for non-aerosol adhesives applied on the interior of the building (inside of the weatherproofing system). Provide certification or validation of indoor air quality for aerosol adhesives used on the interior of the building (inside of the weatherproofing system).

2.5 ROUGH HARDWARE

Unless otherwise indicated or specified, rough hardware must be of the type and size necessary for the project requirements. Sizes, types, and spacing of fastenings of manufactured building materials must be as recommended by the product manufacturer unless otherwise indicated or specified. Rough hardware exposed to the weather or embedded in or in contact with preservative treated wood, exterior masonry, or concrete walls or slabs must be hot-dip zinc-coated in accordance with ASTM A153/A153M. Nails and fastenings for fire-retardant treated lumber and woodwork exposed to the weather must be copper alloy or hot-dipped galvanized fasteners as recommended by the treated wood manufacturer.

2.5.1 Bolts, Nuts, Studs, and Rivets

ASME B18.2.1, ASME B18.5.2.1M, ASME B18.5.2.2M and ASME B18.2.2.

2.5.2 Anchor Bolts

ASTM A307, size as indicated, complete with nuts and washers.

2.5.3 Expansion Shields

CID A-A-1923, CID A-A-1924, and CID A-A-1925. Except as shown otherwise, maximum size of devices must be 3/8 inch.

2.5.4 Lag Screws and Lag Bolts

ASME B18.2.1.

2.5.5 Wood Screws

ASME B18.6.1.

2.5.6 Nails

ASTM F547, size and type best suited for purpose

2.5.7 Wire Nails

ASTM F1667.

2.6 AIR INFILTRATION BARRIER

Refer to other spec sections.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

Conform to AWC WFCM and install in accordance with the National Association of Home Builders (NAHB) Advanced Framing Techniques: Optimum Value Engineering, unless otherwise indicated or specified.

3.1.1 Plastic Lumber

In conjunction with above requirements, follow manufacturer's recommendations for plastic lumber installation, including requirements for structural support, thermal movement, working, fastening, and finishing. Use standard woodworking tools, including carbide tips, coarse saw blades, and routers with aggressive cutters. Follow manufacturer's recommendations for repair by melting.

3.2 MISCELLANEOUS

3.2.1 Wood Roof Nailers, Edge Strips, Crickets, Curbs, and Cants

Provide sizes and configurations indicated or specified and anchored securely to continuous construction.

3.2.1.1 Roof Nailing Strips

Provide roof nailing strips for roof decks as indicatedspecified herein. Apply nailing strips in straight parallel rows in the direction and spacing indicated.

3.2.1.2 Roof Edge Strips and Nailers

Provide at perimeter of roof, around openings through roof, and where roofs abut walls, curbs, and other vertical surfaces. Except where indicated otherwise, nailers must be 6 inches wide and the same thickness as the insulation. Anchor nailers securely to underlying construction. Anchor perimeter nailers in accordance with FM 4435.

3.2.1.3 Crickets, Cants, and Curbs

Provide wood saddles or crickets, cant strips, and at expansion joints, as indicated, specified, or necessary.

3.2.2 Wood Blocking

Provide proper sizes and shapes at proper locations for the installation and attachment of wood and other finish materials, fixtures, equipment, and items indicated or specified.

3.2.3 Temporary Centering, Bracing, and Shoring

Provide for the support and protection of masonry work during construction as specified.

-- End of Section --

SECTION 07 21 13

BOARD AND BLOCK INSULATION
02/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C552	(2017; E 2018) Standard Specification for Cellular Glass Thermal Insulation
ASTM C578	(2019) Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation
ASTM C591	(2020) Standard Specification for Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
ASTM C930	(2019) Standard Classification of Potential Health and Safety Concerns Associated with Thermal Insulation Materials and Accessories
ASTM D3833/D3833M	(1996; R 2011) Water Vapor Transmission of Pressure-Sensitive Tapes
ASTM E84	(2020) Standard Test Method for Surface Burning Characteristics of Building Materials

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2018) International Building Code

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2020; ERTA 20-1 2020; ERTA 20-2 2020; TIA 20-1; TIA 20-2; TIA 20-3; TIA 20-4) National Electrical Code
NFPA 211	(2019) Standard for Chimneys, Fireplaces, Vents, and Solid Fuel-Burning Appliances

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.134	Respiratory Protection

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control

approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Manufacturer's Standard Details; G

Block or Board Insulation; G

Vapor Retarder; G

Pressure Sensitive Tape; G

Protection Board or Coatings; G

Accessories including sealants; G

Recycled Content for Block or Board Insulation; S

SD-07 Certificates

Block or Board Insulation; G

Vapor Retarder; G

Protection Board or Coating; G

Draft Special Warranties; G

Final Special Warranties; G

Indoor Air Quality For Block Or Board Insulation; S

SD-08 Manufacturer's Instructions

Block or Board Insulation

Adhesive

1.3 MANUFACTURER'S DETAILS

Submit manufacturer's standard details indicating methods of attachment and spacing, transition and termination details, and installation details. Include verification of existing conditions.

1.4 PRODUCT DATA

Include data for material descriptions, recommendations for product shelf life, requirements for protection board or coatings, and precautions for flammability and toxicity. Include data to verify compatibility of sealants with insulation.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver materials to the site in original sealed wrapping bearing manufacturer's name and brand designation, specification number, type, grade, R-value, and class. Store and handle to protect from damage. Do not allow insulation materials to become wet, soiled, crushed, or covered with ice or snow. Comply with manufacturer's recommendations for handling, storing, and protecting of materials before and during installation.

1.5.2 Storage

Inspect materials delivered to the site for damage and store out of weather in manufacturer's original packaging. Store only in dry locations, not subject to open flames or sparks, and easily accessible for inspection and handling. Keep materials wrapped and separated from off-gassing materials (such as drying paints and adhesives). Do not use materials that have visible moisture or biological growth. Comply with manufacturer's recommendations for handling, storage, and protection of materials before and during installation.

1.6 SAFETY PRECAUTIONS

1.6.1 Respirators

Provide installers with dust/mist respirators, training in their use, and protective clothing, all approved by the National Institute for Occupational Safety and Health (NIOSH)/Mine Safety and Health Administration (MSHA) and in accordance with 29 CFR 1910.134.

1.6.2 Other Safety Considerations

Comply with the safety requirements of ASTM C930.

1.7 SPECIAL WARRANTIES

1.7.1 Guarantee

Guarantee insulation installation against failure due to ultraviolet light exposure for a period of three years from the date of Beneficial Occupancy or Substantial Completion.

1.7.2 Warranty

Provide manufacturer's material warranty for all system components for a period of three years from the date of Beneficial Occupancy or Substantial Completion.

PART 2 PRODUCTS

2.1 BLOCK OR BOARD INSULATION

Provide thermal insulating materials as recommended by manufacturer for each type of application indicated. Provide insulation with the following physical properties and in accordance with the following standards:

a. Cellular Glass: ASTM C552

b. Extruded Preformed Cellular Polystyrene: ASTM C578 REV A

c. Unfaced Preformed Rigid Polyurethane and Polyisocyanurate Board: ASTM C591

2.1.1 Thermal Resistance

Comply with ASHRE 90.1.

2.1.2 Fire Protection Requirements

a. Flame spread index of 75 or less when tested in accordance with ASTM E84.

b. Smoke developed index of 450 or less when tested in accordance with ASTM E84.

c. Provide insulated assemblies in accordance ICC IBC Chapter Fire and Smoke Protection Features.

2.1.3 Recycled Materials

Provide thermal insulation containing recycled materials to the extent practicable, provided that the material meets all other requirements of this section. The minimum required recycled material contents (by weight, not volume) are:

Polyisocyanurate/Polyurethane:	9 percent
Phenolic Rigid Foam:	5 percent
Perlite Board:	75 percent post consumer paper

Provide data identifying percentage of recycled content for block or board insulation.

2.1.4 Indoor Air Quality

Provide certification of indoor air quality for block or board insulation.

2.1.5 Prohibited Materials

Do not provide materials containing asbestos.

2.2 VAPOR RETARDER

2.2.1 Vapor Retarder in Framed Walls and Roofs

a. Refer to other spec sections.

2.3 PRESSURE SENSITIVE TAPE

As recommended by manufacturer of vapor retarder(s). Match water vapor permeance rating for each vapor retarder specified. Provide tape in accordance with ASTM D3833/D3833M.

2.4 PROTECTION BOARD OR COATING

As recommended by insulation manufacturer.

2.5 ACCESSORIES

2.5.1 Adhesive

As recommended by insulation manufacturer.

2.5.2 Mechanical Fasteners

Corrosion resistant fasteners as recommended by the insulation manufacturer.

PART 3 EXECUTION

3.1 EXISTING CONDITIONS

Prior to installation, ensure all areas that are in contact with the insulation are dry and free of projections that could cause voids, compressed insulation, or punctured vapor retarders. For foundation perimeter or under slab applications, check that subsurface fill is flat, smooth, dry, and well tamped. Do not proceed with installation if moisture or other conditions are present, and notify the Contracting Officer of such conditions. Do not proceed with the work until conditions have been corrected and verified to be dry.

3.2 PREPARATION

3.2.1 Blocking Around Heat Producing Devices

Provide noncombustible blocking at all spaces between heat producing devices and the floors, ceilings and roofs through which they pass. Provide in accordance with ICC IBC Section 2111.12 Fireplace Blocking and with the following clearances:

a. Recessed lighting fixtures, including wiring compartments, ballasts, and other heat producing devices, unless certified for installation surrounded by insulation: 3 inches from outside face of fixtures and devices or as required by NFPA 70 and, if insulation is placed above fixture or device, 24 inches above fixture.

b. Vents and vent connectors used for venting products of combustion, flues, and chimneys other than masonry chimneys: Minimum clearances as required by NFPA 211.

3.3 INSTALLATION

3.3.1 Installation and Handling

Provide insulation in accordance with the manufacturer's printed installation instructions. Keep material dry and free of extraneous materials.

3.3.2 Electrical Wiring

Do not install insulation in a manner that would enclose electrical wiring between two layers of insulation.

3.3.3 Cold Climate Requirement

Place insulation on the outside of pipes.

3.3.4 Continuity of Insulation

Butt tightly against adjoining boards, studs, rafters, joists, sill plates, headers and obstructions. Provide continuity and integrity of insulation at corners, wall to ceiling joint, roof, and floor. Avoid creating thermal bridges and voids. Provide and verify continuity of insulative barrier throughout the building enclosure.

3.3.5 Coordination

Verify final installed insulation thicknesses comply with thicknesses indicated, R-values specified herein, and with the approved insulation submittal(s).

3.4 INSTALLATION ON WALLS

3.4.1 Installation using Furring Strips

Install insulation between members as recommended by insulation manufacturer.

3.4.2 Installation on Masonry Walls

Apply board directly to masonry with adhesive or fasteners as recommended by the insulation manufacturer. Fit between obstructions without impaling board on ties or anchors. Apply in parallel courses with joints breaking midway over course below. Place boards in moderate contact with adjoining insulation without forcing and without gaps. Cut and shape as required to fit around wall penetrations, projections or openings to accommodate conduit or other utilities. Seal around cutouts with sealant. Install insulation in wall cavities so that it leaves at least a nominal 1 inch air space outside of the insulation to allow for cavity drainage.

3.4.3 Mechanical Attachment on Concrete and Masonry Walls

Cut insulation to cover walls. Apply adhesive to wall and set clip or other mechanical fastener in adhesive as recommended by manufacturer. After curing of adhesive, install insulation over fasteners and bend split prongs to provide a flush condition with the insulation. Butt all edges of insulation and seal with tape.

3.4.4 Protection Board or Coating

Install protection board or coating in accordance with manufacturer's printed instructions. Install protection over all exterior exposed insulation and to 1 foot below grade.

3.5 PERIMETER INSULATION

Install perimeter thermal insulation as indicated .

3.5.1 Manufacturer's Instructions

Layout insulation, tape edges, provide vapor retarder and other required accessories to protection against vermin, insects, and damage in accordance

with manufacturer's printed instructions.

3.5.2 Insulation on Vertical Surfaces

Provide thermal insulation as indicated. Fasten insulation with mechanica fasteners.

3.5.3 Protection of Insulation

Protect insulation from damage during construction and back filling by application of protection board or a coating. Do not leave installed vertical insulation unprotected overnight. Protect installed insulation from weather, including rain and ultraviolet light, from mechanical abuse, compression, and dislocation.

3.6 VAPOR RETARDER

Apply vapor retarder continuous across all surfaces. Overlap all joints at least 6 inches and seal with pressure sensitive tape. Seal at sills, header, windows, doors and utility penetrations. Repair punctures or tears with pressure sensitive tape.

-- End of Section --

SECTION 07 27 10.00 10

BUILDING AIR BARRIER SYSTEM
08/19

PART 1 GENERAL

1.1 SUMMARY

This Section specifies the construction and quality control of the installation of an air barrier system. Construct the air barrier system indicated, taking responsibity for the means, methods, and workmanship of the installation of the air barrier system. The air barrier must be contiguous and connected across all surfaces of the enclosed air barrier envelope indicated. The maximum leakage requirements of individual air barrier components and materials are specified in the other specification sections covering these items.

This section also defines the maximum allowable leakage of the final air barrier system. The workmanship must be adequate to meet the maximum allowable leakage requirements of this specification.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referenced within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D4541	(2017) Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers
ASTM E96/E96M	(2016) Standard Test Methods for Water Vapor Transmission of Materials
ASTM E2178	(2013) Standard Test Method for Air Permeance of Building Materials
ASTM E2357	(2017) Standard Test Method for Determining Air Leakage of Air Barrier Assemblies

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 285	(2012) Standard Fire Test Method for Evaluation of Fire Propagation Characteristics of Exterior Non-Load-Bearing Wall Assemblies Containing Combustible Components

1.3 DEFINITIONS

The following terms as they apply to this section:

1.3.1 Air Barrier Accessory

Products designated to maintain air tightness between air barrier materials, air barrier assemblies and air barrier components, to fasten them to the structure of the building, or both (e.g., sealants, tapes, backer rods, transition membranes, fasteners, strapping, primers).

1.3.2 Air Barrier Assembly

The combination of air barrier materials and air barrier accessories that are designated and designed within the environmental separator to act as a continuous barrier to the movement of air through the environmental separator.

1.3.3 Air Barrier Component

Pre-manufactured elements such as windows, doors, dampers and service elements that are installed in the environmental separator.

1.3.4 Air Barrier Envelope

The combination of air barrier assemblies and air barrier components, connected by air barrier accessories that are designed to provide a continuous barrier to the movement of air through an environmental separator. There may be more than one air barrier envelope in a single building. Also known as Air Barrier System.

1.3.5 Air Barrier Material

A building material that is designed, tested and/or produced to provide the primary resistance to airflow through an air barrier assembly of a wall system.

1.3.6 Air Barrier System

Same as AIR BARRIER ENVELOPE.

1.3.7 Air Leakage Rate

The rate of airflow (CFM) driven through a unit surface area (sq.ft.) of an assembly or system by a unit static pressure difference (Pa) across the assembly. (example: 0.25 CFM/sq.ft. @ 75 Pa)

1.3.8 Air Leakage

The total airflow (CFM) driven through the air barrier system by a unit static pressure difference (Pa) across the air barrier envelope. (example: 6500 CFM @ 75 Pa)

1.3.9 Air Permeance

The tested rate of airflow (CFM) through a unit area (sq.ft.) of a material driven by unit static pressure difference (Pa) across the material (example: 0.004 CFM/sq.ft. @ 75 Pa) as established by ASTM E2178.

1.3.10 Environmental Separator

The parts of a building that separate the controlled interior environment from the uncontrolled exterior environment, or that separate spaces within

a building that have dissimilar environments. Also known as the Control Layer.

1.3.11 Vapor Permeance

Vapor permeance is separated into three classes based on the water vapor permeance of a material as tested via ASTM E96/E96M

Class I Vapor Barrier/Retarder	0.1 perm or less
Class II Vapor Barrier/Retarder	0.1 perm to 1.0 perm
Class III Vapor Barrier/Retarder	1.0 perm to 10 perm

1.4 PREPARATORY PHASE OR PRECONSTRUCTION CONFERENCE

Organize pre-construction conferences between the air barrier inspector and the sub-contractors involved in the construction of or penetration of the air barrier system to discuss where the work of each sub-contractor begins and ends, the sequence of installation, and each sub-contractor's responsibility to ensure airtight joints, junctures, penetrations and transitions between materials. Discuss the products, and assemblies of products specified in the different sections to be installed by the different sub-contractors.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Air Barrier System Shop Drawings; G, Manufacturer produced warranted air barrier system

SD-03 Product Data

Air Barrier System Product Data; G

SD-04 Samples

Mock-Up; G

Material Samples For Air Barrier System; G

SD-05 Design Data

Design Data And Calculations For The Air Barrier System; G, Manufacturer produced warranted air barrier system

SD-06 Test Reports

Design Review Report; G

Testing and Inspection; G

SD-07 Certificates

Air Barrier Inspector; G

1.6 AIR BARRIER ENVELOPE SURFACE AREA AND LEAKAGE REQUIREMENTS

The building air barrier systems must meet the following leakage requirements. The allowable leakage rate and the maximum leakage are at a differential test pressure of 75 Pa.

Air Barrier Envelope 1	
Surface Area	As indicated on the drawings.
Architectural Only Test:	
Allowable leakage rate	0.30 CFM/sq.ft

1.7 AIR BARRIER INSPECTOR

Employ a designated Air Barrier Inspector on this project. The Air Barrier Inspector performs a Design Review, oversees quality control testing specified in these specifications, performs quality control air barrier inspection as specified, interfaces with the designer and product manufacturer's representatives to assure all installation requirements are met, and verifies that the constructed work is in accordance with both the manufacturer's recommendations for products used, the content of this specification and other contract drawings or docouments. Qualification for the Air Barrier Inspector are as follows:

a. Training and certification as an Air Barrier Auditor from the Air Barrier Association of America (ABAA) or other third party air barrier association.

b. Or, provide documentation in resume format that demonstrates that the individual proposed has the experience, knowledge, skills and abilities to fulfill the above stated duties as the air barrier inspector.

c. It is acceptable that this individual be employed by the firm who will be performing the building pressurization test or another independent third party entity, provided they meet the above requirements but shall not be a member of the installing contractor or firm.

Provide copies of Air Barrier Inspector qualifications 30 days after Notice to Proceed.

1.8 DESIGN REVIEW

Review the Contract Plans and Specifications and advise the Contracting Officer of any deficiencies that would prevent the construction of an effective air barrier system. Provide a Design Review Report individually listing each deficiency and the corresponding proposed corrective action necessary for proper air barrier system. Provide copies of the Design Review Report not later than 14 days after approval of the Air Barrier Inspector Qualifications. Submit design data and calculations for the Air Barrier System for a manufacturer produced warranted air barrier system.

PART 2 PRODUCTS

2.1 AIR BARRIER

Provide air barrier system of compatible parts from one or several manufacturers coordinated by the contractor or provide a single warranted system provided by a primary manufacturer. The air barrier system as part of a tested exterior wall assembly must meet the conditions of acceptance as tested in accordance with NFPA 285. Materials used for roof assembly air barrier must conform to the appropriate UL and FM wind and fire requirements for the specified roof assemblies.

If a complete air barrier system from a single manufacturer is utilized, weather warranted on not warranted, the air barrier system must conform to ASTM E2357.

Materials in the following categories as used in the air barrier system or assembly of the exterior wall system are tested and are required to conform to ASTM E2178: Self-adhered sheet membranes, fluid applied membranes, spray polyurethane foam, mechanically fastened commercial building wrap, factory bonded membranes to sheathing, and adhesive backed commercial building wrap and accessory products.

Other materials used as an air barrier such as concrete, glass, wood, metal or gypsum board may or may not conform to ASTM E2178 but are acceptable provided that when integrated into the air barrier system or assemblies that they are not subject to material or environmental induced degradation in their final produced state and once incorporated in the permanent construction.

All materials used must be identifiable through manufacturer testing data and/or literature to be compatible with all the attached or adjoining materials or substrates used in the system.

Provide Air Barrier System Shop Drawings, Material Samples for Air Barrier System and Air Barrier System Product Data.

PART 3 EXECUTION

3.1 QUALITY CONTROL

3.1.1 Documentation and Reporting

Document the entire installation process on daily job site reports. These reports include information on the Installer, substrates, substrate

preparation, products used, ambient and substrate temperature, the location of the air barrier installation, the results of the quality control procedures, and testing results.

3.1.2 Construction Mock-Up

Build mock-up prior to building envelope construction.

a. Prepare a construction mock-up to demonstrate proper installation of the air barrier assemblies and components. Include air barrier system connections between floor and wall, wall and window, wall and roof. Also, include the sealing method between membrane joints at transitions from one material or component to another, at pipe or conduit penetrations of the wall and roof, and at duct penetration of the wall and roof. Work will not begin until the mock-up is satisfactory to the Contracting Officer.

b. Size the mock-up to approximately 8 feet long by 8 feet high. The mock-up must be representative of primary exterior wall assemblies and glazing components including backup wall and typical penetrations as acceptable to the Contracting Officer. A corner of the actual building may be used as the mock-up.

3.1.3 Quality Control Testing And Inspection

Conduct the following tests and inspections as applicable in the presence of the Contracting Officer during installation of the air barrier system, and submit quality control reports as indicated below.

a. Provide a Daily Report of Observations with a copy to the Contracting Officer.

b. Inspect to assure continuity of the air barrier system throughout the building enclosure and that all gaps are covered, the covering is structurally sound, and all penetrations are sealed allowing for no infiltration or exfiltration through the air barrier system.

c. Inspect to assure structural support of the air barrier system to withstand design air pressures.

d. Inspect to assure masonry surfaces receiving air barrier materials are smooth, clean, and free of cavities, protrusions and mortar droppings, with mortar joints struck flush or as required by the manufacturer of the air barrier material.

e. Inspect and test to assure site conditions for application temperature, and dryness of substrates are within guidelines.

f. Inspect to assure substrate surfaces are properly primed if applicable and in accordance with manufacturer's instructions. Priming must extend at least 2 inches beyond the air barrier material to make it obvious that the primer was applied to the substrate before the air barrier material.

g. Inspect to assure laps in materials are at least a 2-inch minimum, shingled in the correct direction or mastic applied in accordance with manufacturer's recommendations, and with no fishmouths.

h. Inspect to assure that a roller has been used to enhance adhesion. Identify any defects such as fishmouths, wrinkles, areas of lost adhesion, and improper curing. Note the intended remedy for the deficiencies.

i. Measure application thickness of liquid applied materials to assure that manufacturer's specifications for the specific substrate are met.

j. Inspect to assure that the correct materials are installed for compatibility.

k. Inspect to assure proper transitions for change in direction and structural support at gaps.

l. Inspect to assure proper connection between assemblies (membrane and sealants) for cleaning, preparation and priming of surfaces, structural support, integrity and continuity of seal.

m. Perform adhesion tests for fluid-applied and self-adhered air barrier membranes to assure that the manufacturer's specified adhesion strength properties are met. Determine the bond strength of coatings to substrate in accordance with ASTM D4541.

n. Provide cohesion tests for spray polyurethane foam (SPF). Perform the tests in accordance with the specification sections which specify these materials.

o. Provide written test reports of all tests performed.

3.2 REPAIR AND PROTECTION

Upon completion of inspection, testing, sample removal and similar services, repair damaged construction and restore substrates, coatings and finishes. Protect construction exposed by or for quality control service activities, and protect repaired construction.

-- End of Section --

SECTION 07 27 19.01

SELF-ADHERING AIR BARRIERS
05/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR BARRIER ASSOCIATION OF AMERICA (ABAA)

ABAA Accreditation	Accreditation
ABAA QAP	Quality Assurance Program

ASTM INTERNATIONAL (ASTM)

ASTM D146/D146M	(2004; E 2012; R 2012) Sampling and Testing Bitumen-Saturated Felts and Woven Fabrics for Roofing and Waterproofing
ASTM D412	(2016) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D570	(1998; E 2010; R 2010) Standard Test Method for Water Absorption of Plastics
ASTM D903	(1998; R 2017) Standard Test Method for Peel or Stripping Strength of Adhesive Bonds
ASTM D1876	(2008; R 2015; E 2015) Standard Test Method for Peel Resistance of Adhesives (T-Peel Test)
ASTM D4263	(1983; R 2018) Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D4541	(2017) Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers
ASTM E84	(2020) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E154/E154M	(2008a; R 2013; E 2013) Water Vapor Retarders Used in Contact with Earth Under Concrete Slabs, on Walls, or as Ground Cover
ASTM E283	(2019) Standard Test Method for

	Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E331	(2000; R 2016) Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference
ASTM E2178	(2013) Standard Test Method for Air Permeance of Building Materials
ASTM E2357	(2017) Standard Test Method for Determining Air Leakage of Air Barrier Assemblies

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 285	(2012) Standard Fire Test Method for Evaluation of Fire Propagation Characteristics of Exterior Non-Load-Bearing Wall Assemblies Containing Combustible Components

1.2 RELATED REQUIREMENTS

Submit all materials, components, and assemblies of the air barrier system together as one complete submittal package.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval.Submit non-G submittals to the Government for their record. the Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualifications of Manufacturer; G

Qualifications of Installer; G

SD-02 Shop Drawings

Self-adhering Air Barrier; G

SD-03 Product Data

Self-adhering Air Barrier; G

Primers, Adhesives, and Mastics; G

Safety Data Sheets; G

SD-04 Samples

Self-adhering Air Barrier Mockup; G

SD-06 Test Reports

Field Peel Adhesion Test; G

Flame Propagation of Wall Assemblies; G

Flame Spread and Smoke Developed Index Ratings; G

Site Inspections and Testing; G

SD-07 Certificates

Self-adhering Air Barrier; G

SD-08 Manufacturer's Instructions

Self-adhering Air Barrier; G

Primers, Adhesives, and Mastics; G

1.4 MISCELLANEOUS REQUIREMENTS

For self-adhering air barrier provide the following:

1.4.1 Shop Drawings

Submit self-adhering air barrier shop drawings showing locations and extent of air barrier assemblies and details of all typical conditions, intersections with other building enclosure assemblies and materials, and membrane counterflashings. Show details for bridging of gaps in construction, treatment of inside and outside corners, expansion joints, methods of attachment of materials covering the self-adhered barrier without compromising the barrier. Indicate how miscellaneous penetrations such as conduit, pipes, electric boxes, brick ties, and similar items will be sealed.

1.4.2 Product Data

Submit manufacturer's technical data indicating compliance with performance and environmental requirements, manufacturer's printed instructions for evaluating, preparing, and treating substrates, temperature and other limitations of installation conditions, safety requirements for installation, and Safety Data Sheets. Indicate flame and smoke spread ratings for all products.

1.4.3 Mockup

Provide a mockup of the self-adhering air barrier system specified. Apply product in an area designated by the Contracting Officer. Apply an area of not less than 54 square feet. Include all components specified as representative of the complete system. Notify the Contracting Officer a minimum of 48 hours prior to the test application. Select a test area representative of conditions to be covered including window or door openings, wall to ceiling transitions, flashings, and penetrations, as applicable.

1.4.4 Test Reports

Submit test reports indicating that field peel-adhesion tests on all materials have been performed and the changes made, if required, in order to achieve successful and lasting adhesion. Submit test reports for flame propagation of wall assemblies tested in accordance with NFPA 285. Submit test reports for flame spread and smoke developed index ratings of barrier system materials tested in accordance with ASTM E84.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver and store materials in sufficient quantity to allow for uninterrupted flow of work. Inspect materials delivered to the site for damage and store out of weather. Deliver materials to the jobsite in their original unopened packages, clearly marked with the manufacturer's name, brand designation, description of contents, and shelf life of containerized materials. Store and handle to protect from damage.

1.5.2 Storage

Inspect materials delivered to the site for damage; unload and store out of weather in manufacturer's original packaging. Store only in dry locations, not subject to open flames or sparks, and easily accessible for inspection and handling. Protect stored materials from direct sunlight. Keep materials sealed and separated from absorptive materials, such as wood and insulation.

1.6 FIELD PEEL ADHESION TEST

Perform a field peel-adhesion test on the construction mockup. Test the self-adhering air barrier for adhesion in accordance with ASTM D4541 using a Type II pull tester except use a disk that is 4 inches in diameter and cut through the membrane to separate the material attached to the dish from the surrounding material. Perform test after curing period in accordance with manufacturer's written recommendations. Record mode of failure and area which failed in accordance with ASTM D4541. Compare adhesion values with the manufacturer's established minimum values for the particular combination of material and substrate. Indicate on the inspection report whether the manufacturer's requirement has been met. Where the manufacturer has not declared a minimum adhesion value for their product and substrate combination, the inspector must record actual values.

1.7 QUALITY ASSURANCE

1.7.1 Qualifications of Manufacturer

Submit documentation verifying that the manufacturer of the self-adhering air barrier is currently accredited by Air Barrier Association of America (ABAA Accreditation https://www.airbarrier.org/).

1.7.2 Qualifications of Installer

Submit documentation verifying that installers of the self-adhering air barrier are currently certified in accordance with the ABAA QAP Quality Assurance Program (https://www.airbarrier.org/qap/).

1.8 PRECONSTRUCTION MEETING

Conduct a preconstruction meeting a minimum of two weeks prior to commencing work specified in this Section. Agenda must include, at a minimum, construction and testing of mockup, sequence of construction, coordination with substrate preparation, materials approved for use, compatibility of materials, coordination with installation of adjacent and covering materials, and details of construction. Attendance is required by representatives of related trades including covering materials, substrate materials, adjacent materials, and materials and components of the air barrier system.

1.9 ENVIRONMENTAL CONDITIONS

1.9.1 Temperature

Install air barrier within the range of ambient and substrate temperatures as recommended in writing by the air barrier manufacturer. Verify that the surface to receive self-adhering air barrier is dry for a minimum of 48 hours prior to the installation of the barrier. Do not apply air barrier to damp or wet substrates. Do not apply during inclement weather or when ice, frost, surface moisture, or visible dampness is present on surfaces to be covered, or when precipitation is imminent.

1.9.2 Exposure to Weather and Ultraviolet Light

Protect air barrier products from direct exposure to rain, snow, sunlight, mist, and other extreme weather conditions. Replace, at no additional cost to the government, barrier products that have been exposed to ultraviolet (sun)light longer than allowed by manufacturer's written requirements.

PART 2 PRODUCTS

2.1 SELF ADHERING AIR BARRIER

Provide minimum 0.040 inch thick self-adhering, vapor retarding, air barrier membrane consisting of a cross-laminated high density polyethylene (HDPE) film, fully coated with rubberized asphalt adhesive. Provide membrane in rolls of various widths interleaved with disposable silicone release paper. Self-adhering air barrier must exhibit no visible water leakage when tested in accordance with ASTM E331 and must perform as a liquid water drainage plane flashed to discharge to the exterior any incidental condensation or water penetration. Use regular or low temperature formulation depending on site conditions, within temperature ranges specified by manufacturer.

2.1.1 Physical Properties

a. Air Permeance (ASTM E2178): In accordance with Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM

b. Air Leakage (ASTM E2357, ASTM E283): In accordance with Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM.

c. Tensile Strength (ASTM D412 die C modified): Not less than 400 psi.

d. Tensile Elongation (ASTM D412 die C modified): Not less than 200 percent.

e. Puncture Resistance (ASTM E154/E154M): Not less than 40 lbs.

f. Pliability (ASTM D146/D146M): Unaffected at minus 25 degrees F, 0.063 inch mandrel.

g. Lap Adhesion (ASTM D1876 modified): Not less than 4.0 lbs per inch.

h. Peel Adhesion (ASTM D903): Not less than 5.0 lbs per inch.

j. Water Absorption (ASTM D570): Not to exceed 0.12 percent by weight.

k. Flame propagation of wall assemblies (NFPA 285): Pass

l. Surface Burning Characteristics (ASTM E84):

(1) Flame Spread Index Rating not higher than 75.

(2) Smoke Developed Index Rating not higher than 150.

2.2 PRIMERS, ADHESIVES, AND MASTICS

Provide primers, adhesives, mastics and other accessory materials as recommended in writing by the manufacturer of the self-adhering air barrier for adequate bonding to each type of substrate.

2.3 SHEET METAL FLASHING

Provide as specified in Section 07 60 00 FLASHING AND SHEET METAL.

2.4 JOINT SEALANTS

Provide as specified in Section 07 92 00 JOINT SEALANTS. Verify compatibility with adjacent products that are or will be in contact with one another.

PART 3 EXECUTION

3.1 EXAMINATION

Before installing air barrier, examine substrates, areas, and conditions under which air barrier assemblies will be applied, with Installer present, for compliance with requirements. Ensure the following conditions are met:

a. Surfaces are sound, dry, even, and free of oil, grease, dirt, excess mortar or other contaminants.

b. Concrete surfaces are cured and dry, smooth without large voids, spalled areas or sharp protrusions.

c. Verify substrate is visibly dry and free of moisture. Test for capillary moisture by plastic sheet method in accordance with ASTM D4263 and take suitable measures until substrate passes moisture test.

d. Verify sealants used in sheathing are compatible with membrane proposed for use. Perform field peel adhesion test on materials to which sealants are adhered.

3.2 PREPARATION

Clean, prepare, and treat substrate in accordance with manufacturer's written instructions. Ensure clean, dust-free, and dry substrate for air barrier application.

a. Prime masonry and concrete substrates with conditioning primer.

b. Prime gypsum sheathing an adequate number of coats to achieve required bond, with adequate drying time between coats.

c. Prime wood, metal, and painted substrates with primer.

d. Prepare, treat, and seal vertical and horizontal surfaces at terminations and penetrations through air barrier and at protrusions.

3.3 INSTALLATION

3.3.1 Installation of Self-adhering Air Barrier

Install materials in accordance with manufacturer's recommendations and the following:

a. Apply primer at rate recommended by manufacturer prior to membrane installation. Allow primer to dry completely before membrane application. Apply as many coats as necessary for proper adhesion.

b. When membrane is properly positioned, press into place and roll membrane with roller immediately after placement.

c. Apply membrane sheets to shed water naturally without interception by a sheet edge, unless that edge is sealed with permanently flexible termination mastic.

d. Position subsequent sheets of membrane applied above so that membrane overlaps the membrane sheet below by a minimum of 2-1/2 inches, unless greater overlap is recommended by manufacturer. Roll into place with roller.

e. Make all side laps a minimum of 2-1/2 inches and all end laps a minimum of 5 inches, unless greater overlap is recommended by manufacturer. Roll seams with roller.

f. Roll membrane to adhere to substrate. Cover corners and joints with two layers of reinforcement by first applying a 12 inch width of membrane centered along the axis. Flash drains and projections with a second ply of membrane for a distance of 6 inches from the drain or projection.

g. Seal around all penetrations through the air barrier resulting from pipes, vents, conduit, electrical fixtures, structural members, or other construction passing through it. Seal with termination mastic, extruded silicone sealant, membrane counterflashing or other sealing methods in accordance with manufacturer's written recommendations.

h. Continuously connect the air barrier between walls, roof, floor and below grade assemblies to form a continuous integrated air barrier system around the entire building enclosure. Extend the air barrier membrane into rough openings such as doors, windows, louvers, and other

exterior penetrations. Seal edges of barrier at junctures with rough openings.

i. At changes in substrate plane, provide transition material (e.g. bead of sealant, mastic, extruded silicone sealant, membrane counterflashing or other material recommended by manufacturer) under membrane to eliminate all sharp 90 degree inside corners and to make a smooth transition from one plane to another.

j. Provide mechanically fastened non-corrosive metal sheet to span gaps in substrate plane and to make a smooth transition from one plane to the other. Continuously support membrane with substrate.

k. At deflection and control joints, provide backup for the membrane to accommodate anticipated movement.

l. At expansion and seismic joints provide transition to the joint assemblies.

m. Apply a bead or trowel coat of mastic along membrane seams at reverse lapped seams, rough cuts, and as recommended by the manufacturer.

n. At end of each working day, seal top edge of membrane to substrate with termination mastic.

o. Do not allow materials to come in contact with chemically incompatible materials.

p. Counterflash upper edge of thru-wall flashing and air barrier. Counter flashing and thru-wall flashing are specified in Section 07 60 00 FLASHING AND SHEET METAL.

3.4 FIELD QUALITY CONTROL

3.4.1 Site Inspections and Testing

Provide site inspections and testing in accordance with ABAA protocol to verify conformance with the manufacturer's instructions, the ABAA QAP Quality Assurance Program (https://www.airbarrier.org/qap/), Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM, and this section.

a. Conduct inspections and testing at 5, 50, and 95 percent completion of this scope of work. Forward written site inspections reports to the Contracting Officer within five working days of the inspection and test being performed.

b. If inspections reveal any defects, promptly remove and replace defective work at no additional expense to the Government.

3.5 FIELD PEEL ADHESION TEST

Conduct in accordance with test protocol indicated in Part 1, paragraph FIELD PEEL ADHESION TEST.

3.6 PROTECTION AND CLEANING

3.6.1 Protection

3.6.1.1 Adjacent Surfaces

Protect exposed adjacent surfaces that could be damaged by primers and adhesives associated with air barrier membrane. Provide protection during application and the remainder of construction in accordance with manufacturer's written instructions.

3.6.1.2 The Air Barrier Assembly

Protect finished portions of the air barrier assembly from damage during ongoing application and throughout the remainder of the construction period in accordance with manufacturer's written instructions. Coordinate timing of installation of materials that will cover the air barrier membrane to ensure the exposure period does not exceed that recommended by the air barrier manufacturer's written installation instructions. Remove and replace, at no additional cost to the government, membrane products that exceed the manufacturer's allowed exposure limits.

3.6.2 Cleaning

Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction and as acceptable to the primary material manufacturer.

-- End of Section --

SECTION 07 27 36

SPRAY FOAM AIR BARRIERS
05/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR BARRIER ASSOCIATION OF AMERICA (ABAA)

ABAA Accreditation	Accreditation
ABAA QAP	Quality Assurance Program

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP Z9.2	(2018) Fundamentals Governing the Design and Operation of Local Exhaust Ventilation Systems
ASSP Z88.2	(2015) American National Standard Practices for Respiratory Protection

ASTM INTERNATIONAL (ASTM)

ASTM C518	(2017) Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus
ASTM C1029	(2015) Standard Specification for Spray-Applied Rigid Cellular Polyurethane Thermal Insulation
ASTM C1303/C1303M	(2015) Standard Test Method for Predicting Long-Term Thermal Resistance of Closed-Cell Foam Insulation
ASTM C1338	(2014) Standard Test Method for Determining Fungi Resistance of Insulation Materials and Facings
ASTM D1621	(2016) Standard Test Method for Compressive Properties of Rigid Cellular Plastics
ASTM D1622	(2014) Apparent Density of Rigid Cellular Plastics
ASTM D1623	(2017) Standard Test Method for Tensile and Tensile Adhesion Properties of Rigid Cellular Plastics

ASTM D2126	(2009) Response of Rigid Cellular Plastics to Thermal and Humid Aging
ASTM D2842	(2012) Water Absorption of Rigid Cellular Plastics
ASTM D4541	(2017) Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers
ASTM D6226	(2015) Standard Test Method for Open Cell Content of Rigid Cellular Plastics
ASTM E84	(2020) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E96/E96M	(2016) Standard Test Methods for Water Vapor Transmission of Materials
ASTM E283	(2019) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E736	(2000; R 2011) Cohesion/Adhesion of Sprayed Fire-Resistive Materials Applied to Structural Members
ASTM E2178	(2013) Standard Test Method for Air Permeance of Building Materials
ASTM E2357	(2017) Standard Test Method for Determining Air Leakage of Air Barrier Assemblies

ICC EVALUATION SERVICE, INC. (ICC-ES)

ICC-ES AC377	(2016) Acceptance Criteria for Spray-Applied Foam Plastic Insulation

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2018) International Building Code
ICC IECC	(2015) International Energy Conservation Code

INTERNATIONAL SAFETY EQUIPMENT ASSOCIATION (ISEA)

ANSI/ISEA Z87.1	(2020) Occupational and Educational Personal Eye and Face Protection Devices

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10	(2018; ERTA 1-2 2018) Standard for Portable Fire Extinguishers

NFPA 275	(2017) Standard Method of Fire Tests for the Evaluation of Thermal Barriers
NFPA 285	(2012) Standard Fire Test Method for Evaluation of Fire Propagation Characteristics of Exterior Non-Load-Bearing Wall Assemblies Containing Combustible Components

SPRAY POLYURETHANE FOAM ALLIANCE (SPFA)

SPFA TechDocs	(2015) SPFA Technical Documents Library, four categories: General, Insulation, Roofing, Specialty

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-600-01	(2016; with Change 3, 2019) Fire Protection Engineering for Facilities

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.132	Personal Protective Equipment
29 CFR 1910.133	Eye and Face Protection
29 CFR 1910.134	Respiratory Protection

UNDERWRITERS LABORATORIES OF CANADA (ULC)

ULC S705.2	(2005) Standard for Thermal Insulation - Spray Applied Rigid Polyurethane Foam, Medium Density - Application

1.2 RELATED REQUIREMENTS

Coordinate the requirements of Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM, Section 07 27 19.01 SELF-ADHERING AIR BARRIERS, and other building envelope sections to provide a complete air barrier system. Submit all materials, components, and assemblies of the air barrier system together as one complete submittal package.

1.3 DEFINITIONS

1.3.1 Long Term Thermal Resistance (LTTR)

The thermal resistance value of a closed cell foam insulation product measured using accelerated aging ASTM C1303/C1303M equivalent to the time-weighted average thermal resistance value over 15 years. Loss in thermal resistance is attributable to changes in cell gas composition caused by diffusion of air into and blowing agent out of the foam cells.

1.3.2 SPFA TechDocs

Reformatted documents, named SPFA TechDocs (http://www.sprayfoam.org/technical/spfa-technical-documents), places each document in one of four categories for easy reference and identification: Roofing, Insulation, Specialty and General.

Spray Polyurethane Foam: Thermal and air/vapor barrier system consisting of sprayed polyurethane foam (SPF).

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval.Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualification of Manufacturer; G

Qualification of Installer; G

Quality Control Plan; G

Safety Plan; G

Fire Prevention Plan; G

Respirator Plan; G

SD-02 Shop Drawings

Spray Foam Air Barrier System

Foam Air Barrier System; G

Fire-Rated Assemblies; G

SD-03 Product Data

Closed Cell SPF; G

Transition Membrane; G

Primers, Adhesives, and Mastics; G

Sealants; G

Safety Data Sheets; G

Thermal Barrier Materials; G

Ignition Barrier Coatings; G

Accessories; G

SD-04 Samples

Spray Foam Air Barrier Mockup; G

SD-06 Test Reports

Site Inspections Reports; G

SD-07 Certificates

Closed cell SPF; G

Transition Membrane; G

Indoor Air Quality for Spray Foam Air Barrier; G

SD-08 Manufacturer's Instructions

SPF Handling, Storage, and Spray Procedures; G

Substrate Preparation; G

Thermal Barrier; G

Ignition Barrier; G

Transition Membrane; G

Primers, Adhesives, and Mastics; G

SD-09 Manufacturer's Field Reports

Core Samples; G

Daily Work Record; G

1.5 MISCELLANEOUS REQUIREMENTS

For the spray foam air barrier system provide the following:

1.5.1 Shop Drawings

Submit spray foam air barrier shop drawings showing locations, detailing, and extent of spray foam air barrier assemblies. Provide details of all typical conditions, intersections with other envelope assemblies and materials, membrane counter-flashings. Provide details for fire-rated assemblies and indicate materials for thermal barriers. Show details for bridging of gaps in construction, treatment of inside and outside corners, expansion joints, methods of attachment of materials covering the SPF without compromising the barrier. Indicate how miscellaneous penetrations such as conduit, pipes, electric boxes, brick ties, and similar items will be sealed.

1.5.2 Product Data

Submit manufacturer's technical data indicating compliance with performance and environmental requirements, manufacturer's printed instructions for evaluating, preparing, and treating substrates, temperature and other limitations of installation conditions, safety requirements for installation, and Safety Data Sheets. Indicate flame and smoke spread ratings for all products. Submit thermal barrier literature including material description, physical properties, and fire-ratings.

1.5.3 Mockup

Provide a mockup of each foam system specified. Apply foam in an area designated by the Contracting Officer. Apply an area of not less than 50 square feet. Include all components specified for the finished assembly including primers, support components, expansion and contraction joints, thermal barriers, and other accessories as representative of the complete system. Isolate the area and protect workers as required by 29 CFR 1910.132, 29 CFR 1910.133 and 29 CFR 1910.134. Notify the Contracting Officer a minimum of 48 hours prior to the test application. Select a test area representative of conditions to be sprayed including window or door openings, wall to ceiling transitions, flashings, and penetrations, as applicable.

1.5.4 Test Reports

Submit test reports indicating that field peel adhesion tests on all materials have been performed and the changes made, if required, in order to achieve successful and lasting adhesion. Submit test reports for flame spread and smoke developed index ratings of SPF products tested in accordance with ASTM E84. Submit test reports for flame propagation of wall assemblies tested in accordance with NFPA 285. Submit test reports for fire-ratings of thermal barrier materials tested in accordance with ASTM E84.

1.6 DELIVERY, STORAGE, AND HANDLING

1.6.1 Delivery

Deliver and store materials in sufficient quantity to allow for uninterrupted flow of work. Inspect materials delivered to the site for damage; unload and store out of weather. Deliver materials to the jobsite in their original unopened packages, clearly marked with the manufacturer's name, brand designation, description of contents, and shelf life of containerized materials. Store and handle to protect from damage. Submit SPF Handling, Storage, and Spray Procedures in accordance with submittal procedures.

1.6.2 Storage

Store materials in clean, dry areas, away from excessive heat, sparks, and open flame. Maintain temperatures in the storage area below the materials' flash point(s) and within limits recommended by the manufacturer's printed instructions. Provide ventilation in accordance with ASSP Z9.2 to prevent build-up of flammable gases. Store MDI (A-side) drums in locations that limit the risk of contact with water, acids, caustics (such as lye), alcohols, and strong oxidizing and reducing agents.

1.6.3 Handling

Handle materials and containers safely and in accordance with manufacturer's recommendations. Store liquids in airtight containers and keep containers closed except when removing materials. Do not use equipment or containers containing remains of dissimilar materials. Do not expose foam component containers to direct sunlight. Do not use materials from containers with content temperatures in excess of 80 degrees F.

Containers exposed to long periods of cold may also exhibit separation and poor performance. Do not use materials exposed to temperature ranges

outside of manufacturer's instructions for exposure limits.

Mark and remove from job site materials which have been exposed to moisture, that exceed shelf life limits, or that have been exposed to temperature extremes.

1.6.3.1 Venting and Handling of Material Containers

Partially unscrew material container and drum caps to gradually vent the containers prior to opening. Do not inhale vapors. Decontaminate empty component containers by filling with water and allowing to stand for 48 hours with bung caps removed. Do not, under any circumstances seal, stop, or close containers which have been emptied of foam components.

1.7 FIELD PEEL ADHESION TEST

Perform a field peel adhesion test on the construction mockup. Test the SPF for adhesion in accordance with ASTM D4541 using a Type II pull tester except use a disk that is 4 inches in diameter and cut through the membrane to separate the material attached to the dish from the surrounding material. Perform test after curing period in accordance with manufacturer's written recommendations. Record mode of failure and area which failed in accordance with ASTM D4541. Compare adhesion values with the manufacturer's established minimum values for the particular combination of material and substrate. Indicate on the inspection report whether the manufacturer's requirement has been met. Where the manufacturer has not declared a minimum adhesion value for their product and substrate combination, the inspector must record actual values.

1.8 AIR BARRIER TESTING

Perform air barrier testing in accordance with Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM.

1.9 SAFETY PROVISIONS

1.9.1 Fire Prevention

Provide a written fire prevention plan for the SPF application. Address specific fire hazards such as spontaneous combustion from exothermic heat build-up of SPF components during curing. Provide a continuous fire watch during mixing and spraying of SPF and for a minimum of two hours after completion of work at the end of each day. Maintain fire watch for additional time as required to ensure no potential ignition conditions exist.

1.9.1.1 Fire Extinguishers

Furnish two fire extinguishers of minimum 15 pounds capacity each, in accordance with NFPA 10, in the immediate vicinity of the work. CAUTION: Do not discharge high pressure carbon dioxide extinguishers where explosive vapors exist since the discharge can cause a spark which will ignite the vapors.

1.9.2 Respirator Plan

Provide a written respirator plan in accordance with OSHA regulations that protects installers during application and addresses separation of the area to prevent other workers from entering the work area during spraying.

1.9.3 Isolation

Isolate the work area as recommended by spray foam manufacturer's written requirements. Prevent workers without respiratory, skin, and eye Personal Protective Equipment (PPE) or training from entering the work area or otherwise being exposed to off-gassing of the insulation in excess of permissible exposure limits.

1.9.4 Respirators and Eye Protection

Respiratory protective devices (respirators) must meet the requirements of ASSP Z88.2. Eye and face protective equipment must meet the requirements of ANSI/ISEA Z87.1. Additionally, sprayers and workers in the immediate vicinity of the spray must wear NIOSH-approved, full-face, supplied air respirators (SAR) operated in positive pressure or continuous flow mode. Workers not in the immediate vicinity of the sprayer must wear air purifying respirators (APR) with an organic gas / P100 particulate cartridge. Instruct personnel in the use of devices. Maintain such equipment and inspect regularly. All workers are required to have undergone pulmonary function testing and fit testing and must provide certification that they have done so. Change APR cartridges in accordance with manufacturer's written recommendations.

1.9.5 Clothing and Gloves

Sprayers and workers must wear protective clothing and gloves in accordance with OSHA requirements during materials application. Disposable coveralls must be worn and must cover all exposed skin. Sprayers and workers must wear fabric gloves coated with nitrile, neoprene, butyl or PVC.

1.9.6 Additional Requirements

Require personnel to review the Health, Safety and Environmental Aspects of Spray Polyurethane Foam and Coverings published by the Spray Polyurethane Foam Alliance (SPFA). Verify compliance prior to allowing personnel on site for installation work. http://www.sprayfoam.org.

1.10 QUALITY ASSURANCE

1.10.1 Qualification of Manufacturer

Submit documentation verifying that the manufacturer of the SPF is currently accredited by the Air Barrier Association of America (ABAA Accreditation https://www.airbarrier.org/) and by the Spray Polyurethane Foam Alliance (SPFA).

1.10.2 Qualification of Installer

Submit documentation verifying that installers of the spray foam air barrier are currently certified by ABAA/BPQI (Building Performance Quality Institute) orand by the Spray Polyurethane Foam Alliance (SPFA) Professional Certification Program (PCP). Installers must provide photo identification certification cards for inspection upon request.

1.10.3 General Quality Requirements

Provide all products and installation in accordance with SPFA TechDocs requirements (http://www.sprayfoam.org/technical/spfa-technical-documents)

and documented best practices.

1.11 PRECONSTRUCTION MEETING

Conduct a preconstruction meeting after approval of submittals and a minimum of two weeks prior to commencing work specified in this Section. Attendance is required by the Contracting Officer's designated personnel, Contractor, and representatives of related trades including covering materials, substrate materials, adjacent materials, and materials and components of the air/vapor/thermal barrier system. Agenda must include, at a minimum, the following items:

a. Drawings, specifications and submittals related to the SPF work;

b. Sequence of construction;

c. Coordination with substrate preparation work and responsibility of repairing defects in substrates. Determine method of ensuring SPF work does not begin until substrates have been inspected and accepted;

d. Compatibility of materials;

e. Construction and testing of construction mockup;

f. Application of self-adhering air barrier transitions strips and primer as required for sealing the spray foam air barrier system at openings including but not limited to windows, doors and louvers;

g. Spray foam air barrier system installation; including methods to be used to provide a continuous barrier at thru-wall flashing, penetrations, and covering of embed items;

h. Quality control plan including methods of applying the product so that a consistent thickness across the face of the substrate is achieved.

i. Procedures for SPF manufacturer's technical representative's onsite inspection and acceptance of substrates, contact info for the representative, frequency of visits, and distribution of copies of inspection reports. Determine where core samples will be taken and review procedures for daily documentation of SPF application.

j. Property protection measures, including isolation of the work, and prevention of overspray and clean-up should overspray occur.

k. Safety requirements, including review of PPE, fire prevention, safety plan, respirator plan, ventilation and separation of the work area, fall protection, and posting of warning signs. Provide a complete schedule and a detailed, written fire protection plan including temporary isolation of the product and the work area until permanent isolation or thermal barrier is in place.

1.12 ENVIRONMENTAL CONDITIONS

1.12.1 Temperature and Weather

Install SPF within the range of ambient and substrate surface temperatures in accordance with manufacturer's written instructions. Do not apply SPF to damp or wet substrates. Do not apply SPF during inclement weather or when ice, frost, surface moisture, or visible dampness is present on

surfaces to be covered, or when precipitation is imminent. Do not apply SPF to exterior building surfaces when wind speeds exceed 25 miles per hour. Use moisture measuring methods and equipment to verify that the moisture conditions of substrate surfaces are in accordance with SPF manufacturer requirements prior to application. Substrate temperatures must be within limits recommended by the manufacturer's printed instructions.

1.12.2 Conditions for Primers

Follow manufacturer's printed application and curing instructions. Do not apply primer when ambient temperature is below 40 degrees F or when ambient temperature is expected to fall below 35 degrees F for the duration of the drying or curing period.

1.12.3 Conditions for Ignition Barriers

Ensure that sprayed surfaces comply with manufacturer's written requirements for application coverage, thickness, and curing prior to application of ignition barrier coatings.

1.12.4 Temporary Ventilation

Provide temporary ventilation for work of this section in accordance with manufacturer's written instructions and with OSHA requirements for this type of application.

1.13 FOAM SPRAY EQUIPMENT

1.13.1 Applicator

Use an air purge foam spray gun.

1.13.2 Equipment Calibration

Fully calibrate the foam metering equipment to monitor each liquid component to within 2 percent of the SPF manufacturer's required metering ratio. Calibrate spray equipment each day at the start of operations, after each restart if spraying operations have been terminated for more than one hour, whenever there is a change in fan pattern or pressure, whenever slow curing areas are noticed, whenever a change is made in hose length or working height, and after changeover between materials. Calibration consists of demonstrating that the equipment is adjusted to deliver components in proper mix and proportion. Conduct calibration tests on cardboard or plywood on a wall adjacent to the area to be sprayed.

1.13.3 Metering Equipment Requirements

Use foam metering equipment capable of developing and maintaining the SPF manufacturer's required liquid component pressures and temperatures. Foam metering equipment must have gages for visual monitoring. Equipment must provide temperature control of foam components to within the temperature ranges recommended by the foam manufacturer's printed instructions.

1.13.4 Moisture Protection

Protect surfaces of supply containers and tanks used to feed foam metering equipment from moisture.

1.13.5 Compressed Air

Supply compressed air that is in contact with SPF during mixing or atomization through moisture traps that are continuously bled.

1.13.6 Dispense Excess Materials

Do not deposit materials used for cleaning of equipment or materials dispensed for calibration purposes and establishment of spray gun pattern onto the ground. Dispense such materials into scrap containers or onto plastic film, or cardboard, and dispose of in accordance with safety requirements and jobsite regulations.

PART 2 PRODUCTS

2.1 SPRAY FOAM AIR BARRIER

2.1.1 General

Provide a closed cell, sprayed in place, SPF that forms a continuous air /vapor/thermal barrier at the building enclosure. Provide in accordance with ASTM C1029, with the requirements of UFC 3-600-01, ICC IBC Chapter 26, ICC-ES AC377, and NFPA 285. In the event of a conflict, the most stringent requirement applies. Provide all system components necessary for a complete, code compliant installation, whether indicated or not, including material support components, expansion and contraction joints,thermal barrier materials, and accessories.

2.1.2 Physical Properties

Provide a closed cell product with the following characteristics:

a. Density (ASTM D1622): 2.0 lb per cf, nominal

b. Thermal Resistance (ASTM C518)

(1) Initial R-value per inch thickness: 7 sf·degrees F h per Btu

(2) Aged R-value per inch thickness (180 days at 76 degrees F): 6.6 sf·degrees F·h per Btu

c. Air Permeance (ASTM E2178): In accordance with Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM

d. Air Leakage (ASTM E2357, ASTM E283): In accordance with Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM.

e. Compressive Strength (ASTM D1621): Minimum 28.3 psi

f. Tensile Strength (ASTM D1623)

(1) Medium density: 15 psi

(2) Roofing: 40 psi

h. Vapor Retarder (ICC IBC, ICC IECC) Class I

i. Surface Burning Characteristics (ASTM E84) 3 inch thickness:

(1) Flame Spread (FS) Index Rating less than 75.

(2) Smoke Developed (SD) Index Rating less than 150. SPF with an SD rating greater than 150 but less than 450 may be used when fully encapsulated. Approval of SPF product is contingent upon approval of encapsulation products and assemblies.

j. Closed Cell Content (ASTM D6226): 90 percent

k. Dimensional Stability (Humid Aging) (ASTM D2126): 15 percent at 28 days at 158 degrees F with 97 percent relative humidity.

l. Water Absorption (ASTM D2842): Maximum 1.0 per volume

m. Fungi Resistance (ASTM C1338): Pass, with no growth

n. Recycled Content: Minimum 9 percent (pre- and post-consumer). Provide data identifying percentage of recycled content for closed cell spray foam air barrier.

c. Air Permeance (ASTM E2178): In accordance with Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM.

d. Air Leakage (ASTM E2357, ASTM E283): In accordance with Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM.

e. AC377 Compressive Strength (ASTM D1621): 3-5 psi

f. Tensile Strength (ASTM D1623): 3-5 psi

g. Water Vapor Permeance (ASTM E96/E96M, water method): Maximum 22 Perms at 2 inch thickness

h. Surface Burning Characteristics (ASTM E84) 3 inch thickness:

(1) Flame Spread (FS) Index Rating less than 75.

(2) Smoke Developed (SD) Index Rating less than 150. SPF with an SD rating greater than 150 but less than 450 may be used when fully encapsulated. Approval of SPF product is contingent upon approval of encapsulation products and assemblies.

i. Open Cell Content (ASTM D6226): Greater than 92 percent

j. Fungi Resistance (ASTM C1338): Pass, with no growth

k. Recycled Content: minimum 9 percent (pre- and post-consumer).

2.1.3 Expansion and Contraction

Provide an assembly that allows for relative movement due to temperature, moisture, and air pressure changes. Provide expansion and contraction measures as required by the manufacturer's written recommendations.

2.1.4 Fire-ratings, Flame Spread and Smoke Developed Index Ratings

Where fire-rated materials are indicated, provide products with the appropriate markings of a qualified testing agency. Submit fire-rating test reports. Submit flame spread (FS) and smoke developed (SD) index

data. Where FS and SD values of foam products do not meet requirements, provide corresponding ignition thermal] barrier products or assemblies and verify complete encapsulation of the spray foam air barrier through product data or on shop drawings. Submit for approval in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

2.1.5 Prohibited Materials

Products that contain hexabromocyclododecane (HBCD) flame retardants are prohibited. Products that contain hydrochlorofluorocarbons (HCFCs), chlorofluorocarbons (CFCs), or other high ozone depleting blowing agents, are prohibited. For a list of acceptable substitute foam blowing agents see https://www.epa.gov/snap/foam-blowing-agents. Provide validation of indoor air quality for spray foam air barrier that no prohibited materials are used.

2.1.6 ThermalIgnition Barrier

Provide a thermal barrierignition barrierPP in locations where SPF is exposed to the interior of the building. Provide thermalignition barriers in accordance with ICC IBC Chapter 26 "Plastics," with ICC-ES AC377, ASTM E736, and NFPA 275.

2.2 TRANSITION MEMBRANE

Provide as specified in Section 07 27 19.01 SELF-ADHERING AIR BARRIERS.

2.3 PRIMERS, ADHESIVES, AND MASTICS

Provide primers, adhesives, mastics and other accessory materials as recommended by spray foam manufacturer's printed literature.

2.4 FLASHING

As specified in Section 07 60 00 FLASHING AND SHEET METAL.

2.5 JOINT SEALANTS

As specified in Section 07 92 00 JOINT SEALANTS. Verify compatibility with other system products.

PART 3 EXECUTION

3.1 EXAMINATION

Before installing the spray foam air barrier and with the installer present, examine substrates, areas, and conditions under which SPF will be applied, for compliance with requirements. Ensure that surfaces are sound, dry, even, and free of oil, grease, dirt, excess mortar or other contaminants. Ensure that concrete surfaces are cured and dry, smooth without large voids, spalled areas or sharp protrusions. Correct defects that adversely affect the spray foam application or performance. Verify that work by other trades is in place and complete prior to application of spray foam.

3.2 PREPARATION

3.2.1 Substrate Preparation

Clean, prepare, and treat substrate according to manufacturer's written instructions. Provide clean, dust-free, and dry substrate for spray foam application.

a. Prepare surfaces by brushing, scrubbing, scraping, or grinding to remove loose mortar, dust, oil, grease, oxidation, mill scale and other contaminants which will affect adhesion of the SPF.

b. Wipe down metal surfaces to remove release agents or other non-compatible coatings, using clean sponges or rags soaked in a solvent compatible with the SPF.

3.2.2 Protection

Protect adjacent areas and surfaces from spray applied materials in accordance with the following:

a. Mask and cover adjacent areas to protect from over spray.

b. Ensure required foam stops and back up materials are in place to achieve a complete seal.

c. Seal off ventilation equipment. Install temporary ducting and fans to provide required exhaust of spray fumes. Provide make-up air as required.

d. Erect barriers, isolate area, and post warning signs to notify non-protected personnel of the requirement to avoid the spray area.

3.2.3 Fire and Explosion Hazards

Prohibit open flames, sparks, welding, and smoking in the application area. Provide and maintain fire extinguishers of appropriate type, size and distance, as required by NFPA, in the application area. Mix batches in small enough quantities to avoid spontaneous combustion from exothermic heat build-up of SPF components during curing.

3.2.4 Warning Signs

Post warning signs at ground level adjacent to the work area and a minimum of 150 feet from the application area stating the area is off limits to unauthorized persons and warning of potential hazards. Place clearly visible and legible warning sign at entrance to primary road leading to the project facility warning of presence of flammable materials, irritating fumes, and potential of overspray damage.

3.2.5 Prime Substrate

Provide as recommended by the manufacturer for each substrate to be primed. Use primers at full strength. Do not dilute primers unless required and as recommended in writing by the manufacturer. Do not use cleaning solvents for thinning primers or other materials. Ensure that diluted primer(s) meet VOC requirements.

3.3 INSTALLATION

3.3.1 Sequencing and Coordination

Sequence the work so as to prevent access to the work area by other trades during foam application and curing. Limit access of non-essential workers during application. Notify the Contracting Officer 24 hours in advance of spraying operations. Sequence spray foam work with other trades to permit continuous self-flashing of the spray foam air barrier. Ensure expansion and control joints are provided as detailed on the manufacturer's shop drawings to accommodate the expansion of each layer of the air/vapor /thermal envelope. Provide temporary fire protection of uncured foam, and isolate the work area, until foam application is isolated with a permanent thermal or ignition barrier.

3.3.2 Installation of Transition Membrane

Install transition membrane materials in accordance with the details on the drawings, Section 07 27 19.01 SELF-ADHERING AIR BARRIERS, and the following:

a. Install transition membrane at all required locations prior to installation of other -applied membrane air/vapor barriers.

b. Verify transition membrane is fully adhered to substrate and that its surface is clean, dry and wrinkle free prior to installation of the fluid-applied membrane air/vapor barrier.

c. Verify transition membrane completely covers all transition areas and will provide continuity of the finished SPF air/vapor barrier without gaps or cracks.

3.3.3 Installation of Spray Foam Air Barrier

Install materials in accordance with paragraph SAFETY PROVISIONS, in accordance with manufacturer's recommendations, ULC S705.2 Installation Standard] and in accordance with the following:

a. Use spray equipment that complies with foam manufacturer's recommendations for the specific type of application, and as specified herein. Record equipment settings on the Daily Work Record. Each proportioned unit can supply only one spray gun.

b. Apply only when surfaces and environmental conditions are within limits prescribed by the material manufacturer.

c. Continuously connect the spray foam air barrier between walls, roof, floor, and below grade assemblies to form a continuous integrated air barrier system around the entire building enclosure. Extend the spray foam air barrier into rough openings such as doors, windows, louvers, and other exterior penetrations. Use self-adhering air barrier transition strips if necessary to achieve full extension and continuity of the barrier at these locations. Seal edges of barrier at junctures with rough openings.

d. Install within manufacturer's tolerances, but not more than minus 1/4 inch or plus 1/2 inch.

e. Sequence work so as to completely seal all penetrations resulting from pipes, vents, wires, conduit, electrical fixtures, structural members,

or other construction. If penetrations through the spray foam air barrier are made after the initial SPF application, reapply in accordance with manufacturer's written instructions for such remedial work.

f. Do not install SPF within 3 inches of heat emitting devices such as light fixtures and chimneys.

g. Finished surface of SPF must be free of voids and embedded foreign objects.

h. Remove masking materials and over spray from adjacent areas immediately after foam surface has hardened. Ensure cleaning methods do not damage work performed by other sections.

i. Trim, as required, any excess thickness that would interfere with the application of cladding and covering system by other trades.

j. Clean and restore surfaces soiled or damaged by work of other trades. Before cleaning and restoring damaged work, consult with other trades for appropriate and approved methods for cleaning and restoration to prevent further damage.

k. Complete connections to other components and repair any gaps, holes or other damage using material approved by the manufacturer.

l. Provide expansion joints in the SPF application aligned with expansion joints in the building enclosure, where substrate materials change, and in accordance with manufacturer's recommendations.

m. Provide a continuous fire watch in accordance with paragraph SAFETY PROVISIONS.

3.4 FIELD QUALITY CONTROL

3.4.1 General Site Inspections and Testing

Provide site inspections and testing in accordance with ABAA protocol to verify conformance with the manufacturer's instructions, the ABAA QAP Quality Assurance Program (https://www.airbarrier.org/qap/), Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM, and this section.

a. Conduct inspections and testing at 5, 50, and 95 percent of completion of this scope of work. Forward written inspection reports to the Contracting Officer within 5 working days of the inspection and test being performed.

b. If inspections reveal any defects, promptly remove and replace defective work at no additional expense to the Government.

3.4.2 Manufacturer Site Inspections

Manufacturer's technical representative must visit the site during the installation process to ensure the SPF and accessories are being applied in compliance with requirements. At a minimum, manufacturer's technical representative must be present at work startup and perform field inspection of the first day's completed application and at substantial completion, prior to demobilization. After each inspection, submit an inspection report signed by the manufacturer's technical representative, to the

Contracting Officer within five working days. The inspection report must note overall quality of work, deficiencies, and recommended corrective actions in detail. Notify the Contracting Officer a minimum of two working days prior to site visits by manufacturer's technical representative.

3.4.3 Contractor's Site Inspections

Establish and maintain an inspection procedure to ensure compliance of the foam installation with contract requirements. Conduct inspections and testing at 5, 50, and 95 percent completion of application. Forward written inspection reports to the Contracting Officer within five working days of the inspection and test being performed. Work not in compliance must be promptly removed and replaced or corrected, in an approved manner, at no additional cost to the Government. Quality control must include, but is not limited to, the following:

a. Observation of environmental conditions; number and skill level of insulation workers.

b. Verification of certification, listing, or label.

c. Verification of proper storage and handling of materials before, during, and after installation.

d. Inspection of SPF, support structure, primer, expansion joints, ignition barrier, thermal barrier, vapor retarder, and accessories.

3.5 CORRECTION OF DEFICIENCIES

Upon completion of inspection, testing, or sample taking, repair damaged construction, restore substrates and finishes, and protect repaired construction. Deficiencies found during inspection must be corrected within 48 hours following notification.

3.6 CLEANUP OF SPILLS

Conduct cleanup of uncured product spillage in accordance with paragraph SAFETY PROVISIONS and the manufacturer's written safe handling instructions. In the event of a conflict, the most stringent requirement governs.

3.7 PROTECTION AND CLEANING

3.7.1 Protection of Installed Work

Protect SPF installation from damage during application and remainder of construction period in accordance with manufacturer's written instructions. Repair damaged areas to new condition.

3.7.2 Cleaning of Adjacent Surfaces

Clean overspray from adjacent construction using cleaning agents and procedures as recommended in writing by the manufacturer of each type of affected construction and as acceptable to same.

-- End of Section --

SECTION 07 42 13

METAL WALL PANELS
05/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 501.1	(2017) Standard Test Method for Water Penetration of Windows, Curtain Walls and Doors Using Dynamic Pressure
AAMA 800	(2016) Voluntary Specifications and Test Methods for Sealants

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 341	(2016) Seismic Provisions for Structural Steel Buildings

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI S100	(2012) North American Specification for the Design of Cold-Formed Steel Structural Members
AISI SG03-3	(2002; Suppl 2001-2004; R 2008) Cold-Formed Steel Design Manual Set

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7-16	(2017; Errata 2018; Supp 1 2018) Minimum Design Loads and Associated Criteria for Buildings and Other Structures

AMERICAN WELDING SOCIETY (AWS)

AWS A5.1/A5.1M	(2012) Specification for Carbon Steel Electrodes for Shielded Metal Arc Welding
AWS D1.1/D1.1M	(2020) Structural Welding Code - Steel
AWS D1.2/D1.2M	(2014; Errata 1 2014; Errata 2 2020) Structural Welding Code - Aluminum

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A123/A123M	(2017) Standard Specification for Zinc

	(Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A653/A653M	(2020) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A755/A755M	(2018) Standard Specification for Steel Sheet, Metallic Coated by the Hot-Dip Process and Prepainted by the Coil-Coating Process for Exterior Exposed Building Products
ASTM A780/A780M	(2020) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A792/A792M	(2010; R 2015) Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process
ASTM A1008/A1008M	(2020) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants
ASTM D522/D522M	(2017) Mandrel Bend Test of Attached Organic Coatings
ASTM D523	(2014; R 2018) Standard Test Method for Specular Gloss
ASTM D610	(2008; R 2019) Standard Practice for Evaluating Degree of Rusting on Painted Steel Surfaces
ASTM D714	(2002; R 2017) Standard Test Method for Evaluating Degree of Blistering of Paints
ASTM D822	(2013; R 2018) Filtered Open-Flame Carbon-Arc Exposures of Paint and Related Coatings
ASTM D968	(2017) Standard Test Methods for Abrasion Resistance of Organic Coatings by Falling Abrasive
ASTM D1056	(2014) Standard Specification for Flexible Cellular Materials - Sponge or Expanded Rubber

ASTM D1308	(2002; R 2013) Effect of Household Chemicals on Clear and Pigmented Organic Finishes
ASTM D1654	(2008; R 2016; E 2017) Standard Test Method for Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments
ASTM D1667	(2017) Standard Specification for Flexible Cellular Materials - Poly (Vinyl Chloride) Foam (Closed-Cell)
ASTM D2244	(2016) Standard Practice for Calculation of Color Tolerances and Color Differences from Instrumentally Measured Color Coordinates
ASTM D2247	(2015) Testing Water Resistance of Coatings in 100% Relative Humidity
ASTM D2794	(1993; R 2019) Standard Test Method for Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact)
ASTM D3359	(2017) Standard Test Methods for Rating Adhesion by Tape Test
ASTM D3363	(2005; E 2011; R 2011; E 2012) Film Hardness by Pencil Test
ASTM D4214	(2007; R 2015) Standard Test Method for Evaluating the Degree of Chalking of Exterior Paint Films
ASTM D4587	(2011; R 2019; E 2019) Standard Practice for Fluorescent UV-Condensation Exposures of Paint and Related Coatings
ASTM D5894	(2016) Standard Practice for Cyclic Salt Fog/UV Exposure of Painted Metal, (Alternating Exposures in a Fog/Dry Cabinet and a UV/Condensation Cabinet)
ASTM E72	(2015) Conducting Strength Tests of Panels for Building Construction
ASTM E84	(2020) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E283	(2019) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E331	(2000; R 2016) Standard Test Method for Water Penetration of Exterior Windows,

	Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference
ASTM E1592	(2017) Standard Test Method for Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference
ASTM G152	(2013) Operating Open Flame Carbon Arc Light Apparatus for Exposure of Nonmetallic Materials
ASTM G153	(2013) Operating Enclosed Carbon Arc Light Apparatus for Exposure of Nonmetallic Materials

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)

MBMA MBSM	(2018) Metal Building Systems Manual

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM AMP 500	(2006) Metal Finishes Manual

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1793	(2012) Architectural Sheet Metal Manual, 7th Edition

UNDERWRITERS LABORATORIES (UL)

UL Bld Mat Dir	(updated continuously online) Building Materials Directory

1.2 DEFINITIONS

Metal Wall Panel: Metal wall panels, attachment system components and accessories necessary for a complete weather-tight wall system.

1.3 DESCRIPTION OF WALL PANEL SYSTEM

Factory color finished, galvalume metal wall panel system with exposed fastener attachment. Panel profile must be corrugated as shown on drawings].

1.3.1 Metal Wall Panel General Performance

Comply with performance requirements, conforming to AISI S100, without failure due to defective manufacture, fabrication, installation, or other defects in construction. Wall panels and accessory components must conform to the following standards:

ASTM A1008/A1008M
ASTM A123/A123M
ASTM A36/A36M

ASTM A755/A755M for metallic coated steel sheet for exterior coil pre-painted applications.

ASTM A780/A780M for repair of damage or uncoated areas of hot-dipped galvanized coating.

ASTM D522/D522M for applied coatings
UL Bld Mat Dir

1.3.2 Structural Performance

Maximum calculated fiber stress must not exceed the allowable value in the AISI or AA manuals; a one third overstress for wind is allowed. Midspan deflection under maximum design loads is limited to L/180. Contract drawings show the design wind loads and the extent and general assembly details of the metal siding. Contractor must provide design for members and connections not shown on the drawings. Siding panels and accessories must be the products of the same manufacturer.

Provide metal wall panel assemblies complying with the load and stress requirements in accordance with ASTM E1592. Wind Load force due to wind action governs the design for panels.

Wall systems and attachments are to resist the wind loads as determined by ASTM E72 and ASCE 7-16 in the geographic area where the construction will take place, in pounds per square foot. Submit five copies of wind load tests and seismic tests to the Contracting Officer.

Provide metal wall panel assembly for seismic conditions complying with the applicable requirements of AISC 341.

1.3.3 Air Infiltration

Air leakage must conform to the limits through the wall assembly area when tested according to ASTM E283.

1.3.4 Water Penetration Under Static Pressure

No water penetration when tested according to ASTM E331.

1.3.5 Water Penetration Under Dynamic Pressure

No evidence of water leakage when tested according to AAMA 501.1.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval.Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submit Documentation for the following items:

Qualification of Manufacturer; G

Qualification of Installation Contractor; G

Sample Warranty; G

SD-02 Shop Drawings

Installation Drawings ; G

SD-03 Product Data

Submit Manufacturer's catalog data for the following items:

Wall Panels ; G
Factory Color Finish
Closure Materials
Pressure Sensitive Tape
Sealants and Caulking
Galvanizing Repair Paint
Enamel Repair Paint

Accessories

SD-04 Samples

Submit as required each of the following samples:

Wall Panels, 12 inches long by actual panel width; G
Fasteners; G
Metal Closure Strips, 10 inches long of each type; G
Color chart and chips ; G

Submit manufacturer's color charts and chips, approximately 4 by 4 inches, showing full range of colors, textures and patterns available for wall panels with factory applied finishes.

SD-05 Design Data

Wind load design analysis ; G

As applicable, submit the following wind load design analysis data, to include, but not limited to:
Wind speed exposure category,co-efficient,importance factor
type of facility
negative pressures for each zone
methods and requirements of attachment

SD-06 Test Reports

Submit test reports for the following in accordance with the referenced articles in this section.

Leakage Tests; G
Wind Load Tests; G
Coating Tests; G
Chalking Tests; G
Seismic Tests; G]

SD-07 Certificates

Submit certificates for the following items showing conformance with referenced standards contained in this section:

Fasteners; G
Galvanizing Repair Paint; G
Enamel Repair Paint; G

SD-08 Manufacturer's Instructions

Include detailed application instructions and standard manufacturer drawings altered as required by these specifications.

Installation of Wall panels; G

SD-09 Manufacturer's Field Reports

Submit 4 bound copies of the Manufacturer's Field Reports; G

SD-11 Closeout Submittals

Warranty; G
Maintenance Instructions; G

20 year "No Dollar Limit" warranty for labor and material

1.5 QUALITY ASSURANCE

1.5.1 Pre-Installation Conference

Upon notification of submittal receipt and approval by the Contracting Officer; and prior to the commencement of the work, the Contractor must attend a pre-installation conference to review the following:

a. Drawings and Specifications.

b. Qualification of Installer, Qualification of Welders.

c. Sustainable acquisition

d. Approved Warranty

e. Sample wall panels, 12 inches long by actual panel width

f. Sample metal closure strips, 10 inches long of each type

g. Color charts and chips

h. Coatings and base metal tests, chalking tests

i. Construction schedule, availability of materials, Installer's personnel, equipment and facilities required to progress with the work without delay.

j. Methods and procedures related to installation of wall panels, including manufacturer's written instructions. Explicitly identify in writing, differences between manufacturer's instructions and the specified requirements.

k. Support conditions for compliance with requirements, including alignment between and attachment to structural members.

l. Flashing, special siding details, wall penetrations, openings, and condition of other construction that will affect metal wall panels.

m. Governing regulations and requirements for insurance, certificates, and tests and inspections if applicable.

n. Temporary protection requirements for metal wall panel assembly during and after installation.

o. Wall panel observation and repair procedures after metal wall panel installation. Provide detailed written instructions including copies of Safety Data Sheets for maintenance and repair materials, and manufacturer's maintenance instructions.

1.5.1.1 Installation Drawings

Installation shop drawings for wall panels, flashing, accessories, and anchorage systems must indicate completely dimensioned structural frame and erection layouts, openings in the wall, special framing details, and construction details at corners, building intersections and flashing, location and type of mastic and metal filler strips.

1.5.1.2 Wind Load Design Analysis

Wind design analysis must include wall plan delineating dimensions and attachment patterns for each zone. Wind design analysis must be prepared and sealed by Licensed Project Engineer in the geographic area where the construction will take place.

1.5.2 Manufacturer's Technical Representative

The representative must have authorization from manufacturer to approve field changes and be thoroughly familiar with the products and installations in the geographical area where construction will take place.

1.5.3 Qualification of Manufacturer

Certify that metal wall panel system manufacturer has a minimum of five (5) years experience in manufacturing metal wall system and accessory products.

Manufacturer must also provide engineering services by an authorized engineer; currently licensed in the geographical area where construction will take place, having a minimum of four (4) years experience as an engineer knowledgeable in wind load design analysis, protocols and procedures per MBMA MBSM, "Metal Building Systems Manual"; ASCE 7-16, and ASTM E1592 and seismic design conforming to AISC 341.

Provide certified engineering calculations, using the products submitted, for Wind load requirements in accordance with ASCE 7-16.

1.5.3.1 Manufacturer's Certificates

Also provide the following certifications from the manufacturer:

Coil Stock
Fasteners

Galvanizing Repair Paint
Enamel Repair Paint

Submit certification from coil stock manufacturer or supplier that the machinery used will form the provided coil stock without warping, waviness, or rippling that is not a part of the panel profile, and without damage, abrasion or marring of the finish coating.

Provide evidence that products used within this specification are manufactured in the United States.

1.5.4 Certified Qualification of Installation Contractor

The installation contractor must be approved and certified by the metal wall panel manufacturer prior to beginning the installation of the metal wall panel system. Subcontracting by Certified Contractor for the metal wall panel work is not permitted.

1.5.4.1 Qualifications for Welding Work

Qualification of welders and welding must conform to AWS A5.1/A5.1M, AWS D1.1/D1.1Mfor steel or AWS D1.2/D1.2M for aluminum.

1.5.5 Single Source

Obtain each type of metal wall panels, clips, closure materials and other accessories from the standard products of the single source from a single manufacturer to operate as a complete system for the intended use.

1.5.6 Manufacturer's Maintenance Instructions

Provide manufacturer's detailed written instructions including copies of Safety Data Sheets for maintenance and repair materials.

1.6 DELIVERY, HANDLING, AND STORAGE

Deliver and protect package components, sheets, metal wall panels, and other manufactured items to prevent damage or deformation during transportation and handling.

Unload, store, and erect metal wall panels in a manner to prevent bending, warping, twisting, and surface damage.

Stack and store metal wall panels horizontally on platforms or pallets, covered with suitable weather-tight and ventilated covering to ensure dryness, with positive slope for drainage of water. Do not store metal wall panels in contact with other materials that might cause staining, denting, or other surface damage.

Retain strippable protective covering on metal wall panel until actual installation.

1.7 PROJECT CONDITIONS

1.7.1 Field Measurements

Verify locations of wall framing and opening dimensions by field measurements before metal wall panel fabrication and indicate measurements on Shop Drawings.

1.7.2 Weather Limitations

Proceed with installation preparation only when existing and forecasted weather conditions permit Work to proceed without water entering into wall system or building.

1.8 WARRANTY

Warranty must conform to the Sample Warranty as reviewed and approved by the Contracting Officer.

1.8.1 20 Year "No Dollar Limit" Warranty for Labor and Material

Furnish manufacturer's no-dollar-limit warranty for the metal wall panel system. The warranty period is to be no less than twenty (20) years from the date of Government acceptance of the work. The warranty is to be issued directly to the Government. The warranty is to provide that if within the warranty period the metal wall panel system shows evidence of corrosion, perforation, rupture or excess weathering due to deterioration of the wall panel system resulting from defective materials and correction of the defective workmanship is to be the responsibility of the metal wall panel system manufacturer. Repairs that become necessary because of defective materials and workmanship while metal wall panel system is under warranty are to be performed within 24 hours after notification, unless additional time is approved by the Contracting Officer. Failure to perform repairs within 24 hours of notification will constitute grounds for having emergency repairs performed by others and not void the warranty.

PART 2 PRODUCTS

2.1 FABRICATION

Unless approved otherwise, fabricate and finish metal wall panels and accessories at the factory to greatest extent possible, by manufacturer's standard procedures and processes and as necessary to fulfill indicated and specified performance requirements. Comply with indicated profiles and with dimensional and structural requirements.

Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel. Fabricate metal wall panel side laps with factory-installed captive gaskets or separator strips that provide a tight seal and prevent metal-to-metal contact, in a manner that will seal weather-tight and minimize noise from movements within panel assembly.

2.1.1 Sheet Metal Accessories

Fabricate flashing and trim to comply with recommendations in SMACNA 1793 that apply to the design, dimensions, metal, and other characteristics of item indicated:

a. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.

b. End Seams: fabricate nonmoving end seams with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints for additional strength.

c. Sealed Joints: form non-expansion but movable joints in metal to accommodate elastomeric sealant to comply with SMACNA 1793.

d. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of accessories exposed to view.

e. Fabricate cleats and attachment devices of size and metal thickness recommended by SMACNA 1793 or by metal wall panel manufacturer for application, but not less than thickness of metal being secured.

2.2 PANEL MATERIALS

2.2.1 Steel Sheet

Roll-form steel wall panels to the specified profile, with: fy= 80 ksi and 26 gauge and depth as indicated. Material must be plumb and true, and within the tolerances listed:

a. Galvanized: Steel Sheet conforming to ASTM A653/A653M and AISI SG03-3.

b. Galvaume: Aluminum-Zinc Alloy-coated Steel Sheet conforming to ASTM A792/A792M and AISI SG03-3. Hot-dip coating of corrosion resistant,aluminum zinc alloy. Coating consists of an alloy of nominally 55% aluminum, 1.6% silicon, and the balance zinc by weight, as listed in ASTM designation A 792.

c. Individual panels must be continuous length to cover the entire length of any unbroken wall area with no joints or seams and formed without warping, waviness, or ripples that are not part of the panel profile and free of damage to the finish coating system.

d. Provide panels with thermal expansion and contraction consistent with the type of system specified.

1. Profile and coverage to be a minimum height and width from manufacturer's standard for the indicated wall area.

2. Profile to be a 1/2 inch high rib at 2 5/8" inches o.c. , 24 inch overall width with exposed fasteners.

3. Smooth.

2.2.2 Factory Color Finish

Comply with NAAMM AMP 500 for recommendations for applying and designating finishes. Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved samples and are assembled or installed to minimize contrast.

All panels are to receive a factory-applied Kynar 500/Hylar 5000 finish consisting of a baked-on top-coat with a manufacturer's recommended prime coat conforming to the following:

2.2.2.1 Metal Preparation

Carefully prepare all metal surface for painting on a continuous process coil coating line by alkali cleaning, hot water rinsing, application of

chemical conversion coating, cold water rinsing, sealing with acid rinse, and thorough drying.

2.2.2.2 Prime Coating

Apply a base coat of epoxy paint, specifically formulated to interact with the top-coat, to the prepared surfaces by roll coating to a dry film thickness of 0.20 plus 0.05 mils. Prime coat must be oven cured prior to application of finish coat.

2.2.2.3 Exterior Finish Coating

Roll coat the finish coating over the primer by roll coating to dry film thickness of 0.80 plus 5 mils (3.80 plus 0.50 mils for Vinyl Plastisol) for a total dry film thickness of 1.00 plus 0.10 mils (4.00 plus 0.10 mils for Vinyl Plastisol). Oven-cure finish coat.

2.2.2.4 Interior Finish Coating

Apply a wash-coat on the reverse side over the primer by roll coating to a dry film thickness of 0.30 plus 0.05 mils for a total dry film thickness of 0.50 plus 0.10 mils. Oven-cured the wash coat.

2.2.2.5 Color

Provide exterior finish color as selected by the Contracting Officer from the manufacturer's standard color chart.

2.2.2.6 Physical Properties

Coating must conform to the industry and manufacturer's standard performance criteria as listed by the following certified test reports:

General:	ASTM D5894 and ASTM D4587
Abrasion:	ASTM D968
Adhesion:	ASTM D3359
Chalking:	ASTM D4214
Chemical Pollution:	ASTM D1308
Color Change and Conformity:	ASTM D2244
Creepage:	ASTM D1654
Cyclic Corrosion Test:	ASTM D5894
Flame Spread:	ASTM E84
Flexibility:	ASTM D522/D522M
Formability:	ASTM D522/D522M

Gloss at 60 and 85 degrees:	ASTM D523
Humidity:	ASTM D2247 and ASTM D714
Oxidation:	ASTM D610
Pencil Hardness:	ASTM D3363
Reverse Impact:	ASTM D2794
Salt Spray:	ASTM B117
Weatherometer:	ASTM G152, ASTM G153 and ASTM D822

2.3 MISCELLANEOUS METAL FRAMING

Cold-formed metallic-coated steel sheet conforming to ASTM A653/A653M or unless otherwise indicated.

2.3.1 Fasteners for Miscellaneous Metal Framing

Type, material, corrosion resistance, size and sufficient length to penetrate the supporting member a minimum of 1 inch with other properties required to fasten miscellaneous metal framing members to supporting members and substrates in accordance with the wall panel manufacturer's and ASCE 7-16 requirements.

2.4 FASTENERS

2.4.1 General

2.4.1.1 Exposed Fasteners

Provide corrosion resistant fasteners for wall panels, made of 300 - series corrosion resisting stainless steel305 - series corrosion resisting stainless steel, or nylon capped steel compatible with the sheet panel or flashing and of a type and size recommended by the manufacturer to meet the performance requirements and design loads.

Fasteners for accessories must be the manufacturer's standard. Provide an integral metal washer matching the color of attached material with compressible sealing EPDM gasket approximately 3/32 inch thick.

2.4.1.2 Screws

Screws to be stainless steel being the type and size recommended by the manufacturer to meet the performance requirements.

2.4.1.3 Rivets

Rivets to be closed-end type, corrosion resistant coated steel, aluminum or stainless steel where watertight connections are required.

2.4.1.4 Attachment Clips

Fabricate clips from steel hot-dipped galvanized in accordance with ASTM A653/A653M, Z275 G 90 or Series 300 stainless steel. Size, shape, thickness and capacity as required meeting the insulation thickness and design load criteria specified.

2.5 ACCESSORIES

2.5.1 General

All accessories must be compatible with the metal wall panels. Sheet metal flashing, trim, metal closure strips, caps and similar metal accessories must not be less than the minimum thickness specified for the wall panels. Exposed metal accessories/finishes to match the panels furnished, except as otherwise indicated. Molded foam rib, ridge and other closure strips must be non-absorbent closed-cell or solid-cell synthetic rubber or pre-molded neoprene to match configuration of the panels.

2.5.2 Rubber Closure Strips

Provide closed-cell, expanded cellular rubber conforming to ASTM D1056 and ASTM D1667; extruded or molded to the configuration of the specified wall panel and in lengths supplied by the wall panel manufacturer.

2.5.3 Metal Closure Strips

Provide factory fabricated closure strips to be the same material, gauge thickness, color, finish and profile of the specified wall panel.

2.5.4 Joint Sealants

2.5.4.1 Sealants and Caulking

Provide approved gun type sealants for use in hand- or air-pressure caulking guns at temperatures above 40 degrees F (or frost-free application at temperatures above 10 degrees F with minimum solid content of 85 percent of the total volume. Sealants must dry with a tough, durable surface skin which permit remaining soft and pliable underneath, providing a weather-tight joint. No migratory staining is permitted on painted or unpainted metal, stone, glass, vinyl, or wood.

Prime all joints receiving sealants with a compatible one-component or two-component primer as recommended by the wall panel manufacturer.

2.5.4.2 Shop-Applied

Sealant for shop-applied caulking must be non-curing butyl compliant with AAMA 800 to ensure the sealant's plasticity at the time of field erection.

2.5.4.3 Field-Applied

Sealant for field-applied caulking must be an approved gun grade, non-sag one component polysulfide or two-component polyurethane with an initial maximum Shore A durometer hardness of 25, and conforming to ASTM C920, Type II. Color to match panel colors.

2.5.4.4 Pressure Sensitive Tape

Provide pressure sensitive tape sealant, 100 percent solid with a release paper backing; permanently elastic, non-sagging, non-toxic and non-staining as approved by the wall panel manufacturer.

2.6 SHEET METAL FLASHING AND TRIM

2.6.1 Fabrication

Shop fabricate sheet metal flashing and trim where practicable to comply with recommendations in SMACNA 1793 that apply to design, dimensions, metal, and other characteristics of item indicated. Obtain field measurements for accurate fit before shop fabrication.

Fabricate sheet metal flashing and trim without excessive oil canning, buckling, and tool marks and true to line and levels indicated, with exposed edges folded back to form hems.

2.7 REPAIR OF FINISH PROTECTION

Repair paint for color finish enameled wall panel must be compatible paint of the same formula and color as the specified finish furnished by the wall panel manufacturer.

PART 3 EXECUTION

3.1 EXAMINATION

Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal wall panel supports, and other conditions affecting performance of the Work.

Examine primary and secondary wall framing to verify that rafters, purlins, angles, channels, and other structural panel support members and anchorages have been installed within alignment tolerances required by metal wall panel manufacturer, UL, ASTM, ASCE 7-16 and as required for the geographical area where construction will take place.

Examine solid wall sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by metal wall panel manufacturer.

Examine roughing-in for components and systems penetrating metal wall panels to verify actual locations of penetrations relative to seam locations of metal wall panels before metal wall panel installation.

Submit to the Contracting Officer a written report, endorsed by Installer, listing conditions detrimental to performance of the Work. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

Clean substrates of substances harmful to insulation, including removing projections capable of interfering with insulation attachment. Miscellaneous framing installation, including sub-purlins, girts, angles, furring, and other miscellaneous wall panel support members and anchorage must be according to metal wall panel manufacturer's written instructions.

3.3 WALL PANEL INSTALLATION

Provide full length metal wall panels, from sill to eave as indicated, unless otherwise indicated or restricted by shipping limitations. Anchor metal wall panels and other components of the Work securely in place, with provisions for thermal and structural movement in accordance with MBMA MBSM.

Erect wall panel system in accordance with the approved erection drawings, the printed instructions and safety precautions of the manufacturer.

Sheets are not to be subjected to overloading, abuse, or undue impact. Bent, chipped, or defective sheets shall not be applied.

Sheets must be erected true and plumb and in exact alignment with the horizontal and vertical edges of the building, securely anchored, and with the indicated eave, and sill.

Work is to allow for thermal movement of the wall panel, movement of the building structure, and to provide permanent freedom from noise due to wind pressure.

Field cutting metal wall panels by torch is not permitted.

3.3.1 Steel Wall Panels

Use stainless-steel fasteners for exterior and interior surfaces.

3.3.2 Anchor Clips

Anchor metal wall panels and other components of the Work securely in place, using manufacturer's approved fasteners according to manufacturers' written instructions.

3.3.3 Metal Protection

Where dissimilar metals will contact each other or corrosive substrates, protect against galvanic action by painting contact surfaces with bituminous coating, by applying rubberized-asphalt underlayment to each contact surface, or by other permanent separation as recommended by metal wall panel manufacturer.

3.3.4 Joint Sealers

Install gaskets, joint fillers, and sealants where indicated and where required for weatherproof performance of metal wall panel assemblies. Provide types of gaskets, fillers, and sealants indicated or, if not indicated, types recommended by metal wall panel manufacturer.

3.4 FASTENER INSTALLATION

Anchor metal wall panels and other components of the Work securely in place, using manufacturer's approved fasteners according to manufacturers' written instructions.

3.5 FLASHING, TRIM AND CLOSURE INSTALLATION

3.5.1 General Requirements

Comply with performance requirements, manufacturer's written installation

instructions, and SMACNA 1793. Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams to form permanently watertight and weather resistant.

Install sheet metal work is to form weather-tight construction without waves, warps, buckles, fastening stresses or distortion, and allow for expansion and contraction. Cutting, fitting, drilling, and other operations in connection with sheet metal required to accommodate the work of other trades is to be performed by sheet metal mechanics.

3.5.2 Metal Flashing

Install exposed metal flashing at building corners, sills and eaves, junctions between metal siding and walling. Exposed metal flashing must be the same material, color, and finish as the specified metal wall panel.

Fasten flashing at a minimum of 8 inches on center, except where flashing is held in place by the same screws that secure covering sheets.

Flashing is to be furnished in at least 8 foot lengths. Exposed flashing is to have 1 inch locked and blind-soldered end joints, and expansion joints at intervals of not more than 16 feet.

Exposed flashing and flashing subject to rain penetration to be bedded in the specified joint sealant.

Isolate flashing which is in contact with dissimilar metals by means of the specified asphalt mastic material to prevent electrolytic deterioration.

Form drips to the profile indicated, with the edge folded back 1/2 inch to form a reinforced drip edge.

3.5.3 Closures

Install metal closure strips at open ends of corrugated or ribbed pattern walls, and at intersection of wall and wall unless open ends are concealed with formed eave flashing; and in other required areas.

Install mastic closure strips at intersection of the wall with metal walling; top and bottom of metal siding; heads of wall openings; and in other required locations.

3.6 WORKMANSHIP

Make lines, arises, and angles sharp and true. Free exposed surfaces from visible wave, warp, buckle, and tool marks. Fold back exposed edges neatly to form a 1/2 inch hem on the concealed side. Make sheet metal exposed to the weather watertight with provisions for expansion and contraction.

Make surfaces to receive sheet metal plumb and true, clean, even, smooth, dry, and free of defects and projections which might affect the application. For installation of items not shown in detail or not covered by specifications conform to the applicable requirements of SMACNA 1793. Provide sheet metal flashing in the angles formed where roof decks abut walls, curbs, ventilators, pipes, or other vertical surfaces and wherever indicated and necessary to make the work watertight.

3.7 ACCEPTANCE PROVISIONS

3.7.1 Erection Tolerances

Erect metal wall panels straight and true with plumb vertical lines correctly lapped and secured in accordance with the manufacturer's written instructions.

3.7.2 Leakage Tests

Finished application of metal wall panels are to be subject to inspection and test for leakage by request of the Contracting Officer, Architect/Engineer. Conduct inspection and tests at no cost to the Government.

Inspection and testing is to be made promptly after erection to permit correction of defects and the removal and replacement of defective materials.

3.7.3 Repairs to Finish

Scratches, abrasions, and minor surface defects of finish may be repaired with the specified repair materials. Finished repaired surfaces must be uniform and free from variations of color and surface texture.

Repaired metal surfaces that are not acceptable to the project requirements and/or Contracting Officer are to be immediately removed and replaced with new material.

3.7.4 Paint-Finish Metal Siding

Paint-finish metal siding will be tested for color stability by the Contracting Officer during the manufacturer's specified guarantee period.

Panels that indicate color changes, fading, or surface degradation, determined by visual examination, must be removed and replaced with new panels at no expense to the Government.

New panels will be subject to the specified tests for an additional year from the date of their installation.

3.8 FIELD QUALITY CONTROL

3.8.1 Construction Monitoring

Make visual inspections as necessary to ensure compliance with specified requirements. Additionally, verify the following:

a. Materials comply with the specified requirements.

b. All materials are properly stored, handled and protected from damage. Damaged materials are removed from the site.

c. Framing and substrates are in acceptable condition, in compliance with specification, prior to application of wall panels.

d. Panels are installed without buckles, ripples, or waves and in uniform alignment and modulus.

e. Side laps are formed, sealed, fastened or seam locked as required.

f. The proper number, type, and spacing of attachment clips and fasteners are installed.

g. Installer adheres to specified and detailed application parameters.

h. Associated flashing and sheet metal are installed in a timely manner in accord with the specified requirements.

Provide three bound copies of Manufacturer's Field Reports to the Contracting Officer two weeks prior to project close-out.

3.9 CLEAN-UP AND DISPOSAL

Clean all exposed sheet metal work at completion of installation. Remove metal shavings, filings, nails, bolts, and wires from work area. Remove grease and oil films, excess sealants, handling marks, contamination from steel wool, fittings and drilling debris and scrub the work clean. Exposed metal surfaces must be free of dents, creases, waves, scratch marks, solder or weld marks, and damage to the finish coating.

Collect and place scrap/waste materials in containers. Promptly dispose of demolished materials. Do not allow demolished materials to accumulate on-site; transport demolished materials from government property and legally dispose of them.

-- End of Section --

SECTION 07 52 00

MODIFIED BITUMINOUS MEMBRANE ROOFING

MCBCL 10JUN2020

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7	(2017) Minimum Design Loads for Buildings and Other Structures

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.24	(2014) Roofing - Safety Requirements of Low-Sloped Roofs

ASPHALT ROOFING MANUFACTURER'S ASSOCIATION (ARMA)

ARMA 410BUR88	(2001) Manual of Roof Maintenance and Repair
ARMA PMBRG98	(1998) Quality Control Guideline for the Application of Polymer Modified Bitumen Roofing

ASTM INTERNATIONAL (ASTM)

ASTM C208	(2012; R 2017; E 2017; E 2019) Standard Specification for Cellulosic Fiber Insulating Board
ASTM C728	(2017a) Standard Specification for Perlite Thermal Insulation Board
ASTM C1289	(2018a) Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board
ASTM D41/D41M	(2011; R 2016) Standard Specification for Asphalt Primer Used in Roofing, Dampproofing, and Waterproofing
ASTM D312/D312M	(2016a) Standard Specification for Asphalt Used in Roofing
ASTM D2170/D2170M	(2018) Standard Test Method for Kinematic Viscosity of Asphalts (Bitumens)
ASTM D4073/D4073M	(2006; E 2019; R 2019) Standard Test Method for Tensile-Tear Strength of Bituminous Roofing Membranes

ASTM D4263	(1983; R 2018) Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D4402/D4402M	(2015) Viscosity Determination of Asphalt at Elevated Temperatures Using a Rotational Viscometer
ASTM D4586/D4586M	(2007; E 2012; R 2012) Asphalt Roof Cement, Asbestos-Free
ASTM D5147/D5147M	(2014) Standard Test Methods for Sampling and Testing Modified Bituminous Sheet Material
ASTM D6163/D6163M	(2016) Standard Specification for Styrene Butadiene Styrene (SBS) Modified Bituminous Sheet Materials Using Glass Fiber Reinforcements
ASTM D6298	(2016) Standard Specification for Fiberglass Reinforced Styrene-Butadiene-Styrene (SBS) Modified Bituminous Sheet with a Factory Applied Metal Surface
ASTM E108	(2011) Fire Tests of Roof Coverings

FM GLOBAL (FM)

FM 4470	(2010) Single-Ply, Polymer-Modified Bitumen Sheet, Built-up Roof (BUR), and Liquid Applied Roof Assemblies for Use in Class 1 and Noncombustible Roof Deck Construction
FM APP GUIDE	(updated on-line) Approval Guide http://www.approvalguide.com/

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2018) International Building Code

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 58	(2020) Liquefied Petroleum Gas Code
NFPA 241	(2019) Standard for Safeguarding Construction, Alteration, and Demolition Operations

NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)

NRCA C3701	(1997) Repair Manual for Low Slope Membrane Roof Systems
NRCA CONDET	(2014) Construction Details Manual

NRCA RoofMan	(2017) The NRCA Roofing Manual

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1793	(2012) Architectural Sheet Metal Manual, 7th Edition

SINGLE PLY ROOFING INDUSTRY (SPRI)

ANSI/SPRI/FM 4435/ES-1	(2017) Test Standard for Edge Systems Used with Low Slope Roofing Systems

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910	Occupational Safety and Health Standards
29 CFR 1910.12	Construction Work
29 CFR 1926	Safety and Health Regulations for Construction
29 CFR 1926.16	Rules of Construction

UNDERWRITERS LABORATORIES (UL)

UL 790	(2004; Reprint Jul 2014) Standard Test Methods for Fire Tests of Roof Coverings
UL RMSD	(2012) Roofing Materials and Systems Directory

1.2 DESCRIPTION OF ROOF MEMBRANE SYSTEMS

Minimum two-ply SBS modified bitumen roof membrane consisting of modified bitumen base sheet and cap sheet. Modified bitumen roof membrane must be set in hot asphalt

All work must follow the NRCA RoofMan guidelines and standards stated within this Section.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Roof Plan; G drawing depicting wind loads and boundaries of enhanced perimeter and corner attachments of roof system components, as applicable

Field Inspection and Existing Conditions Report

Identify all fire safety issues including exposed or concealed combustible materials, which may require additional protection during roof installation.

SD-03 Product Data

Modified Bitumen Sheets; G

Heat Island Reduction; S

Asphalt

Fiberglass Felt; G

Primer; G

Modified Bitumen Roof Cement; G

Pre-Manufactured Accessories

Fasteners And Plates; G

Polyisocyanurate Boards; G

Gutters, Downspouts, and miscellaneous metal accessories

Sample Warranty certificate; G

Submit all data required by Section 07 22 00 ROOF AND DECK INSULATION, together with requirements of this section. Include in data written acceptance by the roof membrane manufacturer of the products and accessories provided. Provide oroducts as listed in the applicable wind uplift and fire rating classification listings, unless approved otherwise by the Contracting Officer.

SD-05 Design Data

Wind Uplift Calculations; G

Provide Engineering calculations, signed, sealed, and dated by a qualified Engineer validating the wind resistance per ASCE 7, ASTM D4073/D4073M, and ANSI/SPRI/FM 4435/ES-1 of non-rated roof system.

SD-07 Certificates

Provide evidence that products used within this specification are manufactured in the United States.

Qualification of Manufacturer

Certify that the manufacturer of the modified bitumen membrane meets requirements specified under paragraph QUALIFICATION OF MANUFACTURER.

Qualification of Applicator

Certify that the applicator meets requirements specified under paragraph QUALIFICATION OF APPLICATOR.

Qualification of Engineer of Record

Certify that the Engineer of Record is fully qualified, competent, and currently licensed to practice in the project jurisdiction.

Bill of Lading

Submit bill of lading when labels of asphalt containers do not bear the flash point (FP), finished blowing temperature (FBT), and equiviscous temperature (EVT).

Wind Uplift Resistance; G classification, as applicable

Fire Resistance classification; G

Submit the roof system assembly wind uplift and fire rating classification listings.

SD-08 Manufacturer's Instructions

Modified Bitumen Membrane Application; G

Flashing; G

Temperature Limitations for Asphalt

Base Sheet attachment, including pattern and frequency of mechanical attachments required in field of roof, corners, and perimeters to provide for the specified wind resistance.

Primer

Fasteners

Ventilating Base Sheets

Coating Application; G

Cold Weather Installation; G

Include detailed application instructions and standard manufacturer drawings altered as required by these specifications. Include membrane manufacturer requirements for nailers and backnailing of roof membrane on steep slopes. Explicitly identify in writing, differences between manufacturer's instructions and the specified requirements.

SD-11 Closeout Submittals

Warranty

Information Card

Instructions To Government Personnel

Include copies of Safety Data Sheets for maintenance/repair materials.

Submit 30 year "No-Dollar-Limit" warranty for labor and materials including metal edge system in accordance with ANSI/SPRI ES-1 requirements.

1.4 QUALITY ASSURANCE

1.4.1 Qualification of Manufacturer

Modified bitumen sheet roofing system manufacturer must have a minimum of 20 years experience in manufacturing modified bitumen roofing products.

1.4.2 Qualification of Applicator

Roofing system applicator must be approved, authorized, or licensed in writing by the modified bitumen sheet roofing system manufacturer and have a minimum of five years experience as an approved, authorized, or licensed applicator with that manufacturer and be approved at a level capable of providing the specified warranty. The applicator must supply the names, locations and client contact information of five projects of similar size and scope that the applicator has constructed using the manufacturer's roofing products submitted for this project within the previous three years.

1.4.3 Qualification of Engineer of Record

Engineer of Record must be currently licensed within the jurisdiction of the project.

Engineer of Record must be approved, authorized, and currently licensed by the state of North Carolina, and have a minimum of five years experience as an approved Engineer for manufacturers of similar roof systems. Engineer of Record must supply the names and locations of five projects of similar size and scope for which he has provided engineering calculations using the manufacturer's products submitted for this project within the previous three years. Engineer of Record must provide certified engineering calculations for:

Wind uplift requirements in accordance with Local and State codes

ASCE 7,in accordance with International Building Code.

Seismic requirements per local and state building codes

Seismic requirements per ICC IBC Chapter 16, Section 1608.3

Snow load requirements per ICC IBC Chapter 16 Section 1608.3 and Section 7 of ASCE 7

1.4.4 Fire Resistance

Complete roof covering assembly must:

a. Be Class A rated in accordance with ASTM E108, FM 4470, or UL 790; and

b. Be listed as part of Fire-Classified roof deck construction in UL RMSD, or Class I roof deck construction in FM APP GUIDE.

FM or UL approved components of the roof covering assembly must bear the appropriate FM or UL label.

1.4.5 Wind Uplift Resistance

Provide a complete roof system assembly that is rated and installed to resist wind loads calculated in accordance with ASCE 7 and validated by uplift resistance testing in accordance with Factory Mutual (FM) test procedures. Do not install non-rated systems, except as approved by the Contracting Officer. Submit licensed engineer's Wind uplift calculations and substantiating data to validate any non-rated roof system. Base wind uplift measurements on a design wind speed of 150 mph in accordance with ASCE 7 and other applicable building code requirements.

1.4.6 Preroofing Conference

After approval of submittals and before performing roofing and insulation system installation work, hold a preroofing conference to review the following:

a. Drawings, including Roof Plan, specifications and submittals related to the roof work

b. Roof system components installation

c. Procedure for the roof manufacturer's technical representative's onsite inspection and acceptance of the roof structure, and roofing substrate, the name of the manufacturer's technical representatives, the frequency of the onsite visits, distribution of copies of the inspection reports from the manufacturer's technical representatives to roof manufacturer

d. Contractor's plan for coordination of the work of the various trades involved in providing the roofing system and other components secured to the roofing

e. Quality control, (ARMA PMBRG98) plan for the roof system installation

f. Field inspection and existing conditions report identifying all fire safety issues including exposed or concealed combustible materials, which may require additional protection during roof installation

g. Safety requirements

Coordinate preroofing conference scheduling with the Contracting Officer. The conference must be attended by the Contractor, the Contracting Officer's designated personnel, and personnel directly responsible for the installation of roofing and insulation, flashing and sheet metal work, mechanical and electrical work, other trades interfacing with the roof work, designated safety personnel trained to enforce and comply with ASSP A10.24, Fire Marshall, and a representative of the roofing materials manufacturer. Before beginning roofing work, provide a copy of meeting notes and action items to all attending parties. Note action items requiring resolution prior to start of roof work.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver materials in manufacturers' original unopened containers and rolls with labels intact and legible. Mark and remove wet or damaged materials from the site. Where materials are covered by a referenced specification,

the container must bear the specification number, type, and class, as applicable. Labels or bill of lading for roofing asphalt must indicate asphalt type, FP, FBT, and EVT, that is, the temperature at which the viscosity is either 125 centistokes when tested in accordance with ASTM D2170/D2170M or 75 centipoise when tested in accordance with ASTM D4402/D4402M. Deliver materials in sufficient quantity to allow work to proceed without interruption.

1.5.2 Storage

Protect materials against moisture absorption and contamination or other damage. Avoid crushing or crinkling of roll materials. Store roll materials on end on clean raised platforms or pallets one level high in dry locations with adequate ventilation, such as an enclosed building or closed trailer. Do not store roll materials in buildings under construction until concrete, mortar, and plaster work is finished and dry. Maintain roll materials at temperatures above 50 degrees F for 24 hours immediately before application. Do not store materials outdoors unless approved by the Contracting Officer. Completely cover felts stored outdoors, on and off roof, with waterproof canvas protective covering. Do not use polyethylene sheet as a covering. Tie covering securely to pallets to make completely weatherproof. Provide sufficient ventilation to prevent condensation. Do not store more materials on roof than can be installed the same day and remove unused materials at end of each days work. Distribute materials temporarily stored on roof to stay within live load limits of the roof construction.

Maintain a minimum distance of 35 foot for all stored flammable materials, including materials covered with shrink wraps, craft paper or tarps from all torch/welding applications.

Immediately remove wet, contaminated or otherwise damaged or unsuitable materials from the site. Damaged materials may be marked by the Contracting Officer.

1.5.3 Handling

Prevent damage to edges and ends of roll materials. Do not install damaged materials in the work. Select and operate material handling equipment to prevent damage to materials or applied roofing.

1.6 ENVIRONMENTAL REQUIREMENTS

Do not install roofing system when air temperature is below 40 degrees F, during any form of precipitation, including fog, or when there is ice, frost, moisture, or any other visible dampness on the roof deck. Follow manufacturer's printed instructions for Cold Weather Installation.

1.7 HOT-MOPPED ASPHALT APPLIED MODIFIED BITUMEN MEMBRANE SAFETY

1.7.1 Property Protection

Take all precautions necessary to prevent ignition of combustible materials during hot-mopped asphalt application of roofing. Immediately call the fire department if a fire commences. Review all fire safety procedures as outlined at the pre-roofing conference.

Install materials using the techniques recommended by CERTA NRCA/MRCA Certified Roofing Torch Applicator Program available from the National

Roofing Contractors Association (NRCA) and the Midwest Roofing Contractors Association (MRCA) as endorsed by the Asphalt Roofing Manufacturers Association (ARMA) and the United Union of Roofers, Waterproofers and Allied Workers. Application procedures must comply with NFPA 241, OSHA 29 CFR 1910 and 29 CFR 1910.12, 29 CFR 1926.16, 29 CFR 1926 Subpart F., UL Fire Resistance Directory Volume No. 1, NRCA R&W Manual, and Florida Building Code Volume 2004.

Do not store flammable liquids on the roof.

Provide a minimum of two 2.65 gallon containers of water and two fully charged minimum 20 pound CO2 20 pound ABC (dry chemical) fire extinguishers in separate, easily accessible locations on the roof and within 10 foot of each hot-mopped kettle at all times.

No AsphaltKettles are allowed on roofs. Locate kettles and supply LP-Gas Cylinders safely and secured per NFPA 241 outside of the building's perimeter a minimum of 20 foot from the structure and any combustible materials.

Maintain a minimum separation of 20 foot between LP-Gas Cylinders and kettle. Provide protective fire retardant blanket barrier or shield between any building structure to a minimum height of 8 foot and a clear surround distance of 4 foot if operations force placement of kettle within a distance of 20 foot. Do not obstruct or place kettles or Cylinder storage within 10 foot of exits, means of egress, gates, roadways, entrances. Locate kettles downwind and away from any building air intakes.

Provide a minimum of two portable fully charged 20 pound CO2 (dry chemical) fire extinguishers no closer than 5 foot and no further than 25 foot of horizontal travel distance from each kettle at all times while kettle is in operation, in easily accessible and identifiable locations. Also provide a minimum of one multipurpose 2-A:20-B:C portable fire extinguisher on the roof being covered or repaired.

Comply with the following safety procedures:

a. Fuel containers, burners, and related appurtenances of roofing equipment in which liquefied petroleum gas is used for heating must comply with the requirements of NFPA 58.

b. Fuel containers having capacities greater than one pound must be located a minimum of 10 foot clear distance from the burner flame.

c. Clearly label all LP-Gas Cylinders as "Flammable Gas", and secure to prevent accidental tip-over.

d. Check all pressure regulators and hoses prior to use for proper functioning and integrity.

e. Turn off fuel supply at LP Gas Cylinder when kettle is not in use.

f. Equip all kettles with a functioning temperature measuring device to ensure no heating in excess of 50 degrees F below the flash point.

g. Provide covers, lid, or top which are close fitting, constructed of minimum No.14 manufacturer's gauge steel, and can be gravity closed on all kettles.

h. Clean all roofing mops and rags free of excess asphalt and store safely away from all combustible materials. Store discarded roofing mops and rags in a non-combustible container and remove from site each day.

i. Position all pump lines handling hot asphalt securely and equip all pump lines with a shut-off valve on each with a coupler which may be opened when lines are full. Do not subject pump lines to pressures in excess of safe and recommended NRCA and ARMA working pressures. Station an operator near the equipment to cut off flow and care for other emergencies while conducting heating, pumping and application operations.

j. Asphalt bucket used by roofers or workers in similar trades must be constructed of minimum No. 24 gauge or heavier sheet steel and have a metal bail of no less than 1/4 inch diameter material. The bail is to be fastened to offset ears or equivalent which have been riveted, welded, or otherwise safely and securely attached to the bucket. Soldered bail sockets are prohibited. Position workers and other employees to avoid being struck by bucket or other roofing materials, which may accidentally fall while being hoisted, lowered, or used in the roofing operation. Provide safety barriers and caution signs at all skylights or other roof holes.

k. Do not use flammable liquids with a flash point below100 degrees F (gasoline and similar products) for cleaning purposes.

Do not use solid fuel or Class I liquids as fuel for roofing asphalt kettles. Provide a minimum of one employee fully knowledgeable of kettle operations and hazards to maintain constant surveillance during kettle operation within a minimum distance of 25 foot of the kettle.

Check all fire extinguishers prior to commencement of work, and upon completion of the day's work, to ensure fullness and operability.

Project supervisor must make daily inspections with the facility manager of all conditions and operations which could present hazards during hot-mopped applications and issue directives to address all such concerns and items of the work and existing conditions.

Identify and protect all combustible roof components, possible fire traps, and hidden hazards. Seal off voids or openings in the substrate with non-combustible materials prior to installing hot-mopped applied materials in the area. Install protective fire retardant blankets and shields at building walls, eaves, parapets and equipments curbs constructed of combustible materials within 3 foot radius of the area of hot-mopped kettle prior to commencement of the work.

When working around intakes and openings, temporarily disconnect and block to prevent fumes from kettle from being drawn into the opening.

1.7.2 Fire Watch

All personnel on the roof during hot-mopped application must be properly trained to use a fire extinguisher. Provide a fire watch for a minimum of 30 minutes after completion of hot-mopped kettle operations at the end of each work shift. Maintain the fire watch for additional time required to ensure no potential ignition conditions exist. Utilize heat sensing meters to scan for hot spots in the work. Provide a minimum duration fire watch of two hours conducted by personnel properly trained in the use of the camera

to survey the underside of the roof deck, attic, and plenum spaces (where possible) and the topside of possible smoldering elements. Camera must have a manufacturer's certificate of calibration, and the use of the camera must be in compliance with Installation security policies.

Do not leave the rooftop unattended during breaks in work during a work shift. Walk and scan all areas of application checking for hot spots, fumes, or smoldering, especially at wall and curb areas, prior to departure at the end of each work shift. Ensure any and all suspect conditions are eliminated prior to leaving the site each work shift.

1.7.3 Equipment and Personnel Safety

All crew members must be trained in preventive measures for indirect and direct dangers and hazards associated with roofing work, which include, but are not limited to the following:

a. Heat Stress: Wear light colored clothing, a hat for ultra-violet protection, and other eye protective devices. Drink sufficient quantities of non-alcoholic, non-caffeine liquids. Stage shifts for crew members to allow for breaks from heat and sun exposure without interfering with work progress.

b. First Aid for Burns: Immediately call for an ambulance. Contact local Occupational Health Services (OHS).

All crew members must wear correct personal protective equipment (PPE), including. but not limited to the following items:

a. Long-sleeved shirts buttoned at the collar and cuffs, and must be made of non-flammable materials. Polyester materials are not allowed.

b. Work boots covering ankles with rubber or composite soles.

c. Long pants without cuffs to extend over the top of the work boots, and must be made of non-flammable materials. No polyester allowed.

d. OSHA and ANSI/ISEA Z87.1 approved face shields, goggles and/or safety glasses to be worn during hour work operations and any other applicable roofing functions.

e. OSHA and ANSI approved hard hats.

1.7.4 Wind Conditions

Use side shields with all torching operations when winds are occurring to prevent flame distortion of end burners. Use torch machine equipment with bottom shield plate to prevent flame spread on to roof deck and substrate. When high wind gusts are present, notify the safety officer and cease all use of torching equipment until wind conditions lower and authorization from the safety officer to proceed is received.

1.8 SEQUENCING

Coordinate the work with other trades to ensure that components which are to be secured to or stripped into the roofing system are available and that permanent flashing and counter flashing, per NRCA CONDET, and are installed as the work progresses. Ensure temporary protection measures are in place to preclude moisture intrusion or damage to installed materials.

Apply roofing immediately following application of insulation as a continuous operation. Coordinate roofing operations with insulation work so that all roof insulation applied each day is covered with roof membrane installation the same day.

1.9 WARRANTY

Provide roof system material and workmanship warranties meeting specified requirements. Provide revision or amendment to standard membrane manufacturer warranty as required to comply with the specified requirements. Provide a manufacturer's warranty that has no dollar limit, covers full system water-tightness, and has a minimum duration of 30 years.

1.9.1 Roof Membrane Manufacturer Warranty

Furnish the roof membrane manufacturer's 30-year no dollar limit roof system materials and installation workmanship warranty, including flashing, insulation in compliance with ASTM C1289, and accessories necessary for a watertight roof system construction. Provide one sole source warranty for roof system (30 years)including the edge metal (ANSI SPRI ES-1 CODE) the coating system (10 year finish warranty). A signed letter from the president of the manufacturer stating the roof membrane, edge metal and coatings are products of the manufacturer shall accompany the roof submittal package. No relabeled products from third party manufacturers are acceptable. Provide coverage for damage to the roofing system caused by sustained winds having a velocity of 130 mph or less. Provide warranty directly to the Government and commence warranty effective date at time of Government's acceptance of the roof work. The warranty must state that:

a. If within the warranty period the roof system, as installed for its intended use in the normal climatic and environmental conditions of the facility, becomes non-watertight, shows evidence of moisture intrusion within the assembly, blisters, splits, tears, delaminates, separates at the seams, or shows evidence of excessive weathering due to defective materials or installation workmanship, the repair or replacement of the defective and damaged materials of the roof system assembly and correction of defective workmanship are the responsibility of the roof membrane manufacturer. All costs associated with the repair or replacement work are the responsibility of the roof membrane manufacturer.

b. When the manufacturer or his approved applicator fail to perform the repairs within 72 hours of notification, emergency temporary repairs performed by others does not void the warranty.

c. Upon completion of installation, and acceptance by the Contracting Officer and Roofing System Engineer of Record, the manufacturer must supply the appropriate warranty to the Owner.

d. Installer must submit a minimum two year warranty to the membrane manufacturer from the date of acceptance, with a copy to the Contracting Officer and Roofing System Engineer of Record.

1.9.2 Roofing System Installer Warranty

The roof system installer must warrant for a period of two years that the roof system, as installed, is free from defects in installation workmanship, to include the roof membrane, flashing, insulation, accessories, attachments, and sheet metal installation integral to a

complete watertight roof system assembly. Write the warranty directly to the Government. The roof system installer is responsible for correction of defective workmanship and replacement of damaged or affected materials. The roof system installer is responsible for all costs associated with the repair or replacement work.

1.9.3 Continuance of Warranty

Repair or replacement work, ARMA 410BUR88, NRCA C3701 that becomes necessary within the warranty period and accomplished in a manner so as to restore the integrity of the roof system assembly and validity of the roof membrane manufacturer warranty for the remainder of the manufacturer warranty period.

1.10 CONFORMANCE AND COMPATIBILITY

Provide the entire roofing and flashing system in accordance with specified and indicated requirements, including fire and wind resistance (ANSI/SPRI/FM 4435/ES-1) requirements. Work not specifically addressed and any deviation from specified requirements must be in general accordance with recommendations of the NRCA Roofing and Waterproofing Manual, membrane manufacturer published recommendations and details, and compatible with surrounding components and construction. Submit any deviation from specified or indicated requirements to the Contracting Officer for approval prior to installation.

1.11 ELIMINATION, PREVENTION OF FALL HAZARDS

1.11.1 Fall Protection

Refer to MCBCL Standard Spec Sec 11 24 24 ROOF FALL PROTECTION

PART 2 PRODUCTS

2.1 MATERIALS

Coordinate with other specification sections related to the roof work. Furnish a combination of specified materials that comprise a roof system acceptable to the roof membrane manufacturer and meeting specified requirements. Protect materials provided from defects and make suitable for the service and climatic conditions of the installation.

2.2 MODIFIED BITUMEN SHEETS AND FIBERGLASS FELT MATERIALS

Furnish a combination of specified materials that comprise the modified bitumen manufacturer's standard system of the number and type of plies specified. Provide materials suitable for the service and climatic conditions of the installation. Modified bitumen sheets must be watertight and visually free of pinholes, particles of foreign matter, non-dispersed raw material, factory splices, or other conditions that might affect serviceability. Polymer modifier must comply with ARMA PMBRG98 and be uniformly dispersed throughout the sheet. Edges of sheet must be straight and flat.

a. Fiberglass Felt Base Sheet (Concrete deck applications only): ASTM D4601/D4601M,ASTM D1668/D1668M Type II, as approved by the modified bitumen roof membrane manufacturer.
The reinforced fabric must contain two fibers interwoven, stitched

composite polyester/ fiberglass scrim.
Glued composite scrims are not acceptable.

b. SBS Base Sheet:
ASTM D6163/D6163M], Type III , Grade S, minimum 80 mils thick.
Tensile Strength (ASTM D5147): 2 in/min. @ 73.4 +/- 3.6°F MD 100 lbf/in CMD 100 lbf/in; 50 mm/min. @23 +/- deg. C; MD 17.5 kN/m; CMD 17.5kN/m. Page 14
Tear Strength (ASTM D5147): 2 in/min. @ 73.4 +/- 3.6° FMD 110 lbf; CMD 100 lbf/in. 50 mm/min. @23 +/- 3 deg. C; MD 489 N; CMD 444 N.
Elongation at Maximum Tensile (ASTM D5147): 2 in/min. @ 73.4 +/- 3.6 Deg. F; FMD 4%; CMD 4%; 50 mm/min @23 +/- 3 deg. C; MD 4%; CMD 4%.
Low Temperature Flexibility (ASTM D5147): Passes -40°F (-40°C).

c. SBS Cap Sheet: ASTM; Type III, Grade G , minimum 170 mils thick, and as required to provide specified fire safety rating. The cap sheet is to contain a minimum 6% recycled content.
Tensile Strength (ASTM D5147): 2 in/min @ 73.4 +/- 3.6 deg. FMD 1000 1bf/in; CMD 1100 bf/in 50 mm/min @ 23 +/- 3 deg. MD 175 N CMD 192.5 KN/M.
Tear Strength (ASTM D5147) 2 in/min @ 73.4 +/- 3.6 deg. FMD 17001bf; CMD 1800 1bf/in 50 mm/min @ 23 +/- 3 deg. C MD 7561.6N; CMD 8006.4N
Elongation at Maximum Tensile (ASTM D5147): 2 in/min @ 73.4 +/- 3.6 deg. F; MD 16.0% CMD 16.0% 50 mm/min @ 23 +/- 3 deg. C MD 16.0%
Low Temperature Flexibility (ASTM D 5147): Passes -40 deg. F (-40°C).

2.3 BASE FLASHING MEMBRANE

Membrane manufacturer's standard, minimum two-ply modified bitumen membrane flashing system compatible with the roof membrane specified and as recommended in membrane manufacturer's published literature. Provide flashing membranes that meet or exceed the properties of the material standards specified for the modified bitumen base, interply and cap sheet, except that flashing membrane thickness must be as recommended by the membrane manufacturer. Provide metal clad flashing membrane that complies with ASTM D6298.

All flashings are to be set in modified hot asphalt and consist of one layer of tri-laminate base sheet and finish flashing the same as the mineral cap.

Perform three course repairs on all laps and aluminize. The tri-laminate base sheet shall have the following characteristics.

All flashings shall have double coated reinforced scrim with the following minimum performance requirements according to ASTM D5147:

The sheet is to contain a minimum of 29% recycled content and be manufactured by the Membrane Roof Manufacturer.

Tensile Strength (ASTM D5147): 2 in/min @ 73.4 +/- 3.6 deg. F MD 315 1bf/in CMD 315 1bf/in.

Tear Strength (ASTM D5147): 2 in/min @ 73.4 +/- 3.6 deg. F MD 550 1bf/in CMD 550 1bf/in

Elongation at Maximum Tensile (ASTM D5147): 2 in/min @ 73.4 +/- 3.6 deg. F MD 5% CMD 5% 50 mm/min @ 23 +/- 3 deg. C MD 5% CMD 5%

2.4 ASPHALT

ASTM D312/D312M, Type III or IV, in accordance with modified bitumen membrane manufacturer requirements and compatible with the slope conditions of the installation for vapor barriers and insulation boards on concrete decks only. SEBS modified hot asphalt to be used on flashing, base, and cap sheets on concrete deck and all other applications unles otherwise noted to have the following characteristics:

Elongation @ 77 degree F (ASTM D412) 750% Min.

Softening point (ASTM D36) 203 degree F - 221 degree F.

2.5 MEMBRANE SURFACING

Provide modified bitumen roof membrane cap sheet with factory-applied granule surfacing of color as selected from membrane manufacturer's standard colors. Provide modified bitumen membrane manufacturer's recommended field-applied protective coating. Coat the entire roof surface with white, reflective coating system to meet or exceed the following:

Base Coat - White Elastomeric Roof Coating: Energy Star, CRRC, Title 24 approved white acrylic roof coating ASTM E 903, C 1549 Reflectance 81%, SRI (Solar Reflective Index) 101.

Top Coat - White Kynar Aquatec Roof Coating: Energy Star, CRRC, Title 24 approved white water based, fluoropolymer-acrylic resin roof coating. ASTM C 1549 Reflectance 90%, SRI (Solar Reflective Index) 112.

Both the base coat and top coat must be products of the roof membrane manufacturer with the proper paperwork to accompany submittals.

2.6 PRIMER

ASTM D41/D41M, or other primer compatible with the application and as approved in writing by the modified bitumen membrane manufacturer.

2.7 MODIFIED BITUMEN ROOF CEMENT

ASTM D4586/D4586M, Type II for vertical surfaces, Type I for horizontal surfaces, compatible with the modified bitumen roof membrane and as recommended by the modified bitumen membrane manufacturer.

2.8 CANT AND TAPERED EDGE STRIPS

Provide standard cants and tapered edge strips of perlite conforming to ASTM C728 the same material as the roof insulation or when roof insulation material is not available, provide pressure preservative treated wood, wood fiberboard, or rigid perlite board cants and edge strips as recommended by the manufacturer or wood fiber conforming to ASTM C208 treated with bituminous impregnation, sizing, or waxing and fabricated to provide maximum 45 degree change in direction of membrane. Cant strips must be minimum 5 inch face and 3-1/2 inch vertical height when installed at 45

degree face angle , except where clearance restricts height to lesser dimension. Taper edge strips at a rate of one to 1-1/2 inch per foot to a minimum of 1/8 inch of thickness. Provide kiln-dried preservative-treated wood cants, in compliance with requirements of Section 06 10 00 ROUGH CARPENTRY at base of wood nailers set on edge and wood curbing and where otherwise indicated.

2.9 FASTENERS AND PLATES

Provide coated, corrosion-resistant fasteners as recommended by the modified bitumen sheet manufacturer's printed instructions and meeting the requirements of FM 4470 and FM APP GUIDE for Class I roof deck construction and the wind uplift resistance specified. For fastening of membrane or felts to wood materials, provide fasteners driven through 1 inch diameter metal discs, or one piece composite fasteners with heads not less than 1 inch in diameter or 1 inch square with rounded or 45 degree tapered corners.

2.9.1 Masonry or Concrete Walls and Vertical Surfaces

Use hardened steel nails or screws with flat heads, diamond shaped points, and mechanically deformed shanks not less than 1 inch long for securing felts, modified bitumen sheets, metal items, and accessories to masonry or concrete walls and vertical surfaces. Use power-driven fastenersonly when approved in writing by the Contracting Officer.

2.9.2 Metal Plates

Provide flat corrosion-resistant round stress plates as recommended by the modified bitumen sheet manufacturer's printed instructions and meeting the requirements of FM 4470; not less than 2 inch in diameter. Form discs to prevent dishing or cupping.

2.10 PRE-MANUFACTURED ACCESSORIES

Pre-manufactured accessories must be manufacturer's standard for intended purpose, comply with applicable specification section, compatible with the membrane roof system and approved for use by the modified bitumen membrane manufacturer.

2.10.1 Pre-fabricated Curbs

Provide 20 gauge AZ55 galvalume curbs with minimum 4 inch flange for attachment to roof nailers. Curbs must be minimum height of 10 inch above the finished roof membrane surface.

2.10.2 Elevated Metal Walkways and Platforms

As specified in Section 05 50 13 MISCELLANEOUS METAL FABRICATIONS 05 51 33 METAL LADDERS 05 52 00 METAL RAILINGS 05 51 00 METAL STAIRS.

2.11 WALKPADS

Provide roof walkpads that are polyester reinforced, granule-surfaced modified bitumen membrane material, minimum197 mils thick, compatible with the modified bitumen sheet roofing and as recommended by the modified bitumen sheet roofing manufacturer. Panels must not exceed 4 foot in length. Other walkpad materials require approval of the Contracting Officer prior to installation.

2.12 PAVER BLOCKS

Precast concrete, minimum 1-1/2 inch thick, minimum 18 inch square for walkways and minimum 6 inch by 12 inch for use in supporting surface bearing components but extending not less than 2 inch beyond all sides of surface bearing bases. Install walkpad material under all paver blocks.

2.13 ROOF INSULATION BELOW MODIFIED BITUMEN MEMBRANE SYSTEM

Provide insulation compatible with the roof membrane, approved by the membrane manufacturer and meeting all the requirements of of ASTM C1289 Polyisocyanurate Boards.

Type II, Class I, Grade 3, 25 psi-minimum. 25 R-Value (Minimum). Tapered or as indicated in other documents.

Fasteners: Provide flush-driven fasteners through flat round or hexagonal steel or plastic plates. Provide zinc-coated steel plates, flat round not less than 35 mm 1 3/8 inch diameter, hexagonal not less than 0.4 mm 28 gage. Provide high-density plastic plates, molded thermoplastic with smooth top surface, reinforcing ribs and not less than 75 mm 3 inches in diameter. Fully recess fastener head into plastic plate after it is driven. Form plates to prevent dishing. Do not use bell or cup shaped plates. Provide fasteners in accordance with insulation manufacturer's recommendations for holding power when driven, to withstand 130 MPH wind.

Vapor Barrier (Concrete Decks only. Two plies of Type IV fiberglass plies set in hot Type III asph

2.14 COVER BOARD (Recovery Board)

Cement Roof Board manufactured to conform to ASTM C1325.

Nominal thickness: 1/2 in.

Nominal weight: 2.4 lbs/SF.

Flexural strength (parallel) per ASTM C947: > 750 psi.

Compressive strengths: > 1000 psi.

Flute spanability per ASTM E661: 12 in.

Permeance per ASTM E96: 5.84 perms.

R Value per ASTM E831: 0.39 .SF.h/BTU.

Water Absorption per ASTM C473: < 0.07% MAX.

Mold resistance per ASTM D3273: 10.

Minimum bending radius: 6 ft.

2.15 ALUMINUM

ANSI-SPRI ES-1.

ASTM B209M ASTM B209 anodized color form alloy and temper appropriate for use.

Alclad 3003 or Alclad 3004, or Alclad 3005, clad on one side.

Finish: Baked-on factory-applied color coating of polyvinylidene fluoride (PVF2) or other equivalent fluorocarbon coating applied after metal substrates have been cleaned and pretreated.

Finish coating dry-film thickness: 0.020 to 0.033 mm 0.8 to 1.3 mils

Color: Per BEAP

2.16 EDGE METAL/FLASHING/GUTTERS/DOWNSPOUTS/FASCIA

Use only aluminum manufactured for the purpose of flashing.

All exposed sheet metal gutters, including hangers, downspouts, gravel stops, and fascias; CAP, valley, steeped, base, and eave flashing, expansion joints,and related accessories must be of the same material.

Furnish sheet metal items in 8 to 10 foot lengths. Single pieces less than 8 feet long may be used to connect to factory -fabricated inside and outside corners, and at ends of runs. Factory fabricate corner pieces with minimum 12 inch legs. Provide all accessories and other items essential to complete the sheet metal installation. Provide accessories made of the same or compatible materials as the items to which they are applied.

Aluminum alloy sheet and plate: ASTM B209M anodized color form alloy, and temper appropriate for use. ALCLAD 3003, ALCLAD 3004, ALCLAD 3005, clad on both sides.

Exposed exterior finish: Baked-on, factory-applied color coating of polyvinylidene fluoride (PVF2) or other equivalent fluorocarbon coating applied after metal substrates have been cleaned and pretreated. Provide finish coating dry-film coating dry-film thickness of 0.020 to 0.033 min. 0.8 to 1.3 mills. Color as selected from standard color wheel.

Aluminum alloy, extruded bars, rods, shapes, and tubes: ASTM B221M and ASTM B221.

Fasteners: Use the same metal or a metal compatible with the item fastened. Use stainless steel fasteners to fasten dissimilar materials (ASTM A480/A480M, type 302 or 304, 2D finish, fully annealed).

Minimum thickness of 0.025" (22Gage) for: Base course; wall opening heads and sills; through wall and spandrel; cap and base flashing; vertical and horizontal surfaces; roof edges, ridges, and hips; crickets, valleys, or gutters; chimney pans; and ledge flashing.

Minimum thickness of 0.032" for: coping widths up to 12".

Minimum thickness of 0.040" for: coping widths above 12".

Minimum thickness of 0.032" for: soffits.

2.16.1 ADHESIVE - HOT

Hot Type III SBS Modified asphalt

2.16.2 AHESIVE - COLD

Cold adhesive is not alternate material to hot applied methods. Use cold adhesive if shown in drawings. Provide membrane manufacturer's recommended low volatile organic compound (VOC) cold process adhesive for application of the membrane plies. Provide moisture-cured, asphalt modified polyester polymer based adhesive. Provide product that will cure in 1 to 5 days maximum depending on climatic conditions. Apply product as recommended by manufacturer, including but not limited to: tools, temperature, coverage rate, etc.)2.16.2.1 POLYUREA FOR DRAINAGE

Single component alaphatic Polyurea

Tensile Strength (ASTM D 412) 2300 psi

Tear Strength (ASTM D 624) 230 lbs / SF

Wet Film Thickness 32 minimum 32 mils

PART 3 EXECUTION

3.1 EXAMINATION

Ensure that the following conditions exist prior to application of the roofing materials:

a. Do not install items that show visual evidence of biological growth.

b. Drains, curbs, cants, control joints, expansion joints, perimeter walls, roof penetrating components, and equipment supports are in place.

c. Surfaces are rigid, clean, dry, smooth, and free from cracks, holes, and sharp changes in elevation. Joints in the substrate are sealed to prevent dripping of bitumen into building or down exterior walls.

d. The plane of the substrate does not vary more than 1/4 inchwithin an area 10 by 10 foot when checked with a10 foot straight edge placed anywhere on the substrate.

e. Substrate is sloped as indicated to provide positive drainage.

f. Walls and vertical surfaces are constructed to receive counter flashing, and will permit mechanical fastening of the base flashing materials.

g. Treated wood nailers are in place on non-nailable surfaces, to permit nailing of base flashing at minimum height of 8 inch above finished roofing surface.

h. Protect all combustible materials and surfaces which may contain concealed combustible or flammable materials. All fire extinguishing equipment has been placed as specified.

i. Verify all Fire Watch personnel assignments.

j. Treated wood nailers are fastened in place at eaves, gable ends,

openings, and intersections with vertical surfaces for securing of membrane, edging strips, attachment flanges of sheet metal, and roof fixtures. Embedded nailers are flush with deck surfaces. Surface-applied nailers are the same thickness as the roof insulation.

k. Cants are securely fastened in place in the angles formed by walls and other vertical surfaces. The angle of the cant is 45 degrees and the height of the vertical leg is not less than 3-1/2 inch.

l. Venting is provided in accordance with the following:

(1) Edge Venting: Perimeter nailers are kerfed across the width of the nailers to permit escape of gaseous pressure at roof edges.

(2) Underside Venting: Vent openings are provided in steel form decking for cast-in-place concrete substrate.

m. Exposed nail heads in wood substrates are properly set. Warped and split sheets have been replaced. There are no cracks or end joints 1/4 inch in width or greater. Knot holes are covered with sheet metal and nailed in place. Wood, Plywood decks are covered with rosin paper or unsaturated felt prior to base sheet or roof membrane application. Joints in plywood substrates are taped or otherwise sealed to prevent air leakage from the underside.

n. Insulation boards are installed smoothly and evenly, and are not broken, cracked, or curled. There are no gaps in insulation board joints exceeding 1/4 inch in width. Insulation is being roofed over on the same day the insulation is installed.

o. Cast-in-place substrates have been allowed to cure and the surface dryness requirements specified under paragraph FIELD QUALITY CONTROL have been met.

p. Joints between precast concrete deck units are grouted, leveled, and stripped in with felt or bituminous stripping membrane set in bituminous cement prior to applying other roofing materials over the area.

q. Roof deck and framing are sloped as indicated to provide positive drainage.

3.2 PREPARATION

3.2.1 Protection of Property

3.2.1.1 Protective Coverings

Install protective coverings at paving and building walls adjacent to hoists , and kettles prior to starting the work. Lap protective coverings not less than 6 inch, secure against wind, and vent to prevent collection of moisture on covered surfaces. Keep protective coverings in place for the duration of the roofing work.

3.2.1.2 Bitumen Stops

Provide felt bitumen stops or other means to prevent bitumen drippage at roof edges, openings, and vertical projections before hot mopped application of the roofing membrane.

3.2.2 Equipment

3.2.2.1 Mechanical Application Devices

Mount mechanical application devices on pneumatic-tired wheels. Use devices designed and maintained to operate without damaging the insulation, roofing membrane, or structural components.

3.2.2.2 Flame-Heated Equipment

Do not place flame-heated equipment on roof. Provide and maintain a fire extinguisher adjacent to flame-heated equipment and on the roof.

3.2.2.3 Electric-Heated Equipment

Provide adequate electrical service as required by manufacturer of electrical equipment to ensure against damage to equipment and property and to ensure proper application of roofing materials.

3.2.3 Heating of Asphalt

Break up solid asphalt on a surface free of dirt and debris. Heat asphalt in kettle designed to prevent contact of flame with surfaces in contact with the asphalt. Utilize kettles with visible working thermometer and thermostatic controls set to the temperature limits specified herein. Keep controls in working order and calibrated. Use immersion thermometer, accurate within a tolerance of plus or minus 1.8 degrees F, to check temperatures of the asphalt frequently. When temperatures exceed maximums specified, remove asphalt from the site. Do no permit cutting back, adulterating, or fluxing of asphalt.

3.2.3.1 Temperature Limitations for Asphalt

Heat and apply asphalt at the temperatures specified below unless specified otherwise by manufacturer's printed application instructions. Use thermometer to check temperature during heating and application. Have kettle attended constantly during heating process to ensure specified temperatures are maintained. Do not heat asphalt above its finished blowing temperature (FBT). Do not heat asphalt between 500 and 525 degrees F for longer than four consecutive hours. Do not heat asphalt to the flash point (FP). Apply asphalt and embed membrane sheets when temperature of asphalt is within plus or minus 25 degrees F of the equiviscous temperature (EVT) but not less than 400 degrees F. Before heating and application of asphalt refer to the asphalt manufacturer's label or bill of lading for FP, FBT, and EVT of the asphalt used.

3.2.4 Priming of Surfaces

Prime all surfaces to be in contact with adhered membrane materials. Apply primer at the rate of 0.75 gallon per 100 sq. ft. or as recommended by modified bitumen sheet manufacturer's printed instructions to promote adhesion of membrane materials. Allow primer to dry prior to application of membrane materials to primed surface. Avoid flammable primer material conditions in torch applied membrane applications.

3.2.4.1 Priming of Concrete and Masonry Surfaces

After surface dryness requirements have been met, coat concrete and masonry

surfaces which are to receive membrane materials uniformly with primer.

3.2.4.2 Priming of Metal Surfaces

Prime flanges of metal components to be embedded into the roof system prior to setting in bituminous materials or stripping into roofing system.

3.2.5 Membrane Preparation

Unroll modified bitumen membrane materials and allow to relax a minimum of 30 minutes prior to installation. In cold weather, adhere to membrane manufacturer's additional recommendations for pre-installation membrane handling and preparation. Inspect for damage, pinholes, particles of foreign matter, non-dispersed raw material, factory splices, or other conditions that might affect serviceability. Edges of seams must be straight and flat so that they may be seamed to one another without forming fish mouths or wrinkles. Discard damaged or defective materials.

3.2.6 Substrate Preparation

Apply membrane to clean, dry surfaces only. Do not apply membrane to surfaces that have been wet by rain or frozen precipitation within the previous 12 hours. Provide cleaning and artificial drying as necessary to ensure clean, dry surface prior to membrane application.
Open flame operations are not allowed.

3.3 APPLICATION

Apply roofing materials as specified herein unless approved otherwise by the Contracting Officer. Keep roofing materials dry before and during application. Complete application of roofing in a continuous operation. Begin and apply only as much roofing in one day as can be completed that same day. Maintain specified temperatures for asphalt. Provide temporary roofing and flashing as specified herein prior to application of permanent roofing system.

3.3.1 Phased Membrane Construction

Phased application of membrane plies is prohibited unless otherwise approved by the Contracting Officer and supported by the membrane manufacturer's written application instructions. If cap sheet installation is delayed, thoroughly clean the applied membrane material surface and dry immediately prior to cap sheet installation. Priming of the applied membrane surface may be required at the discretion of the Contracting Officer prior to cap sheet installation.

3.3.2 Temporary Roofing and Flashing

Provide watertight temporary roofing and flashing where considerable work by other trades, such as installing cooling towers, antennas, pipes, ducts, and to other items shown in the construction documents, is to be performed on the roof or where construction scheduling or weather conditions require protection of the building's interior before permanent roofing system can be installed. Do not install temporary roofing over permanently installed insulation. Provide rigid pads for traffic over temporary roofing.

3.3.2.1 Removal

Completely remove temporary roofing and flashing before continuing with

application of the permanent roofing system.

3.3.3 Application Method

3.3.3.1 Hot Asphalt Application of Modified Bitumen Membrane

Apply membrane immediately following application of hot asphalt. Apply hot asphalt within 6 foot of roll. Do not work ahead with asphalt. Asphalt must be completely fluid, with mop temperatures within the asphalt's EVT range, but not less than 400 degrees F, at the instant membrane comes into contact with asphalt. Apply bitumen between layers to provide full, continuous, uniform coverage and complete contact of hot asphalt with the sheet above and below. Embed sheets in asphalt. As sheets are being rolled into hot asphalt, immediately and thoroughly apply uniform positive pressure by squeegee, roll, or broom to ensure full adhesion and lap seal, eliminate trapped air and to provide tight, smooth laminations. Avoid excessive extrusion of asphalt at lap areas. Control asphalt bleed out to approximately 1 inch maximum.

3.3.4 Ventilating Base Sheets

Apply ventilating base sheets with 3 inch side laps and 6 inch end laps in accordance with manufacturer's printed application instructions for substrate and wind uplift conditions specified. Provide mechanical attachments as required for wind resistance specified and to include increased frequency of attachment at corner and perimeter areas. Drive fasteners flush with no dishing or cupping of fastener plate. Top mop perforated sheet with a full, continuous mopping of hot asphalt.

3.3.5 Fiberglass Felt Modified Bitumen Base Sheet

Fully adhere base sheets in accordance with membrane manufacturer's printed instructions. Roll and broom in the base sheet to ensure full contact with the hot asphalt application. On nailable substrates, mechanically fasten base sheet in conformance with specified wind resistance requirements and membrane manufacturer's printed instructions, and to include increased fastening frequency in corner and perimeter areas. Drive fasteners flush with no dishing or cupping of fastener plate. Where applicable, mechanically fasten base sheet in conjunction with insulation to the substrate, in accordance with membrane manufacturers printed instructions. Apply sheets in a continuous operation. Apply sheets with side laps at a minimum of 2 inch unless greater side lap is recommended by the manufacturer's standard written application instructions. Provide end laps of not less than 6 inch and staggered a minimum of 36 inch. Apply sheets at right angles to the roof slope so that the direction of water flow is over and not against the laps so that plies of sheets extend from eave line on one side of the barrel-type roof and 18 inch over the center line of the crown of the roof. Apply sheets on the other side in the same manner, resulting in twice the normal amount of roofing sheets and asphalt at the crown. Extend base sheets approximately 2 inch above the top of cant strips at vertical surfaces and to the top of cant strips elsewhere. Trim base sheet to a neat fit around vent pipes, roof drains, and other projections through the roof. Application must be free of ridges, wrinkles, and buckles.

3.3.6 Modified Bitumen Membrane Application

Ensure proper sheet alignment prior to installation. Apply membrane layers perpendicular to slope of roof in shingle fashion to shed water, including

application on areas of tapered insulation that change slope direction. Bucking or backwater laps are prohibited. Fully adhere membrane sheets to underlying substrate materials. Provide minimum 3 inch side laps and minimum 6 inch end laps and as otherwise required by membrane manufacturer. Stagger end laps minimum 36 inch. Offset side laps between membrane layers a minimum of 12 inch. Offset end laps between membrane layers a minimum of 36 inch. Install all membrane layers the same workday, unless supported otherwise by roof membrane manufacturer application instructions and approved by the Contracting Officer. Provide tight smooth laminations of each membrane layer without wrinkles, ridges, buckles, kinks, fishmouths, or voids. Ensure full membrane adhesion and full lap seals. Rework to seal any open laps prior to application of subsequent membrane layers. The completed membrane application must be free of surface abrasions, air pockets, blisters, ridges, wrinkles, buckles, kinks, fishmouths, voids, or open seams.

3.3.6.1 Cap Sheet Installation

Underlying applied membrane must be inspected and repaired free of damage, holes, puncture, gouges, abrasions, and any other defects, and free of moisture, loose materials, debris, sediments, dust, and any other conditions required by the membrane manufacturer prior to cap sheet installation. Do not apply cap sheet if rain or frozen precipitation has occurred within the previous 24 hours. Align cap membrane and apply by the specified method with the proper side and end lap widths. Set cap sheet in hot asphalt apply as recommended by the modified bitumen membrane manufacturer when the roof deck and materials used in the installation of the roofing system are non-combustible. Cut at a 45 degree angle across selvage edge of cap membrane to be overlapped in end lap areas prior to applying overlapping cap membrane. Apply matching granules in any areas of bitumen bleed out while the asphalt is still hot . Minimize traffic on newly installed cap sheet membrane.

3.3.6.2 Backnailing of Cap Sheet

Unless otherwise recommended by the modified bitumen membrane manufacturer and approved by the Contracting Officer, provide minimum 3-1/2 inch wide nailing strips matching insulation thickness and applied perpendicular to roof slope for backnailing of roof membrane. Space nailing strips as recommended by the membrane manufacturer, but not exceeding 16 foot on center unless approved otherwise by the Contracting Officer. Coordinate the nailer installation with insulation requirements. Install the modified bitumen cap sheet to provide for end laps at nailer locations. Nail the modified bitumen cap sheet at the end lap area across the width of the sheet. Nail within 1 inch of each edge of the sheet and at 8 inch to 8-1/2 inch on center across the width of the sheet in a staggered fashion. Nails must have 1 inch diameter metal cap or be nailed through 1 inch diameter caps. Cover nails by overlapping adjacent upslope sheet at the end lap area.

3.3.7 Membrane Flashing

Apply two-ply modified bitumen strip flashing and sheet flashing in the angles formed where the roof deck abuts walls, curbs, ventilators, pipes, and other vertical surfaces, and where necessary to make the work watertight. Apply membrane flashing in accordance with the roof membrane manufacturers printed instructions and as specified. Cut at a 45 degree angle across terminating end lap area of cap membrane prior to applying adjacent overlapping cap membrane. Press flashing into place to ensure

full adhesion and avoid bridging. Ensure full lap seal in all lap areas. Mechanically fasten top edge of modified bituminous base flashing 150 mm (6 inches) on center through minimum 1 inch diameter tin caps with fasteners of sufficient length to embed minimum one inch into attachment substrate. Apply matching granules in any areas of asphalt bleed out while the asphalt is still hot . Apply membrane liner over top of exposed nailers and blocking and to overlap top edge of base flashing installation at curbs, parapet walls, expansion joints and as otherwise indicated to serve as waterproof lining under sheet metal flashing components. Metal flashing per SMACNA 1793 guidelines and standards is specified under Section 07 60 00 FLASHING AND SHEET METAL. Do not set metal flashing in hot asphalt.

3.3.7.1 Membrane Strip Flashing

Set primed flanges of metal flashing in full bed of modified bituminous cement material and securely fasten through to attachment substrate. Strip-in with membrane flashing so that strip extends not less than 4 inch beyond outer edge of flange. Where multiple membrane stripping plies are installed, extend each additional stripping ply minimum 4 inch beyond edge of previous ply.

3.3.7.2 Membrane Flashing at Roof Drain

Roof drains are specified in Section 22 00 00 PLUMBING, GENERAL PURPOSE. Flashing for roof drains, is specified in Section 07 60 00 FLASHING AND SHEET METAL. Extend membrane sheets to edge of drain bowl opening at the roof drain deck flange in accordance with membrane manufacturer's printed application instructions. Securely clamp membrane sheets and metal roof drain flashing and strip flashing in the flashing clamping ring. Secure clamps so that sheets and metal flashing are free from wrinkles and folds. Trim stripping must be flush with inside of clamping ring.

3.3.7.3 Pre-fabricated Curbs

Securely anchor prefabricated curbs to nailer or other base substrate and flash with modified bitumen membrane.

3.3.7.4 Set-On Accessories

Where pipe or conduit blocking, supports and similar roof accessories are set on the membrane, adhere walkpad material to bottom of accessories prior to setting on roofing membrane. Install set-on accessories to permit normal movement due to expansion, contraction, vibration, and similar occurrences without damaging roofing membrane. Do not mechanically secure set-on accessories through roofing membrane into roof deck substrate.

3.3.7.5 Lightning Protection

Flash and attach lightning protection system components to the roof membrane in a manner acceptable to the roof membrane manufacturer.

3.3.8 Roof Walkpads

Install walkpads at roof access points and where otherwise indicated for traffic areas and for access to mechanical equipment, in accordance with the modified bitumen sheet roofing manufacturer's printed instructions. Provide minimum 6 inch separation between adjacent walkpads to accommodate drainage. Provide walkpad or an additional layer of cap sheet under precast concrete paver blocks to protect the roofing.

3.3.9 Elevated Metal Walkways and Platforms

Install over completed roof system in accordance with Section 05 50 13 MISCELLANEOUS METAL FABRICATIONS,or Section 05 51 33 METAL LADDERS, or Section 05 52 00 METAL RAILINGS, orSection 05 51 00 METAL STAIRS, or other construction documents. Provide for protection of roof membrane by placing walkpad material, or other material approved by the Contracting Officer, at all surface bearing support locations.

3.3.10 Paver Blocks

Install paver blocks where indicated and as necessary to support surface bearing items traversing the roof area. Set paver block on a layer of walkpad or cap sheet applied over the completed roof membrane.

3.3.11 Field Applied Surfacing

After completion of roof membrane and flashing installation, and correction of tears, gouges, and other deficiencies in the installed work, apply specified surfacing.

3.3.11.1 Aggregate

Uniformly flood coat the surface with hot asphalt at a rate of approximate 60 pounds per square. While asphalt is still hot, apply gravel aggregate surfacing material at a rate of 400 pounds per square or 300 pounds per square for slag or other approved aggregate surfacing. Provide for full and uniform coverage of the roof surface. Solidly adhere approximately 50 percent of the aggregate in the asphalt.

3.3.11.2 Coating Application

Apply surface coating materials to membrane and flashing in accordance with coating material manufacturer's recommendations.

3.3.12 Correction of Deficiencies

Where any form of deficiency is found, take additional measures as deemed necessary by the Contracting Officer to determine the extent of the deficiency and perform corrective actions as directed by the Contracting Officer.

3.3.13 Clean Up

Remove debris, scraps, containers and other rubbish and trash resulting from installation of the roofing system from job site each day.

3.4 CORRECTION OF DEFICIENCIES

Where any form of deficiency is found, take additional measures as deemed necessary by the Contracting Officer to determine the extent of the deficiency and perform corrective actions as directed by the Contracting Officer.

3.5 PROTECTION OF APPLIED ROOFING

At the end of the day's work and when precipitation is imminent, protect applied modified bitumen roofing system from water intrusion.

3.5.1 Water Cutoffs

Straighten insulation line using loose-laid cut insulation sheets and seal the terminated edge of modified bitumen roofing system in an effective manner. Seal off flutes in metal decking along the cutoff edge. Remove the water cut-offs to expose the insulation when resuming work, and remove the insulation sheets used for fill-in.

3.5.2 Temporary Flashing for Permanent Roofing

Provide temporary flashing at drains, curbs, walls and other penetrations and terminations of roofing sheets until permanent flashing can be applied. Remove temporary flashing before applying permanent flashing.

3.5.3 Temporary Walkways, Runways, and Platforms

Do not permit storing, walking, wheeling, and trucking directly on applied roofing materials. Provide temporary walkways, runways, and platforms of smooth clean boards, mats or planks as necessary to avoid damage to applied roofing materials, and to distribute weight to conform to live load limits of roof construction. Use rubber-tired equipment for roofing work.

3.6 FIELD QUALITY CONTROL

Perform field tests in the presence of the Contracting Officer. Notify the Contracting Officer one day before performing tests.

3.6.1 Test for Surface Dryness

Before application of membrane sheets and starting work on the area to be roofed, perform test for surface dryness in accordance with the following:

a. Foaming: When poured on the surface to which membrane materials are to be applied, one pint of asphalt when heated in the range of 350 to 400 degrees F, must not foam upon contact.

b. Strippability: On cementitious substrate surfaces, after asphalt used in the foaming test application has cooled to ambient temperatures, test coating for adherence. Should a portion of the sample be readily stripped clean from the surface, do not consider the surface to be dry and do not start application. Should rain occur during application, stop work and do not resume until surface has been tested by the method above and found dry.

c. Prior to installing any roof system on a concrete deck, conduct a test per ASTM D4263. The deck is acceptable for roof system application when there is no visible moisture on underside of plastic sheet after 24 hours.

3.6.2 Construction Monitoring

During progress of the roof work, make visual inspections as necessary to ensure compliance with specified parameters. Additionally, verify the following:

a. Materials comply with the specified requirements.

b. Materials are not installed in adverse weather conditions.

All materials are properly stored, handled and protected from moisture or other damages.

c. Equipment is in working order. Metering devices are accurate.

d. Substrates are in acceptable condition, in compliance with specification, prior to application of subsequent materials.

(1) Nailers and blocking are provided where and as needed.

Insulation substrate is smooth, properly secured to its substrate, and without excessive gaps prior to membrane application.

(2) The proper number, type, and spacing of fasteners are installed.

Membrane heating, hot mopping, or adhesive application is provided uniformly and as necessary to ensure full adhesion of roll materials. Asphalt is heated and applied within the specified temperature range.

The proper number and types of plies are installed, with the specified overlaps.

Applied membrane surface is inspected, cleaned, dry, and repaired as necessary prior to cap sheet installation.

(3) Lap areas of all plies are completely sealed.

Membrane is fully adhered without ridges, wrinkles, kinks, fishmouths, or other voids or delaminations.

Installer adheres to specified and detailed application parameters.

Associated flashing and sheet metal are installed in a timely manner in accord with the specified requirements.

Temporary protection measures are in place at the end of each work shift.

3.6.2.1 Manufacturer's Inspection

Manufacturer's technical representative must visit the site a minimum of once per week during the installation for purposes of reviewing materials installation practices and adequacy of work in place.
Inspections must occur during the first 20 squares of membrane installation, at mid-point of the installation, and at substantial completion, at a minimum. Additional inspections must not exceed one for each 100 squares of total roof area with the exception that follow-up inspections of previously noted deficiencies or application errors must be performed as requested by the Contracting Officer. After each inspection, submit a report, signed by the manufacturer's technical representative to the Contracting Officer within 3 working days. Note in the report overall quality of work, deficiencies and any other concerns, and recommended corrective action.

]3.6.3 Samples of Roofing

Take samples per ASTM D5147/D5147M, sized 4-inch by 40-inch cut across

width of modified bitumen sheets as directed by the Contracting Officer. Cut samples will be examined by the Contracting Officer for specified number of plies, proper lap width, complete lap seal, full uniform adhesive compound application and adhesion, full bond between plies, harmful foreign materials, presence of moisture, and wet insulation. Where cuts are not retained by the Contracting Officer or disposed, set cut strip back in cut area in bed of modified bitumen cement. Repair area of cut with new minimum two-ply modified bitumen membrane patch.

3.6.4 Roof Drain Test

After completing roofing, but prior to Government acceptance, perform the following test for watertight integrity. Plug roof drains and fill with water to edge of drain sump for 8 hours. Do not plug secondary overflow drains at the same time as adjacent primary drain. To ensure some drainage from roof, do not test all drains at same time. Measure water at beginning and end of the test period. When precipitation occurs during test period, repeat test. When water level falls, remove water, thoroughly dry, and inspect installation; repair or replace roofing at drain to provide for a properly installed watertight flashing seal. Repeat test until there is no water leakage.

3.7 INSTRUCTIONS TO GOVERNMENT PERSONNEL

Furnish written and verbal instructions on proper maintenance procedures to designated Government personnel. Furnish instructions by a competent representative of the modified bitumen membrane manufacturer and include a minimum of 4 hours on maintenance and emergency repair of the membrane. Include a demonstration of membrane repair, and give sources of required special tools. Furnish information on safety requirements during maintenance and emergency repair operations.

3.8 INFORMATION CARD

For each roof, furnish a typewritten information card for facility Records and a card laminated in plastic and framed for interior display at roof access point, or a photoengraved 0.039 inch thick aluminum card for exterior display. Card must be 8 1/2 by 11 inch minimum, identifying facility name and number; location; contract number; approximate roof area; detailed roof system description, including deck type, membrane, number of plies, method of application, manufacturer, insulation and cover board system and thickness; presence of tapered insulation for primary drainage, presence of vapor retarder; date of completion; installing contractor identification and contact information; membrane manufacturer warranty expiration, warranty reference number, and contact information. Install card at roof top or access location as directed by the Contracting Officer and provide a paper copy to the Contracting Officer.

-- End of Section --

SECTION 07 60 00

FLASHING AND SHEET METAL
05/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.2/D1.2M	(2014; Errata 1 2014; Errata 2 2020) Structural Welding Code - Aluminum

ASTM INTERNATIONAL (ASTM)

ASTM A480/A480M	(2020a) Standard Specification for General Requirements for Flat-Rolled Stainless and Heat-Resisting Steel Plate, Sheet, and Strip
ASTM A653/A653M	(2020) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B32	(2008; R 2014) Standard Specification for Solder Metal
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B221	(2014) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B370	(2012; R 2019) Standard Specification for Copper Sheet and Strip for Building Construction
ASTM D41/D41M	(2011; R 2016) Standard Specification for Asphalt Primer Used in Roofing, Dampproofing, and Waterproofing
ASTM D1784	(2020) Standard Specification for Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D4586/D4586M	(2007; E 2012; R 2012) Asphalt Roof Cement, Asbestos-Free

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1793	(2012) Architectural Sheet Metal Manual, 7th Edition

SINGLE PLY ROOFING INDUSTRY (SPRI)

ANSI/SPRI RD-1	(2014) Performance Standard for Retrofit Drains

1.2 GENERAL REQUIREMENTS

Finished sheet metal assemblies must form a weathertight enclosure without waves, warps, buckles, fastening stresses or distortion, while allowing for expansion and contraction without damage to the system. The sheet metal installer is responsible for cutting, fitting, drilling, and other operations in connection with sheet metal modifications required to accommodate the work of other trades. Coordinate installation of sheet metal items used in conjunction with roofing, openings (Windows, Louvers, Doors, roof and wall penetrations, curbs, expansion joints, etc.) work to permit continuous, uninterrupted building operations.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Exposed Sheet Metal Coverings; G

Gutters; G

Downspouts; G

Expansion Joints; G

Gravel Stops and fascia; G

Splash Pans; G

Flashing for Roof Drains; G

Base Flashing; G

Counterflashing; G

Flashing at Roof Penetrations and Equipment Supports; G

Reglets; G

Scuppers; G

Copings; G

Drip Edges; G

Conductor Heads; G

Open Valley Flashing; G

Eave Flashing; G

One-piece window and louver Flashing; G

Exterior walls through flashings; G

SD-03 Product Data

Materials Data; G

SD-04 Samples

Finish Samples for color selection; G

SD-08 Manufacturer's Instructions

Instructions for Installation; G

Quality Control Plan; G

SD-10 Operation and Maintenance Data

Cleaning and Maintenance; G

1.4 MISCELLANEOUS REQUIREMENTS

1.4.1 Product Data

Indicate thicknesses, dimensions, fastenings, anchoring methods, expansion joints, and other provisions necessary for thermal expansion and contraction. Scaled manufacturer's catalog data may be submitted for factory fabricated items.

1.4.2 Finish Samples

Submit two color charts and two finish sample chips from manufacturer's standard color and finish options for each type of finish indicated.

1.4.3 Operation and Maintenance Data

Submit detailed instructions for installation and quality control during installation, cleaning and maintenance, for each type of assembly indicated.

1.5 DELIVERY, HANDLING, AND STORAGE

Package and protect materials during shipment. Uncrate and inspect materials for damage, dampness, and wet-storage stains upon delivery to the job site. Remove from the site and replace damaged materials that cannot

be restored to like-new condition. Handle sheet metal items to avoid damage to surfaces, edges, and ends. Store materials in dry, weather-tight, ventilated areas until installation.

PART 2 PRODUCTS

2.1 RECYCLED CONTENT

Provide products with recycled content. Provide data for each product with recycled content, identifying percentage of recycled content.

2.2 MATERIALS

Do not use lead, lead-coated metal, or galvanized steel. Use any metal listed by SMACNA 1793 for a particular item, unless otherwise indicated. Provide materials, thicknesses, and configurations in accordance with SMACNA 1793 for each material. Contact between dissimilar metals must be avoided.

Furnish sheet metal items in 8 to 10 foot lengths. Single pieces less than 8 feet long may be used to connect to factory-fabricated inside and outside corners, and at ends of runs. Factory fabricate corner pieces with minimum 12 inch legs. Provide accessories and other items essential to complete the sheet metal installation. Provide accessories made of the same or compatible materials as the items to which they are applied. Fabricate sheet metal items of the materials specified below and to the gage, thickness, or weight shown in Table I at the end of this section. Provide sheet metal items with mill finish unless specified otherwise. Where more than one material is listed for a particular item in Table I, each is acceptable and may be used, except as follows:

2.2.1 Exposed Sheet Metal Items

Must be of the same material. Consider the following as exposed sheet metal: gutters, including hangers; downspouts; gravel stops and fascia; cap, valley, steeped, base, eave flashings, through wall penetrations, flashing for openings (head, jambs and sill), penetration hoods, etc. and related accessories.

2.2.2 Drainage

Do not use copper for an exposed item if drainage from that item will pass over exposed masonry, stonework or other metal surfaces. In addition to the metals listed in Table I, lead-coated copper may be used for such items.

2.2.3 Copper, Sheet and Strip

Provide in accordance with ASTM B370, cold-rolled temper, H 00 (standard).

2.2.4 Steel Sheet, Zinc-Coated (Galvanized)

Provide in accordance with ASTM A653/A653M.

2.2.5 Stainless Steel

Provide in accordance with ASTM A480/A480M, Type 302 or 304, 2D Finish, fully annealed, dead-soft temper.

2.2.6 Aluminum Alloy Sheet and Plate

Provide in accordance with ASTM B209 anodized color as selected by the Architect from the manufacturer's standard color wheel form alloy, and temper appropriate for use. Provide material not less than 0.032-in] in thickness.

2.2.6.1 Alclad

When fabricated of aluminum, fabricate the following items with Alclad 3003, Alclad 3004, or Alclad 3005, clad on both sides unless otherwise indicated.

a. Gutters, downspouts, and hangers

b. Gravel stops and fascia

c. Flashing

2.2.7 Finishes

Provide exposed exterior sheet metal and aluminum with a baked on, factory applied color coating of polyvinylidene fluoride (PVF2) or approved equal fluorocarbon coating. Dry film thickness of coatings must be 0.8 to 1.3 mils. Color to be selected from manufacturer's standard range of color choicesmanufacturer's full range of color choices. Field applications of color coatings are prohibited and will be rejected.

2.2.8 Aluminum Alloy, Extruded Bars, Rods, Shapes, and Tubes

ASTM B221.

2.2.9 Solder

Provide in accordance with ASTM B32, 95-5 tin-antimony.

2.2.10 Reglets

2.2.10.1 Polyvinyl Chloride Reglets

Provide in accordance with ASTM D1784, Type II, Grade 1, Class 14333-D, 0.075 inch minimum thickness.

2.2.10.2 Metal Reglets

Provide factory fabricated caulked type or friction type reglets with a minimum opening of 1/4 inch and a depth of 1-1/4 inch, as approved.

2.2.10.2.1 Caulked Reglets

Provide with rounded edges, temporary reinforcing cores, and accessories as required for securing to adjacent construction. Provide built-up mitered corner pieces for inside and outside corners.

2.2.10.2.2 Friction Reglets

Provide with flashing receiving slots not less than 5/8 inch deep, one inch jointing tongues, and upper and lower anchoring flanges installed at 24 inch maximum snap-lock type receiver.

2.2.11 Conductor Heads

Provide conductor heads and screens in the same material as downspouts. Provide outlet tubes not less than 4 inches long.

2.2.12 Splash Pans

Provide splash pans where downspouts discharge onto roof surfaces and at locations indicated. Unless otherwise indicated, provide pans not less than 24 inches long by 18 inches wide with metal ribs across bottoms of pans. Provide sides of pans with vertical baffles not less than one inch high in the front, and 4 inches high in the back.

2.2.13 Copings

Unless otherwise indicated, provide copings in copper sheets, 8 or 10 feet long, joined by a 3/4 inch locked and soldered seam.

2.2.14 Bituminous Plastic Cement

Provide in accordance with ASTM D4586/D4586M, Type I.

2.2.15 Asphalt Primer

Provide in accordance with ASTM D41/D41M.

2.2.16 Fasteners

Use the same metal as, or a metal compatible with the item fastened. Use stainless steel fasteners to fasten. Confirm compatibility of fasteners and items to be fastened to avoid galvanic corrosion due to dissimilar materials.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Workmanship

Make lines and angles sharp and true. Free exposed surfaces from visible wave, warp, buckle, and tool marks. Fold back exposed edges neatly to form a 1/2 inch hem on the concealed side. Make sheet metal exposed to the weather watertight with provisions for expansion and contraction.

Make surfaces to receive sheet metal plumb and true, clean, even, smooth, dry, and free of defects and projections. For installation of items not shown in detail or not covered by specifications conform to the applicable requirements of SMACNA 1793, Architectural Sheet Metal Manual. Provide sheet metal flashing in the angles formed where roof decks abut walls, curbs, ventilators, pipes, or other vertical surfaces and wherever indicated and necessary to make the work watertight. Join sheet metal items together as shown in Table II.

3.1.2 Cleats

Provide cleats for sheet metal 18 inches and over in width. Space cleats evenly not over 12 inches on center unless otherwise specified or indicated. Unless otherwise specified, provide cleats of 2 inches wide by

3 inches long and of the same material and thickness as the sheet metal being installed. Secure one end of the cleat with two nails and the cleat folded back over the nailheads. Lock the other end into the seam. Where the fastening is to be made to concrete or masonry, use screws and drive in expansion shields set in concrete or masonry. Pre-tin cleats for soldered seams.

3.1.3 Bolts, Rivets, and Screws

Install bolts, rivets, and screws where indicated or required. Provide compatible washers where required to protect surface of sheet metal and to provide a watertight connection. Provide mechanically formed joints in aluminum sheets 0.040 inches or less in thickness.

3.1.4 Seams

Straight and uniform in width and height with no solder showing on the face.

3.1.4.1 Lap Seams

Finish soldered seams not less than one inch wide. Overlap seams not soldered, not less than 3 inches.

3.1.4.2 Loose-Lock Expansion Seams

Not less than 3 inches wide; provide minimum one inch movement within the joint. Completely fill the joints with the specified sealant, applied at not less than 1/8 inch thick bed.

3.1.5 Soldering

Where soldering is specified, apply to copper, terne-coated stainless steel, zinc-coated steel, and stainless steel items. Pre-tin edges of sheet metal before soldering is begun. Seal the joints in aluminum sheets of 0.040 inch or less in thickness with specified sealants. Do not solder aluminum.

3.1.5.1 Edges

Scrape or wire-brush the edges of lead-coated material to be soldered to produce a bright surface. Flux brush the seams in before soldering. Treat with soldering acid flux the edges of stainless steel to be pre-tinned. Seal the joints in aluminum sheets of 0.040 inch or less in thickness with specified sealants. Do not solder aluminum.

3.1.6 Welding and Mechanical Fastening

Use welding for aluminum of thickness greater than 0.040 inch. Aluminum 0.040 inch or less in thickness must be butted and the space backed with formed flashing plate; or lock joined, mechanically fastened, and filled with sealant as recommended by the aluminum manufacturer.

3.1.6.1 Welding of Aluminum

Use welding of the inert gas, shield-arc type. For procedures, appearance and quality of welds, and the methods used in correcting welding work, conform to AWS D1.2/D1.2M.

3.1.6.2 Mechanical Fastening of Aluminum

Use No. 12, aluminum alloy, sheet metal screws or other suitable aluminum alloy or stainless steel fasteners. Drive fasteners in holes made with a No. 26 drill in securing side laps, end laps, and flashings. Space fasteners 12 inches maximum on center. Where end lap fasteners are required to improve closure, locate the end lap fasteners not more than 2 inches from the end of the overlapping sheet.

3.1.7 Protection from Contact with Dissimilar Materials

3.1.7.1 Copper or Copper-bearing Alloys

Paint with heavy-bodied bituminous paint surfaces in contact with dissimilar metal, or separate the surfaces by means of moistureproof building felts.

3.1.7.2 Aluminum

Do not allow aluminum surfaces in direct contact with other metals except stainless steel, zinc, or zinc coating. Where aluminum contacts another metal, paint the dissimilar metal with a primer followed by two coats of aluminum paint. Where drainage from a dissimilar metal passes over aluminum, paint the dissimilar metal with a non-lead pigmented paint.

3.1.7.3 Metal Surfaces

Paint surfaces in contact with mortar, concrete, or other masonry materials with alkali-resistant coatings such as heavy-bodied bituminous paint.

3.1.7.4 Wood or Other Absorptive Materials

Paint surfaces that may become repeatedly wet and in contact with metal with two coats of aluminum paint or a coat of heavy-bodied bituminous paint.

3.1.8 Expansion and Contraction

Provide expansion and contraction joints at not more than 32 foot intervals for aluminum and at not more than 40 foot intervals for other metals. Provide an additional joint where the distance between the last expansion joint and the end of the continuous run is more than half the required interval. Space joints evenly. Join extruded aluminum gravel stops and fascia by expansion and contraction joints spaced not more than 12 feet apart.

3.1.9 Base Flashing

Lay the base flashings with each course of the roof covering, shingle fashion, where practicable, where sloped roofs abut chimneys, curbs, walls, or other vertical surfaces. Extend up vertical surfaces of the flashing not less than 8 inches and not less than 4 inches under the roof covering. Where finish wall coverings form a counterflashing, extend the vertical leg of the flashing up behind the applied wall covering not less than 6 inches. Overlap the flashing strips with the previously laid flashing not less than 3 inches. Fasten the strips at their upper edge to the deck. Horizontal flashing at vertical surfaces must extend vertically above the roof surface and fastened at their upper edge to the deck a minimum of 6 inches on center with large headed stainless steel screws a minimum of 2 inch lap of any surface. Solder end laps and provide for expansion and contraction.

Extend the metal flashing over crickets at the up-slope side of curbs, and similar vertical surfaces extending through sloping roofs, the metal flashings. Extend the metal flashings onto the roof covering not less than 4.5 inches at the lower side of vertical surfaces extending through the roof decks. Install and fit the flashings so as to be completely weathertight. Provide factory-fabricated base flashing for interior and exterior corners.

3.1.10 Counterflashing

Except where indicated or specified otherwise, insert counterflashing in reglets located from 9 to 10 inches above roof decks, extend down vertical surfaces over upturned vertical leg of base flashings not less than 3 inches. Fold the exposed edges of counterflashings 1/2 inch. Where stepped counterflashings are required, they may be installed in short lengths a minimum 8 inches by 8 inches or may be of the preformed single piece type. Provide end laps in counterflashings not less than 3 inches and make it weathertight with plastic cement. Do not make lengths of metal counterflashings exceed 10 feet. Form flashings to the required shapes before installation. Factory form corners not less than 12 inches from the angle. Secure the flashings in the reglets with lead wedges and space not more than 18 inches apart; short runs, place wedges closer together. Fill caulked-type reglets or raked joints which receive counterflashing with caulking compound. Turn up the concealed edge of counterflashings built into masonry or concrete walls not less than 1/4 inch and extend not less than 2 inches into the walls. Install counterflashing to provide a spring action against base flashing. Where bituminous base flashings are provided, extend down the counter flashing as close as practicable to the top of the cant strip. Factory form counter flashing to provide spring action against the base flashing.

3.1.11 Metal Reglets

Keep temporary cores in place during installation. Ensure factory fabricated caulked type or friction type, reglets have a minimum opening of 1/4 inch and a minimum depth of 1-1/4 inch, when installed.

3.1.11.1 Caulked Reglets

Wedge flashing in reglets with lead wedges every 18 inches, caulked full and solid with an approved compound.

3.1.11.2 Friction Reglets

Install flashing snap lock receivers at 24 inches on center maximum. When flashing has been inserted the full depth of the slot, caulk the slot, lock , and fill with sealant.

3.1.12 Polyvinyl Chloride Reglets for Temporary Construction

Rigid polyvinyl chloride reglets may be provided in lieu of metal reglets for temporary construction.

3.1.13 Gravel Stops and fascia

Prefabricate in the shapes and sizes indicated and in lengths not less than 8 feet. Extend flange at least 4 inches onto roofing. Provide prefabricated, mitered corners internal and external corners. Install gravel stops and fascia after all plies of the roofing membrane have been

applied, but before the flood coat of bitumen is applied. Prime roof flange of gravel stops and fascia on both sides with an asphalt primer. After primer has dried, set flange on roofing membrane and strip-in. Nail flange securely to wood nailer with large-head, barbed-shank roofing nails 1.5 inch long spaced not more than 3 inches on center, in two staggered rows.

3.1.13.1 Edge Strip

Hook the lower edge of fascia at least 3/4 inch over a continuous strip of the same material bent outward at an angle not more than 45 degrees to form a drip. Nail hook strip to a wood nailer at 6 inches maximum on center. Where fastening is made to concrete or masonry, use screws spaced 12 inches on center driven in expansion shields set in the concrete or masonry. Where horizontal wood nailers are slotted to provide for insulation venting, install strips to prevent obstruction of vent slots. Where necessary, install strips over 1/16 inch thick compatible spacer or washers.

3.1.13.2 Joints

Leave open the section ends of gravel stops and fascia 1/4 inch and backed with a formed flashing plate, mechanically fastened in place and lapping each section end a minimum of 4 inches set laps in plastic cement. Face nailing will not be permitted. Install prefabricated aluminum gravel stops and fascia in accordance with the manufacturer's printed instructions and details.

3.1.14 Metal Drip Edges

Provide a metal drip edge, designed to allow water run-off to drip free of underlying construction, at eaves and rakes prior to the application of roofing shingles. Apply directly on the wood deck at the eaves and over the underlay along the rakes. Extend back from the edge of the deck not more than 3 inches and secure with compatible nails spaced not more than 10 inches on center along upper edge.

3.1.15 Gutters

The hung type of shape indicated and supported on underside by brackets that permit free thermal movement of the gutter. Provide gutters in sizes indicated complete with mitered corners, end caps, outlets, brackets, and other accessories necessary for installation. Bead with hemmed edge or reinforce the outer edge of gutter with a stiffening bar not less than 3/4 by 3/16 inch of material compatible with gutter. Fabricate gutters in sections not less than 8 feet. Lap the sections a minimum of one inch in the direction of flow or provide with concealed splice plate 6 inches minimum. Join the gutters, other than aluminum, by riveted and soldered joints. Join aluminum gutters with riveted sealed joints. Provide expansion-type slip joints midway between outlets. Install gutters below slope line of the roof so that snow and ice can slide clear. Support gutters on adjustable hangers spaced not more than 30 inches on center by continuous cleats and or by cleats spaced not less than 36 inches apart. Adjust gutters to slope uniformly to outlets, with high points occurring midway between outlets. Fabricate hangers and fastenings from compatible metals.

3.1.16 Downspouts

Space supports for downspouts according to the manufacturer's

recommendation for the substrate. Types, shapes and sizes are indicated. Provide complete including elbows and offsets. Provide downspouts in approximately 10 foot lengths. Provide end joints to telescope not less than 1/2 inch and lock longitudinal joints. Provide gutter outlets with wire ball strainers for each outlet. Provide strainers to fit tightly into outlets and be of the same material used for gutters. Keep downspouts not less than one inch away from walls. Fasten to the walls at top, bottom, and at an intermediate point not to exceed 5 feet on center with leader straps or concealed rack-and-pin type fasteners. Form straps and fasteners of metal compatible with the downspouts.

3.1.16.1 Terminations

Neatly fit into the drainage connection the downspouts terminating in drainage lines and fill the joints with a portland cement mortar cap sloped away from the downspout. Provide downspouts terminating in splash blocks with elbow-type fittings. Provide splash pans as specified.

3.1.17 Flashing for Roof Drains

Provide a 30 inches square sheet indicated. Taper insulation to drain from 24 inches out. Set flashing on finished felts in a full bed of asphalt roof cement, ASTM D4586/D4586M. Heavily coat the drain flashing ring with asphalt roof cement. Clamp the roof membrane, flashing sheet, and stripping felt in the drain clamping ring. Secure clamps so that felts and drain flashing are free of wrinkles and folds. Retrofit roof drains must conform to ANSI/SPRI RD-1.

3.1.18 Conductor Heads

Set the depth of the top opening equal to two-thirds of the width or the conductor head. Flat-lock solder seams. Where conductor heads are used in conjunction with scuppers, set the conductor a minimum of 2 inches wider than the scupper. Attach conductor heads to the wall with masonry fasteners. Securely fasten screens to heads.

3.1.19 Splash Pans

Install splash pans lapped with horizontal roof flanges not less than 4 inches wide to form a continuous surface. Bend the rear flange of the pan to contour of can't strip and extend up 6 inches under the side wall covering or to height of base flashing under counterflashing. Bed the pans and roof flanges in plastic bituminous cement and strip-flash as specified.

3.1.20 Eave Flashing

One piece in width, applied in 8 to 10 foot lengths with expansion joints spaced as specified in paragraph EXPANSION AND CONTRACTION. Provide a 3/4 inch continuous fold in the upper edge of the sheet to engage cleats spaced not more than 10 inches on center. Locate the upper edge of flashing not less than 18 inches from the outside face of the building, measured along the roof slope. Fold lower edge of the flashing over and loose-lock into a continuous edge strip on the fascia. Where eave flashing intersects metal valley flashing, secure with one inch flat locked joints with cleats that are 10 inches on center.

3.1.21 Sheet Metal Covering on Flat, Sloped, or Curved Surfaces

Except as specified or indicated otherwise, cover and flash all minor flat,

sloped, or curved surfaces such as crickets, bulkheads, dormers and small decks with metal sheets of the material used for flashing; maximum size of sheets, 16 by 18 inches. Fasten sheets to sheathing with metal cleats. Lock seams and solder. Lock aluminum seams as recommended by aluminum manufacturer. Provide an underlayment of roofing felt for all sheet metal covering.

3.1.22 Expansion Joints

Provide expansion joints as indicated. Provide expansion joints in continuous sheet metal to match existing conditions.

3.1.22.1 Roof Expansion Joints

Consist of curb with wood nailing members on each side of joint, bituminous base flashing, metal counterflashing, and metal joint cover. Bituminous base flashing is specified in Roofing Section. Provide counterflashing as specified in paragraph COUNTERFLASHING, except as follows: Provide counterflashing with vertical leg of suitable depth to enable forming into a horizontal continuous cleat. Secure the inner edge to the nailing member. Make the outer edge projection not less than one inch for flashing on one side of the expansion joint and be less than the width of the expansion joint plus one inch for flashing on the other side of the joint. Hook the expansion joint cover over the projecting outer edges of counterflashing. Provide roof joint with a joint cover of the width indicated. Hook and lock one edge of the joint cover over the shorter projecting flange of the continuous cleat, and the other edge hooked over and loose locked with the longer projecting flange. Joints are specified in Table II.

3.1.23 Flashing at Roof Penetrations and Equipment Supports

Provide metal flashing for all structural components, pipes, ducts, expansion joints, vents, equipment curbs, and conduits projecting through the roof surface and for equipment supports, guy wire anchors, and similar items supported by or attached to the roof deck. Goose-necks, rain hoods, power roof ventilators, and , as indicated.

3.1.24 Single Pipe Vents

See Table I, footnote (d). Set flange of sleeve in bituminous plastic cement and nail 3 inches on center. Bend the top of sleeve over and extend down into the vent pipe a minimum of 2 inches. For long runs or long rises above the deck, where it is impractical to cover the vent pipe with lead, use a two-piece formed metal housing. Set metal housing with a metal sleeve having a 4 inches roof flange in bituminous plastic cement and nailed 3 inches on center. Extend sleeve a minimum of 8 inches above the roof deck and lapped a minimum of 3 inches by a metal hood secured to the vent pipe by a draw band. Seal the area of hood in contact with vent pipe with an approved sealant.

3.1.25 Stepped Flashing

Provide stepped flashing where sloping roofs surfaced with shingles abut vertical surfaces. Place separate pieces of base flashing in alternate shingle courses.

3.2 PAINTING

Touch ups in the field may be applied only after metal substrates have been cleaned and pretreated in accordance with manufacturer's written instructions and products.

Field-paint sheet metal for separation of dissimilar materials.

3.2.1 Aluminum Surfaces

Clean with solvent and apply one coat of zinc-molybdate primer and one coat of aluminum paint.

3.3 CLEANING

Clean exposed sheet metal work at completion of installation. Remove grease and oil films, handling marks, contamination from steel wool, fittings and drilling debris, and scrub-clean. Free the exposed metal surfaces of dents, creases, waves, scratch marks, and solder or weld marks.

3.4 REPAIRS TO FINISH

Scratches, abrasions, and minor surface defects of finish may be repaired in accordance with the manufacturer's printed instructions and as approved. Repair damaged surfaces caused by scratches, blemishes, and variations of color and surface texture. Replace items which cannot be repaired.

3.5 FIELD QUALITY CONTROL

Establish and maintain a Quality Control Plan for sheet metal used in conjunction with roofing to assure compliance of the installed sheet metalwork with the contract requirements. Remove work that is not in compliance with the contract and replace or correct. Include quality control, but not be limited to, the following:

a. Observation of environmental conditions; number and skill level of sheet metal workers; condition of substrate.

b. Verification that specified material is provided and installed.

c. Inspection of sheet metalwork, for proper size(s) and thickness(es), fastening and joining, and proper installation.

3.5.1 Procedure

Submit for approval prior to start of roofing work. Include a checklist of points to be observed. Document the actual quality control observations and inspections. Furnish a copy of the documentation to the Contracting Officer at the end of each day.

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES					
Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch	Terne-Coated Stainless Steel, inch	
Building Expansion Joints					
Cover	16	.032	.015	.015	24
Waterstop-bellow or flanged, U-type.	16	-	.015	.015	-
Covering on minor flat, pitched or curved surfaces	20	.040	.018	.018	-
Downspouts and leaders	16	.032	.015	.015	24
Downspout clips and anchors	-	.040 clip .125 anchor	-	-	-
Downspout straps, 2-inch	48 (a)	.060	.050	-	-
Conductor heads	16	.032	.015	.015	-
	20	.032	.015	.015	-
	No. 9 gage	.144 diameter	.109 diameter	-	
Flashings:					
Base	20	.040	.018	.018	24
Cap (Counter-flashin	16	.032	.015	.015	26
Eave	16	-	.015	.015	24
	10	-	.010	.010	-
Bond barrier	16	-	.015	.015	-
Stepped	16	.032	.015	.015	-
	16	.032	.015	.015	-

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES					
Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch	Terne-Coated Stainless Steel, inch	
Roof drain	16 (b)				
Pipe vent sleave (d)					
	16	-	-	-	-
Extrusions	-	.075	-	-	-
Sheets, corrugated	16	.032	.015	.015	-
Sheets, smooth	20	.050	.018	.018	24
Edge strip	24	.050	.025	-	-
Gutters:					
Gutter section	16	.032	.015	.015	24
Continuous cleat	16	.032	.015	.015	24
Hangers, dimensions	1 inch by 1/8 inch (a)	1 inch by .080 inch (c)	1 inch by inch	-	-
Joint Cover plates (See Table II)	16	.032	.015	.015	24
Reglets (c)	10	-	.010	.010	-
Splash pans	16	.040	.018	.018	-
(a) Brass.					
(b) May be lead weighing 4 pounds per square foot.					
(c) May be polyvinyl chloride.					

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES					
Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch	Terne-Coated Stainless Steel, inch	
(d) 2.5 pound minimum lead sleeve with 4 inch flange. Where lead sleeve is impractical, refer to paragraph SINGLE PIPE VENTS for optional material.					

TABLE II. SHEET METAL JOINTS			
TYPE OF JOINT			
Item Designation	Copper, Terne-Coated Stainless Steel, Zinc-Coated Steel and Stainless Steel	Aluminum	Remarks
Joint cap for building expansion seam, cleated joint at roof	1.25 inch single lock, standing seam, cleated	1.25 inch single lock, standing	--
Flashings			
Base	One inch 3 inch lap for expansion joint	One inch flat locked, soldered; sealed; 3 inch lap for expansion joint	Aluminum manufacturer's recommended hard setting sealant for locked aluminum joints. Fill each metal expansion joint with a joint sealing compound.
Cap-in reglet	3 inch lap	3 inch lap	Seal groove with joint sealing compound.

TABLE II. SHEET METAL JOINTS			
TYPE OF JOINT			
Item Designation	Copper, Terne-Coated Stainless Steel, Zinc-Coated Steel and Stainless Steel	Aluminum	Remarks
Reglets	Butt joint	--	Seal reglet groove with joint sealing compound.
Eave	One inch flat locked, cleated. One inch loose locked, sealed expansion joint, cleated.	One inch flat locked, locked, cleated one inch loose locked, sealed expansion joints, cleated	Same as base flashing.
Stepped	3 inch lap	3 inch lap	--
Valley	6 inch lap cleated	6 inch lap cleated	--
Edge strip	Butt	Butt	--
Gravel stops:			
Extrusions	--	Butt with 1/2 inch space	Use sheet flashing beneath and a cover plate
Sheet, smooth	Butt with 1/4 inch space	Butt with 1/4 inch space	Use sheet flashing backup plate.
Sheet, corrugated	Butt with 1/4 inch space	Butt with 1/4 inch space	Use sheet flashing beneath and a cover plate or a combination unit
Gutters	1.5 inch lap, riveted and soldered	One inch flat locked riveted and sealed	Aluminum producers recommended hard setting sealant for locked aluminum joints.
(a) Provide a 3 inch lap elastomeric flashing with manufacturer's recommended sealant.			
(b) Seal Polyvinyl chloride reglet with manufacturer's recommended sealant.			

] -- End of Section --

SECTION 07 92 00

JOINT SEALANTS
08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C834	(2017) Standard Specification for Latex Sealants
ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants
ASTM C1193	(2013) Standard Guide for Use of Joint Sealants
ASTM C1521	(2013) Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints
ASTM D2452	(2015; R 2019) Standard Test Method for Extrudability of Oil- and Resin-Base Caulking Compounds
ASTM D2453	(2015; R 2020; E 2020) Standard Test Method for Shrinkage and Tenacity of Oil- and Resin-Base Caulking Compounds

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2017) Adhesive and Sealant Applications

UNDERWRITERS LABORATORIES (UL)

UL 2818	(2013) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Sealants; G

Primers; G

Bond Breakers; G

Backstops; G

SD-06 Test Reports

Field Adhesion; G

SD-07 Certificates

Indoor Air Quality For Interior Sealants; S

Indoor Air Quality For Interior Floor Joint Sealants; S

Indoor Air Quality For Interior Acoustical Sealants; S

Indoor Air Quality For Interior Caulking; S

1.3 PRODUCT DATA

Include storage requirements, shelf life, curing time, instructions for mixing and application, and accessories. Provide manufacturer's Safety Data Sheets (SDS) for each solvent, primer and sealant material proposed.

1.4 CERTIFICATIONS

1.4.1 Indoor Air Quality Certifications

Submit required indoor air quality certifications in one submittal package.

1.4.1.1 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body.. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

]1.5 ENVIRONMENTAL CONDITIONS

Apply sealant when the ambient temperature is between 40 and 90 degrees F.

1.6 DELIVERY AND STORAGE

Deliver materials to the jobsite in unopened manufacturers' sealed shipping containers, with brand name, date of manufacture, color, and material designation clearly marked thereon. Label elastomeric sealant containers to identify type, class, grade, and use. Handle and store materials in accordance with manufacturer's printed instructions. Prevent exposure to foreign materials or subjection to sustained temperatures exceeding 90 degrees F or lower than 0 degrees F. Keep materials and containers closed and separated from absorptive materials such as wood and insulation.

1.7 QUALITY ASSURANCE

1.7.1 Compatibility with Substrate

Verify that each sealant is compatible for use with each joint substrate in accordance with sealant manufacturer's printed recommendations for each application.

1.7.2 Joint Tolerance

Provide joint tolerances in accordance with manufacturer's printed instructions.

1.7.3 Mock-Up

Provide a mock-up of each type of sealant using materials, colors, and techniques approved for use on the project. Approved mock-ups may be incorporated into the Work.

1.7.4 Adhesion

Provide in accordance with ASTM C1193 or ASTM C1521.

PART 2 PRODUCTS

2.1 SEALANTS

Provide sealant products that have been tested, found suitable, and documented as such by the manufacturer for the particular substrates to which they will be applied.

In areas with ambient temperatures that exceed 110 degrees F, do not use polybutene, bituminous, acrylic-latex, polyvinyl acetate latex sealants, polychloroprene (neoprene), polyvinyl chloride (PVC), and polyurethane foams, and neoprene, PVC, and styrene butadiene rubber extruded seals and closure strips due to these materials having maximum recommended surface temperature ranges from 130 to 180 degrees F.

2.1.1 Interior Sealants

Provide ASTM C834 Provide sealant products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content

requirements of SCAQMD Rule 1168. Provide certification or validation of indoor air quality for interior sealants. Location(s) and color(s) of sealant for the following. Note, color "as selected" refers to manufacturer's full range of color options

LOCATION	COLOR
a. Perimeter of frames at doors, windows, and access panels which adjoin exposed interior concrete and masonry surfaces.	As selected
b. Joints of interior masonry walls and partitions which adjoin columns, pilasters, concrete walls, and exterior walls unless otherwise detailed.	As selected
c. Joints between edge members for acoustical tile and adjoining vertical surfaces.	As selected
d. Interior locations, not otherwise indicated or specified, where small voids exist between materials specified to be painted.	As selected

2.1.2 Exterior Sealants

For joints in vertical surfaces, provide ASTM C920, Type S or M, Grade NS, Class 25, Use NT. For joints in horizontal surfaces, provide ASTM C920, Type S or M, Grade P, Class 25, Use T. Provide location(s) and color(s) of sealant as follows. Note, color "as selected" refers to manufacturer's full range of color options:

a. As selected from manufactuirer's recommended products compatible with system provided.

2.2 PRIMERS

Non-staining, quick drying type and consistency as recommended by the sealant manufacturer for the particular application. Provide primers for interior applications that meet the indoor air quality requirements of the paragraph SEALANTS above.

2.3 BOND BREAKERS

Type and consistency as recommended by the sealant manufacturer to prevent adhesion of the sealant to the backing or to the bottom of the joint. Provide bond breakers for interior applications that meet the indoor air quality requirements of the paragraph SEALANTS above.

2.4 BACKSTOPS

Provide glass fiber roving, neoprene, butyl, polyurethane, or polyethylene foams free from oil or other staining elements as recommended by sealant

manufacturer. Provide 25 to 33 percent oversized backing for closed cell and 40 to 50 percent oversized backing for open cell material, unless otherwise indicated. Provide backstop material that is compatible with sealant. Do not use oakum or other types of absorptive materials as backstops.Type, Class, Grade, and configuration compatible with the system provided. Provide manufacturer's data sheets with tested product.

2.4.1 Rubber

Provide in accordance with ASTM D1056.,Type, Class, Grade, and configuration compatible with the system provided. Provide manufacturer's data sheets with tested product.

2.4.2 PVC

Provide in accordance with ASTM D1667.

2.4.3 Synthetic Rubber

Provide in accordance with ASTM C509.

2.4.4 Neoprene

Provide in accordance with ASTM D1056.

2.4.5 Butyl Rubber Based

Provide in accordance with ASTM C1311.

2.4.6 Silicone Rubber Base

Provide in accordance with ASTM C920.

2.5 CAULKING

For interior use and only where there is little or no anticipated joint movement. Provide in accordance with ASTM D2452 and ASTM D2453, Types for each application. Provide products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide certification or validation of indoor air quality for interior caulking.

2.6 CLEANING SOLVENTS

Provide type(s) recommended by the sealant manufacturer and in accordance with environmental requirements herein. Protect adjacent aluminum and bronze surfaces from solvents. Provide solvents for interior applications that meet the indoor air quality requirements of the paragraph SEALANTS above.

PART 3 EXECUTION

3.1 FIELD QUALITY CONTROL

Perform a field adhesion test in accordance with manufacturer's instructions and ASTM C1193, Method A or ASTM C1521, Method A, Tail Procedure. Remove sealants that fail adhesion testing; clean substrates,

reapply sealants, and re-test. Test sealants adjacent to failed sealants. Submit field adhesion test report indicating tests, locations, dates, results, and remedial actions taken.

3.2 SURFACE PREPARATION

Prepare surfaces according to manufacturer's printed installation instructions. Clean surfaces from dirt, frost, moisture, grease, oil, wax, lacquer, paint, or other foreign matter that would destroy or impair adhesion. Remove oil and grease with solvent; thoroughly remove solvents prior to sealant installation. Wipe surfaces dry with clean cloths. When resealing an existing joint, remove existing caulk or sealant prior to applying new sealant. For surface types not listed below, provide in accordance with sealant manufacturer's printed instructions for each specific surface.

3.2.1 Steel Surfaces

Remove loose mill scale by sandblasting or, if sandblasting is impractical or would damage finished work, scraping and wire brushing. Remove protective coatings by sandblasting or using a residue free solvent. Remove resulting debris and solvent residue prior to sealant installation.

3.2.2 Aluminum or Bronze Surfaces

Remove temporary protective coatings from surfaces that will be in contact with sealant. When masking tape is used as a protective coating, remove tape and any residual adhesive prior to sealant application. For removing protective coatings and final cleaning, use non-staining solvents recommended by the manufacturer of the item(s) containing aluminum or bronze surfaces.

3.2.3 Concrete and Masonry Surfaces

Where surfaces have been treated with curing compounds, oil, or other such materials, remove materials by sandblasting or wire brushing. Remove laitance, efflorescence and loose mortar from the joint cavity. Remove resulting debris prior to sealant installation.

3.2.4 Wood Surfaces

Ensure wood surfaces that will be in contact with sealants are free of splinters, sawdust and other loose particles.

3.2.5 Removing Existing Hazardous Sealants

For sealants applied prior to 1979, or that have been tested and found to contain polychlorinated biphenyls (PCBs), remove and dispose of these sealants in accordance with Section 02 84 33 REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBs).

3.3 SEALANT PREPARATION

Do not add liquids, solvents, or powders to sealants. Mix multicomponent elastomeric sealants in accordance with manufacturer's printed instructions.

3.4 APPLICATION

3.4.1 Joint Width-To-Depth Ratios

Acceptable Ratios:

JOINT WIDTH	JOINT DEPTH	
	Minimum	Maximum
For metal, glass, or other nonporous surfaces:		
1/4 inch (minimum)	1/4 inch	1/4 inch
over 1/4 inch	1/2 of width	Equal to width
For wood, concrete, masonry, stone:		
1/4 inch (minimum)	1/4 inch	1/4 inch
over 1/4 inch to 1/2 inch	1/4 inch	Equal to width
over 1/2 inch to 1 inch	1/2 inch	5/8 inch
Over 1 inch	prohibited	

Unacceptable Ratios: Where joints of acceptable width-to-depth ratios have not been provided, clean out joints to acceptable depths and grind or cut to acceptable widths without damage to the adjoining work. Grinding is prohibited at metal surfaces.

3.4.2 Unacceptable Sealant Use

Do not install sealants in lieu of other required building enclosure weatherproofing components such as flashing, drainage components, and joint closure accessories, or to close gaps between walls, floors, roofs, windows, and doors, that exceed acceptable installation tolerances. Remove sealants that have been used in an unacceptable manner and correct building enclosure deficiencies to comply with contract documents requirements.

3.4.3 Masking Tape

Place masking tape on the finished surface on one or both sides of joint cavities to protect adjacent finished surfaces from primer or sealant smears. Remove masking tape within 10 minutes of joint filling and tooling.

3.4.4 Backstops

Provide backstops dry and free of tears or holes. Tightly pack the back or bottom of joint cavities with backstop material to provide joints in specified depths. Provide backstops where indicated and where backstops are not indicated but joint cavities exceed the acceptable maximum depths specified in JOINT WIDTH-TO-DEPTH RATIOS Table.

3.4.5 Primer

Clean out loose particles from joints immediately prior to application of.

Apply primer to joints in concrete masonry units, wood, and other porous surfaces in accordance with sealant manufacturer's printed instructions. Do not apply primer to exposed finished surfaces.

3.4.6 Bond Breaker

Provide bond breakers to surfaces not intended to bond in accordance with, sealant manufacturer's printed instructions for each type of surface and sealant combination specified.

3.4.7 Sealants

Provide sealants compatible with the material(s) to which they are applied. Do not use a sealant that has exceeded its shelf life or has jelled and cannot be discharged in a continuous flow from the sealant gun. Apply sealants in accordance with the manufacturer's printed instructions with a gun having a nozzle that fits the joint width. Work sealant into joints so as to fill the joints solidly without air pockets. Tool sealant after application to ensure adhesion. Apply sealant uniformly smooth and free of wrinkles. Upon completion of sealant application, roughen partially filled or unfilled joints, apply additional sealant, and tool smooth as specified. Apply sealer over sealants in accordance with the sealant manufacturer's printed instructions.

3.5 PROTECTION AND CLEANING

3.5.1 Protection

Protect areas adjacent to joints from sealant smears. Masking tape may be used for this purpose if removed 5 to 10 minutes after the joint is filled and no residual tape marks remain.

3.5.2 Final Cleaning

Upon completion of sealant application, remove remaining smears and stains and leave the work in a clean and neat condition.

a. Masonry and Other Porous Surfaces: Immediately remove fresh sealant that has been smeared on adjacent masonry, rub clean with a solvent, and remove solvent residue, in accordance with sealant manufacturer's printed instructions. Allow excess sealant to cure for 24 hour then remove by wire brushing or sanding. Remove resulting debris.

b. Metal and Other Non-Porous Surfaces: Remove excess sealant with a solvent moistened cloth. Remove solvent residue in accordance with solvent manufacturer's printed instructions.

-- End of Section --

SECTION 08 11 13

STEEL DOORS AND FRAMES
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2020) Structural Welding Code - Steel

ASTM INTERNATIONAL (ASTM)

ASTM A653/A653M	(2020) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A924/A924M	(2020) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM C578	(2019) Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation
ASTM C591	(2020) Standard Specification for Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
ASTM C612	(2014; R 2019) Standard Specification for Mineral Fiber Block and Board Thermal Insulation
ASTM D2863	(2019) Standard Test Method for Measuring the Minimum Oxygen Concentration to Support Candle-Like Combustion of Plastics (Oxygen Index)
ASTM F2247	(2018) Standard Test Method for Metal Doors Used in Blast Resistant Applications (Equivalent Static Load Method)
ASTM F2927	(2012) Standard Test Method for Door Systems Subject to Airblast Loadings

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.115	(2016) Hardware Preparation in Steel Doors and Steel Frames

STEEL DOOR INSTITUTE (SDI/DOOR)

SDI/DOOR 111	(2009) Recommended Details for Standard Steel Doors, Frames, and Accessories and Related Components
SDI/DOOR 113	(2013; R2018) Standard Practice for Determining the Steady-State Thermal Transmittance of Steel Door and Frame Assemblies
SDI/DOOR A250.4	(2018) Test Procedure and Acceptance Criteria for Physical Endurance for Steel Doors, Frames and Frame Anchors
SDI/DOOR A250.6	(2015) Recommended Practice for Hardware Reinforcing on Standard Steel Doors and Frames
SDI/DOOR A250.8	(2017) Specifications for Standard Steel Doors and Frames
SDI/DOOR A250.11	(2012) Recommended Erection Instructions for Steel Frames

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 4-010-01	(2018) DoD Minimum Antiterrorism Standards for Buildings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Doors; G

Frames and Flashing; G

Accessories

Schedule of Doors; G

Schedule of Frames; G

SD-03 Product Data

Doors; G

Frames; G

Accessories

]1.3 DELIVERY, STORAGE, AND HANDLING

Deliver doors, frames, and accessories undamaged and with protective wrappings or packaging. Provide temporary steel spreaders securely fastened to the bottom of each welded frame. Store doors and frames on platforms under cover in clean, dry, ventilated, and accessible locations, with 1/4 inch airspace between doors. Remove damp or wet packaging immediately and wipe affected surfaces dry. Replace damaged materials with new.

PART 2 PRODUCTS

2.1 STANDARD STEEL DOORS

SDI/DOOR A250.8, except as specified otherwise. Prepare doors to receive door hardware as specified in Section 08 71 00 DOOR HARDWARE. Undercut where indicated. Provide exterior doors with top edge closed flush and sealed to prevent water intrusion. Provide doors at 1-3/4 inch thick, unless otherwise indicated. Provide door material that uses a minimum of 25 percent recycled content. Provide data indicating percentage of recycled content for steel door product. Exterior doors must be tested in accordance with ASTM F2247 or ASTM F2927 to meet requirements of UFC 4-010-01.

2.1.1 Classification - Level, Performance, Model

2.1.1.1 Maximum Duty Doors

SDI/DOOR A250.8, Level 4, physical performance Level A, Model 2 with core construction as required by the manufacturer for indicated exterior doors, of size(s) and design(s) indicated. Where vertical stiffener cores are required, the space between the stiffeners must be filled with board insulation.

2.2 INSULATED STEEL DOOR SYSTEMS

Provide insulated steel doors and frames in accordance with SDI/DOOR 113 at entrances to dwelling units and where indicated. Meet energy requirements including Solar Heat Gain Coefficient (SHGC) and U-factor. Provide insulated steel doors with a core of polyurethane foam; face sheets, edges, and frames of galvanized steel not lighter than 23 gage, 16 gage, and 16 gage respectively; magnetic weatherstripping; nonremovable-pin hinges; thermal-break aluminum threshold; and vinyl door bottom. Provide to doors and frames a phosphate treatment, rust-inhibitive primer, and baked acrylic enamel finish. Test doors in accordance with SDI/DOOR A250.4 and meet the requirements for Level C. Prepare doors to receive specified hardware. Provide doors 1-3/4 inch thick.

2.3 INSULATION CORES

Provide insulating cores at all exterior doors provide an apparent U-factor of .48 in accordance with SDI/DOOR 113 and conforming to:

a. Rigid Cellular Polyisocyanurate Foam: ASTM C591, Type I or II, foamed-in-place or in board form, with oxygen index of not less than 22 percent when tested in accordance with ASTM D2863; or

b. Rigid Polystyrene Foam Board: ASTM C578, Type I or II; or

c. Mineral board: ASTM C612, Type I.

2.4 STANDARD STEEL FRAMES

SDI/DOOR A250.8, Level 4. Form frames to sizes and shapes indicated, with welded corners.

2.4.1 Welded Frames

Continuously weld frame faces at corner joints. Mechanically interlock or continuously weld stops and rabbets. Grind welds smooth.

Weld frames in accordance with the recommended practice of the Structural Welding Code Sections 1 through 6, AWS D1.1/D1.1M and in accordance with the practice specified by the producer of the metal being welded.

2.4.2 Anchors

Provide anchors to secure the frame to adjoining construction. Provide steel anchors, zinc-coated not lighter than 18 gage.

2.4.2.1 Wall Anchors

Provide at least three anchors for each jamb. For frames which are more than 7.5 feet in height, provide one additional anchor for each jamb for each additional 2.5 feet or fraction thereof.

a. Completed openings: Secure frames to previously placed concrete or masonry with expansion bolts in accordance with SDI/DOOR 111; and

2.4.2.2 Floor Anchors

Provide floor anchors drilled for 3/8 inch anchor bolts at bottom of each jamb member.

2.5 EXTERIOR FRAMES

Provide thermal insulation in all exterior frames. Provide frames of a minimum Level 4, with frames of a minimum thickness of 0.067 inch, 14 gage. Frame grouting will not be acceptable.

2.6 HARDWARE PREPARATION

Drill and tap doors and frames to receive finish hardware. Prepare doors and frames for hardware in accordance with the applicable requirements of SDI/DOOR A250.8 and SDI/DOOR A250.6. For additional requirements refer to ANSI/BHMA A156.115. Drill and tap for surface-applied hardware at the project site. Build additional reinforcing for surface-applied hardware into the door at the factory. Punch door frames, with the exception of frames that will have weatherstripping to receive a minimum of two rubber or vinyl door silencers on lock side of single doors and one silencer for each leaf at heads of double doors. Set lock strikes out to provide clearance for silencers.

2.7 FINISHES

2.7.1 Hot-Dip Zinc-Coated and Factory-Primed Finish

Fabricate exteriordoors and frames from hot dipped zinc coated steel, alloyed type, that complies with ASTM A924/A924M and ASTM A653/A653M. The coating weight must meet or exceed the minimum requirements for coatings having 0.4 ounces per square foot, total both sides, i.e., A40. Repair damaged zinc-coated surfaces by the application of zinc dust paint. Thoroughly clean and chemically treat to insure maximum paint adhesion. Factory prime as specified in SDI/DOOR A250.8.

2.8 FABRICATION AND WORKMANSHIP

Provide finished doors and frames that are strong and rigid, neat in appearance, and free from defects, waves, scratches, cuts, dents, ridges, holes, warp, and buckle. Provide molded members that are clean cut, straight, and true, with joints coped or mitered, well formed, and in true alignment. Dress exposed welded and soldered joints smooth. Design door frame sections for use with the wall construction indicated. Corner joints must be well formed and in true alignment. Conceal fastenings where practicable.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Frames

Set frames in accordance with SDI/DOOR A250.11. Plumb, align, and brace securely until permanent anchors are set. Anchor bottoms of frames with expansion bolts or powder-actuated fasteners. Build in or secure wall anchors to adjoining construction.

3.1.2 Doors

Hang doors in accordance with clearances specified in SDI/DOOR A250.8. After erection and glazing, clean and adjust hardware.

3.2 PROTECTION

Protect doors and frames from damage. Repair damaged doors and frames prior to completion and acceptance of the project or replace with new, as directed. Wire brush rusted frames until rust is removed. Clean thoroughly. Apply an all-over coat of rust-inhibitive paint of the same type used for shop coat.

3.3 CLEANING

Upon completion, clean exposed surfaces of doors and frames thoroughly. Remove mastic smears and other unsightly marks.

-- End of Section --

SECTION 08 51 13

ALUMINUM WINDOWS
05/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF45	(2003; Reaffirmed 2009) Designation System for Aluminum Finishes

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 611	(2014) Voluntary Specification for Anodized Architectural Aluminum
AAMA 701/702	(2011) Voluntary Specification for Pile Weatherstripping and Replaceable Fenestration Weatherseals
AAMA 907	(2015) Voluntary Specification for Corrosion Resistant Coatings on Carbon Steel Components Used in Windows, Doors and Skylights
AAMA 1503	(2009) Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections
AAMA/WDMA/CSA 101/I.S.2/A440	(2017) North American Fenestration Standard/Specification for Windows, Doors, and Skylights

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 169	(2013) Climate Data for Building Design Standards

ASTM INTERNATIONAL (ASTM)

ASTM E90	(2009; R2016) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements
ASTM E413	(2016) Classification for Rating Sound Insulation
ASTM E1300	(2016) Standard Practice for Determining Load Resistance of Glass in Buildings

ASTM E1332	(2016) Standard Classification for Rating Outdoor-Indoor Sound Attenuation
ASTM E1886	(2019) Standard Test Method for Performance of Exterior Windows, Curtain Walls, Doors, and Impact Protective Systems Impacted by Missile(s) and Exposed to Cyclic Pressure Differentials
ASTM E1996	(2017) Standard Specification for Performance of Exterior Windows, Curtain Walls, Doors, and Impact Protective Systems Impacted by Windborne Debris in Hurricanes
ASTM F2248	(2012) Standard Practice for Specifying an Equivalent 3-Second Duration Design Loading for Blast Resistant Glazing Fabricated with Laminated Glass

NATIONAL FENESTRATION RATING COUNCIL (NFRC)

NFRC 100	(2017) Procedure for Determining Fenestration Product U-Factors
NFRC 200	(2017) Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Windows; G

Fabrication Drawings

SD-03 Product Data

Windows; G

Hardware; G

Fasteners; G

Window Performance; G

Thermal-Barrier Windows; G

Mullions; G

Screens; G

Weatherstripping; G

Accessories; G

Adhesives

Thermal Performance; G

SD-04 Samples

Finish Sample for color selection

Window Mock-Ups including Flashing; G

SD-05 Design Data

Structural Calculations for Deflection; G

Design Analysis; G

SD-06 Test Reports

Minimum Condensation Resistance Factor

Standard Airblast Test; G

Windborne-Debris-Impact Performance

SD-10 Operation and Maintenance Data

Windows, Data Package 1; G

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.3 QUALITY ASSURANCE

1.3.1 Qualification of Manufacturer

Window manufacturer must specialize in designing and manufacturing the type of aluminum windows specified in this section, and have a minimum of 5 years of documented successful experience. Manufacturer must have the facilities capable of meeting contract requirements, single-source responsibility and warranty.

1.3.2 Shop Drawing Requirements

Take field measurements prior to preparation of drawings and fabrications. Provide drawings that indicate elevations of windows, full-size sections, thickness and gages of metal, fastenings, proposed method of anchoring, size and spacing of anchors, details of construction, method of glazing, details of operating hardware, method and materials for weatherstripping, method of attaching screens,material and method of attaching subframes, stools,casings,sills,trim,flashing at Jambs, sill and head, installation

details, and other related items.

1.3.3 Sample Requirements

1.3.3.1 Finish Sample Requirements

Submit color chart of standard factory color coatings when factory-finish color coating is to be provided.

1.3.3.2 Window Sample Requirements

Submit one full-size window of each type proposed for use, complete with AAMA Label, glazing, hardware, anchors, and other accessories. Where screens or weatherstripping is required, fit sample windows with such items that are to be used. After approval, install each sample in work, clearly identified, and record its location.

1.3.3.3 Mock-Ups

Before fabrication, full-size mock-up of each type of aluminum window complete with glass and AAMA certification label for structural purposes and NFRC Temporary and Permanent Label for certification of thermal performance rating will be required for review of window construction and quality of hardware operation. Must provide all flashing conditions (sill, jambs and head) in such a way where each item will not be concealed.

1.3.4 Test Report Requirements

Submit test reports for each type of window attesting that identical windows have been tested and meet the requirements specified herein for conformance to AAMA/WDMA/CSA 101/I.S.2/A440 including test size, and minimum condensation resistance factor (CRF), resistance to forced entry, and, for Antiterrorism windows, in lieu of a Design Analysis, results of a Standard Airblast Test

1.4 DELIVERY AND STORAGE

Deliver windows to project site in an undamaged condition. Use care in handling and hoisting windows during transportation and at the jobsite. Store windows and components out of contact with the ground, under a weathertight covering, so as to prevent bending, warping, or otherwise damaging the windows. Repair damaged windows to an "as new" condition as approved. If windows can not be repaired, provide a new unit.

1.5 PERFORMANCE REQUIREMENTS

1.5.1 Wind Loading Design Pressure

Design window components, including mullions, hardware, and anchors, to withstand a wind-loading design pressure as follows: Determine the wind pressure on the building by converting the ASCE-7 basic wind speed to wind pressure and find the corresponding structural test pressure in the AAMA specific requirements or optional performance tables. Provide for exterior windows.

Windows must support a pressure of 69 PSF acting towards the interior spaces and 73 PSF acting away from the interior spaces.

Windows must have impact resistant glazing that is in compliance with ASTM E1996 and ASTM E1886 to protect against wind borne debris.

1.5.2 Tests

Test windows proposed for use in accordance with AAMA/WDMA/CSA 101/I.S.2/A440 for the particular type and quality window specified.

Perform tests by a nationally recognized independent testing laboratory equipped and capable of performing the required tests. Submit the results of the tests as certified laboratory reports required herein.

1.6 DRAWINGS

Submit the Fabrication Drawings for aluminum window units showing complete window assembly including hardware, weatherstripping,all flashing conditions, and subframe assembly details.

1.7 WINDOW PERFORMANCE

Aluminum windows must meet the following performance requirements. Perform testing requirements by an independent testing laboratory or agency.

1.7.1 Structural Performance

Structural test pressures on window units must be for positive load (inward) and negative load (outward). After testing, there will be no glass breakage, permanent damage to fasteners, hardware parts, support arms or actuating mechanisms or any other damage which could cause window to be inoperable. There must be no permanent deformation of any main frame, sash or ventilator member in excess of the requirements established by AAMA/WDMA/CSA 101/I.S.2/A440 for the window types and classification specified in this section.

1.7.2 Air Infiltration

Air infiltration must not exceed the amount established by AAMA/WDMA/CSA 101/I.S.2/A440 for each window type.

1.7.3 Water Penetration

Water penetration must not exceed the amount established by AAMA/WDMA/CSA 101/I.S.2/A440 for each window type.

1.7.4 Thermal Performance

Windows (including frames and glass) will be independently tested and certified with a Solar Heat Gain Coefficient (SHGC) determined according to NFRC 200 procedures and a whole window U-factor determined in accordance with NFRC 100 within the ranges as indicated below according to the ASHRAE 169 Climate Zone of the project location. Provide visual Transmittance (VT) of 0.5 or greater.

1.7.5 Sound Attenuation

When tested in accordance with AAMA/WDMA/CSA 101/I.S.2/A440 or the

following below, provide a minimum Sound Transmission Class (STC) of 35 in accordance with ASTM E90 and as determined by ASTM E413 or Outside-Indoor Transmission Class (OITC) of 25 in accordance with ASTM E1332 and as determined by ASTM E413 with the window glazed with 1/2 inch air space between two pieces of 1/4 inch.

1.7.6 Windborne-Debris-Impact Performance

Exterior window system including glazing must comply with indicated basis or enhanced protection testing requirements in ASTM E1996 for the MC New River Base Wind Zone when tested according to ASTM E1886. Test specimens must be no smaller in width and length than glazing indicated for use on Project and must be installed in same manner as glazing indicated for use on Project.

1.8 WARRANTY

Provide Manufacturer's standard performance guarantees or warranties that extend beyond a 1 year period.

PART 2 PRODUCTS

2.1 WINDOWS

Provide prime windows that comply with AAMA/WDMA/CSA 101/I.S.2/A440 and the requirements specified herein. In addition to compliance with AAMA/WDMA/CSA 101/I.S.2/A440, window framing members for each individual light of glass must not deflect to the extent that deflection perpendicular to the glass light exceeds L/175 of the glass edge length when subjected to uniform loads at specified design pressures. Provide Structural calculations for deflection to substantiate compliance with deflection requirements. Provide windows of types, performance classes, performance grades, combinations, and sizes indicated or specified. Provide aluminum window frames with a minimum recycled content of 20 percent. Provide data identifying percentage of recycled content of aluminum windows. Design windows to accommodate hardware, glass, weatherstripping, screens, and accessories to be furnished. Each window must be a complete factory assembled unit with or without glass installed. Dimensions shown are minimum. Provide windows with insulating glass and thermal break necessary to achieve a minimum Condensation Resistance Factor (CRF) to meet ASHRAE 90.1 U-Factor. when tested in accordance with AAMA 1503. Provide manufacturer's standard hardware fabricated from aluminum, stainless steel, carbon steel complying with AAMA 907, or other corrosion-resistant material compatible with adjacent materials; designed to smoothly operate, tightly close, and securely lock windows, and sized to accommodate sash weight and dimensions.

2.1.1 Fixed Windows (F)

Frame and glazing in compliance with ASTM E1996 for Wind Region of 150 mile/Hr; Wind Zone 3
Performance Grade, Design Presure as indicated in 1.5.1 above. .

2.1.2 Glass and Glazing

Materials are specified in Section 08 81 00 GLAZING.

2.1.3 Caulking and Sealing

Are specified in Section 07 92 00 JOINT SEALANTS.

2.1.4 Weatherstripping

AAMA/WDMA/CSA 101/I.S.2/A440. Provide for all ventilating (operable) sash for all windows. Provide woven wool pile weatherstripping 0.210 inch thick, conforming to AAMA 701/702, or polypropylene multifilament fiber weatherstripping installed in an integral weatherstripping groove in the sash or frame, and flexible polyvinylchloride weatherstripping installed in the sill member.

2.2 FABRICATION

Fabrication of window units must comply with AAMA/WDMA/CSA 101/I.S.2/A440.

2.2.1 Provisions for Glazing

Design windows and rabbets suitable for glass thickness specified. Design sash for inside double glazing and for securing glass with glazing channels.

2.2.2 Fasteners

Use window manufacturer's standard for windows, trim, and accessories in compliance with ASTM E1996 for Wind Region of 150 mile/Hr; Wind Zone 3. Self-tapping sheet-metal screws are not acceptable for material more than 1/16 inch thick.

2.2.3 Adhesives

Provide joint sealants as specified in Section 07 92 00 JOINT SEALANTS. For interior application of joint sealants, comply with applicable regulations regarding reduced VOC's, and as specified in Section 07 92 00 JOINT SEALANTS.

2.2.4 Drips and Weep Holes

Provide continuous drips over heads of top ventilators. Where fixed windows adjoin ventilators, drips must be continuous across tops of fixed windows. Provide drips and weep holes as required to return water to the outside. Weep holes if provided must not replace one-piece sill flashing.

2.2.5 Mullions and Transom Bars

Provide mullions between multiple window units to resist two times (2X) glazing resistance in accordance with ASTM F2248 and ASTM E1300. Provide mullions with a thermal break. Secure mullions and transom bars to adjoining construction and window units in such a manner as to permit expansion and contraction and to form a weathertight joint. Provide mullion covers on the interior and exterior to completely close exposed joints and recesses between window units and to present a neat appearance. Provide special covers over structural support at mullions as indicated.

2.2.6 Accessories

Provide windows complete with necessary hardware, fastenings, clips, fins, anchors, glazing beads, and other appurtenances necessary for complete installation and proper operation. Furnish extruded aluminum subframe

receptors and subsill with each window unit. Provide one-piece sill flashing as shown in drawings.

2.2.6.1 Hardware

AAMA/WDMA/CSA 101/I.S.2/A440. The item, type, and functional characteristics must be the manufacturer's standard for the particular window type. Provide stainless steel hardware of suitable design and of sufficient strength to perform the function for which it is used. Equip all operating ventilators with a lock or latching device which can be secured from the inside.

2.2.6.2 Fasteners

Provide concealed anchors of the type recommended by the window manufacturer for the specific type of construction in compliance with ASTM E1996 for Wind Region of 150 mile/Hr; Wind Zone 3. Anchors and fasteners must be compatible with the window and the adjoining construction. Provide a minimum of three anchors for each jamb located approximately 6 inches from each end and at midpoint.

2.2.7 Finishes

Exposed aluminum surfaces must be factory finished with an anodic / duronodic coating. Color must be as indicated. All windows for each building must have the same finish..

2.2.7.1 Anodic Coating

Clean exposed aluminum surfaces and provide an anodized finish conforming to AA DAF45 and AAMA 611. Finish must be:

a. Architectural Class I (0.7 mil or thicker), designation AA-M10-C22-, integral coloranodized.

2.3 THERMAL-BARRIER WINDOWS

Provide thermal-barrier windows, complete with accessories and fittings, where indicated.

Specify material and construction except as follows:

a. Aluminum alloy must be 6063-T6.

b. Frame construction, including operable sash, must be factory-assembled and factory-sealed inner and outer aluminum completely separated from metal-to-metal contact. Join assembly by a continuous, concealed, low conductance divider housed in an interlocking extrusion of the inner frame. Metal fasteners, straps, or anchors must not bridge the connection between the inner and outer frame.

c. Operating hardware for each sash must consist of spring-loaded nylon cushion blocks and pin locks designed to lock in predetermined locations.

d. Sash must be completely separated from metal-to-metal contact by means of woven-pile weatherstripping, plastic, or elastomeric separation members.

e. Operating and storm sash must be factory-glazed with the type of glass indicated and of the quality specified in Section 08 81 00 GLAZING.

2.4 MULLIONS

Provide thermal-barrier mullions between multiple-window units where indicated.

Provide profiles for mullions and mullion covers, reinforced as required for the specified wind loading, and securely anchored to the adjoining construction. Mullion extrusion will include serrations or pockets to receive weatherstripping, sealant, or tape at the point of contact with each window flange.

Mullion assembly must include aluminum window clamps or brackets screwed or bolted to the mullion and the mullion cover.

Mullion cover must be screw-fastened to the mullion unless otherwise indicated.

Mullion reinforcing members must be fabricated of the materials specified in AAMA/WDMA/CSA 101/I.S.2/A440 and meet the specified design loading.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Method of Installation

Install in accordance with the window manufacturer's printed instructions and details. Build in windows as the work progresses or install without forcing into prepared window openings. Set windows at proper elevation, location, and reveal; plumb, square, level, and in alignment; and brace, strut, and stay properly to prevent distortion and misalignment. Protect ventilators and operating parts against accumulation of dirt and building materials by keeping ventilators tightly closed and locked to frame. Bed screws or bolts in sill members, joints at mullions, contacts of windows with sills, built-in fins, and subframes in mastic sealant of a type recommended by the window manufacturer. Install and caulk windows in a manner that will prevent entrance of water and wind. Fasten insect screens securely in place.

Any materials that show visual evidence of biological growth due to the presence of moisture must not be installed on the building project.

3.1.2 Dissimilar Materials

Where aluminum surfaces are in contact with, or fastened to masonry, concrete, wood, or dissimilar metals, except stainless steel or zinc, protect the aluminum surface from dissimilar materials as recommended in the Appendix to AAMA/WDMA/CSA 101/I.S.2/A440. Do not coat surfaces in contact with sealants after installation with any type of protective material. Do not apply coatings or lacquers to surfaces to which caulking and glazing components must adhere.

3.1.3 Anchors and Fastenings

Make provision for securing units to each other, to masonry, and to other adjoining construction. Windows installed in masonry walls must have head

and jamb members designed to recess into masonry wall not less than 7/16 inch.

3.1.4 Adjustments After Installation

After installation of windows and completion of glazing and field painting, adjust all ventilators and hardware to operate smoothly and to provide weathertight sealing when ventilators are closed and locked. Lubricate hardware and operating parts as necessary. Verify that products are properly installed, connected, and adjusted.

3.2 CLEANING

Clean interior and exterior surfaces of window units of mortar, plaster, paint spattering spots, and other foreign matter to present a neat appearance, to prevent fouling of weathering surfaces and weather-stripping, and to prevent interference with the operation of hardware. Replace all stained, discolored, or abraded windows that cannot be restored to their original condition with new windows.

-- End of Section --

SECTION 08 71 00

DOOR HARDWARE
02/16, CHG 3: 08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E283	(2019) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.1	(2016) Butts and Hinges
ANSI/BHMA A156.2	(2017) Bored and Preassembled Locks and Latches
ANSI/BHMA A156.3	(2020) Exit Devices
ANSI/BHMA A156.4	(2013) Door Controls - Closers
ANSI/BHMA A156.5	(2020) Cylinder and Input Devices for Locks
ANSI/BHMA A156.7	(2016) Template Hinge Dimensions
ANSI/BHMA A156.13	(2017) Mortise Locks & Latches Series 1000
ANSI/BHMA A156.16	(2018) Auxiliary Hardware
ANSI/BHMA A156.18	(2020) Materials and Finishes
ANSI/BHMA A156.21	(2019) Thresholds
ANSI/BHMA A156.22	(2017) Door Gasketing and Edge Seal Systems
ANSI/BHMA A156.29	(2012) Exit Locks, Exit Alarms, Alarms for Exit Devices
ANSI/BHMA A156.36	(2010) Auxiliary Locks

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 72	(2019; TIA 19-1; ERTA 1 2019) National Fire Alarm and Signaling Code
NFPA 80	(2019) Standard for Fire Doors and Other

	Opening Protectives
NFPA 101	(2021) Life Safety Code
NFPA 252	(2017) Standard Methods of Fire Tests of Door Assemblies

STEEL DOOR INSTITUTE (SDI/DOOR)

SDI/DOOR A250.8	(2017) Specifications for Standard Steel Doors and Frames

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191	Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines

UNDERWRITERS LABORATORIES (UL)

UL Bld Mat Dir	(updated continuously online) Building Materials Directory

1.2 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Manufacturer's Detail Drawings; G

Verification of Existing Conditions; G

Hardware Schedule; G

Keying System; G

SD-03 Product Data

Hardware Items; G

SD-08 Manufacturer's Instructions

Installation

SD-10 Operation and Maintenance Data

Hardware Schedule Items, Data Package 1; G

SD-11 Closeout Submittals

Key Bitting

1.3 SHOP DRAWINGS

Submit manufacturer's detail drawings indicating all hardware assembly components and interface with adjacent construction. Base shop drawings on verified field measurements and include verification of existing conditions.

1.4 PRODUCT DATA

Indicate fire-ratings at applicable components. Provide documentation of ABA/ADA accessibility compliance of applicable components, as required by 36 CFR 1191 Appendix D - Technical.

1.5 HARDWARE SCHEDULE

Prepare and submit hardware schedule in the following form:

Hardware Item	Quantity	Size	Reference Publi- cation Type No.	Finish	Mfr Name and Catalog No.	Key Control Symbols	UL Mark (If fire- rated and listed	BHMA Finish Desig- nation

In addition, submit hardware schedule data package 1 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.6 KEY BITTING CHART REQUIREMENTS

1.6.1 Requirements

Submit key bitting charts to the Contracting Officer prior to completion of the work. Include:

a. Complete listing of all keys (e.g. AA1 and AA2).

b. Complete listing of all key cuts (AA1-123456, AA2-123458).

c. Tabulation showing which key fits which door.

d. Copy of floor plan showing doors and door numbers.

e. Listing of 20 percent more key cuts than are presently required in each master system.

1.7 QUALITY ASSURANCE

1.7.1 Hardware Manufacturers and Modifications

Provide, as far as feasible, locks, hinges, and closers of one lock, hinge, or closer manufacturer's make. Modify hardware as necessary to provide features indicated or specified.

1.7.2 Key Shop Drawings Coordination Meeting

Prior to the submission of the key shop drawing, the Contracting Officer, Contractor, Door Hardware Subcontractor, using Activity and Base Locksmith must meet to discuss and coordinate key requirements for the facility.

1.8 DELIVERY, STORAGE, AND HANDLING

Deliver hardware in original individual containers, complete with necessary appurtenances including fasteners and instructions. Mark each individual container with item number as shown on hardware schedule. Deliver permanent keys and removable cores to the Contracting Officer, either directly or by certified mail. Deliver construction master keys with the locks.

PART 2 PRODUCTS

2.1 TEMPLATE HARDWARE

Hardware applied to metal or to prefinished doors must be manufactured using a template. Provide templates to door and frame manufacturers in accordance with ANSI/BHMA A156.7 for template hinges. Coordinate hardware items to prevent interference with other hardware.

2.2 HARDWARE FOR FIRE DOORS AND EXIT DOORS

Provide all hardware necessary to meet the requirements of NFPA 72 for door alarms, NFPA 80 for fire doors, NFPA 101 for exit doors, NFPA 252 for fire tests of door assemblies, ABA/ADA accessibility requirements, and all other requirements indicated, even if such hardware is not specifically mentioned in paragraph HARDWARE SCHEDULE. Provide Underwriters Laboratories, Inc. labels for such hardware in accordance with UL Bld Mat Dir or equivalent labels in accordance with another testing laboratory approved in writing by the Contracting Officer.

2.3 HARDWARE ITEMS

Clearly and permanently mark with the manufacturer's name or trademark, hinges, locks, latches, exit devices, bolts and closers where the identifying mark is visible after the item is installed. For closers with covers, the name or trademark may be beneath the cover.

2.3.1 Hinges

Provide in accordance with ANSI/BHMA A156.1. Provide hinges that are 4-1/2 by 4-1/2 inch unless otherwise indicated. Construct loose pin hinges for interior doors and reverse-bevel exterior doors so that pins are non-removable when door is closed. Other anti-friction bearing hinges may be provided in lieu of ball bearing hinges.

2.3.2 Locks and Latches

a. At exterior locations provide locksets of full stainless steel type 302 or 304 construction including fronts, strike, escutcheons, knobs, bolts and all interior working parts. Marine Grade I, fully non-ferrous.

b. In non-air-conditioned interior environments or humid interior environments, provide interior locksets on the same Marine Grade I,

fully non-ferrous as exterior locksets.

2.3.2.1 Mortise Locks and Latches

Provide in accordance with ANSI/BHMA A156.13, Series 1000, Operational Grade 1, Security Grade 2. Cut escutcheons to fit cylinders and provide trim items with straight, beveled, or smoothly rounded sides, corners, and edges. Provide knobs and roses of mortise locks with screwless shanks and no exposed screws.

2.3.2.2 Bored Locks and Latches

Provide in accordance with ANSI/BHMA A156.2, Series 4000, Grade 1.

2.3.2.3 Auxiliary Locks

Provide in accordance with ANSI/BHMA A156.36, Grade 1.

2.3.3 Exit Devices

Provide in accordance with ANSI/BHMA A156.3, Grade 1. Provide adjustable strikes for rim type and vertical rod devices. Provide open back strikes for pairs of doors with mortise and vertical rod devices. Provide touch bars in lieu of conventional crossbars and arms. Provide escutcheons not less than 7 by 2-1/4 inch.

Use stainless steel base metal with plated finishes. Also include stainless steel fasteners and screws.

2.3.4 Exit Locks With Alarm

Provide in accordance with ANSI/BHMA A156.3 and ANSI/BHMA A156.29, Type E0431 (with full width horizontal actuating bar) for single doors; Type E0431 (with actuating bar) or E0471 (with actuating bar and top and bottom bolts, both leaves active) for pairs of doors, unless otherwise specified. Provide terminals for connection to remote indicating panel.Provide outside control key. Provide door alarms integrated with the fire alarm system in accordance with NFPA 72.

2.3.5 Cylinders and Cores

Provide cylinders and cores for new locks, including locks provided under other sections of this specification. Provide cylinders and cores with seven pin tumblers. Provide cylinders from the products of one manufacturer, and provide cores from the products of one manufacturer. Rim cylinders, mortise cylinders, and knobs of bored locksets have interchangeable cores which are removable by special control keys. Stamp each interchangeable core with a key control symbol in a concealed place on the core.

2.3.6 Push Button Mechanisms

Provide in accordance with ANSI/BHMA A156.5, Grade 1.

2.3.7 Keying System

Provide a master keying system an extension of the existing keying system.

2.3.8 Lock Trim

Provide cast, forged, or heavy wrought construction and commercial plain design for lock trim.

2.3.8.1 Knobs and Roses

Provide in accordance with ANSI/BHMA A156.2 and ANSI/BHMA A156.13 for knobs, roses, and escutcheons. For unreinforced knobs, roses, and escutcheons, provide a 0.050 inch thickness. For reinforced knobs, roses, and escutcheons, provide an outer shell thickness of 0.035 inch and a combined total thickness of 0.070 inch, except at knob shanks. Provide knob shanks 0.060 inch thick.

2.3.8.2 Lever Handles

Provide lever handles where indicated in the Hardware Schedule. Provide in accordance with ANSI/BHMA A156.3 for mortise locks of lever handles for exit devices. Provide lever handle locks with a breakaway feature (such as a weakened spindle or a shear key) to prevent irreparable damage to the lock when force in excess of that specified in ANSI/BHMA A156.13 is applied to the lever handle. Provide lever handles return to within 1/2 inch of the door face.

2.3.8.3 Texture

Provide knurled or abrasive coated lever handles doors.

2.3.9 Keys

Provide one file key, one duplicate key, and one working key for each key change keying system.

2.3.10 Closers

Provide in accordance with ANSI/BHMA A156.4, Series C02000, Grade 1, with PT 4C. Provide with brackets, arms, mounting devices, fasteners, full size covers and other features necessary for the particular application. Size closers in accordance with manufacturer's printed recommendations, or provide multi-size closers, Sizes 1 through 6, and list sizes in the Hardware Schedule. Provide manufacturer's 10 year warranty.

Use stainless steel inside bracketed or door mounted closers on exterior doors. Non-ferrous closers, such as aluminum or cast bronze, are permissible where door utilization is minimal. On interior doors use closers of 302 or 304 stainless steel or non-ferrous materials. On surface-mounted closers use or apply rust inhibiting finish on all ferrous parts. Also apply this finish on concealed closers.

2.3.10.1 Identification Marking

Engrave each closer with manufacturer's name or trademark, date of manufacture, and manufacturer's size designation in locations that will be visible after installation.

2.3.11 Door Stops and Silencers

Provide in accordance with ANSI/BHMA A156.16. Silencers Type L03011. Provide three silencers for each single door, two for each pair.

2.3.12 Thresholds

Provide in accordance with ANSI/BHMA A156.21. Use J35100, with vinyl or silicone rubber insert in face of stop, for exterior doors opening out, unless specified otherwise.

2.3.13 Weatherstripping Gasketing

Provide in accordance with ANSI/BHMA A156.22. Provide the type and function designation where specified in paragraph HARDWARE SCHEDULE. Provide a set to include head and jamb seals, sweep strips, and, for pairs of doors, astragals. Air leakage of weatherstripped doors not to exceed 0.5 cubic feet per minute of air per square foot of door area when tested in accordance with ASTM E283. Provide weatherstripping with one of the following:

2.3.13.1 Extruded Aluminum Retainers

Extruded aluminum retainers not less than 0.050 inch wall thickness with vinyl, neoprene, silicone rubber, or polyurethane inserts. Provide anodized aluminum.

2.3.13.2 Interlocking Type

Zinc or bronze not less than 0.018 inch thick.

2.3.14 Rain Drips

Provide in accordance with ANSI/BHMA A156.22. Provide extruded aluminum rain drips, not less than 0.08 inch thick, anodized factory painted finish. Provide the manufacturer's full range of color choices to the Contracting Officer for color selection. Provide rain drips with a 4 inch overlap on each side of each exterior door that is not protected by an awning, roof, eave or other horizontal projection. Set drips in sealant and fasten with stainless steel screws.

2.3.14.1 Door Rain Drips

Approximately 1-1/2 inch high by 5/8 inch projection. Align bottom with bottom edge of door.

2.3.14.2 Overhead Rain Drips

Approximately 1-1/2 inch high by 2-1/2 inch projection. Align bottom with door frame rabbet.

2.3.15 Auxiliary Hardware (Other than locks)

Provide in accordance with ANSI/BHMA A156.16, Grade 1.

2.3.16 Special Tools

Provide special tools, such as spanner and socket wrenches and dogging keys, as required to service and adjust hardware items.

2.4 FASTENERS

Provide fasteners of type, quality, size, and quantity appropriate to the

specific application. Fastener finish to match hardware. Provide stainless steel or nonferrous metal fasteners in locations exposed to weather. Verify metals in contact with one another are compatible and will avoid galvanic corrosion when exposed to weather.

2.5 FINISHES

Provide in accordance with ANSI/BHMA A156.18. Provide hardware in BHMA 630 finish (satin stainless steel), unless specified otherwise. Provide hinges for exterior doors in stainless steel with BHMA 630 finish. Furnish exit devices in BHMA 626 finish in lieu of BHMA 630 finish . Match exposed parts of concealed closers to lock and door trim.

PART 3 EXECUTION

3.1 INSTALLATION

Provide hardware in accordance with manufacturers' printed installation instructions. Fasten hardware to wood surfaces with full-threaded wood screws or sheet metal screws. Provide machine screws set in expansion shields for fastening hardware to solid concrete and masonry surfaces. Provide toggle bolts where required for fastening to hollow core construction. Provide through bolts where necessary for satisfactory installation.

3.1.1 Weatherstripping Installation

Provide full contact, weathertight seals that allow operation of doors without binding the weatherstripping.

3.1.1.1 Stop Applied Weatherstripping

Fasten in place with color matched sheet metal screws not more than 9 inch on center after doors and frames have been finish painted.

3.1.1.2 Interlocking Type Weatherstripping

Provide interlocking, self adjusting type on heads and jambs and flexible hook type at sills. Nail weatherstripping to door 1 inch on center and to heads and jambs at 4 inch on center.

3.1.1.3 Spring Tension Type Weatherstripping

Provide spring tension type on heads and jambs. Provide bronze nails with bronze. Provide stainless steel nails with stainless steel. Space nails not more than 1-1/2 inch on center.

3.1.2 Threshold Installation

Extend thresholds the full width of the opening and notch end for jamb stops. Set thresholds in a full bed of sealant and anchor to floor with cadmium-plated, countersunk, steel screws in expansion sleeves. For aluminum thresholds placed on top of concrete surfaces, coat the underside surfaces that are in contact with the concrete with fluid applied waterproofing as a separation measure prior to placement.

3.2 FIRE DOORS AND EXIT DOORS

Provide hardware in accordance with NFPA 72 for door alarms, NFPA 80 for fire doors, NFPA 101 for exit doors, and NFPA 252 for fire tests of door assemblies.

3.3 HARDWARE LOCATIONS

Provide in accordance with SDI/DOOR A250.8, unless indicated or specified otherwise.

a. Kick and Armor Plates: Push side of single-acting doors.

b. Mop Plates: Bottom flush with bottom of door.

3.4 FIELD QUALITY CONTROL

After installation, protect hardware from paint, stains, blemishes, and other damage until acceptance of work. Submit notice of testing 15 days before scheduled, so that testing can be witnessed by the Contracting Officer. Adjust hinges, locks, latches, bolts, holders, closers, and other items to operate properly. Demonstrate that permanent keys operate respective locks, and give keys to the Contracting Officer. Correct, repair, and finish, errors in cutting and fitting and damage to adjoining work.

3.5 HARDWARE SETS

HARDWARE SET No. 1

3 HINGES BB1199 4 1/2 X 4 1/2 NRP US32D HA
1 RIM CYLINDER 1E-72 STD US26D BE
1 EXIT DEVICE 98NL X 992L-NL US32D VO
1 CLOSER UNI-7500-H SN-134 689 NO
1 SADDLE THRESHOLD 424 X DW AL NGP
1 GASKETING 127 NA 1 X DW + 2 X DH NGP
1 DOOR BOTTOM 319 VA X DW NGP
110 degree swing

Manufacturers List Code	Manufacturers Name:
BE	Best Lock
IV	H.B. Ives
KA	Kawneer
MC	McKinney
NGP	National Guard
NO	Norton
RO	Rockwood
RX	Rixson
HA	Hagar
TR	Trimco
VO	Von Duprin

-- End of Section --

SECTION 08 81 00

GLAZING
05/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 800	(2016) Voluntary Specifications and Test Methods for Sealants

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z97.1	(2015) Safety Glazing Materials Used in Buildings - Safety Performance Specifications and Methods of Test

ASTM INTERNATIONAL (ASTM)

ASTM C509	(2006; R 2015) Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM C864	(2005; R 2015) Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers
ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants
ASTM C1021	(2008; R 2014) Standard Practice for Laboratories Engaged in Testing of Building Sealants
ASTM C1036	(2016) Standard Specification for Flat Glass
ASTM C1048	(2018) Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass
ASTM C1087	(2016) Standard Test Method for Determining Compatibility of Liquid-Applied Sealants with Accessories Used in Structural Glazing Systems
ASTM C1172	(2019) Standard Specification for Laminated Architectural Flat Glass
ASTM C1184	(2014) Standard Specification for Structural Silicone Sealants

ASTM C1281	(2016) Standard Specification for Preformed Tape Sealants for Glazing Applications
ASTM D395	(2016; E 2017) Standard Test Methods for Rubber Property - Compression Set
ASTM D2287	(2019) Nonrigid Vinyl Chloride Polymer and Copolymer Molding and Extrusion Compounds
ASTM E1300	(2016) Standard Practice for Determining Load Resistance of Glass in Buildings
ASTM E2190	(2010) Standard Specification for Insulating Glass Unit Performance and Evaluation

GLASS ASSOCIATION OF NORTH AMERICA (GANA)

GANA Glazing Manual	(2008) Glazing Manual
GANA Sealant Manual	(2008) Sealant Manual

INSULATING GLASS MANUFACTURERS ALLIANCE (IGMA)

IGMA TB-1200	(1983; R 2016) Guidelines for Insulating Glass Dimensional Tolerances
IGMA TB-3001	(2001) Guidelines for Sloped Glazing
IGMA TM-3000	(1990; R 2016) North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial & Residential Use

NATIONAL FENESTRATION RATING COUNCIL (NFRC)

NFRC 100	(2017) Procedure for Determining Fenestration Product U-Factors
NFRC 200	(2017) Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

16 CFR 1201	Safety Standard for Architectural Glazing Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Insulating Glass

Plastic Glazing

Glazing Accessories

Sealants

Joint Backer

SD-04 Samples

Insulating Glass

Plastic Sheet

Glazing Compound

Glazing Tape

Sealing Tapes

SD-07 Certificates

Insulating Glass

SD-08 Manufacturer's Instructions

Setting and Sealing Materials

Glass Setting

SD-11 Closeout Submittals

Warranty for Insulated Glass Units

1.3 SYSTEM DESCRIPTION

Fabricate and install watertight and airtight glazing systems to withstand thermal movement and wind loading without glass breakage, gasket failure, deterioration of glazing accessories, or defects in the work. Glazed panels must comply with the safety standards, in accordance with ANSI Z97.1, and comply with indicated wind/snow loading in accordance with ASTM E1300.

1.4 QUALITY CONTROL

Submit two 8 by 10 inch samples of each of the following: insulating glass units.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver products to the site in unopened containers, labeled plainly with manufacturers' names and brands. Store glass and setting materials in safe, enclosed dry locations and do not unpack until needed for installation. Handle and install materials in a manner that will protect

them from damage.

1.6 ENVIRONMENTAL REQUIREMENTS

Do not start glazing work until the outdoor temperature is above40 degrees F and rising, unless procedures recommended by the glass manufacturer and approved by the Contracting Officer are made to warm the glass and rabbet surfaces. Provide ventilation to prevent condensation of moisture on glazing work during installation. Do not perform glazing work during damp or rainy weather.

1.7 WARRANTY

1.7.1 Warranty for Insulated Glass Units

Warranty insulating glass units against development of material obstruction to vision (such as dust, fogging, or film formation on the inner glass surfaces) caused by failure of the hermetic seal, other than through glass breakage, for a 10-year period following acceptance of the work. Provide new units for any units failing to comply with terms of this warranty within 45 working days after receipt of notice from the Government.

PART 2 PRODUCTS

2.1 PRODUCT SUSTAINABILITY CRITERIA

2.2 GLASS

ASTM C1036, unless specified otherwise. In doors and sidelights, provide safety glazing material conforming to 16 CFR 1201.

2.2.1 Annealed Glass

Annealed glass must be Type I transparent flat type, Class 1 - clear, Quality q3 - glazing select, conforming to ASTM C1036.

2.2.2 Laminated Glass

ASTM C1172, Laminated glass fabricated from two nominal 1/8 inch pieces of Type I, Class 1, clearglass conforming to ASTM C1036. Flat glass to be laminated together with a minimum of 0.030 inch inch thick, clear polyvinyl butyrallaminate, conforming to requirements of 16 CFR 1201 and ASTM C1172. The total thickness of nominally 1/4 inches. Color to be clear. Provide a glazing frame bite in accordance with ASTM F 2248.

2.3 INSULATING GLASS UNITS

Two panes of glass separated by a dehydrated airspace, filled with argon gas, or filled with krypton gas, or filled with aerogel and hermetically sealed, conforming to ASTM E2190. Submit performance and compliance documentation for each type of insulating glass.

Insulated glass units must have a Solar Heat Gain Coefficient (SHGC) maximum of 0.24 determined according to NFRC 200 and a U-factor maximum of 0.24 Btu per square foot by hr by degree F in accordance with NFRC 100. Glazing must meet or exceed a luminous efficacy of 1.0. Glazed panels must be rated for not less than 26 Sound Transmission Class (STC) when tested for laboratory sound transmission loss acco rding to ASTM E90 and determined by ASTM E413.

Dimensional tolerances must be as specified in IGMA TB-1200. Spacer must be black, roll-formed, thermally broken aluminum with bent or tightly welded or keyed and sealed joints to completely seal the spacer periphery and eliminate moisture and hydrocarbon vapor transmission into airspace through the corners. Primary seal must be compressed polyisobutylene and the secondary seal must be a specially formulated silicone.

The inner light must be ASTM C1036, Type I, Class 1, Quality q4, 1/4 inch thick.

The outer light must be ASTM C1036, Type I, Class 2 (solar-reflective), Quality q4, 1/4" inch thick

2.3.1 Low Emissivity Coatings

Interior and exterior glass panes for Low-E insulating units must be Type I annealed flat glass, Class 1-clear with anti-reflective low-emissivity coating or heat-strengthened or fully tempered glass complying with ASTM C1048, Condition C on No. 2 surface (inside surface of exterior pane) Quality q3 - glazing select, conforming to ASTM C1036. Glass performance must be U value maximum of 0.54Btu/hr-ft2-F, Solar Heat Gain Coefficient (SHGC) maximum of 0.24.

2.4 SETTING AND SEALING MATERIALS

Provide as specified in the GANA Glazing Manual, IGMA TM-3000, IGMA TB-3001, and manufacturer's recommendations, unless specified otherwise herein. Do not use metal sash putty, nonskinning compounds, nonresilient preformed sealers, or impregnated preformed gaskets. Materials exposed to view and unpainted must be gray or neutral color. Sealant testing must be performed by a testing agency qualified according to ASTM C1021.

Submit glass manufacturer's recommendations for setting and sealing materials and for installation of each type of glazing material specified.

2.4.1 Putty and Glazing Compound

Provide glazing compound as recommended by manufacturer for face-glazing metal sash. Putty must be linseed oil type. Do not use putty and glazing compounds with insulating glass or laminated glass.

2.4.2 Glazing Compound

Use for face glazing metal sash. Do not use with insulating glass units or laminated glass.

2.4.3 Sealants

Provide elastomeric sealants.

2.4.3.1 Elastomeric Sealant

ASTM C920, Type S, Grade NS, Class 12.5, Use G. Use for channel or stop glazing wood and metal sash. Sealants must be chemically compatible with setting blocks, edge blocks, and sealing tapes, with sealants used in manufacture of insulating glass units . Color of sealant must be white.

2.4.3.2 Structural Sealant

ASTM C1184, Type S.

2.4.4 Joint Backer

Joint backer must have a diameter size at least 25 percent larger than joint width; type and material as recommended in writing by glass and sealant manufacturer.

2.4.5 Glazing Tapes

2.4.5.1 Back-Bedding Mastic Glazing Tapes

Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C1281 and AAMA 800 for products indicated below:

a. AAMA 804.3 tape, where indicated.

b. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.

c. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.

2.4.5.2 Expanded Cellular Glazing Tapes

Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:

a. AAMA 810.1, Type 1, for glazing applications in which tape acts as the primary sealant.

b. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

2.4.6 Sealing Tapes

Preformed, semisolid, PVC-based material of proper size and compressibility for the particular condition, complying with ASTM D2287. Use only where glazing rabbet is designed for tape and tape is recommended by the glass or sealant manufacturer. Provide spacer shims for use with compressible tapes. Tapes must be chemically compatible with the product being set.

2.4.7 Setting Blocks and Edge Blocks

Closed-cell neoprene setting blocks must be dense extruded type conforming to ASTM C509 and ASTM D395, Method B, Shore A durometer between 70 and 90. Edge blocking must be Shore A durometer of 50 (plus or minus 5). Provide silicone setting blocks when blocks are in contact with silicone sealant. Profiles, lengths and locations must be as required and recommended in writing by glass manufacturer. Block color must be black.

2.4.8 Glazing Gaskets

Glazing gaskets must be extruded with continuous integral locking

projection designed to engage into metal glass holding members to provide a watertight seal during dynamic loading, building movements and thermal movements. Glazing gaskets for a single glazed opening must be continuous one-piece units with factory-fabricated injection-molded corners free of flashing and burrs. Glazing gaskets must be in lengths or units recommended by manufacturer to ensure against pull-back at corners. Provide glazing gasket profiles as recommended by the manufacturer for the intended application.

2.4.8.1 Fixed Glazing Gaskets

Fixed glazing gaskets must be closed-cell (sponge) smooth extruded compression gaskets of cured elastomeric virgin neoprene compounds conforming to ASTM C509, Type 2, Option 1.

2.4.8.2 Wedge Glazing Gaskets

Wedge glazing gaskets must be high-quality extrusions of cured elastomeric virgin neoprene compounds, ozone resistant, conforming to ASTM C864, Option 1, Shore A durometer between 65 and 75.

2.4.8.3 Aluminum Framing Glazing Gaskets

Glazing gaskets for aluminum framing must be permanent, elastic, non-shrinking, non-migrating, watertight and weathertight.

2.4.9 Accessories

Provide as required for a complete installation, including glazing points, clips, shims, angles, beads, and spacer strips. Provide noncorroding metal accessories. Provide primer-sealers and cleaners as recommended by the glass and sealant manufacturers. Use ASTM C1087 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of glazing sealants to surface.

PART 3 EXECUTION

Any materials that show visual evidence of biological growth due to the presence of moisture must not be installed on the building project.

3.1 PREPARATION

Preparation, unless otherwise specified or approved, must conform to applicable recommendations in the GANA Glazing Manual, GANA Sealant Manual, IGMA TB-3001, IGMA TM-3000, and manufacturer's recommendations. Determine the sizes to provide the required edge clearances by measuring the actual opening to receive the glass. Grind smooth in the shop glass edges that will be exposed in finish work. Leave labels in place until the installation is approved, except remove applied labels on heat-absorbing glass and on insulating glass units as soon as glass is installed. Securely fix movable items or keep in a closed and locked position until glazing compound has thoroughly set.

3.2 GLASS SETTING

Shop glaze or field glaze items to be glazed using glass of the quality and thickness specified or indicated. Glazing, unless otherwise specified or approved, must conform to applicable recommendations in the GANA Glazing Manual, GANA Sealant Manual, IGMA TB-3001, IGMA TM-3000, and

manufacturer's recommendations. Aluminum windows, wood doors, and wood windows may be glazed in conformance with one of the glazing methods described in the standards under which they are produced, except that face puttying with no bedding will not be permitted. Handle and install glazing materials in accordance with manufacturer's instructions. Use beads or stops which are furnished with items to be glazed to secure the glass in place. Verify products are properly installed, connected, and adjusted.

3.2.1 Sheet Glass

Cut and set with the visible lines or waves horizontal.

3.2.2 Insulating Glass Units

Do not grind, nip, or cut edges or corners of units after the units have left the factory. Springing, forcing, or twisting of units during setting will not be permitted. Handle units so as not to strike frames or other objects. Installation must conform to applicable recommendations of IGMA TB-3001 and IGMA TM-3000.

3.2.3 Installation of Laminated Glass

Sashes which are to receive laminated glass must be weeped to the outside to allow water drainage into the channel.

3.3 CLEANING

Clean glass surfaces and remove labels, paint spots, putty, and other defacement as required to prevent staining. Glass must be clean at the time the work is accepted.

3.4 PROTECTION

Protect glass work immediately after installation. Identify glazed openings with suitable warning tapes, cloth or paper flags, attached with non-staining adhesives. Protect reflective glass with a protective material to eliminate any contamination of the reflective coating. Place protective material far enough away from the coated glass to allow air to circulate to reduce heat buildup and moisture accumulation on the glass. Upon removal, separate protective materials for reuse or recycling. Remove and replace glass units which are broken, chipped, cracked, abraded, or otherwise damaged during construction activities with new units.

-- End of Section --

SECTION 09 29 00

GYPSUM BOARD
08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C475/C475M	(2017) Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board
ASTM C840	(2020) Standard Specification for Application and Finishing of Gypsum Board
ASTM C954	(2018) Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs from 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness
ASTM C1002	(2018) Standard Specification for Steel Self-Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs
ASTM C1047	(2019) Standard Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base
ASTM C1177/C1177M	(2017) Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing
ASTM C1396/C1396M	(2017) Standard Specification for Gypsum Board
ASTM D412	(2016) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D624	(2000; R 2020) Standard Test Method for Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers
ASTM D1149	(2007; R 2012) Standard Test Method for Rubber Deterioration - Surface Ozone Cracking in a Chamber

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

GYPSUM ASSOCIATION (GA)

GA 214	(2010) Recommended Levels of Gypsum Board Finish
GA 216	(2010) Application and Finishing of Gypsum Panel Products
GA 253	(2012) Application of Gypsum Sheathing

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2017) Adhesive and Sealant Applications

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Glass Mat Covered or Reinforced Gypsum Sheathing

Glass Mat Covered or Reinforced Gypsum Sheathing Sealant

Accessories

Gypsum Board

SD-07 Certificates

Asbestos Free Materials; G

Certify that gypsum board types, gypsum backing board types, cementitious backer units, and joint treating materials do not contain asbestos.

1.3 DELIVERY, STORAGE, AND HANDLING

1.3.1 Delivery

Deliver materials in the original packages, containers, or bundles with

each bearing the brand name, applicable standard designation, and name of manufacturer, or supplier.

1.3.2 Storage

Keep materials dry by storing inside a sheltered building. Where necessary to store gypsum board and cementitious backer units outside, store off the ground, properly supported on a level platform, and protected from direct exposure to rain, snow, sunlight, and other extreme weather conditions. Provide adequate ventilation to prevent condensation. Store per manufacturer's recommendations for allowable temperature and humidity range.

Do not store gypsum wallboard with materials which have high emissions of volatile organic compounds (VOCs) or other contaminants. Do not store panels near materials that may offgas or emit harmful fumes, such as kerosene heaters, fresh paint, or adhesives. Do not use materials that have visible moisture or biological growth.

1.3.3 Handling

Neatly stack gypsum board and cementitious backer units flat to prevent sagging or damage to the edges, ends, and surfaces.

1.4 QUALIFICATIONS

Furnish type of gypsum board work specialized by the installer with a minimum of 3] years of documented successful experience.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to specifications, standards and requirements specified. Provide gypsum board types, gypsum backing board types, cementitious backing units, and joint treating materials manufactured from asbestos free materials only.

Submit Safety Data Sheets and manufacturer maintenance instructions for gypsum materials including adhesives.

2.1.1 Gypsum Board

ASTM C1396/C1396M.

2.1.1.1 Regular

48 inch wide, 5/8 inch thick, tapered edges.

2.1.2 Glass Mat Covered or Reinforced Gypsum Sheathing

Exceeds physical properties of ASTM C1396/C1396M and ASTM C1177/C1177M. Provide 1/2 inch, gypsum sheathing. Provide gypsum board of with a noncombustible water-resistant core, with glass mat surfaces embedded to the gypsum core or reinforcing embedded throughout the gypsum core. Warrant gypsum sheathing board for at least twelve months against delamination due to direct weather exposure. Provide continuous, vapor barrier as specified. Seal all joints, seams, and penetrations with compatible sealant.

2.1.2.1 Glass Mat Covered or Reinforced Gypsum Sheathing Sealant

Provide sealant compatible with glass mat covered or reinforced gypsum

sheathing, rubber washers for masonry veneer anchors, and other associated cavity wall components such as anchors and through wall flashing. Provide sealants for glass mat covered or reinforced gypsum sheathing board edge seams and veneer anchor penetrations recommended by the glass mat covered or reinforced gypsum sheathing manufacturer and have the following performance requirements:

a. ASTM D412: Tensile Strength, 80 psi
b. ASTM D412: Ultimate Tensile Strength (maximum elongation), 170 psi
c. ASTM D624: Tear Strength, dieB, 27 ppi
d. ASTM D1149: Joint Movement Capability after 14 Days cure, plus or minus 50 percent.

2.1.3 Joint Treatment Materials

ASTM C475/C475M. Product must be low emitting VOC types with VOC limits not exceeding 50 g/L. Provide data identifying VOC content of joint compound. Use all purpose joint and texturing compound containing inert fillers and natural binders, including lime compound. Pre-mixed compounds must be free of antifreeze, vinyl adhesives, preservatives, biocides and other slow releasing compounds.

2.1.3.1 Embedding Compound

Specifically formulated and manufactured for use in embedding tape at gypsum board joints and compatible with tape, substrate and fasteners.

2.1.3.2 Finishing or Topping Compound

Specifically formulated and manufactured for use as a finishing compound.

2.1.3.3 All-Purpose Compound

Specifically formulated and manufactured to serve as both a taping and a finishing compound and compatible with tape, substrate and fasteners.

2.1.3.4 Setting or Hardening Type Compound

Specifically formulated and manufactured for use with fiber glass mesh tape.

2.1.3.5 Joint Tape

Use cross-laminated, tapered edge, reinforced paper, or fiber glass mesh tape recommended by the manufacturer.

2.1.4 Fasteners

2.1.4.1 Screws

ASTM C1002, Type "G", Type "S" or Type "W" steel drill screws for fastening gypsum board to gypsum board, wood framing members and steel framing members less than 0.033 inch thick. ASTM C954 steel drill screws for fastening gypsum board to steel framing members 0.033 to 0.112 inch thick. Provide cementitious backer unit screws with a polymer coating.

2.1.5 Adhesives

Provide non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions

requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for non-aerosol adhesives applied on the interior of the building (inside of the weatherproofing system). Provide certification or validation of indoor air quality for aerosol adhesives used on the interior of the building (inside of the weatherproofing system).

2.1.5.1 Adhesive for Fastening Gypsum Board to Metal Framing

Not permitted.

2.1.5.2 Adhesive for Fastening Gypsum Board to Wood Framing

Not permitted.

2.1.5.3 Adhesive for Laminating

Not permitted.

2.1.6 Gypsum Studs

Provide one inch minimum thickness and 6 inch minimum width. Studs may be of one inch thick gypsum board or multilayers fastened to required thickness. Conform to ASTM C1396/C1396M for material and GA 216 for installation.

2.1.7 Accessories

ASTM C1047. Fabricate from corrosion protected steel or plastic designed for intended use. Accessories manufactured with paper flanges are not acceptable. Flanges must be free of dirt, grease, and other materials that may adversely affect bond of joint treatment. Provide prefinished materials.

2.1.8 Water

Provide clean, fresh, and potable water.

PART 3 EXECUTION

3.1 EXAMINATION

3.1.1 Framing and Furring

Verify that framing and furring are securely attached and of sizes and spacing to provide a suitable substrate to receive gypsum board and cementitious backer units. Verify that all blocking, headers and supports are in place to support plumbing fixtures and to receive soap dishes, grab bars, towel racks, and similar items. Do not proceed with work until framing and furring are acceptable for application of gypsum board and cementitious backer units.

3.1.2 Gypsum Board and Framing

Verify that surfaces of gypsum board and framing to be bonded with an adhesive are free of dust, dirt, grease, and any other foreign matter. Do not proceed with work until surfaces are acceptable for application of gypsum board with adhesive.

3.1.3 Masonry and Concrete Walls

Verify that surfaces of masonry and concrete walls to receive gypsum board applied with adhesive are dry, free of dust, oil, form release agents, protrusions and voids, and any other foreign matter. Do not proceed with work until surfaces are acceptable for application of gypsum board with adhesive.

3.1.4 Building Construction Materials

Do not install building construction materials that show visual evidence of biological growth.

3.2 APPLICATION OF GYPSUM BOARD

Apply gypsum board to framing and furring members in accordance with ASTM C840 or GA 216 and the requirements specified. Apply gypsum board with separate panels in moderate contact; do not force in place. Stagger end joints of adjoining panels. Neatly fit abutting end and edge joints. Use gypsum board of maximum practical length; select panel sizes to minimize waste. Cut out gypsum board to make neat, close, and tight joints around openings. In vertical application of gypsum board, provide panels in lengths required to reach full height of vertical surfaces in one continuous piece. Lay out panels to minimize waste; reuse cutoffs whenever feasible. Surfaces of gypsum board and substrate members may not be bonded together with an adhesive. Treat edges of cutouts for plumbing pipes, screwheads, and joints with water-resistant compound as recommended by the gypsum board manufacturer.

3.2.1 Application of Gypsum Board to Steel Framing and Furring

Apply in accordance with ASTM C840, System VIII or GA 216.

3.2.2 Exterior Application

Apply exterior gypsum board (such as at soffits) in accordance with ASTM C840, System XI or GA 216.

3.2.3 Glass Mat Covered or Fiber Reinforced Gypsum Sheathing

Apply glass mat covered or fiber reinforced gypsum sheathing in accordance to gypsum association publications GA 253. Follow gypsum sheathing manufacturer's requirements of design details for joints and fasteners and be properly installed to protect the substrate from moisture intrusion. Do not leave exposed surfaces of the glass mat covered or fiber reinforced gypsum sheathing beyond the manufacturer's recommendation without a weather barrier cladding. Provide continuous asphalt impregnated building felt over sheathing surface in shingle fashion with edges and ends lapped a minimum of 6 inch. Properly flash the openings. Seal all joints, seams, and penetrations with a compatible silicone sealant.

3.2.4 Control Joints

Install expansion and contraction joints in ceilings and walls in accordance with ASTM C840, System XIII or GA 216. Fill control joints between studs in fire-rated construction with firesafing insulation to match the fire-rating of construction.

3.3 FINISHING OF GYPSUM BOARD

Tape and finish gypsum board in accordance with ASTM C840, GA 214 and GA 216. Finish plenum areas above ceilings to Level 1 in accordance with GA 214. Finish water resistant gypsum backing board, ASTM C1396/C1396M, to receive ceramic tile to Level 2 in accordance with GA 214. Finish walls and ceilings to receive a heavy-grade wall covering or heave textured finish before painting to Level 3 in accordance with GA 214. Finish walls and ceilings without critical lighting to receive flat paints, light textures, or wall coverings to Level 4 in accordance with GA 214. Unless otherwise specified, finish all gypsum board walls, partitions and ceilings to Level 5 in accordance with GA 214. Provide joint, fastener depression, and corner treatment. Tool joints as smoothly as possible to minimize sanding and dust. Do not use self-adhering fiber glass mesh tape with conventional drying type joint compounds; use setting or hardening type compounds only. Provide treatment for water-resistant gypsum board as recommended by the gypsum board manufacturer. Protect workers, building occupants, and HVAC systems from gypsum dust.

3.3.1 Uniform Surface

Wherever gypsum board is to receive eggshell, semigloss or gloss paint finish, or where severe, up or down lighting conditions occur, finish gypsum wall surface in accordance to GA 214 Level 5. In accordance with GA 214 Level 5, apply a thin skim coat of joint compound to the entire gypsum board surface, after the two-coat joint and fastener treatment is complete and dry.

3.4 SEALING

Seal openings around pipes, fixtures, and other items projecting through gypsum board and cementitious backer units as specified in Section 07 92 00 JOINT SEALANTS. Apply material with exposed surface flush with gypsum board or cementitious backer units.

3.4.1 Sealing for Glass Mat or Reinforced Gypsum Board Sheathing

Apply silicone sealant in a 3/8 inch bead to all joints and trowel flat. Apply enough of the same sealant to all fasteners penetrating through the glass mat gypsum board surface to completely cover the penetration when troweled flat. Do not place construction and materials behind sheathing until a visual inspection of sealed joints during daylight hours has been completed by Contracting Officer.

3.5 PATCHING

Patch surface defects in gypsum board to a smooth, uniform appearance, ready to receive finishes.

-- End of Section --

SECTION 09 90 00

PAINTS AND COATINGS
02/21

PART 1 GENERAL

1.1 RELATED REQUIREMENTS

1.1.1 Painting Included

Where a space or surface is indicated to be painted, include the following unless indicated otherwise.

a. Surfaces behind portable objects and surface mounted articles readily detachable by removal of fasteners, such as screws and bolts.

b. New factory finished surfaces that require identification or color coding and factory finished surfaces that are damaged during performance of the work.

c. Existing coated surfaces that are damaged during performance of the work.

1.1.1.1 Exterior Painting

Includes new surfaces, existing coated surfaces, and existing uncoated surfaces, of the building and appurtenances. Also included are existing coated surfaces made bare by cleaning operations.

1.1.1.2 Interior Painting

Includes new surfaces, existing uncoated surfaces, and existing coated surfaces of the building and appurtenances as indicated and existing coated surfaces made bare by cleaning operations. Where a space or surface is indicated to be painted, include the following items, unless indicated otherwise.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH 0100	(2017; Suppl 2020) Documentation of the Threshold Limit Values and Biological Exposure Indices

ASTM INTERNATIONAL (ASTM)

ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants
ASTM D235	(2002; R 2012) Mineral Spirits (Petroleum Spirits) (Hydrocarbon Dry Cleaning Solvent)

ASTM D523	(2014; R 2018) Standard Test Method for Specular Gloss
ASTM D2824/D2824M	(2018) Standard Specification for Aluminum-Pigmented Asphalt Roof Coatings, Non-Fibered, and Fibered without Asbestos
ASTM D4214	(2007; R 2015) Standard Test Method for Evaluating the Degree of Chalking of Exterior Paint Films
ASTM D4263	(1983; R 2018) Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D4444	(2013; R 2018) Standard Test Method for Laboratory Standardization and Calibration of Hand-Held Moisture Meters
ASTM D6386	(2016a) Standard Practice for Preparation of Zinc (Hot-Dip Galvanized) Coated Iron and Steel Product and Hardware Surfaces for Painting
ASTM F1869	(2016a) Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride

CENTERS FOR DISEASE CONTROL AND PREVENTION (CDC)

Intelligence Bulletin 65	(2013) Occupational Exposure to Carbon Nanotubes and Nanofibers

MASTER PAINTERS INSTITUTE (MPI)

MPI 1	(2012) Aluminum Paint
MPI 2	(2012) Aluminum Heat Resistant Enamel (up to 427 C and 800 F
MPI 3	(2016) Primer, Alkali Resistant, Water Based
MPI 4	(2016) Interior/Exterior Latex Block Filler
MPI 5	(2015) Primer, Exterior Alkyd Wood
MPI 6	(2015) Primer, Exterior Latex Wood
MPI 8	(2016) Alkyd, Exterior Flat (MPI Gloss Level I)
MPI 9	(2016) Alkyd, Exterior Gloss (MPI Gloss Level 6)
MPI 10	(2016) Latex, Exterior Flat (MPI Gloss Level 1)
MPI 11	(2016) Latex, Exterior Semi-Gloss, MPI

	Gloss Level 5
MPI 13	(2016) Stain, Exterior Solvent-Based, Semi-Transparent
MPI 16	(2016) Stain, Exterior, Water Based, Solid Hide
MPI 17	(2016) Primer, Bonding, Water Based
MPI 19	(2012) Primer, Zinc Rich, Inorganic
MPI 21	(2012) Heat Resistant Coating, (Up to 205°C/402°F), MPI Gloss Level 6
MPI 22	(2012) Aluminum Paint, High Heat (up to 590° C/1100° F)
MPI 23	(2015) Primer, Metal, Surface Tolerant
MPI 27	(2016) Floor Enamel, Alkyd, Gloss (MPI Gloss Level 6)
MPI 31	(2012) Varnish, Polyurethane, Moisture Cured, Gloss (MPI Gloss Level 6)
MPI 38	(2016) Elastomeric Coating, Exterior, Water Based, Non-Flat
MPI 39	(2018) Primer, Latex, for Interior Wood
MPI 42	(2012) Textured Coating, Latex, Flat
MPI 44	(2016) Latex, Interior, (MPI Gloss Level 2)
MPI 45	(2016) Primer Sealer, Interior Alkyd
MPI 46	(2016) Undercoat, Enamel, Interior
MPI 47	(2016) Alkyd, Interior, Semi-Gloss (MPI Gloss Level 5)
MPI 48	(2016) Alkyd, Interior, Gloss (MPI Gloss Level 6-7)
MPI 49	(2015) Alkyd, Interior, Flat (MPI Gloss Level 1)
MPI 50	(2015) Primer Sealer, Latex, Interior
MPI 51	(2016) Alkyd, Interior, (MPI Gloss Level 3)2
MPI 52	(2016) Latex, Interior, (MPI Gloss Level 3)
MPI 54	(2016) Latex, Interior, Semi-Gloss (MPI Gloss Level 5)
MPI 56	(2012) Varnish, Interior, Polyurethane,

	Oil Modified, Gloss
MPI 57	(2012) Varnish, Interior, Polyurethane, Oil Modified, Satin
MPI 59	(2016) Floor Paint, Alkyd, Low Gloss
MPI 60	(2016) Floor Paint, Latex, Low Gloss
MPI 68	(2016) Floor Paint, Latex, Gloss
MPI 71	(2012) Varnish, Polyurethane, Moisture Cured, Flat (MPI Gloss Level 1)
MPI 72	(2016) Polyurethane, Two-Component, Pigmented, Gloss (MPI Gloss Level 6-7)
MPI 76	(2016) Primer, Alkyd, Quick Dry, for Metal
MPI 77	(2015) Epoxy, Gloss
MPI 79	(2016) Primer, Alkyd, Anti-Corrosive for Metal
MPI 90	(2012) Stain, Semi-Transparent, for Interior Wood
MPI 94	(2016) Alkyd, Exterior, Semi-Gloss (MPI Gloss Level 5)
MPI 95	(2015) Primer, Quick Dry, for Aluminum
MPI 101	(2016) Primer, Epoxy, Anti-Corrosive, for Metal
MPI 107	(2016) Primer, Rust-Inhibitive, Water Based
MPI 108	(2015) Epoxy, High Build, Low Gloss
MPI 113	(2018) Elastomeric, Pigmented, Exterior, Water Based, Flat
MPI 116	(2012) Block Filler, Epoxy
MPI 119	(2016) Latex, Exterior, Gloss (MPI Gloss Level 6)
MPI 120	(2020) Epoxy, High Build, Self Priming, Low Gloss
MPI 134	(2015) Primer, Galvanized, Water Based
MPI 138	(2016) Latex, Interior, High Performance Architectural, (MPI Gloss Level 2)
MPI 139	(2016) Latex, Interior, High Performance Architectural, (MPI Gloss Level 3)
MPI 140	(2016) Latex, Interior, High Performance

	Architectural, (MPI Gloss Level 4)
MPI 141	(2016) Latex, Interior, High Performance Architectural, Semi-Gloss (MPI Gloss Level 5)
MPI 144	(2016) Latex, Interior, Institutional Low Odor/VOC, (MPI Gloss Level 2)
MPI 145	(2016) Latex, Interior, Institutional Low Odor/VOC, (MPI Gloss Level 3)
MPI 146	(2016) Latex, Interior, Institutional Low Odor/VOC, (MPI Gloss Level 4)
MPI 147	(May 2016) Latex, Interior, Institutional Low Odor/VOC, Semi-Gloss (MPI Gloss Level 5)
MPI 149	(2016) Primer Sealer, Interior, Institutional Low Odor/VOC
MPI 151	(2016) Light Industrial Coating, Interior, Water Based (MPI Gloss Level 3)
MPI 153	(2016) Light Industrial Coating, Interior, Water Based, Semi-Gloss (MPI Gloss Level 5)
MPI 154	(2016) Light Industrial Coating, Interior, Water Based, Gloss (MPI Gloss Level 6)
MPI 161	(2016) Light Industrial Coating, Exterior, Water Based (MPI Gloss Level 3)
MPI 163	(2016) Light Industrial Coating, Exterior, Water Based, Semi-Gloss (MPI Gloss Level 5)
MPI 164	(2016) Light Industrial Coating, Exterior, Water Based, Gloss (MPI Gloss Level 6)
MPI 177	(2020) Epoxy, Semi-Gloss (MPI Gloss Level 5)
MPI 214	(2016) Latex, Exterior (MPI Gloss Level 2)
MPI ASM	(2019) Architectural Painting Specification Manual
MPI GPS-1-14	(2014) Green Performance Standard GPS-1-14
MPI GPS-2-14	(2014) Green Performance Standard GPS-2-14
MPI MRM	(2015) Maintenance Repainting Manual

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC 7/NACE No.4	(2007) Brush-Off Blast Cleaning
SSPC Glossary	(2011) SSPC Protective Coatings Glossary

SSPC Guide 6	(2015) Guide for Containing Surface Preparation Debris Generated During Paint Removal Operations
SSPC Guide 7	(2015) Guide to the Disposal of Lead-Contaminated Surface Preparation Debris
SSPC PA 1	(2016) Shop, Field, and Maintenance Coating of Metals
SSPC SP 1	(2015) Solvent Cleaning
SSPC SP 2	(2018) Hand Tool Cleaning
SSPC SP 3	(2018) Power Tool Cleaning
SSPC SP 6/NACE No.3	(2007) Commercial Blast Cleaning
SSPC SP 10/NACE No. 2	(2007) Near-White Blast Cleaning
SSPC VIS 1	(2002; E 2004) Guide and Reference Photographs for Steel Surfaces Prepared by Dry Abrasive Blast Cleaning
SSPC VIS 3	(2004) Guide and Reference Photographs for Steel Surfaces Prepared by Hand and Power Tool Cleaning
SSPC VIS 4/NACE VIS 7	(1998; E 2000; E 2004) Guide and Reference Photographs for Steel Surfaces Prepared by Waterjetting
SSPC-SP WJ-1/NACE WJ-1	(2012) Clean to Bare Substrate, Waterjet Cleaning of Metals
SSPC-SP WJ-2/NACE WJ-2	(2012) Very Thorough Cleaning, Waterjet Cleaning of Metals
SSPC-SP WJ-3/NACE WJ-3	(2012) Thorough Cleaning, Waterjet Cleaning of Metals
SSPC-SP WJ-4/NACE WJ-4	(2012) Light Cleaning, Waterjet Cleaning of Metals

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2014) Safety and Health Requirements Manual

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA Method 24	(2000) Determination of Volatile Matter Content, Water Content, Density, Volume Solids, and Weight Solids of Surface Coatings

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FED-STD-313	(2018) Material Safety Data, Transportation Data and Disposal Data for Hazardous Materials Furnished to Government Activities

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000	Air Contaminants
29 CFR 1910.1001	Asbestos
29 CFR 1910.1025	Lead
29 CFR 1926.62	Lead

1.3 DEFINITIONS

1.3.1 Qualification Testing

Qualification testing is the performance of all test requirements listed in the product specification. This testing is accomplished by MPI to qualify each product for the MPI Approved Product List, and may also be accomplished by Contractor's third-party testing lab if an alternative to Batch Quality Conformance Testing by MPI is desired.

1.3.2 Batch Quality Conformance Testing

Batch quality conformance testing determines that the product provided is the same as the product qualified to the appropriate product specification. This testing must be accomplished by an MPI testing lab.

1.3.3 Coating

SSPC Glossary; (1) A liquid, liquefiable, or mastic composition that is converted to a solid protective, decorative, or functional adherent film after application as a thin layer; (2) Generic term for paint, lacquer, enamel.

1.3.4 DFT or dft

Dry film thickness, the film thickness of the fully cured, dry paint or coating.

1.3.5 DSD

Degree of Surface Degradation, the MPI system of defining degree of surface degradation. Five levels are generically defined under the Assessment sections in the MPI MRM, MPI Maintenance Repainting Manual.

1.3.6 EXT

MPI short term designation for an exterior coating system.

1.3.7 INT

MPI short term designation for an interior coating system.

1.3.8 Loose Paint

Paint or coating that can be removed with a dull putty knife.

1.3.9 mil / mils

The English measurement for 0.001 in or one one-thousandth of an inch.

1.3.10 MPI Gloss Levels

MPI system of defining gloss. Seven gloss levels (G1 to G7) are generically defined under the Evaluation sections of the MPI Manuals. Traditionally, Flat refers to G1/G2, Eggshell refers to G3, Semigloss refers to G5, and Gloss refers to G6.

Gloss levels are defined by MPI as follows:

Gloss Level	Description	Units at 60 degree angle	Units at 80 degree angle
G1	Matte or Flat	0 to 5	10 max
G2	Velvet	0 to 10	10 to 35
G3	Eggshell	10 to 25	10 to 35
G4	Satin	20 to 35	35 min
G5	Semi-Gloss	35 to 70	
G6	Gloss	70 to 85	
G7	High Gloss		

Gloss is tested in accordance with ASTM D523. Historically, the Government has used Flat (G1 / G2), Eggshell (G3), Semi-Gloss (G5), and Gloss (G6).

1.3.11 MPI System Number

The MPI coating system number in each MPI Division found in either the MPI Architectural Painting Specification Manual or the Maintenance Repainting Manual and defined as an exterior (EXT/REX) or interior system (INT/RIN).

1.3.12 Paint

SSPC Glossary; (1) Any pigmented liquid, liquefiable, or mastic composition designed for application to a substrate in a thin layer that is converted to an opaque solid film after application. Used for protection, decoration, identification, or to serve some other functional purposes; (2) Application of a coating material.

1.3.13 REX

MPI short term designation for an exterior coating system used in repainting projects or over existing coating systems.

1.3.14 RIN

MPI short term designation for an interior coating system used in repainting projects or over existing coating systems.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit non-G submittals to the Government for their record. The Government reserves the right to provide additional comments, request resubmittal, rejection and re-submittal to all the non-G submittals. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Samples of specified materials may be taken and tested for compliance with specification requirements.

SD-02 Shop Drawings

Piping Identification

SD-03 Product Data

Coating; G

Product Data Sheets

Sealant

SD-04 Samples

Color; G

Textured Wall Coating System; G

SD-07 Certificates

Indoor Air Quality for Paints and Primers

Indoor Air Quality for Consolidated Latex Paints

SD-08 Manufacturer's Instructions

Application Instructions

Mixing

Manufacturer's Safety Data Sheets

SD-10 Operation and Maintenance Data

Coatings, Data Package 1; G

1.5 QUALITY ASSURANCE

1.5.1 Regulatory Requirements

1.5.1.1 Environmental Protection

In addition to requirements specified elsewhere for environmental protection, provide coating materials that conform to the restrictions of

the local Air Pollution Control District and regional jurisdiction. Notify Contracting Officer of any paint specified herein which fails to conform.

1.5.1.2 Lead Content

Do not use coatings having a lead content over 0.06 percent by weight of nonvolatile content.

1.5.1.3 Chromate Content

Do not use coatings containing zinc-chromate or strontium-chromate.

1.5.1.4 Asbestos Content

Provide asbestos-free materials.

1.5.1.5 Mercury Content

Provide materials free of mercury or mercury compounds.

1.5.1.6 Silica

Provide abrasive blast media containing no free crystalline silica.

1.5.1.7 Human Carcinogens

Provide materials that do not contain ACGIH 0100 confirmed human carcinogens (A1) or suspected human carcinogens (A2).

1.5.1.8 Carbon Based Fibers / Tubes

Materials must not contain carbon based fibers such as carbon nanotubes or carbon nanofibers. Intelligence Bulletin 65 ranks toxicity of carbon nanotubes on a par with asbestos.

1.5.2 Approved Products List

The current MPI, "Approved Product List" which lists paint by brand, label, product name and product code as of the date of Contract award, will be used to determine compliance with the submittal requirements of this specification. The Contractor may choose to use a subsequent MPI "Approved Product List", however, only one list may be used for the entire Contract and each coating system is to be from a single manufacturer. Provide all coats on a particular substrate from a single manufacturer. No variation from the MPI Approved Products List is acceptable.

1.5.3 Paints and Coatings Indoor Air Quality Certifications

Provide paint and coating products certified to meet indoor air quality requirements by MPI GPS-1-14, MPI GPS-2-14 or provide certification by other third-party programs. Provide current product certification documentation from certification body.

Provide certification of Indoor Air Quality for Paints and Primers. Submit required indoor air quality certifications in one submittal package.

1.5.4 Field Samples and Tests

The Contracting Officer may choose up to two coatings that have been

delivered to the site to be tested at no cost to the Government. Take samples of each chosen product as specified in the paragraph SAMPLING PROCEDURE. Test each chosen product as specified in the paragraph TESTING PROCEDURE. Remove products from the job site which do not conform, and replace with new products that conform to the referenced specification. Test replacement products that failed initial testing as specified in the paragraph TESTING PROCEDURE at no cost to the Government.

1.5.4.1 Sampling Procedure

Select paint at random from the products that have been delivered to the job site for sample testing. The Contractor must provide one quart samples of the selected paint materials. Take samples in the presence of the Contracting Officer, and label, and identify each sample. Provide labels in accordance with the paragraph PACKAGING, LABELING, AND STORAGE.

1.5.4.2 Testing Procedure

Provide Batch Quality Conformance Testing for specified products, as defined by and performed by MPI. As an alternative to Batch Quality Conformance Testing, the Contractor may provide Qualification Testing for specified products above to the appropriate MPI product specification, using the third-party laboratory approved under the paragraph QUALIFICATION TESTING laboratory for coatings. Include the backup data and summary of the test results within the qualification testing lab report. Provide a summary listing of all the reference specification requirements and the result of each test. Clearly indicate in the summary whether the tested paint meets each test requirement. Note that Qualification Testing may take 4 to 6 weeks to perform, due to the extent of testing required.

Submit name, address, telephone number, FAX number, and e-mail address of the independent third party laboratory selected to perform testing of coating samples for compliance with specification requirements. Submit documentation that laboratory is regularly engaged in testing of paint samples for conformance with specifications, and that employees performing testing are qualified. If MPI is chosen to perform the Batch Quality Conformance testing, the above submittal information is not required, only a letter is required from the Contractor stating that MPI will perform the testing.

1.6 PACKAGING, LABELING, AND STORAGE

Provide paints in sealed containers that legibly show the Contract specification number, designation name, formula or specification number, batch number, color, quantity, date of manufacture, manufacturer's formulation number, manufacturer's directions including any warnings and special precautions, and name and address of manufacturer. Furnish pigmented paints in containers not larger than 5 gallons. Store paints and thinners in accordance with the manufacturer's written directions, and as a minimum, stored off the ground, under cover, with sufficient ventilation to prevent the buildup of flammable vapors, and at temperatures between 40 to 95 degrees F. Do not store paint, polyurethane, varnish, or wood stain products with materials that have a high capacity to absorb VOC emissions. Do not store paint, polyurethane, varnish, or wood stain products in occupied spaces.

1.7 SAFETY AND HEALTH

Comply with applicable Federal, State, and local laws and regulations, and

with the ACCIDENT PREVENTION PLAN, including the Activity Hazard Analysis as specified in Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS and in Appendix A of EM 385-1-1. Include in the Activity Hazard Analysis the potential impact of painting operations on painting personnel and on others involved in and adjacent to the work zone.

1.7.1 Toxic Materials

To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

a. The applicable manufacturer's Safety Data Sheets (SDS) or local regulation.

b. 29 CFR 1910.1000.

c. ACGIH 0100, threshold limit values.

d. The appropriate OSHA standard in 29 CFR 1910.1025 and 29 CFR 1926.62 for surface preparation on painted surfaces containing lead. Removal and disposal of coatings which contain lead is specified in Section 02 83 00 LEAD REMEDIATION. Additional guidance is given in SSPC Guide 6 and SSPC Guide 7. Refer to drawings for list of hazardous materials located on this project. Coordinate paint preparation activities with this specification section.

e. The appropriate OSHA standards in 29 CFR 1910.1001 for surface preparation of painted surfaces containing asbestos. Removal and disposal of coatings which contain asbestos materials is specified in Section 02 82 00 ASBESTOS REMEDIATION. Refer to drawings for list of hazardous materials located on this project. Coordinate paint preparation activities with this specification section.

Submit manufacturer's Safety Data Sheets for coatings, solvents, and other potentially hazardous materials, as defined in FED-STD-313.

1.8 ENVIRONMENTAL REQUIREMENTS

Comply, at minimum, with manufacturer recommendations for space ventilation during and after installation.

1.8.1 Coatings

Do not apply coating when air or substrate conditions are:

a. Less than 5 degrees F above dew point;

b. Below 50 degrees F or over 95 degrees F, unless specifically pre-approved by the Contracting Officer and the product manufacturer. Do not, under any circumstances, violate the manufacturer's application recommendations.

1.8.2 Post-Application

Vacate space for as long as possible after application. Wait a minimum of 48 hours before occupying freshly painted rooms. Maintain one of the following ventilation conditions during the curing period, or for 72 hours after application:

a. Supply 100 percent outside air 24 hours a day.

b. Supply airflow at a rate of 6 air changes per hour, when outside temperatures are between 55 degrees F and 85 degrees F and humidity is between 30 percent and 60 percent.

c. Supply airflow at a rate of 1.5 air changes per hour, when outside air conditions are not within the range stipulated above.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to the coating specifications and standards referenced in PART 3. Submit Product Data Sheets for specified coatings and solvents. Provide preprinted cleaning and maintenance instructions for all coating systems. Submit Manufacturer's Instructions on Mixing: Detailed mixing instructions, minimum and maximum application temperature and humidity, pot life, and curing and drying times between coats.

2.2 COLOR SELECTION OF FINISH COATS

Provide colors of finish coats as indicated or specified. Allow Contracting Officer to select colors not indicated or specified. Manufacturers' names and color identification are used for the purpose of color identification only. Named products are acceptable for use only if they conform to specified requirements. Products of other manufacturers are acceptable if the colors are approximately the colors indicated and the product conforms to specified requirements.

Provide color, texture, and pattern of wall coating systems as indicated. Submit manufacturer's samples of paint colors. Cross reference color samples to color scheme as indicated. Submit color stencil codes. Tint each coat progressively darker to enable confirmation of the number of coats.

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED

Prior to surface preparation and coating applications, remove, mask, or otherwise protect hardware, hardware accessories, machined surfaces, radiator covers, plates, lighting fixtures, public and private property, and other such items not to be coated that are in contact with surfaces to be coated. Following completion of painting, reinstall removed items by workmen skilled in the trades. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 RESEALING OF EXISTING EXTERIOR JOINTS

3.2.1 Surface Condition

Begin with surfaces that are clean, dry to the touch, and free from frost and moisture; remove grease, oil, wax, lacquer, paint, defective backstop, or other foreign matter that would prevent or impair adhesion. Where adequate grooves have not been provided, clean out to a depth of 1/2 inch and grind to a minimum width of 1/4 inch without damage to adjoining work. Grinding is not required on metal surfaces.

3.2.2 Backstops

In joints more than 1/2 inch deep, install glass fiber roving or neoprene, butyl, polyurethane, or polyethylene foams free of oil or other staining elements as recommended by sealant manufacturer. Provide backstop material compatible with sealant. Do not use oakum and other types of absorptive materials as backstops.

3.2.3 Primer and Bond Breaker

Install the type recommended by the sealant manufacturer.

3.2.4 Ambient Temperature

Between 38 degrees F and 95 degrees F when applying sealant.

3.2.5 Exterior Sealant

For joints in vertical surfaces, provide ASTM C920, Type S or M, Grade NS, Class 25, Use NT. For joints in horizontal surfaces, provide ASTM C920, Type S or M, Grade P, Class 25, Use T. Color(s) will be selected by the Contracting Officer. Apply the sealant in accordance with the manufacturer's printed instructions. Force sealant into joints with sufficient pressure to fill the joints solidly. Apply sealant uniformly smooth and free of wrinkles.

3.2.6 Cleaning

Immediately remove fresh sealant from adjacent areas using a solvent recommended by the sealant manufacturer. Upon completion of sealant application, remove remaining smears and stains and leave the work in a clean condition. Allow sealant time to cure, in accordance with manufacturer's recommendations, prior to coating.

3.3 SURFACE PREPARATION

Remove dirt, splinters, loose particles, grease, oil, disintegrated coatings, and other foreign matter and substances deleterious to coating performance as specified for each substrate before application of paint or surface treatments. Remove oil and grease prior to mechanical cleaning. Schedule cleaning so that dust and other contaminants will not fall on wet, newly painted surfaces. Spot-prime exposed ferrous metals such as nail heads on or in contact with surfaces to be painted with water-thinned paints, with a suitable corrosion-inhibitive primer capable of preventing flash rusting and compatible with the coating specified for the adjacent areas. Refer to MPI ASM and MPI MRM for additional more specific substrate preparation requirements.

3.3.1 Additional Requirements for Preparation of Surfaces With Existing Coatings

Before application of coatings, perform the following on surfaces covered by soundly-adhered coatings, defined as those which cannot be removed with a putty knife:

a. Test existing finishes for lead before sanding, scraping, or removing. If lead is present, refer to paragraph Toxic Materials.

b. Wipe previously painted surfaces to receive solvent-based coatings,

except stucco and similarly rough surfaces clean with a clean, dry cloth saturated with mineral spirits, ASTM D235 or as specified in MPI MRM. Wipe the surfaces dry with a clean, dry, lint free cloth. Wipe immediately preceding the application of the first coat of any coating, unless specified otherwise.

c. Sand existing glossy surfaces to be painted to reduce gloss. Brush, and wipe clean with a damp cloth to remove dust.

d. The requirements specified are minimum. Comply also with the application instructions of the paint manufacturer and specific surface preparation requirements as outlined in MPI MRM Exterior Surface Preparation and Interior Surface Preparation.

e. Thoroughly clean previously painted surfaces specified to be repainted damaged during construction of all grease, dirt, dust or other foreign matter.

f. Remove blistering, cracking, flaking and peeling or otherwise deteriorated coatings.

g. Remove chalk so that when tested in accordance with ASTM D4214, the chalk resistance rating is no less than 8.

h. Roughen slick surfaces. Repair damaged areas such as, but not limited to, nail holes, cracks, chips, and spalls with suitable material to match adjacent undamaged areas.

i. Feather and sand smooth edges of chipped paint.

j. Clean rusty metal surfaces in accordance with SSPC requirements. Use solvent, mechanical, or chemical cleaning methods to provide surfaces suitable for painting.

k. Provide new, proposed coatings that are compatible with existing coatings.

3.3.2 Existing Coated Surfaces with Minor Defects

Sand, spackle, and treat minor defects to render them smooth. Minor defects are defined as scratches, nicks, cracks, gouges, spalls, alligatoring, chalking, and irregularities due to partial peeling of previous coatings. Remove chalking by sanding or blasting so that when tested in accordance with ASTM D4214, the chalk rating is not less than 8.

3.3.3 Removal of Existing Coatings

Remove existing coatings from the following surfaces:

a. As indicated.

3.3.4 Substrate Repair

a. Repair substrate surface damaged during coating removal;

b. Sand edges of adjacent soundly-adhered existing coatings so they are tapered as smooth as practical to areas involved with coating removal; and

c. Clean and prime the substrate as specified.

3.4 PREPARATION OF METAL SURFACES

3.4.1 Existing and New Ferrous Surfaces

a. Ferrous Surfaces including Shop-coated Surfaces and Small Areas That Contain Rust, Mill Scale and Other Foreign Substances: Solvent clean in accordance with SSPC SP 1 to remove oil and grease. Where shop coat is missing or damaged, clean according to SSPC SP 2, SSPC SP 3, SSPC SP 6/NACE No.3, or SSPC SP 10/NACE No. 2. Brush-off blast remaining surface in accordance with SSPC 7/NACE No.4]; Water jetting to SSPC-SP WJ-4/NACE WJ-4 may be used to remove loose coating and other loose materials. Use inhibitor as recommended by coating manufacturer to prevent premature rusting. Protect shop-coated ferrous surfaces from corrosion by treating and touching up corroded areas immediately upon detection.

3.4.2 Final Ferrous Surface Condition:

3.4.2.1 Tool Cleaned Surfaces

Comply with SSPC SP 2 and SSPC SP 3. Use as a visual reference, photographs in SSPC VIS 3 for the appearance of cleaned surfaces.

3.4.2.2 Abrasive Blast Cleaned Surfaces

Comply with SSPC 7/NACE No.4, SSPC SP 6/NACE No.3, and SSPC SP 10/NACE No. 2. Use as a visual reference, photographs in SSPC VIS 1 for the appearance of cleaned surfaces.

3.4.2.3 Waterjet Cleaned Surfaces

Comply with SSPC-SP WJ-1/NACE WJ-1, SSPC-SP WJ-2/NACE WJ-2, SSPC-SP WJ-3/NACE WJ-3 or SSPC-SP WJ-4/NACE WJ-4. Use as a visual reference, photographs in SSPC VIS 4/NACE VIS 7 for the appearance of cleaned surfaces.

3.4.3 Galvanized Surfaces

a. New or Existing Galvanized Surfaces With Only Dirt and Zinc Oxidation Products: Clean with solvent, or non-alkaline detergent solution in accordance with SSPC SP 1. Completely remove coating by brush-off abrasive blast if the galvanized metal has been passivated or stabilized. Do not "passivate" or "stabilize" new galvanized steel to be coated. If the absence of hexavalent stain inhibitors is not documented, test as described in ASTM D6386, Appendix X2, and remove by one of the methods described therein.

b. Galvanized with Slight Coating Deterioration or with Little or No Rusting: Water jetting to SSPC-SP WJ-3/NACE WJ-3 to remove loose coating from surfaces with less than 20 percent coating deterioration and no blistering, peeling, or cracking. Use inhibitor as recommended by the coating manufacturer to prevent rusting.

3.4.4 Non-Ferrous Metallic Surfaces

Aluminum and aluminum-alloy, lead, copper, and other nonferrous metal

surfaces.

Surface Cleaning: Solvent clean in accordance with SSPC SP 1 and wash with mild non-alkaline detergent to remove dirt and water soluble contaminants.

3.4.5 Existing Surfaces with a Bituminous or Mastic-Type Coating

Remove chalk, mildew, and other loose material by washing with a solution of 1/2 cup trisodium phosphate, 1/4 cup household detergent, one quart 5 percent sodium hypochlorite solution and 3 quarts of warm water.

3.5 PREPARATION OF CONCRETE AND CEMENTITIOUS SURFACE

3.5.1 Concrete and Masonry

a. Curing: Allow concrete, stucco and masonry surfaces to cure at least 30 days before painting, and concrete slab on grade to cure at least 90 days before painting.

b. Surface Cleaning: Remove the following deleterious substances.

(1) Dirt, Chalking, Grease, and Oil: Wash new and existing surfaces with a solution composed of 1/2 cup trisodium phosphate, 1/4 cup household detergent, and 4 quarts of warm water. Then rinse thoroughly with fresh water. Wash existing coated surfaces with a suitable detergent and rinse thoroughly. For large areas, water blasting may be used.

(2) Fungus and Mold: Wash surfaces with a solution composed of 1/2 cup trisodium phosphate, 1/4 cup household detergent, one quart 5 percent sodium hypochlorite solution and 3 quarts of warm water. Rinse thoroughly with fresh water.

(3) Paint and Loose Particles: Remove by wire brushing.

(4) Efflorescence: Remove by scraping or wire brushing followed by washing with a 5 to 10 percent by weight aqueous solution of hydrochloric (muriatic) acid. Do not allow acid to remain on the surface for more than five minutes before rinsing with fresh water. Do not acid clean more than 4 square feet of surface, per workman, at one time.

c. Cosmetic Repair of Minor Defects: Repair or fill mortar joints and minor defects, including but not limited to spalls, in accordance with manufacturer's recommendations and prior to coating application.

d. Allowable Moisture Content: Latex coatings may be applied to damp surfaces, but not to surfaces with droplets of water. Do not apply epoxies to damp vertical surfaces as determined by ASTM D4263 or horizontal surfaces that exceed 3 lbs of moisture per 1000 square feet in 24 hours as determined by ASTM F1869. In all cases follow manufacturer's recommendations. Allow surfaces to cure a minimum of 30 days before painting.

3.5.2 Gypsum Board, Plaster, and Stucco

3.5.2.1 Surface Cleaning

Verify that plaster and stucco surfaces are free from loose matter and that

gypsum board is dry. Remove loose dirt and dust by brushing with a soft brush, rubbing with a dry cloth, or vacuum-cleaning prior to application of the first coat material. A damp cloth or sponge may be used if paint is water-based.

3.5.2.2 Repair of Minor Defects

Prior to painting, repair joints, cracks, holes, surface irregularities, and other minor defects with patching plaster or spackling compound and sand smooth.

3.5.2.3 Allowable Moisture Content

Latex coatings may be applied to damp surfaces, but not surfaces with droplets of water. Do not apply epoxies to damp surfaces as determined by ASTM D4263. Verify that new plaster to be coated has a maximum moisture content of 8 percent, when measured in accordance with ASTM D4444, Method A, unless otherwise authorized. In addition to moisture content requirements, allow new plaster to age a minimum of 30 days before preparation for painting.

3.6 APPLICATION

3.6.1 Coating Application

a. Comply with applicable federal, state and local laws enacted to ensure compliance with Federal Clean Air Standards. Apply coating materials in accordance with SSPC PA 1. SSPC PA 1 methods are applicable to all substrates, except as modified herein.

b. At the time of application, paint must show no signs of deterioration. Maintain uniform suspension of pigments during application.

c. Unless otherwise specified or recommended by the paint manufacturer, paint may be applied by brush, roller, or spray. Use trigger operated spray nozzles for water hoses. Use rollers for applying paints and enamels of a type designed for the coating to be applied and the surface to be coated. Wear protective clothing and respirators when applying oil-based paints or using spray equipment with any paints.

d. Only apply paints, except water-thinned types, to surfaces that are completely free of moisture as determined by sight or touch.

e. Thoroughly work coating materials into joints, crevices, and open spaces. Pay special attention to ensure that all edges, corners, crevices, welds, and rivets receive a film thickness equal to that of adjacent painted surfaces.

f. Apply each coat of paint so that dry film is of uniform thickness and free from runs, drops, ridges, waves, pinholes or other voids, laps, brush marks, and variations in color, texture, and finish. Completely hide all blemishes.

g. Touch up damaged coatings before applying subsequent coats. Broom clean and clear dust from interior areas before and during the application of coating material.

h. Drying Time: Allow time between coats, as recommended by the coating manufacturer, to permit thorough drying, but not to present topcoat

adhesion problems. Provide each coat in specified condition to receive next coat.

i. Primers, and Intermediate Coats: Do not allow primers or intermediate coats to dry more than 30 days, or longer than recommended by manufacturer, before applying subsequent coats. Follow manufacturer's recommendations for surface preparation if primers or intermediate coats are allowed to dry longer than recommended by manufacturers of subsequent coatings. Cover each preceding coat or surface completely by ensuring visually perceptible difference in shades of successive coats.

j. Finished Surfaces: Provide finished surfaces free from runs, drops, ridges, waves, laps, brush marks, and variations in colors.

kp. Thermosetting Paints: Apply topcoats over thermosetting paints (epoxies and urethanes) within the overcoat window recommended by the manufacturer.

3.6.2 Mixing and Thinning of Paints

Reduce paints to proper consistency by adding fresh paint, except when thinning is mandatory to suit surface, temperature, weather conditions, application methods, or for the type of paint being used. Obtain written permission from the Contracting Officer to use thinners. Verify that the written permission includes quantities and types of thinners to use.

When thinning is allowed, thin paints immediately prior to application with not more than one pint of suitable thinner per gallon. The use of thinner does not relieve the Contractor from obtaining complete hiding, full film thickness, or required gloss. Thinning cannot cause the paint to exceed limits on volatile organic compounds. Do not mix paints of different manufacturers.

3.6.3 Two-Component Systems

Mix two-component systems in accordance with manufacturer's instructions. Follow recommendation by the manufacturer for any thinning of the first coat to ensure proper penetration and sealing for each type of substrate.

3.6.4 Coating Systems

a. Systems by Substrates: Apply coatings that conform to the respective specifications listed in the following Tables:

Table for Exterior Applications	
MPI Division	Substrate Application
MPI Division 3	Exterior Concrete Paint Table
MPI Division 4	Exterior Concrete Masonry Units Paint Table
MPI Division 5	Exterior Metal, Ferrous and Non-Ferrous Paint Table

Table for Exterior Applications	
MPI Division 6	Exterior Wood; Dressed Lumber, Paneling, Decking, Shingles Paint Table
MPI Division 9	Exterior Stucco Paint Table
MPI Division 10	Exterior Cloth Coverings and Bituminous Coated Surfaces Paint Table

Table for Interior Applications	
MPI Division	Substrate Application
MPI Division 3	Interior Concrete Paint Table
MPI Division 4	Interior Concrete Masonry Units Paint Table
MPI Division 5	Interior Metal, Ferrous and Non-Ferrous Paint Table
MPI Division 6	Interior Wood Paint Table
MPI Division 9	Interior Plaster, Gypsum Board, Textured Surfaces Paint Table

b. Minimum Dry Film Thickness (DFT): Apply paints, primers, varnishes, enamels, undercoats, and other coatings to a minimum dry film thickness of 1.5 mil each coat unless specified otherwise in the Tables. Coating thickness, where specified, refers to the minimum dry film thickness.

c. Coatings for Surfaces Not Specified Otherwise: Coat unspecified surfaces the same as surfaces having similar conditions of exposure.

d. Existing Surfaces Damaged During Performance of the Work, Including New Patches In Existing Surfaces: Coat surfaces with the following:

(1) One coat of primer.

(2) One coat of undercoat or intermediate coat.

(3) One topcoat to match adjacent surfaces.

e. Existing Coated Surfaces To Be Painted: Apply coatings conforming to the respective specifications listed in the Tables herein, except that pretreatments, sealers and fillers need not be provided on surfaces where existing coatings are soundly adhered and in good condition. Do not omit undercoats or primers.

3.7 COATING SYSTEMS FOR METAL

Apply coatings of Tables in MPI Division 5 for Exterior and Interior.

a. Apply specified ferrous metal primer to steel surfaces on the same day that surface is cleaned, to surfaces that meet all specified surface preparation requirements at time of application.

b. Inaccessible Surfaces: Prior to erection, use one coat of specified

primer on metal surfaces that will be inaccessible after erection.

c. Shop-primed Surfaces: Touch up exposed substrates and damaged coatings to protect from rusting prior to applying field primer.

d. Surface Previously Coated with Epoxy or Urethane: Apply MPI 101, 1.5 mils DFT immediately prior to application of epoxy or urethane coatings.

e. Pipes and Tubing: The semitransparent film applied to some pipes and tubing at the mill is not to be considered a shop coat. Overcoat these items with the specified ferrous-metal primer prior to application of finish coats.

f. Exposed Nails, Screws, Fasteners, and Miscellaneous Ferrous Surfaces. On surfaces to be coated with water thinned coatings, spot prime exposed nails and other ferrous metal with latex primer MPI 107.

3.8 COATING SYSTEMS FOR CONCRETE AND CEMENTITIOUS SUBSTRATES

Apply coatings of Tables in MPI Division 3, 4 and 9 for Exterior and Interior.

3.9 COATING SYSTEMS FOR WOOD AND PLYWOOD

a. Apply coatings of Tables in MPI Division 6 for Exterior and Interior.

b. Prior to erection, apply two coats of specified primer to treat and prime wood and plywood surfaces which will be inaccessible after erection.

c. Apply stains in accordance with manufacturer's printed instructions.

3.10 INSPECTION AND ACCEPTANCE

In addition to meeting previously specified requirements, demonstrate mobility of moving components, including swinging and sliding doors, cabinets, and windows with operable sash, for inspection by the Contracting Officer. Perform this demonstration after appropriate curing and drying times of coatings have elapsed and prior to invoicing for final payment.

3.11 WASTE MANAGEMENT

As specified in the Waste Management Plan and as follows. Do not use kerosene or any such organic solvents to clean up water based paints. Properly dispose of paints or solvents in designated containers. Close and seal partially used containers of paint to maintain quality as necessary for reuse. Store in protected, well-ventilated, fire-safe area at moderate temperature. Place materials defined as hazardous or toxic waste in designated containers. Set aside extra paint for future color matches or reuse by the Government.

3.12 PAINT TABLES

All DFT's are minimum values. Use only materials with a MPI GPS-1-14 green check mark having a minimum MPI "Environmentally Friendly" E1 E2 E3 rating based on VOC (EPA Method 24) content levels. Acceptable products are listed in the MPI Green Approved Products List, available at http://www.specifygreen.com/APL/ProductIdxByMPInum.asp.

3.12.1 Exterior Paint Tables

3.12.1.1 MPI Division 3: Exterior Concrete Paint Table

A. Concrete; Vertical Surfaces, Undersides of Balconies and Soffits

(1) New and uncoated existing and Existing, previously painted concrete; vertical surfaces, including undersides of balconies and soffits but excluding tops of slabs

Latex					
New and uncoated existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI EXT 3.1A-G1 (Flat)	MPI REX 3.1A-G1 (Flat)	MPI 3	MPI 10	MPI 10	3.5 mils
MPI EXT 3.1A-G2 (Velvet)	MPI REX 3.1A-G2 (Velvet)	MPI 3	MPI 214	MPI 214	3.5 mils
MPI EXT 3.1A-G5 (Semigloss)	MPI REX 3.1A-G5 (Semigloss)	MPI 3	MPI 11	MPI 11	3.5 mils
MPI EXT 3.1A-G6 (Gloss)	MPI REX 3.1A-G6 (Gloss)	MPI 3	MPI 119	MPI 119	3.5 mils
Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces.					

(2) New and uncoated existing and Existing, previously painted concrete, textured system; vertical surfaces, including undersides of balconies and soffits but excluding tops of slabs

Latex Aggregate					
New and uncoated existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI EXT 3.1B-G2 (Flat)	MPI REX 3.1A-G1 (Flat)	MPI 42	MPI 10	MPI 10	N/A
MPI EXT 3.1B-G5 (Semigloss)	MPI REX 3.1A-G5 (Semigloss)	MPI 42	MPI 11	MPI 11	N/A
MPI EXT 3.1B-G6 (Gloss)	MPI REX 3.1A-G6 (Gloss)	MPI 42	MPI 119	MPI 119	N/A
Texture - Fine Surface preparation and number of coats in accordance with manufacturer's instructions. Topcoat: Coating to match adjacent surfaces.					

(3) New and uncoated existing and Existing, previously painted concrete,

elastomeric system; vertical surfaces, including undersides of balconies and soffits but excluding tops of slabs

Elastomeric Coating					
New and uncoated existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI EXT 3.1F-G1 (Flat)	MPI REX 3.1F-G1 (Flat)	Per Manufacturer	MPI 113	MPI 113	16 mils
MPI EXT 3.1F-G2/3 (Velvet)	MPI REX 3.1F-G2/3 (Velvet)	Per Manufacturer	MPI 38	MPI 38	16 mils
Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces. Surface preparation and number of coats in accordance with manufacturer's instructions. NOTE: Apply sufficient coats to achieve a minimum dry film thickness of 16 mils.					

3.12.1.2 MPI Division 4: Exterior Concrete Masonry Units Paint Table

A. New and Existing concrete masonry on uncoated surface

Latex						
New	Existing	Block Filler	Primer	ntermediat	Topcoat	System DFT
MPI EXT 4.2A-G1 (Flat)	MPI REX 4.2A-G1 (Flat)	MPI 4	N/A	MPI 10	MPI 10	11 mils
MPI EXT 4.2A-G5 (Semigloss)	MPI REX 4.2A-G5 (Semigloss)	MPI 4	N/A	MPI 11	MPI 11	11 mils
MPI EXT 4.2A-G6 (Gloss)	MPI REX 4.2A-G6 (Gloss)	MPI 4	N/A	MPI 119	MPI 119	11 mils
Topcoat: Coating to match adjacent surfaces.						

B. New and Existing concrete masonry, textured system; on uncoated surface

Latex Aggregate					
New	Existing	Primer	Intermediate	Topcoat	System DFT
MPI EXT 4.2B-G1 (Flat)	MPI REX 3.1A-G1 (Flat)	MPI 42	MPI 42	MPI 10	N/A

MPI EXT 4.2B-G5 (Semigloss)	MPI REX 3.1A-G5 (Semigloss)	MPI 42	MPI 42	MPI 11	N/A
MPI EXT 4.2B-G6 (Gloss)	MPI REX 3.1A-G6 (Gloss)	MPI 42	MPI 42	MPI 119	N/A
Texture - Fine Medium Coarse. Surface preparation and number of coats in accordance with manufacturer's instructions. Topcoat: Coating to match adjacent surfaces.					

C. New and Existing concrete masonry, elastomeric system; on uncoated surfaces

Elastomeric Coating					
New and uncoated existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI EXT 3.1F-G1 (Flat)	MPI REX 3.1F-G1 (Flat)	Per Manufactur	MPI 113	MPI 113	16 mils
Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces. Surface preparation and number of coats in accordance with manufacturer's instructions. NOTE: Apply sufficient coats of MPI 113 to achieve a minimum dry film thickness of 16 mils.					

3.12.1.3 MPI Division 5: Exterior Metal, Ferrous and Non-Ferrous Paint Table

A. Steel / Ferrous Surfaces

(1) New Steel that has been hand or power tool cleaned to SSPC SP 2 or SSPC SP 3

Alkyd					
New	Existing, uncoated	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1Q-G5 (Semigloss	MPI REX 5.1D-G5 (Semigloss)	MPI 23	MPI 94	MPI 94	5.25 mils
MPI EXT 5.1Q-G6 (Gloss)	MPI REX 5.1D-G6 (Gloss)	MPI 23	MPI 9	MPI 9	5.25 mils
Topcoat: Coating to match adjacent surfaces.					

(2) New Steel that has been blast-cleaned to SSPC SP 6/NACE No.3

Alkyd

New	Existing, uncoated	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1D-G5 (Semigloss)	MPI REX 5.1D-G5 (Semigloss)	MPI 79	MPI 94	MPI 94	5.25 mils
MPI EXT 5.1D-G6 (Gloss)	MPI REX 5.1D-G6 (Gloss)	MPI 79	MPI 9	MPI 9	5.25 mils
Topcoat: Coating to match adjacent surfaces.					

(3) Existing steel that has been spot-blasted to SSPC SP 6/NACE No.3

(a) Surface previously coated with alkyd or latex

Waterborne Light Industrial Coating				
Existing, previously coated with alkyd or latex	Primer	Intermediate	Topcoat	System DFT
MPI REX 5.1C-G5 (Semigloss)	MPI 79	MPI 163	MPI 163	5 mils
MPI REX 5.1C-G6 (Gloss)	MPI 79	MPI 164	MPI 164	5 mils
Topcoat: Coating to match adjacent surfaces.				

(b) Surfaces previously coated with epoxy

Waterborne Light Industrial Coating				
Existing, previously coated with epoxy	Primer	Intermediate	Topcoat	System DFT
MPI REX 5.1L-G5 (Semigloss)	MPI 101	MPI 163	MPI 163	5 mils
MPI REX 5.1L-G6 (Gloss)	MPI 101	MPI 164	MPI 164	5 mils
Topcoat: Coating to match adjacent surfaces.				

Pigmented Polyurethane				
Existing, previously coated with epoxy	Primer	Intermediate	Topcoat	System DFT

MPI REX 5.1H-G6 (Gloss)	MPI 101	MPI 108	MPI 72	8.5 mils
Topcoat: Coating to match adjacent surfaces.				

(4) New and existing steel blast cleaned to SSPC SP 10/NACE No. 2

Waterborne Light Industrial					
New	Existing	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1R-G5 (Semigloss)	MPI EXT 5.1R-G5 (Semigloss)	MPI 101	MPI 108	MPI 163	8.5 mils
MPI EXT 5.1R-G6 (Gloss)	MPI EXT 5.1R-G6 (Gloss)	MPI 101	MPI 108	MPI 164	8.5 mils
Topcoat: Coating to match adjacent surfaces.					

Pigmented Polyurethane					
New	Existing	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1J-G6 (Gloss)	MPI EXT 5.1J-G6 (Gloss)	MPI 101	MPI 108	MPI 72	8.5 mils
Topcoat: Coating to match adjacent surfaces.					

(5) Metal floors (non-shop-primed surfaces or non-slip deck surfaces) with non-skid additive (NSA), load at manufacturer's recommendations

Epoxy					
New	Existing	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1S-G5 (Semi Gloss)	MPI EXT 5.1S-G5 (Semi Gloss)	MPI 120	MPI 177	MPI 177	5.25 mils
MPI EXT 5.1S-G6 (Gloss)	MPI EXT 5.1S-G6 (Gloss)	MPI 120	MPI 77	MPI 77	5.25 mils
Topcoat: Coating to match adjacent surfaces. Load Non-Skid Additive at manufacturer's recommendations.					

B. Exterior Galvanized Surfaces

(1) New Galvanized surfaces

Waterborne Primer / Latex				
New Galvanized Surfaces	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.3H-G1 (Flat)	MPI 134	MPI 10	MPI 10	4.5 mils
EXT 5.3H-G5 (Semigloss)	MPI 134	MPI 11	MPI 11	4.5 mils
MPI EXT 5.3H-G6 (Gloss)	MPI 134	MPI 119	MPI 119	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Waterborne Primer / Waterborne Light Industrial Coating				
New Galvanized Surfaces	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.3J-G5 (Semigloss)	MPI 134	MPI 163	MPI 163	4.5 mils
MPI EXT 5.3J-G6 (Gloss)	MPI 134	MPI 164	MPI 164	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Epoxy Primer / Waterborne Light Industrial Coating				
New Galvanized Surfaces	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.3K-G5 (Semigloss)	MPI 101	MPI 163	MPI 163	5 mils
MPI EXT 5.3K-G6 (Gloss)	MPI 101	MPI 164	MPI 164	5 mils
Topcoat: Coating to match adjacent surfaces.				

Pigmented Polyurethane				
New Galvanized Surfaces	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.3L-G6 (Gloss)	MPI 101	N/A	MPI 72	5 mils

Topcoat: Coating to match adjacent surfaces.

(2) Galvanized surfaces with slight coating deterioration; little or no rusting

Waterborne Light Industrial Coating				
Galvanized Surfaces with slight coating deterioration	Primer	Intermediate	Topcoat	System DFT
MPI REX 5.3J-G5 (Semigloss)	MPI 134	N/A	MPI 163	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Pigmented Polyurethane				
Galvanized Surfaces with slight coating deterioration	Primer	Intermediate	Topcoat	System DFT
MPI REX 5.3D-G6 (Gloss)	MPI 101	N/A	MPI 72	5 mils
Topcoat: Coating to match adjacent surfaces.				

(3) Galvanized surfaces with severely deteriorated coating or rusting

Waterborne Light Industrial Coating				
Galvanized surfaces with severely deteriorated coating or rusting	Primer	Intermediate	Topcoat	System DFT
MPI REX 5.3L-G5(Semigloss)	MPI 101	MPI 108	MPI 163	8.5 mils
MPI REX 5.3L-G6(Gloss)	MPI 101	MPI 108	MPI 164	8.5 mils
Topcoat: Coating to match adjacent surfaces.				

Pigmented Polyurethane

Galvanized surfaces with severely deteriorated coating or rusting	Primer	Intermediate	Topcoat	System DFT
MPI REX 5.3D-G6(Gloss)	MPI 101	MPI 72	MPI 72	5 mils
Topcoat: Coating to match adjacent surfaces.				

C. Exterior Surfaces, Other Metals (Non-Ferrous)

(1) Aluminum, aluminum alloy and other miscellaneous non-ferrous metal items not otherwise specified except hot metal surfaces, roof surfaces, and new prefinished equipment

Alkyd				
New Galvanized Surfaces	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.4F-G1 (Flat	MPI 95	MPI 8	MPI 8	5 mils
MPI EXT 5.4F-G5 (Semigloss)	MPI 95	MPI 94	MPI 94	5 mils
MPI EXT 5.4F-G6 (Gloss)	MPI 95	MPI 9	MPI 9	5 mils
Topcoat: Coating to match adjacent surfaces.				

Waterborne Light Industrial Coating				
New Galvanized Surfaces	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.4F-G1 (Flat	MPI 95	MPI 161	MPI 161	5 mils
MPI EXT 5.4F-G5 (Semigloss)	MPI 95	MPI 163	MPI 163	5 mils
MPI EXT 5.4F-G6 (Gloss)	MPI 95	MPI 164	MPI 164	5 mils
Topcoat: Coating to match adjacent surfaces.				

(2) Existing roof surfaces previously coated

Aluminum Pigmented Asphalt Roof Coating				
Existing roof surfaces previously coated	N/A	Intermediate	Topcoat	System DFT
Non-MPI System	ASTM D2824/D28	N/A	N/A	8 mils
Sufficient coats to provide not less than 8 mils of finished coating system (without asbestos fibers).				

Aluminum Paint				
Existing roof surfaces previously coated	Primer	Intermediate	Topcoat	System DFT
MPI REX 10.2D	MPI 107	MPI 1	MPI 1	3.5 mils
Topcoat: Coating to match adjacent surfaces.				

(3) Surfaces adjacent to painted surfaces; Mechanical, Electrical, Fire extinguishing sprinkler systems including valves, conduit, hangers, supports,exposed copper piping, and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment

Alkyd				
New	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1D-G1 (Flat)	MPI 79	MPI 8	MPI 8	5.25 mils
MPI EXT 5.1D-G5 (Semigloss)	MPI 79	MPI 94	MPI 94	5.25 mils
MPI EXT 5.1D-G6 (Gloss)	MPI 79	MPI 9	MPI 9	5.25 mils
Topcoat: Coating to match adjacent surfaces.				

Waterborne Light Industrial Coating				
New	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1C-G3(Eggshell)	MPI 79	MPI 161	MPI 161	5 mils

MPI EXT 5.1C-G5(Semigloss)	MPI 79	MPI 163	MPI 163	5 mils
MPI EXT 5.1C-G6(Gloss)	MPI 79	MPI 164	MPI 164	5 mils
Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces.				

D. Exterior Hot Surfaces

(1) Hot metal surfaces subject to temperatures up to 400 degrees F

Heat Resistant Enamel				
New	N/A	Intermediate	Topcoat	System DFT
MPI EXT 5.2A	MPI 21	N/A	N/A	Per Manufacturer
Surface preparation and number of coats per manufacturer's instructions.				

(2) Ferrous metal subject to high temperature, up to 750 degrees F

Inorganic Zinc Rich Coating				
New	N/A	Intermediate	Topcoat	System DFT
MPI EXT 5.2C	MPI 19	N/A	N/A	Per Manufacturer
Surface preparation and number of coats per manufacturer's instructions.				

Heat Resistant Aluminum Enamel				
New	N/A	Intermediate	Topcoat	System DFT
MPI EXT 5.2B	MPI 2	N/A	N/A	Per Manufacturer
Surface preparation and number of coats per manufacturer's instructions.				

(3) New surfaces and Existing surfaces made bare subject to temperatures up to 1100 degrees F

(1) New surfaces and Existing surfaces made bare cleaning to SSPC SP 10/NACE No. 2 subject to temperatures up to 1100 degrees F

Heat Resistant Coating					
New	Existing	N/A	Intermediate	Topcoat	System DFT
MPI EXT 5.2D	MPI REX 5.2D	MPI 22	N/A	N/A	Per Manufacturer
Surface preparation and number of coats per manufacturer's instructions.					

3.12.1.4 MPI Division 6: Exterior Wood; Dressed Lumber, Paneling, Decking, Shingles Paint Table

A. New and Existing, uncoated Dressed lumber, Wood and plywood, trim, including top, bottom and edges of doors not otherwise specified

Alkyd					
New	Existing, uncoated	Primer	Intermediate	Topcoat	System DFT
MPI EXT 6.3B-G5 (Semigloss)	MPI EXT 6.3B-G5 (Semigloss)	MPI 5	MPI 94	MPI 94	5 mils
MPI EXT 6.3B-G6 (Gloss)	MPI EXT 6.3B-G6 (Gloss)	MPI 5	MPI 9	MPI 9	5 mils
Topcoat: Coating to match adjacent surfaces.					

Latex					
New	Existing, uncoated	Primer	Intermediate	Topcoat	System DFT
MPI EXT 6.3A-G1 (Flat)	MPI EXT 6.3A-G1 (Flat)	MPI 5	MPI 10	MPI 10	5 mils
MPI EXT 6.3A-G5 (Semigloss)	MPI EXT 6.3B-G5 (Semigloss)	MPI 5	MPI 11	MPI 11	5 mils
MPI EXT 6.3A-G6 (Gloss)	MPI EXT 6.3B-G6 (Gloss)	MPI 5	MPI 119	MPI 119	5 mils
Topcoat: Coating to match adjacent surfaces.					

Waterborne Solid Color Stain					
New	Existing, uncoated	Primer	Intermediate	Topcoat	System DFT
MPI EXT 6.3K	MPI EXT 6.3K	MPI 5	MPI 16	MPI 16	4.25 mils
Topcoat: Coating to match adjacent surfaces.					

B. Existing, dressed lumber, Wood and plywood, trim, including top, bottom and edges of doors previously coated with an alkyd / oil based finish coat not otherwise specified

Alkyd				
Existing, previously coated	Primer	Intermediate	Topcoat	System DFT
MPI REX 6.3B-G5 (Semigloss)	MPI 5	MPI 94	MPI 94	5 mils
MPI REX 6.3B-G6 (Gloss)	MPI 5	MPI 9	MPI 9	5 mils

Latex				
Existing, previously coated	Primer	Intermediate	Topcoat	System DFT
MPI REX 6.3A-G1 (Flat)	MPI 5	MPI 10	MPI 10	5 mils
MPI REX 6.3B-G5 (Semigloss)	MPI 5	MPI 11	MPI 11	5 mils
MPI REX 6.3B-G6 (Gloss)	MPI 5	MPI 119	MPI 119	5 mils

C. Existing, dressed lumber, Wood and plywood, trim, including top, bottom and edges of doors previously coated with a latex / waterborne finish coat not otherwise specified

Latex				
Existing, previously coated	Primer	Intermediate	Topcoat	System DFT
MPI REX 6.3L-G1 (Flat)	MPI 6	MPI 10	MPI 10	4.5 mils
MPI REX 6.3L-G5 (Semigloss)	MPI 6	MPI 11	MPI 11	4.5 mils
MPI REX 6.3L-G6 (Gloss)	MPI 6	MPI 119	MPI 119	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Waterborne Solid Color Stain				
Existing, previously coated	Primer	Intermediate	Topcoat	System DFT
MPI EXT 6.3K	MPI 6	MPI 16	MPI 16	4 mils
Topcoat: Coating to match adjacent surfaces.				

D. Wood Siding

(1) New, Uncoated wood siding

Semi-Transparent Stain				
New	Primer	Intermediate	Topcoat	System DFT
MPI EXT 6.3D	N/A	MPI 13	MPI 13	N/A
Topcoat: Coating to match adjacent surfaces.				

(2) Existing, previously stained wood siding

Latex				
Existing, previously stained	Primer	Intermediate	Topcoat	System DFT
MPI REX 6.2K-G1 (Flat)	MPI 5	MPI 10	MPI 10	4.5 mils
MPI REX 6.2K-G5 (Semigloss)	MPI 5	MPI 11	MPI 11	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

(3) Existing Uncoated or previously semitransparent stained wood siding

Semi-Transparent Stain				
Existing	Primer	Intermediate	Topcoat	System DFT
MPI REX 6.3D	N/A	MPI 13	MPI 13	Per Manufacturer
Topcoat: Coating to match adjacent surfaces.				

E. Wood:

Latex Floor Paint				
New	Primer	Intermediate	Topcoat	System DFT
MPI EXT 6.5A-G2 (Flat)	MPI 5	MPI 60 plus NSA	MPI 60 plus NSA	4.5 mils
MPI EXT 6.5A-G6 (Gloss)	MPI 5	MPI 68 plus NSA	MPI 68 plus NSA	4.5 mils
Topcoat: Coating to match adjacent surfaces. Load non-skid additive (NSA) at manufacturer's recommendations.				

Alkyd Floor Paint

New	Primer	Intermediate	Topcoat	System DFT
MPI EXT 6.5B-G2 (Flat)	MPI 59	MPI 59 plus NSA	MPI 59 plus NSA	5 mils
MPI EXT 6.5B-G6 (Gloss)	MPI 27	MPI 27 plus NSA	MPI 27 plus NSA	5 mils
Topcoat: Coating to match adjacent surfaces. Load non-skid additive (NSA) at manufacturer's recommendations.				

3.12.1.5 MPI Division 9: Exterior Stucco Paint Table

A. New and Existing stucco

Latex					
New	Existing	Primer	Intermediate	Topcoat	System DFT
MPI EXT 9.1A-G1 (Flat)	MPI REX 9.1A-G2 (Flat	MPI 10	MPI 10	MPI 10	4.5 mils
MPI EXT 9.1A-G5 (Semigloss)	MPI REX 9.1A-G5 (Semigloss)	MPI 11	MPI 11	MPI 11	4.5 mils
MPI EXT 9.1A-G6 (Gloss)	MPI REX 9.1A-G6 (Gloss)	MPI 119	MPI 119	MPI 119	4.5 mils
Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces. On existing stucco, apply primer based on surface condition.					

B. New and Existing stucco, elastomeric system

Elastomeric Coating					
New	Existing	Primer	Intermediate	Topcoat	System DFT
MPI EXT 9.1C-G1 (Flat)	MPI REX 9.1C-G1 (Flat)	N/A	MPI 113	MPI 113	16 mils
Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces. Surface preparation and number of coats in accordance with manufacturer's instructions Apply sufficient coats of MPI 113 to achieve a minimum dry film thickness of 16 mils.					

3.12.1.6 MPI Division 10: Exterior Cloth Coverings and Bituminous Coated Surfaces Paint Table

A. Insulation and surfaces of insulation coverings (canvas, cloth, paper): (Interior and Exterior Applications)

Latex				
New	Primer	Intermediate	Topcoat	System DFT
MPI EXT 10.1A-G1 (Flat)	N/A	MPI 10	MPI 10	3.2 mils
MPI EXT 10.1A-G5 (Semigloss)	N/A	MPI 11	MPI 11	3.2 mils
MPI EXT 10.1A-G6 (Gloss)	N/A	MPI 119	MPI 119	3.2 mils
Topcoat: Coating to match adjacent surfaces.				

3.12.2 Interior Paint Tables

3.12.2.1 MPI Division 3: Interior Concrete Paint Table

A. New and uncoated existing and Existing, previously painted Concrete, vertical surfaces, not specified otherwise

Latex					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.1A-G2 (Flat)	MPI RIN 3.1A-G2 (Flat)	MPI 3	MPI 44	MPI 44	4 mils
MPI INT 3.1A-G3 (Eggshell)	MPI RIN 3.1A-G3 (Eggshell)	MPI 3	MPI 52	MPI 52	4 mils
MPI INT 3.1A-G5	MPI RIN 3.1A-G5 (Semigloss)	MPI 3	MPI 54	MPI 54	4 mils
Topcoat: Coating to match adjacent surfaces.					

High Performance Architectural Latex					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.1C-G2 (Flat)	MPI RIN 3.1J-G2 (Flat)	MPI 3	MPI 138	MPI 138	4 mils
MPI INT 3.1C-G3 (Eggshell)	MPI RIN 3.1J-G3 (Eggshell)	MPI 3	MPI 139	MPI 139	4 mils
MPI INT 3.1C-G4 (satin)	MPI RIN 3.1J-G4	MPI 3	MPI 140	MPI 140	4 mils

MPI INT 3.1C-G5 (Semigloss)	MPI RIN 3.1J-G5 (Semigloss)	MPI 3	MPI 141	MPI 141	4 mils
Topcoat: Coating to match adjacent surfaces.					

Institutional Low Odor / Low VOC Latex					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.1M-G2 (Flat)	MPI RIN 3.1L-G2 (Flat)	MPI 149	MPI 144	MPI 144	4 mils
MPI INT 3.1M-G3 (Eggshell)	MPI RIN 3.1L-G3 (Eggshell)	MPI 149	MPI 145	MPI 145	4 mils
MPI INT 3.1M-G4 (satin)	MPI RIN 3.1L-G4	MPI 149	MPI 146	MPI 146	4 mils
MPI INT 3.1M-G5 (Semigloss)	MPI RIN 3.1L-G5 (Semigloss)	MPI 149	MPI 147	MPI 147	4 mils
Topcoat: Coating to match adjacent surfaces.					

B. Concrete Ceilings, Uncoated

Latex Aggregate				
New, uncoated	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.1N-G1 (Flat)	N/A	N/A	MPI 42	Per Manufacturer
Texture - Fine Medium Coarse. Surface preparation, number of coats, and primer in accordance with manufacturer's instructions. Topcoat: Coating to match adjacent surfaces.				

C. New and uncoated existing and Existing, previously painted Concrete in not otherwise specified except floors

Waterborne Light Industrial Coating					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.1L-G3(Eggshell	MPI RIN 3.1C-G3(Eggshell	MPI 3	MPI 151	MPI 151	4.8 mils

MPI INT 3.1L-G5(Semiglos	MPI RIN 3.1C-G5(Semiglos	MPI 3	MPI 153	MPI 153	4.8 mils
MPI INT 3.1L-G6(Gloss)	MPI RIN 3.1C-G6(Gloss)	MPI 3	MPI 154	MPI 154	4.8 mils
Topcoat: Coating to match adjacent surfaces.					

Alkyd					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.1D-G3 (Eggshell)	MPI RIN 3.1D-G3 (Eggshell)	MPI 3	MPI 51	MPI 51	4.5 mils
MPI INT 3.1D-G5 (Semigloss)	MPI RIN 3.1D-G5 (Semigloss)	MPI 3	MPI 47	MPI 47	4.5 mils
MPI INT 3.1D-G6 (Gloss)	MPI RIN 3.1D-G6 (Gloss)	MPI 3	MPI 48	MPI 48	4.5 mils
Topcoat: Coating to match adjacent surfaces.					

Epoxy					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.1F-G6 (Gloss)	MPI RIN 3.1E-G6 (Gloss)	MPI 77	MPI 77	MPI 77	4 mils
Note: Primer may be reduced for penetration per manufacturer's					

D. New and uncoated existing and Existing, previously painted concrete walls and bottom of swimming pools

Chlorinated Rubber					
New and uncoated existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
Chlorinated Rubber	Per Manufacturer	Per Manufacturer	Per Manufacturer	Per Manufacturer	Per Manufacturer
Note: Primer may be reduced for penetration per manufacturer's instructions.					

Epoxy

New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.1F	MPI RIN 3.1E	MPI 77	MPI 77	MPI 77	4 mils
Note: Primer may be reduced for penetration per manufacturer's instructions.					

E. New and uncoated existing and Existing, previously painted concrete floors in following areas

Latex Floor Paint					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT	MPI RIN	MPI 60	MPI 60	MPI 60	5 mils

Alkyd Floor Paint					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.2B-G2 (Flat)	MPI RIN 3.2B-G2 (Flat)	MPI 59	MPI 59	MPI 59	5 mils
Note: Primer may be reduced for penetration per manufacturer's instructions.					

Epoxy					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 3.2C-G6 (Gloss)	MPI RIN 3.2C-G6 (Gloss)	MPI 77	MPI 77	MPI 77	5 mils
Note: Primer may be reduced for penetration per manufacturer's instructions.					

3.12.2.2 MPI Division 4: Interior Concrete Masonry Units Paint Table

A. New and uncoated Existing Concrete Masonry

High Performance Architectural Latex					
New, uncoated Existing	Filler	Primer	Intermediate	Topcoat	System DFT
MPI INT 4.2D-G2 (Flat)	MPI 4	N/A	MPI 139	MPI 138	11 mils

MPI INT 4.2D-G3 (Eggshell)	MPI 4	N/A	MPI 139	MPI 139	11 mils
MPI INT 4.2D-G4 (Satin)	MPI 4	N/A	MPI 140	MPI 140	11 mils
MPI INT 4.2D-G5 (Semigloss)	MPI 4	N/A	MPI 141	MPI 141	11 mils
Fill all holes in masonry surface					

Institutional Low Odor / Low VOC Latex					
New, uncoated Existing	Filler	Primer	Intermediate	Topcoat	System DFT
MPI INT 4.2E-G2 (Flat)	MPI 4	N/A	MPI 144	MPI 144	4 mils
MPI INT 4.2E-G3 (Eggshell)	MPI 4	N/A	MPI 145	MPI 145	4 mils
MPI INT 4.2E-G4 (Satin)	MPI 4	N/A	MPI 146	MPI 146	4 mils
MPI INT 4.2E-G5 (Semigloss)	MPI 4	N/A	MPI 147	MPI 147	4 mils
Fill all holes in masonry surface					

B. Existing, Previously Painted Concrete Masonry

High Performance Architectural Latex					
Existing, previously painted	Filler	Primer	Intermediate	Topcoat	System DFT
MPI RIN 4.2K-G2 (Flat)	N/A	MPI 138	MPI 138	MPI 138	4.5 mils
MPI RIN 4.2K-G3 (Eggshell)	N/A	MPI 139	MPI 139	MPI 139	4.5 mils
MPI RIN 4.2K-G4	N/A	MPI 140	MPI 140	MPI 140	4.5 mils
MPI RIN 4.2K-G5 (Semigloss)	N/A	MPI 141	MPI 141	MPI 141	4.5 mils

Institutional Low Odor / Low VOC Latex

Existing, previously painted	Filler	Primer	Intermediate	Topcoat	System DFT
MPI RIN 4.2L-G2 (Flat)	N/A	MPI 144	MPI 144	MPI 144	4 mils
MPI RIN 4.2L-G3 (Eggshell)	N/A	MPI 145	MPI 145	MPI 145	4 mils
MPI RIN 4.2L-G4 (Satin)	N/A	MPI 146	MPI 146	MPI 146	4 mils
MPI RIN 4.2L-G5 (Semigloss)	N/A	MPI 147	MPI 147	MPI 147	4 mils

C. New and uncoated Existing Concrete masonry units in unless otherwise specified

Waterborne Light Industrial Coating					
New, uncoated Existing	Filler	Primer	Intermediate	Topcoat	System DFT
MPI INT 4.2K-G3(Eggshell)	MPI 4	N/A	MPI 151	MPI 151	11 mils
MPI INT 4.2K-G5(Semigloss	MPI 4	N/A	MPI 153	MPI 153	11 mils
MPI INT 4.2K-G6(Gloss)	MPI 4	N/A	MPI 154	MPI 154	11 mils
Fill all holes in masonry surface					

Alkyd					
New, uncoated Existing	Filler	Primer	Intermediate	Topcoat	System DFT
MPI INT 4.2K-G3(Eggshell)	MPI 4	MPI 50	MPI 51	MPI 51	12 mils
MPI INT 4.2K-G5(Semigloss	MPI 4	MPI 50	MPI 47	MPI 47	12 mils
MPI INT 4.2K-G6(Gloss)	MPI 4	MPI 50	MPI 48	MPI 48	12 mils
Fill all holes in masonry surface					

Epoxy

New, uncoated Existing	Filler	Primer	Intermediate	Topcoat	System DFT
MPI INT 4.2G-G6 (Gloss)	MPI 116	N/A	MPI 77	MPI 77	10 mils
Fill all holes in masonry surface					

D. Existing, previously painted, concrete masonry units in unless otherwise specified

Waterborne Light Industrial Coating					
Existing, previously painted	Filler	Primer	Intermediate	Topcoat	System DFT
MPI RIN 4.2G-G3(Eggshell)	N/A	MPI 151	MPI 151	MPI 151	4.5 mils
MPI RIN 4.2G-G5(Semigloss)	N/A	MPI 153	MPI 153	MPI 153	4.5 mils
MPI RIN 4.2G-G6(Gloss)	N/A	MPI 154	MPI 154	MPI 154	4.5 mils

Alkyd					
Existing, previously painted	Filler	Primer	Intermediate	Topcoat	System DFT
MPI RIN 4.2C-G3 (Eggshell)	N/A	MPI 17	MPI 51	MPI 51	4.5 mils
MPI RIN 4.2C-G5 (Semigloss)	N/A	MPI 17	MPI 47	MPI 47	4.5 mils
MPI RIN 4.2C-G6 (Gloss)	N/A	MPI 17	MPI 48	MPI 48	4.5 mils

Epoxy					
Existing, previously painted	Filler	Primer	Intermediate	Topcoat	System DFT
MPI RIN 4.2D-G6	N/A	MPI 77	MPI 77	MPI 77	5 mils

3.12.2.3 MPI Division 5: Interior Metal, Ferrous and Non-Ferrous Paint Table

A. Interior Steel / Ferrous Surfaces

(1) Metal, not otherwise specified except floors, hot metal surfaces, and new prefinished equipment

High Performance Architectural Latex				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.1R-G2 (Flat)	MPI 76	MPI 138	MPI 138	5 mils
MPI INT 5.1R-G3 (Eggshell)	MPI 76	MPI 139	MPI 139	5 mils
MPI INT 5.1R-G5 (Semigloss)	MPI 76	MPI 141	MPI 141	5 mils
Topcoat: Coating to match adjacent surfaces.				

Alkyd				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.1E-G2 (Flat)	MPI 76	MPI 49	MPI 49	5.25 mils
MPI INT 5.1E-G3 (Eggshell)	MPI 76	MPI 51	MPI 51	5.25 mils
MPI INT 5.1E-G5 (Semigloss)	MPI 76	MPI 47	MPI 47	5.25 mils
MPI INT 5.1E-G6 (Gloss)	MPI 76	MPI 48	MPI 48	5.25 mils
Topcoat: Coating to match adjacent surfaces.				

(2) Metal floors (non-shop-primed surfaces or non-slip deck surfaces) with non-skid additive (NSA), load at manufacturer's recommendations

Alkyd (over q.d. Alkyd Primer)				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.1E-G5 (Semi-Gloss)	MPI 76	MPI 47	MPI 47	5.25 mils
Topcoat: Coating to match adjacent surfaces.				

Epoxy				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT

MPI INT 5.1L-G6 (Gloss)	MPI 101	MPI 101	MPI 101	5.25 mils
Topcoat: Coating to match adjacent surfaces.				

(3) Metal in not otherwise specified except floors, hot metal surfaces, and new prefinished equipment

Alkyd				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.1E-G3 (Eggshell)	MPI 76	MPI 51	MPI 51	5.25 mils
MPI INT 5.1E-G5 (Semigloss)	MPI 76	MPI 47	MPI 47	5.25 mils
MPI INT 5.1E-G6 (Gloss)	MPI 76	MPI 48	MPI 48	5.25 mils
Topcoat: Coating to match adjacent surfaces.				

Alkyd; For Hand Tool Cleaning				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.1T-G3 (Eggshell)	MPI 23	MPI 51	MPI 51	5.25 mils
MPI INT 5.1T-G5 (Semigloss)	MPI 23	MPI 47	MPI 47	5.25 mils
MPI INT 5.1T-G6 (Gloss)	MPI 23	MPI 48	MPI 48	5.25 mils
Topcoat: Coating to match adjacent surfaces.				

(4) Ferrous metal in concealed damp spaces or in exposed areas having unpainted adjacent surfaces as follows:

Aluminum Paint				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.1M	MPI 76	MPI 1	MPI 1	4.25 mils
Topcoat: Coating to match adjacent surfaces.				

(5) Miscellaneous non-ferrous metal items not otherwise specified except

floors, hot metal surfaces, and new prefinished equipment. Match surrounding finish

High Performance Architectural Latex				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.4F-G2 (Flat)	MPI 95	MPI 138	MPI 138	5 mils
MPI INT 5.4F-G3 (Eggshell)	MPI 95	MPI 139	MPI 139	5 mils
MPI INT 5.4F-G4 (Satin)	MPI 95	MPI 140	MPI 140	5 mils
MPI INT 5.4F-G5 (Semigloss)	MPI 95	MPI 141	MPI 141	5 mils
Topcoat: Coating to match adjacent surfaces.				

Alkyd				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.4J-G2 (Flat)	MPI 95	MPI 49	MPI 49	5 mils
MPI INT 5.4J-G3 (Eggshell)	MPI 95	MPI 51	MPI 51	5 mils
MPI INT 5.4J-G5 (Semigloss)	MPI 95	MPI 47	MPI 47	5 mils
MPI INT 5.4J-G6 (Gloss)	MPI 95	MPI 48	MPI 48	5 mils
Topcoat: Coating to match adjacent surfaces.				

B. Hot Surfaces

(1) Hot metal surfaces subject to temperatures up to 400 degrees F

Heat Resistant Enamel				
New	N/A	Intermediate	Topcoat	System DFT
MPI INT 5.2A	MPI 21	N/A	N/A	Per Manufacturer

Surface preparation and number of coats per manufacturer's instructions.

(2) Ferrous metal subject to high temperature, up to 750 degrees F

Inorganic Zinc Rich Coating				
New	N/A	Intermediate	Topcoat	System DFT
MPI INT 5.2C	MPI 19	N/A	N/A	Per Manufacturer
Surface preparation and number of coats per manufacturer's instructions.				

Heat Resistant Aluminum Enamel				
New	N/A	Intermediate	Topcoat	System DFT
MPI INT 5.2B (Aluminum Finish)	MPI 2	N/A	N/A	Per Manufacturer
Surface preparation and number of coats per manufacturer's instructions.				

(3) New and Existing Surfaces made bare subject to temperatures up to 1100 degrees F

(1) New surfaces and Existing surfaces made bare cleaning to SSPC SP 10/NACE No. 2 subject to temperatures up to 1100 degrees F:

Heat Resistant Coating					
New	Existing	N/A	Intermediate	Topcoat	System DFT
MPI INT 5.2D	MPI RIN 5.2D	MPI 22	N/A	N/A	Per Manufacturer
Surface preparation and number of coats per manufacturer's instructions.					

3.12.2.4 MPI Division 6: Interior Wood Paint Table

A. Interior Wood and Plywood

(1) New and Existing, uncoated Wood and plywood not otherwise specified

High Performance Architectural Latex				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT

MPI INT 6.4S-G3 (Eggshell)	MPI 39	MPI 139	MPI 139	4.5 mils
MPI INT 6.4S-G4 (Satin)	MPI 39	MPI 140	MPI 140	4.5 mils
MPI INT 6.4S-G5 (Semigloss)	MPI 39	MPI 141	MPI 141	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Alkyd				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.4B-G3 (Eggshell)	MPI 45	MPI 51	MPI 51	4.5 mils
MPI INT 6.4B-G5 (Semigloss)	MPI 45	MPI 47	MPI 47	4.5 mils
MPI INT 6.4B-G6 (Gloss)	MPI 45	MPI 48	MPI 48	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Institutional Low Odor / Low VOC Latex				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.3V-G2 (Flat)	MPI 39	MPI 144	MPI 144	4 mils
MPI INT 6.3V-G3 (Eggshell)	MPI 39	MPI 145	MPI 145	4 mils
MPI INT 6.3V-G4 (Satin)	MPI 39	MPI 146	MPI 146	4 mils
MPI INT 6.3V-G5 (Semigloss)	MPI 39	MPI 147	MPI 147	4 mils

(2) Existing, previously painted Wood and plywood not otherwise specified

High Performance Architectural Latex				
Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI RIN 6.4B-G3 (Eggshell)	MPI 39	MPI 139	MPI 139	4.5 mils

MPI RIN 6.4B-G4 (Satin)	MPI 39	MPI 140	MPI 140	4.5 mils
MPI RIN 6.4B-G5 (Semigloss)	MPI 39	MPI 141	MPI 141	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Alkyd				
Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI RIN 6.4C-G3 (Eggshell)	MPI 46	MPI 51	MPI 51	4.5 mils
MPI RIN 6.4C-G5 (Semigloss)	MPI 46	MPI 47	MPI 47	4.5 mils
MPI RIN 6.4C-G6 (Gloss)	MPI 46	MPI 48	MPI 48	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Institutional Low Odor / Low VOC Latex				
Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI RIN 6.4D-G2 (Flat)	MPI 39	MPI 144	MPI 144	4 mils
MPI RIN 6.4D-G3 (Eggshell)	MPI 39	MPI 145	MPI 145	4 mils
MPI RIN 6.4D-G4 (Satin)	MPI 39	MPI 146	MPI 146	4 mils
MPI RIN 6.4D-G5 (Semigloss)	MPI 39	MPI 147	MPI 147	4 mils

B. Interior New and Existing, previously finished or stained Wood and Plywood, except floors; natural finish or stained

Natural finish, oil-modified polyurethane					
New	Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.4J-G4	MPI RIN 6.4L-G4	MPI 57	MPI 57	MPI 57	4 mils
MPI INT 6.4J-G6 (Gloss)	MPI RIN 6.4L-G6 (Gloss)	MPI 56	MPI 56	MPI 56	4 mils

Stained, oil-modified polyurethane						
New	Existing	Stain	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.4E-G4	MPI RIN 6.4G-G4	MPI 90	MPI 57	MPI 57	MPI 57	4 mils
MPI INT 6.4E-G6 (Gloss)	MPI RIN 6.4G-G6 (Gloss)	MPI 90	MPI 56	MPI 56	MPI 56	4 mils

Stained, Moisture Cured Urethane						
New	Existing	Stain	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.4V-G2 (Flat)	MPI RIN 6.4V-G2 (Flat)	MPI 90	MPI 71	MPI 71	MPI 71	4 mils
MPI INT 6.4V-G6 (Gloss)	MPI RIN 6.4V-G6 (Gloss)	MPI 90	MPI 31	MPI 31	MPI 31	4 mils

C. Interior New and Existing, previously finished or stained Wood Floors; Natural finish or stained

Natural finish, oil-modified polyurethane					
New	Existing, previously finished or stained	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.5C-G6 (Gloss)	MPI RIN 6.5C-G6 (Gloss)	MPI 56	MPI 56	MPI 56	4 mils

Natural finish, Moisture Cured Polyurethane					
New	Existing, previously finished or stained	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.5K-G6 (Gloss)	MPI RIN 6.5D-G6 (Gloss)	MPI 31	MPI 31	MPI 31	4 mils

Stained, oil-modified polyurethane						
New	Existing, previously finished or stained	Stain	Primer	ntermediat	Topcoat	System DFT

MPI INT 6.5B-G6 (Gloss)	MPI RIN 6.5B-G6 (Gloss)	MPI 90	MPI 56	MPI 56	MPI 56	4 mils

Stained, Moisture Cured Urethane						
New	Existing, previously finished or stained	Stain	Primer	ntermediat	Topcoat	System DFT
MPI INT 6.4V-G6 (Gloss)	MPI RIN 6.4V-G6 (Gloss)	MPI 90	MPI 31	MPI 31	MPI 31	4 mils

D. New and Existing, previously coated Wood floors; pigmented finish

Latex Floor Paint					
New	Existing, previously finished	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.5G-G2 (Flat)	MPI RIN 6.5J-G2 (Flat)	MPI 45	MPI 60	MPI 60	4.5 mils
MPI INT 6.5G-G6 (Gloss)	MPI RIN 6.5J-G6 (Gloss)	MPI 45	MPI 68	MPI 68	4.5 mils
Topcoat: Coating to match adjacent surfaces.					

Alkyd Floor Paint					
New	Existing, previously finished	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.5A-G2 (Flat)	MPI RIN 6.5A-G2 (Flat)	MPI 59	MPI 59	MPI 59	4.5 mils
MPI INT 6.5A-G6 (Gloss)	MPI RIN 6.5A-G6 (Gloss)	MPI 27	MPI 27	MPI 27	4.5 mils
Topcoat: Coating to match adjacent surfaces.					

E. Interior New and Existing, uncoated wood surfaces in not otherwise specified

High-Build Glaze Coatings
As specified in Section 09 96 59 HIGH-BUILD GLAZE COATINGS.

Waterborne Light Industrial				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.3P-G5 (Semigloss)	MPI 45	MPI 153	MPI 153	4.5 mils
MPI INT 6.3P-G6 (Gloss)	MPI 45	MPI 154	MPI 154	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Alkyd				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.3B-G5 (Semigloss)	MPI 45	MPI 47	MPI 47	4.5 mils
MPI INT 6.3B-G6 (Gloss)	MPI 45	MPI 48	MPI 48	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

F. Existing, previously painted wood surfaces in not otherwise specified

High-Build Glaze Coatings
As specified in Section 09 96 59 HIGH-BUILD GLAZE COATINGS.

Waterborne Light Industrial				
Existing, previously finished	Primer	Intermediate	Topcoat	System DFT
MPI RIN 6.3P-G5 (Semigloss)	MPI 39	MPI 153	MPI 153	4.5 mils
MPI RIN 6.3P-G6 (Gloss)	MPI 39	MPI 154	MPI 154	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

Alkyd				
Existing, previously finished	Primer	Intermediate	Topcoat	System DFT

MPI RIN 6.3B-G5 (Semigloss)	MPI 46	MPI 47	MPI 47	4.5 mils
MPI RIN 6.3B-G6 (Gloss)	MPI 46	MPI 48	MPI 48	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

G. Interior New and Existing, previously finished or stained Wood Doors; Natural Finish or Stained

Natural finish, oil-modified polyurethane					
New	Existing, previously finished or stained	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.3K-G4	MPI RIN 6.3K-G4	MPI 57	MPI 57	MPI 57	4 mils
MPI INT 6.3K-G6 (Gloss)	MPI RIN 6.3K-G6 (Gloss)	MPI 56	MPI 56	MPI 56	4 mils
Note: Sand between all coats per manufacturers recommendations.					

Stained, oil-modified polyurethane						
New	Existing, previously finished or stained	Stain	Primer	ntermediat	Topcoat	System DFT
MPI INT 6.3E-G4	MPI RIN 6.3E-G4	MPI 90	MPI 57	MPI 57	MPI 57	4 mils
MPI INT 6.5B-G6 (Gloss)	MPI RIN 6.5B-G6 (Gloss)	MPI 90	MPI 56	MPI 56	MPI 56	4 mils
Note: Sand between all coats per manufacturers recommendations.						

Stained, Moisture Cured Urethane						
New	Existing, previously finished or stained	Stain	Primer	ntermediat	Topcoat	System DFT
MPI INT 6.4V-G2 (Flat)	MPI RIN 6.4V-G2 (Flat)	MPI 90	MPI 71	MPI 71	MPI 71	4 mils
MPI INT 6.4V-G6 (Gloss)	MPI RIN 6.4V-G6 (Gloss)	MPI 90	MPI 31	MPI 31	MPI 31	4 mils
Note: Sand between all coats per manufacturers recommendations.						

H. New and Existing, uncoated Wood Doors; Pigmented finish

Alkyd				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.3B-G5 (Semigloss)	MPI 45	MPI 47	MPI 47	4.5 mils
MPI INT 6.3B-G6 (Gloss)	MPI 45	MPI 48	MPI 48	4.5 mils
Note: Sand between all coats per manufacturers recommendations.				

Pigmented Polyurethane				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.1E-G6 (Gloss)	MPI 72	MPI 72	MPI 72	4.5 mils
Note: Sand between all coats per manufacturers recommendations.				

I. Existing, previously painted Wood Doors; Pigmented finish

Alkyd				
Existing, previously finished	Primer	Intermediate	Topcoat	System DFT
MPI RIN 6.3B-G5 (Semigloss)	MPI 46	MPI 47	MPI 47	4.5 mils
MPI RIN 6.3B-G6 (Gloss)	MPI 46	MPI 48	MPI 48	4.5 mils
Note: Sand between all coats per manufacturers recommendations.				

3.12.2.5 MPI Division 9: Interior Plaster, Gypsum Board, Textured Surfaces Paint Table

A. Interior New and Existing, previously painted Plaster and Wallboard not otherwise specified

Latex					
New	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 9.2A-G2 (Flat)	RIN 9.2A-G2 (Flat)	MPI 50	MPI 44	MPI 44	4 mils

MPI INT 9.2A-G3 (Eggshell)	RIN 9.2A-G3 (Eggshell)	MPI 50	MPI 52	MPI 52	4 mils
MPI INT 9.2A-G5 (Semigloss)	RIN 9.2A-G5 (Semigloss)	MPI 50	MPI 54	MPI 54	4 mils
Topcoat: Coating to match adjacent surfaces.					

High Performance Architectural Latex - High Traffic Areas					
New	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 9.2B-G2 (Flat)	MPI RIN 9.2B-G2 (Flat)	MPI 50	MPI 138	MPI 138	4 mils
MPI INT 9.2B-G3 (Eggshell)	MPI RIN 9.2B-G3 (Eggshell)	MPI 50	MPI 139	MPI 139	4 mils
MPI INT 9.2B-G5 (Semigloss)	MPI RIN 9.2B-G5 (Semigloss)	MPI 50	MPI 141	MPI 141	4 mils
Topcoat: Coating to match adjacent surfaces.					

Institutional Low Odor / Low VOC Latex, New

Institutional Low Odor / Low VOC Latex				
New	Primer	Intermediate	Topcoat	System DFT
MPI INT 9.2M-G2 (Flat)	MPI 149	MPI 144	MPI 144	4 mils
MPI INT 9.2M-G3 (Eggshell)	MPI 149	MPI 145	MPI 145	4 mils
MPI INT 9.2M-G4 (Satin)	MPI 149	MPI 146	MPI 146	4 mils
MPI INT 9.2M-G5 (Semigloss)	MPI 149	MPI 147	MPI 147	4 mils
Topcoat: Coating to match adjacent surfaces.				

Institutional Low Odor / Low VOC Latex, Existing, previously painted

Institutional Low Odor / Low VOC Latex				
Existing, previously painted	Primer	Intermediate	Topcoat	System DFT

MPI RIN 9.2M-G2 (Flat)	MPI 144	MPI 144	MPI 144	4 mils
MPI RIN 9.2M-G3 (Eggshell)	MPI 144	MPI 145	MPI 145	4 mils
MPI RIN 9.2M-G4 (Satin)	MPI 144	MPI 146	MPI 146	4 mils
MPI RIN 9.2M-G5 (Semigloss)	MPI 144	MPI 147	MPI 147	4 mils
Topcoat: Coating to match adjacent surfaces.				

B. Interior New and Existing, previously painted Plaster and Wallboard in not otherwise specified

Waterborne Light Industrial Coating					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 9.2L-G5(Semigloss	MPI RIN 9.2L-G5 (Semigloss)	MPI 50	MPI 153	MPI 153	4 mils
Topcoat: Coating to match adjacent surfaces.					

Alkyd					
New, uncoated Existing	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 9.2C-G5 (Semigloss)	MPI RIN 9.2C-G5 (Semigloss)	MPI 50	MPI 47	MPI 47	4 mils
Topcoat: Coating to match adjacent surfaces.					

Epoxy, New, uncoated Existing

Epoxy				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 9.2E-G6 (Gloss)	MPI 50	MPI 77	MPI 77	4 mils
Topcoat: Coating to match adjacent surfaces.				

Epoxy, Existing, previously painted

Epoxy				
Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI RIN 9.2D-G6 (Gloss)	MPI 17	MPI 77	MPI 77	4 mils
Topcoat: Coating to match adjacent surfaces.				

-- End of Section --

March 2016

Marine Corps Base (MCB) Camp Lejeune Contractor Environmental Guide

Prepared For:

Marine Corps Installations East-Marine Corps Base Camp Lejeune

Version Number 3

Michael Baker INTERNATIONAL

Prepared By:
Michael Baker International, Inc.

PAGE INTENTIONALLY BLANK

TABLE OF CONTENTS

Table of Contents i

Record of Changes ix

Certification Page xi

List of Acronyms and Abbreviations xiii

Contractor's Phone Directory xix

1.0 Contractor Environmental Guide Overview 1-1
- 1.1. Key Definitions and Concepts 1-3
  - 1.1.1. Key Definitions 1-3
  - 1.1.2. Key Concepts 1-4
- 1.2. Installation Background 1-5
  - 1.2.1. Environmental Management Division and Environmental Affairs Department 1-6
  - 1.2.2. Expectations 1-7
- 1.3. Overview of Requirements 1-8
  - 1.3.1. Contractor Environmental Guide 1-9
  - 1.3.2. Environmental and EMS Training 1-10
- 1.4. Points of Contact 1-12
- 1.5. Overview Map 1-13

2.0 Environmental Management System 2-1
- 2.1. Key Definition and Concepts 2-2
  - 2.1.1. Key Definitions 2-2
  - 2.1.2. Key Concepts 2-3
- 2.2. Overview of Requirements 2-5
- 2.3. Environmental Management System 2-6
- 2.4. EMS Responsibilities 2-8
- 2.5. Contractor Environmental Guide and EMS 2-9

3.0 Training 3-1
3.1. Key Definitions and Concepts 3-2
3.1.1. Key Definitions 3-2
3.1.2. Key Concepts 3-3
3.1.3. Environmental Management System 3-4
3.2. Overview of Requirements 3-4
3.3. Training Requirements 3-4
3.3.1. General Environmental Awareness 3-4
3.3.2. Environmental Management System 3-5
3.3.3. Recordkeeping 3-5

4.0 Air Quality 4-1
4.1. Key Definitions and Concepts 4-1
4.1.1. Key Definitions 4-1
4.1.2. Key Concepts 4-2
4.1.3. Environmental Management System 4-3
4.2. Overview of Requirements 4-4
4.3. Permit Requirements 4-5
4.4. Additional Activities of Concern 4-6

5.0 Environmental Emergency Planning and Response 5-1
5.1. Key Definitions and Concepts 5-1
5.1.1. Key Definitions 5-2
5.1.2. Key Concepts 5-3
5.1.3. Environmental Management System 5-4
5.2. Overview of Requirements 5-4
5.3. Spill Notification 5-6
5.3.1. POL/Hazardous Materials Spill Notification Procedures 5-6
5.3.2. Wastewater Spill and Water Line Break Notification 5-8
5.4. Follow-Up 5-9

6.0 Cultural Resources 6-1
6.1. Key Definitions and Concepts 6-1

6.1.1. Key Definitions 6-1
6.1.2. Key Concepts 6-3
6.1.3. Environmental Management System 6-3
6.2. Overview of Requirements 6-4
6.3. Procedures 6-7

7.0 Hazardous Materials/Hazardous Waste Management 7-1
7.1. Key Definitions and Concepts 7-1
7.1.1. Key Definitions 7-2
7.1.2 Key Concepts 7-5
7.1.3 Environmental Management System 7-8
7.2. Overview of Requirements 7-11
7.3. Hazardous Materials Requirements 7-14
7.4. Universal Waste Requirements 7-16
7.5. Hazardous Waste Requirements 7-18
7.5.1. Storage 7-19
7.5.2. Manifesting and Disposal 7-21
7.6. Non–RCRA-Regulated Waste Requirements 7-22
7.6.1. Used Oil and Oil Filters 7-22
7.6.2. Used Antifreeze 7-24
7.6.3. Petroleum-Contaminated Wipes and Oily Rags . 7-25
7.6.4. Used Electronic Equipment 7-25
7.6.5. New and Used Batteries (Not Regulated as Universal Waste) 7-25

8.0 Asbestos 8-1
8.1. Key Definitions and Concepts 8-1
8.1.1. Key Definitions 8-1
8.1.2. Key Concepts 8-3
8.1.3. Environmental Management System 8-4
8.2. Overview of Requirements 8-5
8.3. Responsibilities Before a Demolition or Renovation Project 8-6
8.3.1. Identification of ACM and PACM 8-7

8.3.2. Notification 8-8
8.3.3. Removal 8-8
8.3.4. Training 8-9
8.4. Responsibilities During a Demolition or Renovation Project 8-9
8.5. Disposal of ACM Waste 8-10

9.0 Lead-Based Paint 9-1
9.1. Key Definitions and Concepts 9-1
9.1.1. Key Definitions 9-1
9.1.2. Key Concepts 9-3
9.1.3. Environmental Management System 9-3
9.2. Overview of Requirements 9-4
9.3. Responsibilities Before Renovation or Demolition 9-6
9.4. Permits 9-8
9.5. Disposal 9-8
9.6. Training 9-9

10.0 Natural Resources 10-1
10.1. Key Definitions and Concepts 10-1
10.1.1. Key Definitions 10-2
10.1.2. Key Concepts 10-3
10.1.3. Environmental Management System 10-5
10.2. Overview of Requirements 10-6
10.3. National Environmental Policy Act 10-10
10.4. Timber 10-11
10.5. Threatened and Endangered Species 10-13
10.6. Wetlands 10-14
10.6.1. Avoidance 10-14
10.6.2. Permits 10-15
10.6.3. Impacts 10-18
10.6.4. Mitigation 10-19
10.7. Temporary Construction 10-20

11.0 Stormwater 11-1
11.1. Key Definitions and Concepts 11-1
11.1.1. Key Definitions 11-2
11.1.2. Key Concepts 11-5
11.1.3. Environmental Management System 11-8
11.2. Overview of Requirements 11-9
11.3. Prior to Site Work 11-11
11.3.1. Construction Notifications 11-12
11.3.2. Familiarity with the Stormwater Phase I Industrial Permit 11-12
11.3.3. Familiarity with the Stormwater Phase II Municipal Permit 11-13
11.3.4. Project-Specific Construction Permits 11-13
11.4. Responsibilities During Site Work 11-16

12.0 Solid Waste, Recycling, and Pollution Prevention (P2). 12-1
12.1. Key Definitions and Concepts 12-1
12.1.1. Key Definitions 12-2
12.1.2. Key Concepts 12-3
12.1.3. Environmental Management System 12-4
12.2. Overview of Requirements 12-5
12.3. Solid Waste Requirements 12-7
12.3.1. MCB Camp Lejeune Landfill Acceptable Waste Streams 12-9
12.4. Recycling Requirements 12-14
12.4.1. Recycling Center 12-15
12.4.2. Other Recyclables 12-16
12.5. Pollution Prevention and Green Procurment 12-17

13.0 Potential Discovery of Undocumented Contaminated Sites 13-1
13.1. Key Definitions and Concepts 13-2
13.1.1. Key Definitions 13-2
13.1.2. Key Concepts 13-3

13.1.3. Environmental Management System 13-3
13.2. Overview of Requirements..... 13-3
13.3. Unforeseen Site Condition Procedures..... 13-4
13.3.1. Petroleum, Oil, and Lubricants 13-5
13.3.2. Munitions and Ordnance..... 13-6

14.0 Permitting 14-1
14.1. Key Definitions and Concepts..... 14-1
14.1.1. Key Definitions..... 14-1
14.1.2. Key Concepts 14-2
14.1.3. Environmental Management System 14-3
14.2. Overview of Requirements..... 14-3
14.3. Project Permits and Approvals 14-3
14.3.1. Stormwater (Section 11.0) 14-4
14.3.2. Asbestos (Section 8.0) 14-5
14.3.3. Lead-Based Paint (Section 9.0)..... 14-5
14.3.4. Air Quality (Section 4.0)..... 14-6
14.3.5. Wetlands (Section 10.6)..... 14-7
14.3.6. Drinking Water/Wastewater 14-8

List of Tables

Table 1-1. Contacts in Case of a Spill..... 1-13
Table 2-1. Practices Identified Under MCB Camp Lejeune's EMS 2-10
Table 5-1. Environmental Emergency Response Contacts..... 5-3
Table 12-1. Base Landfill Requirements 12-11

List of Figures

Figure 1-1. Environmental Management Division (MCB Camp Lejeune) Organization Chart 1-7
Figure 1-2. Environmental Affairs Department (MCAS New River) Organization Chart 1-7
Figure 1-3. Overview Map..... 1-14
Figure 2-1. Plan, Do, Check, Act Cycle 2-4
Figure 2-2. Potential Interactions of Construction and Demolition Activities with the Environment..... 2-7
Figure 6-1. Possible Cultural Resource Discovery Flow Chart 6-8
Figure 7-1. Diamond Hazard Label 7-7

Attachments and Appendix

Attachment 2-1 MCB Camp Lejeune's Environmental Policy Statement
Attachment 3-1 Spill Reporting Form
Attachment 4-1 Weekly Hazardous Waste (HW) Site Inspection Form MCB Camp Lejeune
Attachment 4-2 Weekly Hazardous Waste (HW) Site Inspection Form MCAS New River
Appendix General EMS & Environmental Awareness Training for Contractors & Vendors

PAGE INTENTIONALLY BLANK

RECORD OF CHANGES

Date	Description of Changes	Page #	Name/Initials

PAGE INTENTIONALLY BLANK

CERTIFICATION PAGE

I certify that I have read, understood, and accept this document and all attachments, and that all those within my party working on a job site within Marine Corps Base Camp Lejeune and/or Marine Corps Air Station New River will comply with the environmental policies and regulations herein. I am aware that there are penalties for not complying with this Guide.

_____

Signature

_____

Date

PAGE INTENTIONALLY BLANK

LIST OF ACRONYMS AND ABBREVIATIONS

ACM	Asbestos-Containing Material
AHERA	Asbestos Hazard and Emergency Response Act
AHPA	Archaeological and Historic Preservation Act
ARPA	Archeological Resource Protection Act
ASHARA	Asbestos School Hazard Abatement Reauthorization Act
ASD	Accumulation Start Date
ASO	Air Station Order
BMP	Best Management Practice
BO	Base Order
C&D	Construction and Demolition
CAA	Clean Air Act
CAMA	Coastal Area Management Act
CERCLA	Comprehensive Environmental Response, Compensation, and Liability
CETEP	Comprehensive Environmental Training and Education Program
CFC	Chlorofluorocarbon
CFR	Code of Federal Regulations
CG	Commanding General
CWA	Clean Water Act
CZMA	Coastal Zone Management Act
DHHS	Department of Health and Human Services
DLADS	Defense Logistics Agency Disposition Services
DM	Decision Memorandum

DMM	Discarded Military Munitions
DoD	Department of Defense
DoN	Department of Navy
DOT	Department of Transportation
DRMS	Defense Reutilization and Marketing Service
EA	Environmental Assessment
EAD	Environmental Affairs Department
ECON	Environmental Conservation Branch
EISA	Energy Independence and Security Act
EHS	Extremely Hazardous Substances
ELLAP	Environmental Lead Laboratory Accreditation Program
EMD	Environmental Management Division
EMS	Environmental Management System
EO	Executive Order
EOD	Explosives and Ordnance Disposal
EPA	Environmental Protection Agency
EPR	Extended Producer Responsibility
EPCRA	Emergency Planning and Community Right-to-Know Act
EPEAT	Electronic Product Environmental Assessment Tool
FAR	Federal Acquisition Regulation
FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act
FSC	Facilities Support Contracts
FWS	Fish and Wildlife Service
GIS	Geographic Information System
GP	Green Procurement
HAP	Hazardous Air Pollutants

HCFC	Hydrochlorofluorocarbon
HCS	Hazard Communication Standard
HHCU	Health Hazards Control Unit (North Carolina)
HM	Hazardous Material
HMTA	Hazardous Materials Transportation Act
HQMC	Headquarters Marine Corps
HQW	High Quality Water
HVAC	Heating, Ventilation, and Air Conditioning
HW	Hazardous Waste
HWMP	Hazardous Waste Management Plan
IGI&S	Installation Geospatial Information & Services
INRMP	Integrated Natural Resources Management Plan
IRP	Installation Restoration Program
LBP	Lead-Based Paint
LDA	Land-Disturbing Activities
LQG	Large Quantity Generator
MAG	Marine Aircraft Group
MCAS	Marine Corps Air Station
MCB	Marine Corps Base
MCM	Minimum Control Measure
MCIEAST	Marine Corps Installations East
MCO	Marine Corps Order
MEC	Munitions and Explosives of Concern
MEF	Marine Expeditionary Force
MRF	Materials Recovery Facility
MS4	Municipal Separate Storm Sewer Systems
MSW	Municipal Solid Waste
NAPL	Non-Aqueous Phase Liquid

NC	North Carolina
NCAC	North Carolina Administrative Code
NCDAQ	North Carolina Department of Air Quality
NCDCM	North Carolina Division of Coastal Management
NCDEQ	North Carolina Department of Environmental Quality
NCDFR	North Carolina Division of Forest Resources
NCDMS	North Carolina Division of Mitigation Services
NCDWR	North Carolina Division of Water Resources
NEPA	National Environmental Policy Act
NESHAP	National Emission Standards for Hazardous Air Pollutants
NHPA	National Historic Preservation Act
NPDES	National Pollutant Discharge Elimination System
NPL	National Priorities List
NRC	National Response Center
NRHP	National Register of Historic Places
ODS	Ozone-Depleting Substance
OPA	Oil Pollution Act
ORW	Outstanding Resource Water
OSHA	Occupational Safety and Health Administration
OWS	Oil-Water Separator
P2	Pollution Prevention
PACM	Presumed Asbestos-Containing Material
PCB	Polychlorinated biphenyl
POC	Point of Contact
POL	Petroleum, Oil, and Lubricant
PPA	Pollution Prevention Act
ppm	Parts Per Million

PPV	Public-Private Venture
PWD	Public Works Division
QRP	Qualified Recycling Program
RACM	Regulated Asbestos-Containing Material
RCRA	Resource Conservation and Recovery Act
RCRS	Resource Conservation and Recovery Section
ROICC	Resident Officer in Charge of Construction
RRP	Renovation, Repair, and Painting
SAA	Satellite Accumulation Area
SARA	Superfund Amendments & Reauthorization Act
SDS	Safety Data Sheet
SHPO	State Historic Preservation Officer
SPCC	Spill Prevention Control and Countermeasures
SSPP	Strategic Sustainability Performance Plan
SWDA	Solid Waste Disposal Act
SWPPP	Stormwater Pollution Prevention Plan (Also referred to as SPPP in NC)
T&P	Treatment and Processing
TCLP	Toxic Characteristic Leaching Procedure
TSD	Treatment, Storage, and Disposal
TSI	Thermal System Insulation
ULCP	Unit Level Contingency Plan
USC	United States Code
USACE	United States Army Corps of Engineers
USMC	United States Marine Corps
UW	Universal Waste

UXO	Unexploded Ordnance
XRF	X-Ray Fluorescence

CONTRACTOR'S PHONE DIRECTORY

In the event of an emergency, refer to the emergency numbers below. All non-emergency contractor inquiries regarding the operations at Marine Corps Base (MCB) Camp Lejeune and Marine Corps Air Station New River should be directed to the Resident Officer in Charge of Construction (ROICC) or Contract Representative. The ROICC or Contract Representative will either directly contact or refer contractors to the appropriate Division or Organization.

Emergency and Important Non-Emergency Numbers

Fire and Emergency Services Division.....911
Ambulance.....911
Hearing Impaired.....(910) 451-4444
CHEMTREC (Emergency 24-hour/Outside MCB Camp Lejeune).....(800) 424-9300
Hazardous Chemical Spill.....911
Military Police.....911
National Response Center (Outside MCB Camp Lejeune).....(202) 372-2428
Toll Free.....(800) 424-8802
Provost Marshall Office.....911

Marine Corps Base Camp Lejeune

Operator/ Directory Assistance.....(910) 451-1113
Confined Space Program Manager.....(910) 451-5725
Environmental Management Division.....(910) 451-5003
-Environmental Compliance Branch.....(910) 451-5837

Asbestos Management
Resource Conservation and Recovery Section
(910) 451-1482
Hazardous Material Consolidation Site/Free Issue
.....(910) 451-1482
Recycling Center, Building 982.....(910) 451-4214
-Environmental Conservation Branch.....(910) 451-5063
Fish & Wildlife
Forestry Management
NEPA
Conservation Law Enforcement
.....(910) 451-2196/5226
-Environmental Quality Branch.....(910) 451-5068
Air Quality
Underground Storage Tanks
Water Quality
Explosives and Ordnance Disposal.....(910) 451-0558
Public Works Division.....(910) 451-5307
-Construction Project Managers.....(910) 451-2583
-Contracts Branch.....(910) 451-2582
-Officer In Charge of Construction (Main)..(910) 451-2581
-Public Works Base Utility Director.....(910) 451-5024
Water Line Break/Wastewater Line Break.....(910) 451-7190 (x225)
-Public Works Solid Waste Division/Landfill
.....(910) 451-2946
Range Control.....(910) 451-3064
Regional Geospatial Information & Services (Installation Manager).....(910) 451-8915
Safety Department.....(910) 451-5725

Marine Corps Air Station New River

Confined Space Program.....(910) 449-4964
Consolidated Hazardous Material Reutilization and
Inventory Management Program.....(910) 449-4531/4533
Environmental Affairs Department
(Director).....(910) 449-5441
-Environmental Affairs Department (Environmental
Manager).....(910) 449-5442
-Environmental Affairs Department (GIS
Manager).....(910) 449-6144
-Environmental Affairs Department (Hazardous
Waste).....(910) 449-5997
-Conservation Law Enforcement.....(910) 449-0108
Explosives Safety Officer.....(910) 449-5443
Military Police (Non-Emergency).....(910) 449-4248/4249
Public Works Division.....(910) 449-6506
-Officer In Charge of Construction.....(910) 449-5587
Safety Department.....(910) 449-4527

PAGE INTENTIONALLY BLANK

1.0 CONTRACTOR ENVIRONMENTAL GUIDE OVERVIEW

Environmental protection is an integral part of the Marine Corps mission in order to protect public health, preserve environmental quality, comply with regulatory requirements, and develop and strengthen relationships between the Marine Corps community and external stakeholders. The purpose of the MCB Camp Lejeune Contractor Environmental Guide is to assist contractors working aboard Marine Corps Installations East's (MCIEAST's) Marine Corps Base (MCB) Camp Lejeune and Marine Corps Air Station (MCAS) New River in maintaining the mission by complying with Federal and State environmental laws and regulations, as well as the United States Marine Corps (USMC) and installation environmental policies. This guide is written in accordance with Marine Corps Order (MCO) P5090.2A and designed to answer many of the environmental questions that arise, as well as to provide pertinent information on environmental topics and training requirements.

This document should be used only as a *guide* to the environmental issues contractors may face while working aboard MCB Camp Lejeune and MCAS New River.

NOTE: This document should be used only as a guide to the environmental issues contractors may face while working

aboard MCB Camp Lejeune and MCAS New River. It is expected that contractors will work closely with the Environmental Management Division (EMD) at MCB Camp Lejeune, the Environmental Affairs Department (EAD) at MCAS New River, and Contract Representatives regarding environmental management issues, concerns, and/or questions. Should the need arise, this guide provides contractors with EMD, EAD, and emergency response points of contact (POCs). All initial inquiries should be directed to the Resident Officer in Charge of Construction (ROICC) or Contract Representative, who will either direct the contractor or contact the appropriate environmental office if additional clarification regarding an environmental issue is necessary.

Contact the ROICC or Contract Representative with any questions.

NOTE: It is very important to note that this guide is designed to provide requirements specific to MCB Camp Lejeune-issued contracts. It is the contractor's responsibility to know and comply with all Federal, State, and local regulations. MCB Camp Lejeune environmental personnel will assist contractors with compliance issues; however, the primary burden of regulatory identification, familiarity, and compliance lies with the contractor. This training ***does not*** replace any required regulatory environmental training or certification as per contract requirements. All required environmental training should be completed ***prior*** to working at MCIEAST installations.

NOTE: It is the contractor's responsibility to review the project-specific contract and specifications. Additional environmental requirements, submissions, and/or meetings not documented in this guide may be required.

1.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are used throughout this guide. If you have any questions about these definitions or concepts, please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

1.1.1. Key Definitions

- **Environment.** Surroundings, to include all surface water, groundwater, drinking water supply, land surface or subsurface area, or ambient air within the United States or under the jurisdiction of the United States, including manmade structures, indoor air environments, natural resources, and archeological and cultural resources.
- **Environmental Management Division.** MCB Camp Lejeune's division responsible for environmental issues and compliance at MCB Camp Lejeune.
- **Environmental Affairs Department.** MCAS New River's department responsible for environmental issues and compliance at MCAS New River.
- **Environmental Management System (EMS).** A systematic approach for integrating environmental

considerations and accountability into day-to-day decisionmaking and long-term planning processes across all missions, practices, and functions. The EMS institutionalizes processes for continual environmental improvement and reducing risks to mission through ongoing planning, review, and preventive or corrective action.

1.1.2. Key Concepts

- **Environmental Requirement.** A defined standard pertaining to environmental compliance, pollution prevention (P2), or natural/cultural resources, subject to uniform application. Environmental requirements may be in the form of a law, regulation, Executive Order (EO), policy, ordinance, permit, Base Order (BO), or other form that prescribes a standard.
- **Executive Order.** Legally binding orders given by the President, as head of the Executive Branch, to direct Federal agencies and officials in their execution of congressionally established laws or policies.
- **MCB Camp Lejeune.** Throughout this document, MCB Camp Lejeune includes all MCB Camp Lejeune real property and contracts for work performed at MCAS New River and all outlying fields associated with MCB Camp Lejeune.
- **Marine Corps Order.** A directive of continuing authority or information, meant to be a permanent reference and requiring continuing action, issued by Headquarters Marine Corps (HQMC). In accordance

with MCO 5215.1K (10 May 2007), all MCOs shall, where applicable: establish, describe, or change existing policy, programs and major activities, and organizations; define missions; assign responsibilities; issue procedural guidance; and be written in standardized format.

- **Resident Officer In Charge of Construction.** The ROICC administers construction contracts and is the contractor's first line of contact with the government.
- **Regulatory Requirements.** Government (including Federal, State, and local) environmental regulations implemented by environmental statutes. Federal regulations often establish minimum standards for State and local governments' implementing programs.
- **Statutory Requirements.** Federal environmental statutes are laws that generally require compliance by U.S. Department of Defense (DoD) installations.

1.2. INSTALLATION BACKGROUND

MCB Camp Lejeune was established in 1941 in Onslow County, along the southern coast of North Carolina (NC). MCB Camp Lejeune is just south of MCAS New River. MCB Camp Lejeune takes advantage of 156,000 acres and 11 miles of beach capable of supporting amphibious operations, 32 gun positions, 48 tactical landing zones, three state-of-the-art training facilities, and 80 live fire ranges for its training mission.

The primary function of MCB Camp Lejeune is national defense, providing a home installation for the II Marine Expeditionary Force (MEF), 2nd Marine Division, 2nd Force Service Support Group, and other combat units and support commands. MCB Camp Lejeune's mission is to maintain combat-ready units for expeditionary deployment. MCB Camp Lejeune maintains and utilizes supply warehouses, maintenance shops, hazardous material storage, nonhazardous and hazardous waste storage, bulk fuel storage and transfer facilities, fleet parking, housing areas, recreational areas, two golf courses, and a marina.

MCAS New River is the principal USMC helicopter operating location on the East Coast and supports aircrew training in the H-53 helicopter. It is also the evaluation and prospective bed-down site for the V-22 Osprey. The mission of MCAS New River is to provide the necessary support for its Marine Aircraft Group (MAG) tenant units, MAG-26 and MAG-29.

1.2.1. Environmental Management Division and Environmental Affairs Department

MCB Camp Lejeune's EMD, within the Installation and Environment Department, is responsible for all natural resource and environmental matters aboard the installation. EMD works closely with MCB Camp Lejeune personnel, educating and training them to comply with environmental laws while accomplishing the military mission.

The EAD at MCAS New River works closely with the EMD on environmental compliance and protection matters. Due to

various joint operations, MCB Camp Lejeune and MCAS New River participate together in one EMS. See Figure 1-1 and Figure 1-2 for organization charts of EMD and EAD.



Figure 1-1. Environmental Management Division (MCB Camp Lejeune) Organization Chart

Figure 1-2. Environmental Affairs Department (MCAS New River)
Organization Chart

1.2.2. Expectations

Contractors aboard the installation, which are committed to strict compliance with environmental laws and regulations,

assist MCB Camp Lejeune in providing the best possible training facilities for today's Marines and Sailors, while honoring our environmental responsibilities and objectives. Violation of environmental laws may result in severe civil or criminal penalties and fines.

1.3. OVERVIEW OF REQUIREMENTS

Contractors operating aboard MCB Lejeune and MCAS New River must be aware of and adhere to all applicable environmental regulations and requirements, which include but may not be limited to the following:

- **EO 12088, Federal Compliance with Pollution Control Standards (October 13, 1978).** Requires all facilities owned by or leased to or by the military to be designed, operated, and maintained in compliance with all applicable environmental standards. Military and civilian personnel must cooperate with Federal, State, and local environmental protection agencies and comply with applicable standards and criteria issued by these agencies to the extent permitted by law.
- **EO 13423, Strengthening Federal Environmental, Energy, and Transportation Management.** Requires Federal agencies to comply with applicable Federal, State, local, and host nation environmental laws and regulations. Additionally, requirements include more widespread use of EMSs as the framework for sustainability management.

- **EO 13514, Federal Leadership in Environmental, Energy, and Economic Performance.** Requires Federal agencies to meet various sustainability goals, to include the reduction of greenhouse gas emissions. Applicable provisions for meeting these goals are to be included in acquisition and service contracts.
- **MCO P5090.2A, Environmental Compliance and Protection Manual (26 August 2013).** USMC policies and responsibilities for compliance with environmental statutes and regulations, as well as the management of USMC environmental programs.

1.3.1. Contractor Environmental Guide

This guide consists of the following information:

- MCB Camp Lejeune Contractor Environmental Guide
  - EMS overview and requirements
  - Environmental program-specific requirements
- MCB Camp Lejeune General EMS and Environmental Awareness Training for Contractors and Vendors
- Signature Page

Prior to beginning work onsite, or within 30 days of beginning work onsite, all contractors and their employees performing work aboard MCB Camp Lejeune must review these materials and complete EMS and General Environmental Awareness training.

Prior to beginning work onsite, or within 30 days of beginning work onsite, all contractors and their employees performing work aboard MCB Camp Lejeune must review these materials and complete EMS and General Environmental Awareness training. This guide summarizes the EMS and environmental programs at MCB Camp Lejeune, as well as key requirements associated with the various environmental issues contractors may encounter while performing work aboard the installation. Contractors are expected to work with their ROICC or Contract Representatives and EMD/EAD when environmental concerns or issues arise.

1.3.2. Environmental and EMS Training

In accordance with Department of Defense (DoD) instructions and MCOs, EMD has implemented a Comprehensive Environmental Training and Education Program (CETEP). The goal of the CETEP is to ensure that appropriate environmental instruction and related information are provided to all levels of the Marine Corps in the most effective and efficient manner to achieve full compliance with all applicable environmental training

requirements. A major component of the CETEP is to provide general environmental awareness training to all individuals associated with the installation, including contractors.

All contractors are required to receive both EMS and general environmental awareness training at the level necessary for their job function.

In addition to CETEP requirements, MCB Camp Lejeune has implemented an installation-wide EMS. The EMS highlights the fact that the authority and principal responsibility for controlling environmental impacts belong to those commands, units, offices, and personnel (including contractors) whose activities have the potential to impact the environment.

All contractors are required to receive both EMS and general environmental awareness training at the level necessary for their job function. This guide satisfies these training requirements (See the Appendix).

As such, contractors working aboard MCB Camp Lejeune will do the following:

- Conduct job responsibilities in compliance with environmental regulations and in conformance with EMS requirements.
- Complete all applicable environmental training and maintain associated records as per contract requirements.

- Complete EMS and general environmental awareness training, and be aware of and understand the MCB Camp Lejeune Environmental Policy.
- Contact their ROICC or Contract Representative immediately regarding environmental and/or EMS issues.

Prior to beginning work onsite or within 30 days, all contractors must sign and date the signature page and return it to the installation Contract Representative. Anyone who works on a contract at any point during the contract period must receive this information and training.

1.4. POINTS OF CONTACT

EMD Branches and phone numbers are found in the Contractor's Phone Directory on pages xv and xvi of this Guide. All initial inquiries regarding an environmental issue should be directed to the ROICC or Contract Representative, who will either directly contact or refer the contractor to the appropriate environmental office if additional clarification is necessary. In the case of a spill or environmental emergency, immediately dial 911. Additional emergency response procedures are provided in Section 5.0 of this Guide.

Table 1-1. Contacts in Case of a Spill

For spills of:	Call:	Follow-up:
Hazardous waste	**911**	Spill Report
Unknown materials	**911**	Spill Report
Material on a permeable surface	**911**	Spill Report
Any amount of a POL or Hazardous Material	**911**	Spill Report
Material that reaches stormwater inlets or waterways	**911**	
Nonhazardous waste	(910) 451-1482	911

1.5. OVERVIEW MAP

Figure 1-3 provides an overview map that displays the locations of installation facilities discussed throughout this Guide.



Figure 1-3. Overview Map

2.0 ENVIRONMENTAL MANAGEMENT SYSTEM

Three key principles of the Environmental Policy are to comply with relevant environmental laws and regulations, prevent pollution, and continually improve our EMS.

MCB Camp Lejeune and MCAS New River jointly operate an EMS, which provides a systematic way of continually implementing environmental requirements and evaluating performance. The EMS is founded on the principles of MCB Camp Lejeune's Environmental Policy, which is endorsed by the Commanding General (CG). Three key principles of the Environmental Policy are to:

- Comply with relevant environmental laws and regulations;
- Prevent pollution; and
- Continually improve the EMS.

The EMS promotes sustained mission readiness through actively identifying and implementing opportunities for efficient resource use. The USMC implements EMS at all levels to continually improve environmental compliance programs and meet evolving EOs and DoD requirements for mission sustainability. The EMS highlights the fact that the authority and principal responsibility for controlling environmental impacts belong to those commands, units,

offices, and personnel (including contractors and vendors) whose activities have the potential to impact the environment.

2.1. KEY DEFINITION AND CONCEPTS

The following key definitions and concepts are associated with an EMS. Please consult the ROICC or Contract Representative with any questions about these definitions or concepts.

Please consult the ROICC or Contract Representative with any questions.

2.1.1. Key Definitions

- **Environment.** Surroundings in which an organization operates, including air, water, land, natural resources, flora, fauna, humans, and their interrelation.
- **Environmental Aspect.** A characteristic of an organization's activities, products, or services that may cause, in normal operation or upset mode, an impact to an environmental or other resource. Each practice may have several aspects.
- **Environmental Impact.** An effect, beneficial or adverse, of a practice's aspect on an environmental or other resource. Each practice may have several impacts.
- **Environmental Resources.** Sensitive environmental receptors (e.g., air, water, natural

resources) or cultural or historic assets at MCB Camp Lejeune or MCAS New River, in the surrounding community, within the ecosystem, or beyond, that may be impacted by the operation of practices.

- **Practice.** A unit process that supports a military mission and may impact environmental resources. (It is the ability to impact an environmental resource that is key to defining a practice. However, practices may also impact other resources.)
- **Practice Owner.** Person(s) responsible for control of practices. EMS procedures use the term *practice owner* when the assignment of more specific responsibilities is left to the owning organizations.
- **Requirement.** Legislation, regulation, or policy issued by any Executive, Federal, State, local, DoD, Department of Navy (DoN), or USMC authority that addresses environmental considerations and requires action.

2.1.2. Key Concepts

- **Environmental Management System.** A systematic approach for integrating environmental considerations and accountability into day-to-day decisionmaking and long-term planning processes across all missions, activities, and functions. The EMS institutionalizes processes for continual environmental improvement and for reducing risks to mission through ongoing planning, review, and preventive or corrective action.

- **Environmental Policy.** Public commitment by senior leaders to the management of the installation's environmental affairs, including environmental compliance, pollution prevention, natural/cultural resource management, cleanup, risk to mission, and continual improvement of the EMS.

- **Plan, Do, Check, Act.** Four-step model by which the EMS carries out change – **Plan:** establish objectives and processes; **Do:** implement and execute the plan; **Check:** study and analyze the results; **Act:** take action based on what you learned.



Figure 2-1. Plan, Do, Check, Act Cycle

2.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard MCB Camp Lejeune and MCAS New River must be aware of and adhere to all applicable regulations and requirements concerning EMS, which include but may not be limited to the following:

- **EO 13148, Greening the Government Through Leadership in Environmental Management.** Mandates that environmental management considerations must be an integral component of Federal Government policies, operations, planning, and management, with the primary goal for each agency to promote the sustainable management of Federal facility lands through the implementation of cost-effective, environmentally sound practices, and programs to reduce adverse impacts to the natural environment.
- **EO 13423, Strengthening Federal Environmental, Energy, and Transportation Management.** Establishes the EMS as the primary management approach for addressing environmental aspects, including energy and transportation aspects, and as the reporting mechanism for communicating progress on meeting performance goals.
- **EO 13514, Leadership in Environmental, Energy, and Economic Performance.** Requires continuing implementation of formal EMSs at all appropriate organizational levels to support the sustainability performance requirements of the Order.

2.3. ENVIRONMENTAL MANAGEMENT SYSTEM

An EMS is a systematic way to identify and eliminate or minimize the installation's environmental risk-to-mission. MCB Camp Lejeune's EMS identifies practices and their aspects as a starting point for prioritizing environmental management initiatives. Each installation practice, such as construction/renovation/demolition, equipment operation/maintenance/disposal, landscaping, or pesticide/herbicide management and application, has one or more environmental aspects. Figure 2-2 illustrates the simplified potential interactions of one practice, construction/renovation/demolition, with the environment.

Figure 2-2. Potential Interactions of Construction and Demolition Activities with the Environment

2.4. EMS RESPONSIBILITIES

Contractors are expected to understand that the practices they support on the installation may interact with and have the potential to impact the environment. Therefore, it is expected that contractors will do the following:

Contractors are expected to understand that the activities performed on the installation may interact with the environment and have the potential to impact the environment.

- Review the Contractor Environmental Guide.
- Be aware of the Environmental Policy (Attachment 2-1).
- Conduct practices in a way that avoids and/or minimizes impacts to the environment by complying with all applicable Federal, State, and local environmental regulations and BOs.
- Be familiar with spill response procedures.
- Report all environmental emergencies and spills.
- Report any environmental problems or concerns promptly, and notify the ROICC or Contract Representative.
- Respond to data collection efforts upon request.

2.5. CONTRACTOR ENVIRONMENTAL GUIDE AND EMS

The sections of this Contractor Environmental Guide are categorized based on the type of environmental requirements routinely encountered by contractors at MCB Camp Lejeune. The following matrix is derived from MCB Camp Lejeune's EMS Working Group sessions and relates the contents of this guide to the practices aboard MCB Camp Lejeune. It is provided to assist contractors in narrowing down specific requirements that may apply to onsite activities.

Table 2-1. Practices Identified Under MCB Camp Lejeune's EMS

MCB Camp Lejeune 2015 Practices	**Env. Emergency Response/ Spill Response, Section 5.0**	**HM/HW, Section 7.0**	**Potential Discovery of Undocumented Contaminated Sites, Section 13.0**	**Asbestos, Section 8.0**	**Lead-Based Paint, Section 9.0**	**Stormwater, Section 11.0**	**Solid Waste, Recycling, and P2, Section 12.0**	**Training, Section 3.0**	**Cultural Resources, Section 6.0**	**Permitting, Section 14.0**	**Air Quality, Section 4.0**	**Natural Resources, Section 10.0**
Battery management	Applicable to All Practices Conducted Aboard MCB Camp Lejeune	●	Applicable to All Practices Conducted Aboard MCB Camp Lejeune				●	Applicable to All Practices Conducted Aboard MCB Camp Lejeune				
Boat operation/ maintenance		●									●	
Boat, ramp, dock cleaning						●						
Boiler operation		●									●	
Building operation/ maintenance/ repair		●		●			●					
Channel dredging						●						
Chlorination		●									●	
Composting						●	●					
Construction/demo/ renovation				●	●	●	●		●			
Cooling tower operation and maintenance		●										
De-greasing		●									●	
Drinking water management		●										
Engine operation and maintenance		●									●	
Equipment operation/ maintenance/disposal		●		●			●					
Erosion/ runoff control						●						●
Fish stocking												

MCB Camp Lejeune 2015 Practices	Env. Emergency Response/ Spill Response, Section 5.0	HM/HW, Section 7.0	Potential Discovery of Undocumented Contaminated Sites, Section 13.0	Asbestos, Section 8.0	Lead-Based Paint, Section 9.0	Stormwater, Section 11.0	Solid Waste, Recycling, and P2, Section 12.0	Training, Section 3.0	Cultural Resources, Section 6.0	Permitting, Section 14.0	Air Quality, Section 4.0	Natural Resources, Section 10.0
Fueling and fuel mgt./ storage	Applicable to All Practices Conducted Aboard MCB Camp Lejeune	●	Applicable to All Practices Conducted Aboard MCB Camp Lejeune			●		Applicable to All Practices Conducted Aboard MCB Camp Lejeune			●	
Grease traps							●					
Habitat management		●									●	●
HCP operation		●										
HM storage		●				●					●	
HM transportation		●									●	
HW disposal offsite transport		●					●					
HW satellite accumulation area		●									●	
HW storage (<90 days)		●										
HW transportation		●		●	●						●	
Land clearing						●	●		●			●
Landfill gas energy recovery system												
Landscaping		●				●						
Laundry		●										
Live fire range operation		●				●					●	●
Livestock operation						●	●					
Metal working		●					●				●	
Non-destructive inspection		●										
ODS/ halon management		●									●	
Packaging/unpack-aging							●					

MCB Camp Lejeune 2015 Practices	Env. Emergency Response/ Spill Response, Section 5.0	HM/HW, Section 7.0	Potential Discovery of Undocumented Contaminated Sites, Section 13.0	Asbestos, Section 8.0	Lead-Based Paint, Section 9.0	Stormwater, Section 11.0	Solid Waste, Recycling, and P2, Section 12.0	Training, Section 3.0	Cultural Resources, Section 6.0	Permitting, Section 14.0	Air Quality, Section 4.0	Natural Resources, Section 10.0
Paint booth	Applicable to All Practices Conducted Aboard MCB Camp Lejeune		Applicable to All Practices Conducted Aboard MCB Camp Lejeune					Applicable to All Practices Conducted Aboard MCB Camp Lejeune			●	
Paint gun cleaning		●									●	
Paint removal		●			●		●				●	
Painting		●					●				●	
Parts replacement		●		●			●					
Pesticide/herbicide mgt. and application		●				●						
Polishing		●					●				●	
Pumping station/ force main		●										
Range residue clearance		●				●	●					
Recreational facilities operation		●					●					
Road construction and maintenance						●	●		●	●	●	●
Rock-crushing operations							●				●	
Roofing kettle		●										
Sewers												
Sidewalk and road deicing		●				●						
Soil excavation/grading						●			●			●
Solid waste collection/transportation							●				●	
Storage tank management		●					●				●	

MCB Camp Lejeune 2015 Practices	Env. Emergency Response/ Spill Response, Section 5.0	HM/HW, Section 7.0	Potential Discovery of Undocumented Contaminated Sites, Section 13.0	Asbestos, Section 8.0	Lead-Based Paint, Section 9.0	Stormwater, Section 11.0	Solid Waste, Recycling, and P2, Section 12.0	Training, Section 3.0	Cultural Resources, Section 6.0	Permitting, Section 14.0	Air Quality, Section 4.0	Natural Resources, Section 10.0
Stormwater collection/ conveyance	Applicable to All Practices Conducted Aboard MCB Camp Lejeune		Applicable to All Practices Conducted Aboard MCB Camp Lejeune			●		Applicable to All Practices Conducted Aboard MCB Camp Lejeune				
Surface washing												
Swimming pool operation and maintenance		●										
Timber management												●
Universal waste storage/ collection		●										
Urban wildlife management							●					●
UXO/EOD operations		●									●	
Vehicle maintenance		●					●				●	
Vehicle parking						●						
Wash rack						●						

PAGE INTENTIONALLY BLANK

Attachment 2-1

MCB Camp Lejeune's Environmental Policy Statement

PAGE INTENTIONALLY BLANK

COMMANDING GENERAL'S ENVIRONMENTAL POLICY STATEMENT

The protection and enhancement of our natural environment is a valuable tool in sustaining the training and support mission of Marine Corps Installations East-Marine Corps Base Camp Lejeune (MCIEAST-MCB CAMLEJ). As MCIEAST-MCB CAMLEJ prepares for the increasing demands on facilities, training areas, ranges, and quality-of-life services that support the readiness of our forces, we are committed to protecting human health, conserving natural and cultural resources, and complying with regulatory requirements.

The MCIEAST-MCB CAMLEJ Environmental Management System (EMS) promotes sustained mission readiness through actively identifying and implementing solutions and opportunities for efficient resource use. Through the EMS, MCIEAST-MCB CAMLEJ will continually assess daily operations in order to identify and implement improvements to its practices that will ensure compliance with governing regulations and meet the sustainability objectives of Executive Orders 13514 and 13423. In this endeavor, MCIEAST-MCB CAMLEJ will:

- Continue proactive compliance with all environmental laws, regulations, and U. S. Marine Corps policies.
- Integrate natural and cultural resource management with the military mission whenever practical.
- Incorporate sound environmental practices into all of our operations and business decisions.
- Implement pollution prevention initiatives, waste diversion, recycling, and waste minimization programs.
- Assess and remediate contaminated sites aboard the Base that are the result of past disposal practices or spills and leaks of hazardous materials.
- Implement energy efficiency and water conservation management projects.
- Procure sustainable products, including biobased, environmentally preferable, energy efficient, water efficient, and recycled–content products.
- Collaborate with local communities and regulatory agencies to enhance stewardship of the environment, create goodwill and build trust.
- Educate our Marines, Sailors, and Civilian Marines about their responsibility to protect our natural environment, stressing the important role each individual plays in an effective EMS.

Join me in applying these environmental management principles to protect and enhance our natural environment, while strengthening the combat readiness of our forces and the quality-of-life services to our warriors and their families.

R. F. CASTELLVI
Brigadier General, U.S. Marine Corps
Commanding General
Marine Corps Installations East-Marine Corps Base Camp Lejeune

PAGE INTENTIONALLY BLANK

3.0 TRAINING

To minimize the environmental impact of MCB Camp Lejeune operations, all contractors are required to receive both EMS and general environmental awareness training at the level necessary for their job function.

The contractor is responsible for ensuring that every employee completes a program of classroom instruction or on-the-job training that teaches the employee to perform his or her duties in compliance with Federal, State, and local regulatory requirements.

To minimize the environmental impact of MCB Camp Lejeune operations, all civilian and military personnel, including contractors, are required to receive both EMS and general environmental awareness training at the level necessary for their job function. Use of the Contractor Environmental Guide satisfies these training requirements. A training presentation is provided in the Appendix.

NOTE: The contractor is responsible for knowing and complying with Federal, State, and local regulations. MCB Camp Lejeune environmental personnel will assist contractors with compliance issues; however, the primary burden of regulatory identification, familiarity, and compliance lies with the contractor. This training ***does not***

replace any required regulatory training as per contract requirements. Required training should be completed ***prior*** to working at MCB Camp Lejeune.

3.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with contractor training. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

3.1.1. Key Definitions

- **Explicitly Required Training.** Training expressly required by specific laws, regulations, or policies that apply due to the nature of work assignments, job functions, and/or specific licensing or certification requirements mandated by environmental laws, regulations, or policies.
- **Implicitly Required Training.** Instruction/information that is not expressly required by laws, regulations, or policies, but that may be reasonably inferred as being required to maintain compliance or is determined through EMS to reduce overall environmental risk.

3.1.2. Key Concepts

- **Comprehensive Environmental Training and Education Program (CETEP).** The USMC training program designed to ensure that high-quality, efficient, and effective environmental training, education, and information are provided at all levels of the USMC.
- **Environmental Management System (EMS).** The part of the overall management system that includes organizational structure, planning activities, responsibilities, practices, procedures, processes, and resources for developing, implementing, achieving, reviewing, and maintaining the Environmental Policy.
- **EMS Training.** All contractors are required to receive EMS training at the level necessary for their job function.
- **General Environmental Awareness Training.** Instruction designed to ensure that MCB Camp Lejeune and MCAS New River personnel become familiar with the installation environmental policies and programs for regulatory compliance, natural resource conservation, P2, and environmental protection. General EMS and Environmental Awareness Training for contractors and vendors is required for all MCB Camp Lejeune contractors. The training presentation is included as an Appendix to this document.

3.1.3. Environmental Management System

Training is potentially applicable to all EMS practices conducted aboard MCB Camp Lejeune.

3.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard MCB Lejeune and MCAS New River must be aware of and adhere to all applicable regulations and requirements concerning training, which include but may not be limited to the following:

- **Executive Order 13423.** Strengthening Federal Environmental, Energy, and Transportation Management. Requires implementation of an EMS at all appropriate organizational levels.

3.3. TRAINING REQUIREMENTS

3.3.1. General Environmental Awareness

In accordance with DoD instructions and MCO, the EMD at MCB Camp Lejeune has implemented a CETEP. A major component of the CETEP is to provide general environmental awareness training to all individuals associated with the installation, including contractors and vendors. Prior to or within 30 days of beginning work onsite, all contractors and their employees performing work aboard

Prior to or within 30 days of beginning work onsite, all contractors are required to receive both EMS and general environmental awareness training.

MCB Camp Lejeune must receive general environmental awareness training.

3.3.2. Environmental Management System

In addition to CETEP requirements, MCB Camp Lejeune has implemented an installation-wide EMS per EO 13423, *Strengthening Federal Environmental, Energy, and Transportation Management*, and DoD and USMC EMS policy. The EMS highlights the fact that the authority and principal responsibility for controlling environmental impacts belong to those commands, units, offices, and personnel (including contractors and vendors) whose activities have the potential to impact the environment.

Prior to or within 30 days of beginning work onsite, all contractors and their employees performing work aboard MCB Camp Lejeune must receive EMS training.

3.3.3. Recordkeeping

Upon completion of the training materials included in the Appendix of the Contractor Environmental Guide, each employee must sign the Training Roster. The Contracting Representative must maintain these records in the contract file.

All training records, including other applicable environmental training, must be maintained onsite for review.

PAGE INTENTIONALLY BLANK

4.0 AIR QUALITY

The Air Quality Program is responsible for ensuring that the installation complies with all applicable Federal, State, and local air quality regulations. The ROICC or Contract Representative will provide a copy of BO 5090.6A, Air Quality Management, which has additional information.

4.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with air quality. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

4.1.1. Key Definitions

- **Criteria Pollutants.** Pollutants that the U.S. Environmental Protection Agency (EPA) Administrator has determined will cause or contribute to air pollution, that may reasonably be anticipated to endanger public health and welfare, and for which air quality criteria have been established (i.e., sulfur dioxide, nitrogen oxides,

ground-level ozone, carbon monoxide, lead, and particulate matter).

- **Dust-Causing Activity.** Any activity that has the potential to generate an excess level of dust, including but not limited to construction and demolition (C&D), blasting and sanding, construction of haul roads, land clearing, or fallow fields.
- **Hazardous Air Pollutants.** Air pollutants, as identified within 42 United States Code (USC) 7412, that cause or may cause cancer or other serious health effects, such as reproductive effects or birth defects, or adverse environmental and ecological effects.
- **Ozone-Depleting Substance.** Chemicals, such as certain refrigerants, that cause depletion of the stratospheric ozone layer—primarily chlorofluorocarbons (CFCs) and hydrochlorofluorocarbons (HCFCs) and their blends.
- **Particulate Matter.** A criteria air pollutant that includes dust, soot, and other small materials that are released into and transported by air.
- **Title V Operating Permit.** Permit issued under the Clean Air Act (CAA) Amendments of 1990 for all major sources of air pollution. All emission sources at the installation must be listed on the permit.

4.1.2. Key Concepts

- **Emission Sources.** Before beginning any emitting activity, please have the ROICC or Contract

Representative contact EMD to determine whether any permitting, monitoring, reporting, testing, and/or recordkeeping requirements apply.

- **Permitted Sources.** Ensure that construction/authorization permits are in place prior to beginning construction and/or prior to the arrival onsite of new or additional emission sources (emergency generators, paint booths, etc.).

4.1.3. Environmental Management System

Contractor activities associated with air quality include the following:

- Boat operation/maintenance
- Boiler operation
- Chlorination
- Degreasing
- Engine operation and maintenance
- Fueling and fuel management/storage
- Hazardous material (HM) storage/transportation
- Hazardous waste (HW) satellite accumulation area/HW transportation
- Live fire range operations
- Metal working
- Ozone-depleting substance (ODS)/halon management

- Paint booth operations/paint gun cleaning/paint removal
- Polishing
- Road construction and maintenance
- Rock-crushing operations
- Solid waste collection/transportation
- Storage tank management
- Unexploded ordnance (UXO)/explosives and ordnance disposal (EOD) operations
- Vehicle maintenance

The potential impacts of these activities on the environment include degradation of air quality, degradation of quality of life, and depletion of nonrenewable resources.

4.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard the installation must be aware of and adhere to all applicable regulations and requirements regarding air quality, which include but may not be limited to:

- **Clean Air Act Amendments of 1990.** Protect human health and clean air resources by establishing standards and regulations for the control of air pollutants.
- **Title V Operating Permit.** Operating permit required for any major stationary source that emits or

has the potential to emit 100 tons per year or more of any criteria air pollutant and outlines the requirements to address and ensure air quality compliance.

- **BO 5090.6A, Air Quality Management.** Implements policies and procedures at the installation level that all personnel must follow in order to demonstrate compliance with the Title V permit and USMC requirements.
- **Base Bulletin 5090, Open Burning of Vegetative Debris.** Outlines procedures for conducting open burning in accordance with State regulations and installation procedures.
- **North Carolina Department of Air Quality (NCDAQ) Rules.** Outlines all State-specific air quality rules, control requirements, procedures for permits, and approvals contained in 15A North Carolina Administrative Code (NCAC) 02D, 02H, and 02Q applicable to North Carolina entities.

4.3. PERMIT REQUIREMENTS

The installation has a single permit, the CAA Title V Construction and Operating Permit, which includes all stationary air emission sources at the facility; therefore, all permit application submittals to the NCDAQ must be coordinated through the EMD. The NCDAQ will review and process the application and then issue a permit to construct and operate or to modify the emission source(s). A permit is required prior to the construction of any emission source. Timely submittal of the permit application is required to

obtain the final permit prior to commencing construction. The most common types of emission sources at the installation are as follows:

A permit is required for the construction of any emission source. Timely submittal of the permit application is necessary to ensure the permit is available before commencing construction.

- Boilers
- Generators
- Engine test stands
- Surface coating/painting operations
- Paint removal (chemical and mechanical), abrasive blasting, or other surface preparation activities
- Fuel storage and fuel dispensing
- Grinding
- Woodworking
- Welding
- ODS/refrigerant recovery and recycling operations (industrial chillers, refrigerators, air conditioning compressors, cleaning agents, etc.)
- Bulk chemical and flammable materials storage

4.4. ADDITIONAL ACTIVITIES OF CONCERN

Contact the ROICC or Contract Representative for additional information regarding activities that do not

necessarily require modification to the Title V permit, but that must be coordinated with or tracked by EMD or the NCDAQ. Examples of these activities include, but are not limited to, the following:

- **Use, Maintenance, and Management of Refrigerants and other ODS.** Includes installation, recovery, replacement, conversion, or service of refrigerant-containing equipment (chillers, refrigerators, air conditioning condensers, etc.). All contractors will use Best Management Practices (BMPs) during refrigerant management activities. All Heating, Ventilation, and Air Conditioning (HVAC) technicians will maintain their appropriate State-specific licenses and present them to the ROICC or Contract Representative upon request.
- **Emergency Generators.** Includes the installation and temporary use of emergency generators during electrical failures and construction activities. All contractors will coordinate with the ROICC or Contract Representative to determine if the intended generator may be exempted or must be temporarily permitted for the intended use.
- **Open Burning (e.g., right-of-way clearing, storm debris burning).** Open burning activities aboard MCB Camp Lejeune and MCAS New River must coordinated through EMD and the Fire Department. Open burning activities are only permissible for land clearing and right-of-way maintenance when the following conditions are met:

- The wind direction at the time the burning is initiated is away from any public transport roads within 250 feet so they are not affected by smoke, ash, or other air pollutants from the burning.
- The location of the burning is at least 500 feet from any dwelling, group of dwellings, commercial or institutional establishment, or other occupied structure not located on the property on which the burning is conducted, unless an air curtain burner is used. If an air curtain burner is used, the regional office supervisor may grant exceptions to the setback requirements.
- Heavy oils, asphaltic materials (e.g., shingles and other roofing materials), items containing natural or synthetic rubber, or any materials other than vegetative plant growth are not burned.
- Initial burning must begin between 0800 and 1800. After 1800, no material may be added to the fire until 0800 the following day.
- No fires may be started, and no vegetation may be added to existing fires, when the North Carolina Division of Forest Resources has banned burning for that area.
- Burners that have the potential to burn more than 8,100 tons per year may be subject to Title V air quality permitting requirements.

Situations that require a regulatory exemption evaluation by the NCDAQ Regional Office

Supervisor are coordinated through EMD's Environmental Quality Branch Air Quality Program Manager. The ROICC or Contract Representative will address any additional questions or provide a copy of Base Bulletin 5090, which contains a summary of the installation's open burning requirements.

The four designated sites at MCB Camp Lejeune that are permitted for storing and/or burning storm debris are in the following areas: Mainside at the borrow pit near the Piney Green landfill, Courthouse Bay, Camp Johnson, and Camp Geiger. Only storm debris may be accumulated at these sites. EMD must notify the NCDAQ if the installation intends to burn the storm debris at one of these sites. Contact the ROICC or Contract Representative for more information.

- **Fire training outside of designated fire training pits**. State approval is required to conduct fire training outside of the designated fire training pits. First, complete the Notification of Open Burning for the Training of Firefighting Personnel form. The form is available at the following site: http://daq.state.nc.us/enf/openburn/ob_firetrain.pdf.

  Before the training exercise, an accredited North Carolina Asbestos Inspector must inspect any structure to be burned to ensure that it is free from asbestos. Turn in the completed form to EMD for submittal to NCDAQ and the Division of Public Health, Health Hazards Control Unit. Contact the

ROICC or Contract Representative for additional information.

- **Dust-causing activities (e.g., concrete and rock crushing).** Wet suppression is required during the entire dust-causing operation. Ensure that an adequate water supply is available, and coordinate with the Fire and Emergency Services Division if access to a fire hydrant is necessary. Applicable wet suppression may be required during temporary concrete-crushing operations during C&D activities.

- **Noise Management.** USMC commands engaged in any activity resulting in noise emissions must comply with Federal, State, interstate, and local requirements for the control and management of environmental noise to minimize disruption to the local community. To the maximum extent practicable, personnel should limit the use of power tools, machinery, construction equipment, and other noisy devices to normal working hour

5.0 ENVIRONMENTAL EMERGENCY PLANNING AND RESPONSE

Environmental emergency planning and response can reduce injuries, protect employees, reduce asset losses, minimize downtime, and minimize environmental impacts of uncontrolled releases of pollutants to air, land, and water. The purpose of emergency planning is to prepare for, mitigate, respond to, and recover from environmental emergencies while minimizing any potential impacts to human health and the environment. Contractors operating aboard MCB Camp Lejeune must be aware of and adhere to all environmental emergency response procedures and notification requirements to minimize detrimental effects from inadvertent releases.

Procedures relating to emergencies caused by unforeseen site conditions are addressed in Section 5.0of this guide. If an environmental emergency is identified, contact 911 immediately. Additional inquiries should be directed to the ROICC or Contract Representative.

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

5.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with environmental emergency response and spill response requirements. If you have any

questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

5.1.1. Key Definitions

- **Berm.** A mound used to prevent the spread of a contaminant.
- **Discharge.** Any spilling, leaking, pumping, pouring, emitting, emptying, or dumping not explicitly permitted.
- **Navigable waters.** The waters of the United States and territorial seas, including waters that have been or may be used for commerce, waters subject to tidal flow, interstate waters and wetlands, and all other waters (intrastate lakes, rivers, streams, intermittent streams, flats, wetlands, sloughs, prairies, wet meadows, natural ponds, tributaries, etc.).
- **Petroleum, Oil, and Lubricant (POL).** A broad term that includes all petroleum and associated products or oil of any kind or in any form, including, but not limited to, petroleum, fuel oil, vegetable oil, animal oil, sludge, oil refuse, and oil mixed with wastes.
- **Release.** Pumping, pouring, emitting, emptying, discharging, injecting, escaping, leaching, dumping, or disposing into the environment (including the abandonment or discarding of barrels, containers, and other closed receptacles) of any hazardous

chemical, hazardous substance, or extremely hazardous substance (EHS). Releases may be aboveground, belowground, or to water.

- **Spill Event.** The reportable discharge of oil into or upon the navigable waters of the United States or adjoining shorelines in harmful quantities, as defined by the Code of Federal Regulations (CFR) in 40 CFR 110.

5.1.2. Key Concepts

- **Environmental Emergency Response Contacts.** The following table identifies the emergency contact information for various spill scenarios. In addition to these emergency response contacts, the ROICC or Contract Representative should be notified immediately after an incident.

Table 5-1. Environmental Emergency Response Contacts

For spills of:	Call:	Follow-up:
Hazardous waste	**911**	Spill Report
Unknown materials	**911**	Spill Report
Material on a permeable surface	**911**	Spill Report

For spills of:	Call:	Follow-up:
Any amount of a POL or Hazardous Material	**911**	Spill Report
Material that reaches stormwater inlets or waterways	**911**	
Nonhazardous waste	(910) 451-1482	911

- Contractors have containment and cleanup responsibilities following a spill, and there may be additional follow-up reporting or requirements. Contact the ROICC or Contract Representative for additional guidance.

5.1.3. Environmental Management System

Environmental planning and response are potentially applicable to all EMS practices conducted aboard MCB Camp Lejeune.

5.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard MCB Lejeune and MCAS New River must be aware of and adhere to all applicable regulations and requirements regarding emergency response

and spill response procedures, which include but may not be limited to the following:

- **Clean Air Act of 1970, Section 112r** Mandates the prevention and control of air emissions and specifies emergency planning where the potential exists for accidental release of hazardous air pollutants.
- **Clean Water Act (CWA) of 1972.** Establishes the basic structure for regulating discharges of pollutants into the waters of the United States. The CWA establishes that there should be no discharges of oil or hazardous substances into or upon the navigable waters of the United States or adjoining shorelines, which may affect natural resources under the management of the United States.
- **Comprehensive Environmental Response, Compensation, and Liability (CERCLA) Act of 1980.** Authorizes a Federal response to any release or threatened release of a hazardous substance into the environment. This act defines hazardous substances by reference to substances that are listed or designated under other environmental statutes.
- **Emergency Planning and Community Right-to-Know Act (EPCRA) of 1986, Section 304.** Establishes requirements for reporting a release to ensure a quick response by local emergency responders. Notification requirements apply to two chemical lists: the CERCLA Hazardous Substance list and the EHS list. The “List of Lists” provides a comprehensive identification of hazardous

substances and EHSs. In addition, facilities may be required to submit a list of their hazardous materials inventory maintained onsite or Safety Data Sheets (SDS) to response personnel.

- **Oil Pollution Act (OPA) of 1990.** Addresses oil storage at facilities and emphasizes preparedness and response activities. This act prohibits the harmful discharge of oil and hazardous substances into waters of the United States. The OPA requires contingency planning for "worst case" discharges and demonstrated response capabilities through planning, equipment, training, and exercises.
- **Resource Conservation and Recovery Act (RCRA) of 1976.** Protects human health and the environment from the hazards associated with hazardous waste handling, generation, transportation, treatment, storage, and disposal. Subtitle C of the RCRA requires owners and operators of hazardous waste facilities to develop comprehensive management plans that address spill prevention and cleanup.

5.3. SPILL NOTIFICATION

5.3.1. POL/Hazardous Materials Spill Notification Procedures

In accordance with MCB Camp Lejeune notification requirements, any discharge of oil or hazardous materials must be immediately reported to the MCB Camp Lejeune Fire Department at 911.

MCB Camp Lejeune maintains a Spill Prevention, Control, and Countermeasures (SPCC) Plan that establishes procedures to prevent oil spills and documents existing oil spill prevention structures, procedures, and equipment. The Installation SPCC Plan provides general information for any type of response actions needed for spills aboard MCB Camp Lejeune. Contractors engaged in the handling and transfer of POL or hazardous materials must develop a Unit-Level Contingency Plan (ULCP) that addresses the spill response for their specific sites and potential spill types. This ULCP must be maintained onsite, and all personnel working within that site must be made aware of its location and use.

Contractors must develop a Unit-Level Contingency Plan that addresses the spill response for their specific sites and potential spill types.

In the event of a spill, contact the ROICC or Contract Representative (after contacting emergency responders) to obtain a spill report form. Return the completed spill report form to EMD (fax to (910) 451-3471) and to the ROICC or Contract Representative. A copy of the spill report form is included as Attachment 5-1. The following information must be provided when reporting a spill:

- Name and phone number
- Location of spill (building. number, street)
- Number and type of injuries, if any
- Type and amount of spilled material

- Source of the spill (container, vehicle, etc.)
- Action being taken, if any, to control the spill
- Estimated time of spill

Do not wait to report a spill, even if all of the required information is not immediately available.

5.3.2. Wastewater Spill and Water Line Break Notification

Contractors operating aboard MCB Camp Lejeune and MCAS New River must be aware of water and wastewater utilities in their specific work/project area.

Wastewater Spills

In the event of a wastewater spill, report the incident to the Public Works Base Utilities at (910) 451-7190 (x225). In addition, report the incident immediately to the ROICC or Contract Representative. The following information must be provided:

- Name and phone number
- Location of spill (building number, street address)
- Type and amount of spilled material
- Source of the spill
- Action being taken, if any, to control the spill
- Estimated time of spill

Water Line Breaks

In the event of a water line break, report the incident to the Public Works Base Utilities at (910) 451-7190 (x225). In addition, report the incident immediately to the ROICC or Contract Representative. The following information must be provided:

- Name and phone number
- Location of spill (building number, street address)
- Reason for the break
- Estimated time of the break

5.4. FOLLOW-UP

If surface run-off is contaminated, the contractor will, under the advisement of the Fire Department or EMD, construct a temporary berm or containment area. Contaminated surface water will be removed in accordance with all safety and environmental requirements for the installation. Notify the Resource Conservation and Recovery Section (RCRS) at (910) 451-1482); the RCRS will provide concurrence for temporary containment areas and removal of contaminated runoff.

If solid or hazardous waste was generated as the result of a spill, refer to Sections 12.0 and 7.0 of this guide for disposal requirements.

PAGE INTENTIONALLY BLANK

Attachment 5-1

Spill Reporting Form

PAGE INTENTIONALLY BLANK

MARINE CORPS INSALLATIONS EAST
MARINE CORPS BASE CAMP LEJEUNE
UNIT LEVEL SPILL FORM

Spill Date: Spill Time:

RESPONDERS

Response Initiator: Major Command:

Phone Number: Unit Name:

Fire Department Response: Responder Name:

EMD Respond? Responder Name:

GPS Coordinates: X: Y:

SPILL IDENTIFICATION

Spilled Substance: State:

Source (Vehicle, drum, etc.): Building:

Estimated Amount:

Cause of Spill:

Containment/Clean-up Action Taken:

Parties Performing Spill Clean-up/Removal (EMD Turn-in Date):

Additional Assistance Required:

REPORT CERTIFICATION

Printed Name/Rank: Signature:

E-mail: Date:

All releases must be reported to the Base Fire Department by calling 911. The Environmental Management Division can be reached by calling (910) 451-1482. Units are required to maintain a copy of all completed spill forms, preferably in their ESOP Binder.

MCIEAST-MCB CAMLEJ/G-F/EMD/5090.9/18 (2/13) PREVIOUS EDITIONS ARE OBSOLETE ADOBE 9.0

Enclosure (4)

PAGE INTENTIONALLY BLANK

6.0 CULTURAL RESOURCES

MCB Camp Lejeune enjoys a rich history, and remnants of our past may be found throughout the real properties that make up the installation. All personnel at MCB Camp Lejeune are responsible for ensuring the cultural resources entrusted to the USMC care remain intact and available for future generations. Contractors are responsible for notifying the ROICC or Contract Representative immediately if they encounter suspected archaeological sites, artifacts, or human remains.

6.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with cultural resource management. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

6.1.1. Key Definitions

- **Archaeological Resource.** Defined by the Archaeological Resources Protection Act (ARPA) as any material remains of past human life or activities

that are at least 100 years old and are capable of providing scientific or human understanding of past human behavior and cultural adaptation, including the site on which the remains are located. Examples include pottery, basketry, bottles, weapons, weapon projectiles, tools, structures or portions of structures, pit houses, rock paintings, rock carvings, intaglios, graves, human skeletal materials/remains, or any portion or piece of any of the foregoing items or structures. Non-fossilized and fossilized paleontological specimens, or any portion or piece thereof, are not considered archaeological resources unless found in an archaeological context. (According to the National Historic Preservation Act (NHPA) of 1966, some historic properties built within the past 50 years can achieve significance if they are of exceptional importance [National Register Criteria Consideration G].)

- **Cultural Resource.** A generic term for the collective evidence of the past activities and accomplishments of people, including buildings, structures, districts, sites, features, and objects of significance in history, architecture, archaeology, engineering, or culture, per MCO P5090.2A.

- **Effect.** Any condition of a project that may cause a change in the quality of the historic, architectural, archaeological, or cultural character of a property that qualifies it for listing in the National Register of Historic Places (NRHP). A project is considered to have an effect on a historic or cultural property when any aspect of the project changes the integrity of the

location, design, setting, materials, workmanship, feeling, or association of the property that contributes to its significance.

- **Historic Property.** Any prehistoric or historic district, site, building, structure, or object significant in U.S. history, architecture, archaeology, engineering, or culture and included, or eligible for listing in, the NRHP, per the NHPA and MCO P5090.2A.
- **State Historic Preservation Officer.** The person designated to administer the State Historic Preservation Program, including identifying and nominating eligible properties to the NRHP and administering applications for listing historic properties in the NRHP.

6.1.2. Key Concepts

- **Notification.** Contractors must notify the ROICC or Contract Representative if they encounter any cultural resources.
- **Policy.** DoD policy is to preserve significant historic and archaeological resources.

6.1.3. Environmental Management System

Contractor practices associated with cultural resources include the following:

- Construction/demolition/renovation
- Land clearing

- Road construction and maintenance
- Soil excavation/grading

The potential impacts of these activities on the environment include damage, destruction, alteration, theft, or demolition of historic properties.

6.2. OVERVIEW OF REQUIREMENTS

It is DoD policy to integrate the archeological and historic preservation requirements of applicable laws with the planning and management of activities under DoD control; to minimize expenditures through judicious application of options available in complying with applicable laws; and to encourage practical, economically feasible rehabilitation and adaptive use of significant historical resources.

Contractors operating aboard MCB Lejeune and MCAS New River must be aware of and adhere to all applicable regulations and requirements regarding cultural resources, which include but may not be limited to the following:

- **BO 5090.8A.** Sets forth regulations and establishes responsibilities associated with management of archaeological and historic resources aboard MCB Camp Lejeune.
- **Archaeological and Historic Preservation Act (AHPA) of 1974 (16 USC 469 *et seq.)*** Amends the Reservoir Salvage Act to extend its provisions beyond the construction of dams to any terrain alteration resulting from any Federal construction

project or federally licensed project, activity, or program.

- **Archeological Resources Protection Act of 1979 (16 USC 470 et seq.)** Requires Federal land managers to issue permits for the excavation or removal of artifacts from lands under their jurisdiction. The ARPA requires that relevant Native American tribes be notified of permit issuance if significant religious or cultural sites will be affected. It prohibits the excavation, damage, alteration, theft, or defacement of an archaeological site or artifacts unless permitted by the Federal land manager.
- **DoD Directive 4710.1, Archaeological and Historic Resources Management.** Provides policy for the management of archaeological and historic resources on land and in water under DoD control.
- **EO 11593, May 13, 1971.** Requires all Federal agencies to administer cultural properties under their control. Agencies are required to direct their policies, plans, and programs so that significant sites and structures are preserved.
- **Historic Sites, Buildings, and Antiquities Act of 1935 (Public Law 74-292, 16 USC 461 et seq.).** States that it is Federal policy to preserve historic and prehistoric properties of national significance.
- **National Environmental Policy Act (NEPA) of 1969 (42 USC 4321 et seq.).** States that it is Federal government policy to preserve important historic, cultural, and natural aspects of our national heritage

and requires the consideration of environmental concerns during project planning and execution.

- **National Historic Preservation Act of 1966 (16 USC 470 et seq.).** Establishes historic preservation as a national policy and requires Federal agencies undertaking actions that may affect NRHP-eligible historic properties to consult State historic preservation offices and the Advisory Council on Historic Preservation. Section 110 of NHPA requires Federal agencies to inventory, evaluate, identify, and protect cultural resources that are determined eligible for listing in the NRHP.
- **Public Buildings Cooperative Use Act of 1976 (Public Law 94-541).** Encourages adaptive reuse of historic buildings as administrative facilities for Federal agencies.
- **Title 36 CFR Part 65, National Historic Landmarks Program.** Identifies and designates National Historic Landmarks, and encourages the long-range preservation of nationally significant properties that illustrate or commemorate the history and prehistory of the United States.

6.3. PROCEDURES

All contractors are expected to follow these procedures:

- Notify the ROICC or Contract Representative immediately concerning any encounter with suspected archaeological sites, artifacts, human remains, or any other suspected cultural resources during contractor activities.
- Stop work in the immediate area of the discovery until directed by the Contract Representative to resume work.

Notify the ROICC or Contract Representative immediately concerning any encounter with suspected archaeological sites, artifacts, or human remains during contractor activities.

Be particularly aware of surroundings when working in a designated historic area. The Camp Lejeune Installation Geospatial Information & Services Office of the Geospatial Services Division can provide resource mapping of known cultural resource areas for all planners, project managers, contractors, and others, through formal request. The ROICC or Contract Representative will assist with making arrangements to request access for Geographic Information System mapping.



Figure 6-1. Possible Cultural Resource Discovery Flow Chart

7.0 HAZARDOUS MATERIALS/HAZARDOUS WASTE MANAGEMENT

All persons on a USMC installation are subject to compliance with Federal, State, and local regulations and permit conditions addressing the proper management of hazardous materials and waste. Mishandling these wastes and materials may result in violation notices, fines, and/or penalties. The EPA regulates hazardous wastes through the RCRA, which provides specific regulatory definitions for hazardous waste and its management. The RCRA governs all hazardous waste from the point of generation to ultimate disposal, including hazardous waste generated by contractors aboard MCB Camp Lejeune and MCAS New River. Hazardous materials, including those used by contractors aboard the installation, are also regulated by the EPCRA. Additionally, the North Carolina Department of Environmental Quality (NCDEQ) has issued more stringent rules and regulations governing hazardous materials and hazardous waste management that also apply to contractors.

7.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with hazardous materials (HM), hazardous wastes (HW), and their management. If you have any questions or concerns about the information in this section,

Direct questions or concerns about the information in this section to the ROICC or Contract Representative.

please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

7.1.1. Key Definitions

- **90-day Accumulation Area.** These areas are used to store HW temporarily until it is either manifested and shipped off site for disposal or transferred to a permitted storage facility. HW may be accumulated for up to 90 days in these areas. MCB Camp Lejeune's 90-day accumulation facility is located on Michael Road.
- **Generator.** Any person whose activity or process produces HW or whose activity or process subjects HW to regulation.
- **Hazardous Material.** A chemical compound, or a combination of compounds, posing or capable of posing a significant risk to public health, safety, or the environment as a result of its quantity, concentration, or physical/chemical/infectious properties.
- **Hazardous Waste.** Any discarded material (including solid, liquid, or gas) or combination of discarded materials which, due to quantity, concentration, or physical, chemical, or infectious characteristics may:
    - Cause or significantly contribute to an increase in mortality or cause a serious irreversible or incapacitating reversible illness; or

- Pose a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported, disposed of, or otherwise managed.

- **Manifest.** A document that allows all parties involved in HW management (e.g., generators, transporters, disposal facilities, EPA, State agencies) to track the movement of HW from the point of generation to the point of ultimate treatment, storage, or disposal. All HW manifests for waste generated aboard MCB Camp Lejeune must be reviewed and released by personnel from the Resource Conservation and Recovery Section, EMD, who can be contacted at (910) 451-1482.

- **Non–RCRA-Regulated Waste.** Waste that is not regulated or is exempt from regulation under RCRA HW requirements but has other regulatory requirements for proper management.

- **Satellite Accumulation Area (SAA).** Designated areas at or near the point of generation, where HW is accumulated. Generators may accumulate up to 55 gallons of HW or one quart of acute HW at a satellite area for an indefinite amount of time. When 55 gallons of HW (or 1 quart of acute HW) are exceeded, the generator must date the container and transfer it to an approved 90-day site or long-term HW storage facility within 72 hours. EMD authorization for an SAA must be obtained and posted at the site. EMD authorization will establish individual limits for each SAA. No SAA

authorizations will exceed 55 gallons of HW or 1 quart of acute HW. In accordance with installation policy, HW in an SAA should not be stored longer than 365 days, even if the container is not full.

- **Safety Data Sheet (SDS).** A document that provides information about (1) chemical properties, environmental hazards, and health hazards; and (2) protective measures, along with safety precautions, for handling, storing, and transporting hazardous chemical products. The Hazard Communication Standard (HCS), 29 CFR 1910.1200(g), was revised in 2012 to mandate the use of a single Globally Harmonized System of Classification and Labelling of Chemicals (GHS) by manufacturers, distributors and importers to communicate information on chemical-related hazards. The information contained in the SDS is standardized in a 16-section format. Employers must ensure that the SDSs for all hazardous chemicals in the workplace are readily accessible to employees.
- **Treatment.** Any method, technique, or process designed to change the physical, chemical, or biological character or composition of any HW to neutralize the waste; or to recover energy or material resources from the waste; or to render such waste nonhazardous or less hazardous, safer to transport, store, or dispose of, or amenable for recovery or storage, or reduction in volume.
- **Treatment, Storage, and Disposal (TSD) Facilities.** TSD facilities conduct HW treatment,

storage, or disposal operations and require an RCRA part B permit for final approval to operate. The part B permit is maintained to accurately identify the most current operations at the TSD facility. MCB Camp Lejeune does not have a TSD facility.

- **Universal Waste (UW).** UW regulations streamline HW management standards for batteries, pesticides, mercury-containing equipment, and fluorescent lamps. The regulations govern the collection and management of these widely generated wastes, thus facilitating environmentally sound collection and proper recycling or treatment. In North Carolina, batteries, thermostats, obsolete agricultural pesticides, and fluorescent lamps may be managed under the UW Rule. UW must be transferred off site within 1 year of the date when the material was first identified as waste.

- **Used Oil.** Any oil that has been refined from crude oil or synthetic oil and, as a result of use, storage, or handling, has become unsuitable for its original purpose due to the presence of impurities or loss of original properties. Used oil may be suitable for further use and is economically recyclable; therefore, it is managed as a separate category of material.

7.1.2 Key Concepts

- **HW Management.** The systematic control of the collection, source separation, storage, transportation, processing, treatment, recovery, and disposal of HW. In addition, HW Management includes processes to

reduce the HW's effect on the environment and to recover resources from it.

- **HW Minimization.** The USMC policy is to reduce the quantity of HW disposed of by source reduction, recycling, treatment, and disposal. The highest priorities are reducing HW generation, and recycling. The goal of the USMC is to achieve continuous reduction of HW generation through P2 initiatives, BMPs, and use of the best available demonstrated technology.
- **National Fire Protection Association.** The U.S. trade association that creates and maintains private, copyrighted standards and codes, including the diamond hazard label in Figure 7-1, which is used by emergency personnel to quickly and easily identify the risks posed by hazardous materials.



Figure 7-1. Diamond Hazard Label

7.1.3 Environmental Management System

Contractor practices associated with HM and HW management include, but are not limited to, the following:

Battery management

Boat operation/ maintenance

Boiler operation

Building operation/ maintenance/repair

Chlorination

Cooling tower operation and maintenance

Construction/renovation/ demolition

Degreasing

Drinking water management

Engine operation and maintenance

Equipment operation/ maintenance/disposal

Fueling and fuel management/storage

Habitat management

HCP operation

HM storage

HM transportation

HW disposal offsite transport

HW satellite accumulation area

HW storage (<90 days)

HW transportation

Laboratory

Landscaping

Laundry

Live fire range operations

Metal working

Non-destructive inspection

ODS/halon management

Paint gun cleaning

Paint removal

Painting

Parts replacement

Pesticide/herbicide management and application

Polishing

Pumping station/force main

Range residue clearance

Recreational facilities operation

Roofing kettle

Sidewalk and road deicing

Storage tank management

Swimming pool operation and maintenance

Universal waste storage/collection

UXO/EOD operations

Vehicle maintenance

The potential impacts of these activities on the environment include depletion of the HW landfill, depletion of non-renewable resources, and degradation of soil quality.

7.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard MCB Lejeune and MCAS New River must be aware of and adhere to all applicable regulations and requirements regarding HM and HW, which include but may not be limited to the following:

- **BO 5090.9, Hazardous Material/Waste Management/Air Station Order (ASO) 5090.2, Environmental Compliance and Protection Program for MCAS New River.** Establishes procedures and general responsibilities for the disposal of HM and HW under environmental permits and authorizations.
- **Emergency Planning and Community Right-to-Know Act.** Establishes requirements regarding emergency planning and the reporting of hazardous chemical storage and use.
- **Hazardous Material Transportation Act (HMTA) of 1975.** The principal Federal law regulating the transportation of HM. Established to mitigate the risks to health, property, and the environment inherent in the transportation of HM in intrastate, interstate, and foreign commerce. The HMTA is administered by the U.S. Department of Transportation (DOT) and regulates the shipping, marking, labeling, placarding, and recordkeeping requirements for HM, including HW and military munitions.

- **Resource Conservation and Recovery Act of 1976.** Establishes standards for HW generators as necessary to protect human health and the environment by instituting statutory standards for generators and transporters of HW that will ensure the following: proper recordkeeping and reporting; use of a manifest system; use of appropriate labels and containers; containerization and accumulation time; and proper management of TSD facilities. In addition, it gives the EPA and State agencies authority to access facility premises and all records regarding HW management.
- **40 CFR Subchapter I (Parts 260–299), Solid Wastes.** Federal regulations promulgated under the 1976 RCRA that regulate HW management, generators, transporters, and owners or operators of TSD facilities. North Carolina has adopted the Federal HW rules by reference.

Because the installation is designated as a Large Quantity Generator (LQG) of HW, all HW generated aboard MCB Camp Lejeune must meet the regulatory requirements of this generator designation. An LQG may maintain three types of HW accumulation/storage areas: satellite, 90-day, and permitted. Typically, HW is accumulated at an SAA and later transferred to a 90-day or permitted storage area.

Both MCB Camp Lejeune and MCAS New River maintain Hazardous Waste Management Plans (HWMPs) that outline the specific requirements for managing HM and HW. The HWMP identifies and provides guidance to implement all regulatory HW management activities and is available to all

personnel who accumulate, generate, transport (including on-installation transportation), treat, store, or dispose of HW.

Contractors may be required to submit a Hazardous Waste Management Plan to the ROICC or the Contract Representative prior to beginning work.

Contractors are responsible for the management of all HM and the ultimate disposition of any HW generated aboard MCB Camp Lejeune during a contract performance period. The ROICC or Contract Representative will contact Environmental personnel, who will provide additional guidance and oversight to verify compliance with applicable Federal, State, and local laws governing the generation, handling, and disposal of HM, HW, UW, used oil, petroleum-contaminated materials, RCRA-regulated HW, and non–RCRA-regulated waste.

Depending on the type of project, contractors may be required to submit a site-specific HWMP to the ROICC or the Contract Representative prior to beginning work. Additionally, the Contracting Officer may require a Contractor Hazardous Material Inventory Log and corresponding SDSs for all materials to be used during the execution of the contract. EMD/EAD will use the SDSs to help contractors establish their Hazardous Material Storage and SAAs.

7.3. HAZARDOUS MATERIALS REQUIREMENTS

If a project uses HM:

- Reduce/reuse/recycle when possible; meet contract requirements for recycling.
- Segregate incompatible materials. Consult the SDS or material manufacturers with questions about a material's compatibility. Some examples of incompatible materials likely to be used by contractors are:

Do not store large quantities of materials. Keep on hand only what can be used.

  - *Corrosives* (e.g., batteries, stripping and cleaning compounds containing acids or bases) *and Flammables* (e.g., fuels, oils, paints, and adhesives)
  - *Corrosives and Oxidizers* (e.g., peroxide, perchlorates, sodium hypochlorite/bleach, or calcium hypochlorite)
  - *Oxidizers and Flammables*
- All compatible materials should be segregated and stored within designated storage lockers or cabinets (i.e., flammable materials should be stored in designated flammable storage lockers or cabinets, and corrosives should be stored in designated corrosives storage lockers or cabinets).

- Do not store large quantities of materials. Keep on hand only what can be used.
- Maintain an inventory of all HM maintained onsite, with adequate controls in place to prevent unauthorized access.
- Do not dump any HM into floor drains, sinks, oil-water separators (OWSs), or storm drains, or onto the ground.

Stop work immediately if a project unearths a hazardous material (such as MEC/DMM/UXO) and report the situation to the ROICC or Contract Representative.

- Store containers that hold 55 gallons or more (including in-use electrical generators and portable equipment) in proper secondary containment. Permanent secondary containment must be inspected weekly, temporary secondary containment must be inspected daily; all inspections and drainage of stormwater from secondary containment must be documented.
- Maintain SDSs and appropriate spill control/cleanup materials onsite at all times.
- Provide HM storage and usage information for regulatory reporting to the appropriate environmental office upon request.
- Stop work immediately if a project unearths any unknown HM (e.g., munitions and explosives of

concern [MEC], discarded military munitions [DMM], or unexploded ordnance [UXO]), and immediately report the situation to the ROICC or Contract Representative.

- Do not leave HM (or HW) onsite once the contract is completed. Remove it from the installation or make arrangements through the ROICC or Contract Representative to contact RCRS or EAD for turn-in procedures upon completion of the contract.

7.4. UNIVERSAL WASTE REQUIREMENTS

The NCDEQ allows thermostats, obsolete agricultural pesticides, lamps, and certain types of batteries to be managed as UW. UW has less stringent requirements for storage, transport, and collection, but it must still comply with full HW requirements for final recycling, treatment, or disposal. Federal UW requirements are outlined in 40 CFR 273. Contact the ROICC or Contract Representative regarding any additional direction or questions on the handling of UW.

All UW must be properly containerized, stored, and labeled when the waste is first generated. Containers/areas for accumulating UW must be labeled as follows:

- Words: UNIVERSAL WASTE.
- Content: Noun name found on the specific Hazardous Waste Profile Sheet (DRMS Form 1930), which is available from EMD (e.g., *batteries*,

fluorescent lamps, pesticides, mercury-containing equipment).

- Accumulation Start Date (ASD): The ASD must be marked on the subject container as soon as the UW item is placed in the container. Storage of UW cannot exceed 365 days.
- Number of Containers: The number of containers marked reflects the total number of containers disposed of within the current document (i.e., 1 of 1, etc.).

Contractors who need UW accumulation areas should contact the ROICC or Contract Representative, who will contact RCRS or EAD personnel to help contractors establish an accumulation area for UW. Key points for this process:

- The containers must be under the control of the contractor generating the waste and must be closed at all times except when waste is being adding.
- Per installation policy, UW containers/areas must be inspected weekly using the *Weekly Hazardous Waste (HW) Site Inspection Form*, included as Attachment 7-1 and Attachment 7-2. Written records noting discrepancies and corrective actions must be maintained onsite for 3 years. Copies of inspection reports should be provided to the ROICC or Contract Representative.
- When the ASD reaches 1 year, or when the container is full, the waste generator has 72 hours (3 days) to arrange for the transportation of the UW to an RCRA

Part B permitted storage area. Contact the ROICC or Contract Representative to coordinate the removal of the UW when the container is full or the contract is finished.

7.5. HAZARDOUS WASTE REQUIREMENTS

The appropriate environmental office must be notified before any HW is generated on projects managed by the ROICC or the Facilities Support Contracts (FSC). Have the ROICC or Contract Representative contact RCRS or EAD with questions regarding whether or not a waste meets the definition of HW. Installation personnel must approve all regulated waste and HW storage locations.

The appropriate environmental office must be notified before any hazardous waste is generated on projects managed by the ROICC or the FSC.

If a project generates HW:

- Minimize generation through waste minimization and P2 techniques.
- Have the ROICC or Contract Representative contact RCRS or EAD with questions regarding how to manage the waste. Do not mix waste types (e.g., used oil rags and solvent rags).
- Have the ROICC or Contract Representative contact RCRS or EAD for turn-in procedures as wastes are

generated, to determine if waste can be disposed of on the installation.

- Do not dump any HW into floor drains, sinks, OWSs, or storm drains, or onto the ground. Do not place HW into general/municipal trash dumpsters.
- Ensure that HW drums are properly labeled and lids are secured (wrench tight).
- Ensure that SAAs are managed properly and storage limits are not exceeded; have the ROICC or Contract Representative consult RCRS or EAD prior to creating a new SAA.

7.5.1. Storage

All HW must be properly containerized, stored, and labeled at the time the waste is first generated. HW must be stored in containers that meet applicable DOT specifications. HW labels, as required by the EPA and the NCDEQ, must contain the following information:

- Words: HAZARDOUS WASTE.
- Content: Noun name found on the specific Hazardous Waste Profile Sheet (DRMS Form 1930) provided by RCRS or EAD.
- ASD: For HW accumulated in an SAA, the ASD will be affixed once the container is filled or at the 1-year anniversary, whichever comes first.
- Number of Containers: Reflects the total number of containers (e. g., 1 of 1, etc.).

Any HW generated by contractors must be stored in an SAA. Contractors who need an SAA should contact the ROICC or Contract Representative, who will contact RCRS or EAD personnel to help the contractor establish each SAA. A summary of procedures follows:

- The HW generator may accumulate as much as 55 gallons of a specific HW stream (or up to one quart of acute HW) in a container at or near the point of generation.
- The containers must be under the control of the contractor generating the waste and must be kept closed (wrench tight) at all times except when waste is being added.
- HW containers must be inspected weekly using the *Weekly Hazardous Waste (HW) Site Inspection Form*, included as Attachment 7-1 and Attachment 7-2. Written records noting discrepancies and corrective actions must be maintained for a period of 3 years. Copies of inspection reports should be provided to the ROICC or Contract Representative.
- The generating contractor must monitor the level of waste in the SAA container and contact the ROICC or Contract Representative to coordinate disposal or determine if the contractor can turn in the HW to RCRS or EAD before the container is full. If the SAA container becomes full, the generating contractor has 72 hours (3 days) to arrange for the transport of the HW to an RCRA Part B permitted

storage area. Storage of HW in an SAA should not exceed 365 days, even if the container is not full.

7.5.2. Manifesting and Disposal

All disposal of HW generated by contractors must be coordinated with the installation. HW and UW generated aboard MCB Camp Lejeune and MCAS New River must be transported off the installation by a permitted HW transporter and must include a *Uniform Hazardous Waste Manifest* form (EPA Form 8700-22) or an equivalent approved manifest. The following procedures must be followed for disposal of HW:

- Use the MCB Camp Lejeune or MCAS New River EPA identification number for disposal of all contractor-generated HW.
- HW may only be transported by authorized personnel or permitted companies. Prior to transportation offsite, the HW generator must ensure that all DOT requirements for labeling, marking, placarding, and containerizing are met. The HW generator must also ensure that the transporter has obtained the installation's EPA identification number for the transportation of HW and that an appropriate waste manifest accompanies each shipment.

Only personnel from EMD who have been designated in writing by the MCB Camp Lejeune Commanding General can sign the hazardous waste manifest.

- The HW manifest can only be signed by personnel from the installation who have been designated in writing by the CG. The ROICC or Contract Representative should contact RCRS or EAD about manifesting regulated and non-regulated wastes offsite. Under **NO** circumstances can a contractor, ROICC, or Contract Representative sign a HW manifest or use another EPA identification number for wastes generated at the installation.
- All HW must be submitted to a permitted TSD facility. HW generators must certify that the facility receiving the waste employs the most practical and current treatment, storage, or disposal methods for minimizing present and future threats to human health and the environment.

7.6. NON–RCRA-REGULATED WASTE REQUIREMENTS

Non-RCRA-regulated wastes include used oil (when recycled), non-terne (tin and lead alloy) plated oil filters (not mixed with listed waste), CFC refrigerants (from totally enclosed equipment), certain wastes containing Polychlorinated Biphenyl (PCB), asbestos, and batteries not managed as UW.

7.6.1. Used Oil and Oil Filters

Used motor oil itself is *not* regulated as HW in North Carolina if it is recycled or burned for energy recovery. If used oil is not recycled, the generator must determine prior to disposal whether it is HW. Used oil must be collected in

drums or another approved container marked “Used Oil.” If the used oil storage container has a volume of 55 gallons or more, it must be stored in secondary containment.

- Do not dump used oil into drains, sinks, or trash containers, or onto the ground.
- Do not store used oil in open buckets or drip pans, damaged or rusted containers, or containers that cannot be fully closed.
- Do not mix used oil with other waste materials.

Terne plated oil filters contain an alloy of tin and lead. They are considered a hazardous waste due to their lead content and are typically located on industrial and heavy duty vehicles and equipment. All other used oil filters are not regulated as HW in North Carolina, as long as they are not mixed with listed HW. To qualify for this exclusion, the following conditions must be met:

- Used oil filters must be gravity hot-drained by puncturing the filter anti-drain back valve or filter dome and hot draining into a “Used Oil” storage drum. “Hot-drained” means that the oil filter is drained at a temperature that approximates the temperature at which the engine operates.
- Any incidental spillage that occurs must be cleaned up with a dry sweep, rags, or “absorbent matting.”
- Drained used oil filters must be collected in a container that is in good condition and is labeled with the words “Drained Used Oil Filters.”

- No other waste streams should be deposited in containers collecting used oil filters for disposal.
- Coordinate with the ROICC or Contract Representative to determine if the drained used oil filters can be given to RCRS or EAD.

7.6.2. Used Antifreeze

Antifreeze is composed of regulated chemicals, including ethylene glycol and propylene glycol, and during typical use may become contaminated with traces of fuel or metal particles (i.e., lead, cadmium, or chromium). It may also become HW if it has been mixed with other wastes, such as gasoline or solvents. Additional characterization may be required to determine whether or not used antifreeze is HW. Used antifreeze that is not recycled may be regulated as HW if the results from the Toxic Characteristics Leaching Procedure (TCLP) indicate metal contents that meet or exceed RCRA thresholds.

The State of North Carolina does not regulate used antifreeze as HW, as long as it is recycled by reuse, distillation, filtration, or ion exchange. Used antifreeze must be stored in closed containers on an impermeable concrete surface with adequate spill controls (secondary containment, appropriate stocked spill kits, etc.). Contact the ROICC or Contract Representative to determine if used antifreeze can be given to RCRS or EAD.

7.6.3. Petroleum-Contaminated Wipes and Oily Rags

Petroleum-contaminated wipes and oily rags are to be managed as non-regulated waste. Follow these procedures:

- Store oil-contaminated wipes and oily rags in metal containers because of their flammability/combustibility and to protect them from the weather.
- Do not throw these non-regulated waste items into solid waste dumpsters or garbage cans.
- Contact the ROICC or Contract Representative to determine if petroleum-contaminated wipes and oily rags can be given to RCRS or EAD.

7.6.4. Used Electronic Equipment

Used electronic equipment may contain lead solder or PCB oils (e.g., light ballast). Turn in these items as they are generated. Have the ROICC or Contract Representative contact RCRS or EAD for proper handling and/or turn-in procedures.

7.6.5. New and Used Batteries (Not Regulated as Universal Waste)

- Store compatible batteries together (i.e., lithium batteries should be stored with other lithium batteries).

- Store batteries off the ground to prevent them from coming into contact with water.
- Store lead-acid batteries away from an open flame.
- Place rechargeable batteries in plastic bags before storing them with other rechargeable batteries.
- Do not dispose of batteries unless authorized.
- Have the ROICC or Contract Representative contact RCRS or EAD for proper handling and/or turn-in procedures.

Attachment 7-1

Weekly Hazardous Waste (HW) Site Inspection Form
MCB Camp Lejeune

PAGE INTENTIONALLY BLANK

MCB Camp Lejeune Weekly Hazardous Waste (HW) Site Inspection
Universal Waste (UW)/Satellite Accumulation Area (SAA)

Building Number/location of HW Site: _____
Unit Evaluated: _____
Evaluation Date: _____/_____/_____
Evaluation By (Site Manager): _____
Evaluation Time: _____

QUESTION	**YES**	**NO**	**Location of Discrepancy *and* Proposed Corrective Action**
1. Is housekeeping maintained in acceptable manner?			
2. Is any HW present at the site?			
3. Are HW containers properly marked?			
4. Are HW containers in serviceable condition?			
5. Are container bungs, caps, and openings properly secured?			
6. Is a unit spill plan/activation prominently posted?			
7. Is 911 spill response sign posted?			
8. Are **"Danger-Unauthorized Personnel Keep Out"** signs posted so they may be seen from any approach?			
9. Are **"No Smoking"** signs posted?			

QUESTION	**YES**	**NO**	**Location of Discrepancy *and* Proposed Corrective Action**
10. Does the site have emergency communication system or two-man rule in effect? If the two-man rule is implemented, is a sign posted with the legend "**Two-Man Rule in Effect**"?			
11. Are properly charged fire extinguishers, as well as eye wash stations, present and inspected at least monthly?			
12. Is the post indicator valve in good operating condition and secured in the closed position, and are there any structural defects such as cracked concrete?			
13. Is the proper spill response equipment readily available?			
14. Is the site designated and recognizable, and is the EMD Authorization posted within the site as to be visible to personnel placing waste into the container? (SAA site only)			
15. Are all HWs properly segregated and stored in the designated site?			
16. Are any hazardous materials being stored in the Satellite Accumulation Area or < 90-day storage site?			

Attachment 7-2

Weekly Hazardous Waste (HW) Site Inspection Form MCAS New River

PAGE INTENTIONALLY BLANK

Weekly Hazardous Waste Storage
Area Inspection Form

Squadron: _____ **Inspector: _____**

Date: _____ **Signature: _____**

Question	**Yes**	**No**	**Corrective Actions or N/A**
1. Is the HW container located at or near the point of generation?			
2. Is the HW container DOT approved?			
3. Is the HW container marked correctly with the words "Hazardous Waste," correct noun name of contents, NSN'S and unit designator?			
4. Is the HW container closed and wrench tight when no one is adding to the container?			
5. If a funnel is left in place, does that funnel have a plug or ball valve to be considered closed or secured?			
6. Is the HW container in good condition? (No excessive rust or dents in critical areas, seals are in place, no bulging or collapsing and no signs of spillage or leakage)			
7. Is the Spill Contingency Plan posted and in plain view?			
8. Is the SAA Site approval letter from EAD posted at the SAA site?			
9. Is the SAA Site limited to Authorized Personnel only?			

Question	**Yes**	**No**	**Corrective Actions or N/A**
10. Is the HW container below the proper ullage for a liquid to expand? (4 inches from the top)			
11. Are SAA HW containers moved to the 90-Day Site within 72 hours when filled to the proper ullage or weight capacity of the container?			
12. (90-Day Site only) Are all palletized waste streams correctly marked with "Hazardous Waste" or "Universal Waste," noun name of the waste, NSN and unit designator on the pallet or wall of the waste structure?			
13. (90-Day Site only) Are all HW containers turned in prior to the 90th day after the ASD?			
14. Are adequate spill response supplies readily available for use in case of spill or leakage?			
15. Is there a means of emergency communication between storage facilities and working spaces?			
16. Is the SAA site or 90-Day Site in a good state of police?			

NAVOSHENVTRACEN COMPATIBILITY CHART

HMUG GROUP	HCC see note 2	GROUP NAME	EXAMPLES	INCOMPATIBLE MATERIALS	EXAMPLES	REACTION IF MIXED
1	C1, C2, C4, C5	ACIDS	Battery Acid Paint Removers De-Rust Spray	FLAMMABLES/ COMBUSTIBLES ALKALIS/BASES/CAUSTICS OXIDIZERS (HMUG Groups 2, 3, 4, 6, 7, 8, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 22)	Degreasers, Carbon Removers, Anti-Fogging Compounds	HEAT Gas Generation VIOLENT REACTION
2	P1 to P7, P9, T4, V3, V6	ADHESIVES	Epoxies Isocyanates Diethylenetriamine	ACIDS ALKALIS/BASES/CAUSTICS OXIDIZERS (HMUG Group 1, 3, 18)		HEAT FIRE HAZARD
3	B1, B2	ALKALIES BASES/ CAUSTICS	Ammonia Sodium Hydroxide Cleaners	ACIDS/OXIDIZERS FLAMMABLES/COMBUSTIBLES (HMUG Group 1, 2, 6, 8, 9, 10, 11, 14, 17, 18, 19, 20, 22)	Battery acid, Paint Removers, De-Rust Sprays, Paints, Solvents	HEAT Gas Generation VIOLENT REACTION
4	C1-C4, B1-B3, F2 to F7, T4, T6, V2-V4	CLEANING COMPOUNDS	Degreasers Carbon Removers Antifogging Compounds	DETERGENTS/SOAPS OXIDIZERS (HMUG Group 1, 7, 18)	Calcium Hypochlorite, Sodium Nitrite, Hydrogen Peroxide	HEAT FIRE HAZARD
5	G1 to G8	COMPRESSED GASES	Acetylene, Propane, Nitrogen, Argon, Helium, Oxygen	HEAT SOURCES Consult paragraph C23 for specific handling and storage guidance (HMUG Groups 8, 9, 10, 11, 12, 13, 18, 19)		FIRE HAZARD EXPLOSION HAZARD
6	F2 to F6, T6, V2, V3, V6	CORROSION PREVENTIVE COMPOUNDS	Corrosion Inhibitors Chemical Conversion Compounds	ACIDS/BASES OXIDIZERS IGNITION SOURCES (HMUG Group 1, 3, 18, 20)		FIRE HAZARD
7	B3	DETERGENTS/ SOAPS	Trisodium Phosphate Scouring Powders Disinfectants	ACID-CONTAINING COMPOUNDS (HMUG Group 1, 4, 18)	Battery Acid, Paint Removers De-Rust Sprays	VIOLENT REACTION HEAT
8	F8, V4, V7	GREASES	Lithium Grease Silicone Molybdenum	OXIDIZERS ALKALIS/BASES/CAUSTICS (HMUG Group 3, 5, 18)		FIRE HAZARD HEAT
9	T6, V4, V6, V7	HYDRAULIC FLUIDS	Petroleum-Based Synthetic Fire-Resistant	CORROSIVES, OXIDIZERS (HMUG Group 1, 3, 5, 18)		VIOLENT REACTION
10	F2 to F4, T4, T6, V2-V6	INSPECTION PENETRANTS	Petroleum-Based Dyes	CORROSIVES, OXIDIZERS (HMUG Group 1, 3, 5, 18)	Battery Acid Caustic Soda Chlorine laundry bleach Calcium Hypochlorite Hydrogen Peroxide OSA Canisters Paint Removers	
11	F4, T5, V2, V3, V4, V6	LUBRICANTS/ OILS	General Purpose, Gear, Turbine, Weapons			EXPLOSION HAZARD
12	F2 to F6, P1, T3, T4, T6, V3-V6	PAINT MATERIALS	Primers, Enamels, Urethanes, Lacquers, Varnishes, Non-Skid, Thinners	ACIDS, OXIDIZERS (HMUG Group 1, 5, 18)		HEAT FIRE HAZARD
13	C1-C4, B1-B3, D1	PHOTO CHEMICALS	Developers, Stopbath, Toners, Bleaches, Replenishers	ACIDS HEAVY METALS (HMUG Group 1, 18, 20)		HEAT FIRE HAZARD
14	F4	POLISH/WAX COMPOUNDS	Buffing Compounds Metal Polishes General Purpose Waxes	CORROSIVES OXIDIZERS (HMUG Group 1, 3, 18)		HEAT, FIRE HAZARD VIOLENT REACTION
15	F2 to F6, T3, T4, T6, V1-V6	SOLVENTS	Methyl Ethyl Ketone (MEK) Toluene, Xylene Acetone	CORROSIVES OXIDIZERS BATTERIES (HMUG Group 1, 5, 18, 21, 22)	Battery Acid Calcium Hypochlorite Sodium Nitrite Sodium Hydroxide	HEAT FIRE HAZARD
16	T6, T7, Z1	THERMAL INSULATION	Asbestos Fiberglass Glass Wool	MATERIAL IS NOT REACTIVE KEEP DRY		NO REACTION
17	C1-C4, B1-B3, D1	WATER TEST/ TREATMENT CHEMICALS	Nitric Acid Mercuric Nitrate Caustic Soda	CORROSIVES OXIDIZERS HEAVY METALS (HMUG Group 1, 3, 18, 20, 21)		HEAT VIOLENT REACTION
18	D1 to D4	OXIDIZERS	Calcium Hypochlorite Laundry Bleach OSA Canisters	PETROLEUM BASED MATERIALS FUELS, SOLVENTS, CORROSIVES, HEAT (HMUG Group 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 20, 21, 22)		FIRE HAZARD VIOLENT REACTION EXPLOSION HAZARD TOXIC GAS GENERATION
19	F1 to F4, V4, V5, V6	FUELS	JP4, JP5 Gasoline Diesel Fuel	CORROSIVES OXIDIZERS (HMUG Group 1, 3, 5, 18)	Battery Acid Calcium Hypochlorite Sodium Nitrite Sodium Hydroxide	FIRE HAZARD TOXIC GAS GENERATION
20	T6, V7, Z2	HEAVY METALS	Mercury Lead Beryllium	CORROSIVES OXIDIZERS WATER TREATMENT/PHOTO CHEMICALS (HMUG Group 1, 3, 6, 13, 17, 18, 20)		VIOLENT REACTION GENERATION OF TOXIC AND FLAMMABLE GAS
21	Z4 to Z7	BATTERIES	Lead-Acid Dry-Cell Alkaline	SOLVENTS HEAVY METALS OXIDIZERS (HMUG Group 15, 17, 18, 20)	Xylene Toluene Alcohol	HEAT VIOLENT REACTION TOXIC GAS GENERATION
22	T2 to T8	PESTICIDES	Insecticides, Fungicides Rodenticides Fumigants	CORROSIVES OXIDIZERS (HMUG Group 1, 3, 15, 18)		TOXIC GAS GENERATION

1. This chart is to be used as a ***GUIDE ONLY!***
2. Compare the desired HMUG Group/HCC in the left column with the Incompatible Material(s) of that Group in the center column on the same row. Mixing of the HMUG Group/HCC with the Incompatible Material(s) may result in the reaction(s) listed in the right column.
3. Not all applicable HCCs are listed; only the most frequently encountered HCCs (except N1) are listed.

www.safetycenter.navy.mil/training

REV 09-03

PAGE INTENTIONALLY BLANK

8.0 ASBESTOS

Asbestos was widely used in many products (especially building parts) prior to 1990 for its fire resistance, strength, and affordability. However, exposure to friable asbestos can lead to lung diseases including cancer. Contractors working aboard the installation must follow all Federal, State, and local regulations/specifications for the proper notification, removal, disposal, and management of all asbestos-containing materials (ACM) associated with demolition and renovation projects.

8.1. KEY DEFINITIONS AND CONCEPTS

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

The following key definitions and concepts are associated with asbestos and its management. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate EMD program if additional clarification is necessary.

8.1.1. Key Definitions

- **Abatement.** Work performed to repair, maintain, remove, isolate, or encapsulate ACM.
- **Asbestos.** Asbestos is the generic term for a group of naturally occurring fibrous silicate minerals, including those that typically exhibit high tensile

strength, flexibility, and resistance to thermal, chemical, and electrical conditions. Asbestos was commonly used in installed products such as roofing shingles, floor tiles, cement pipe and sheeting, roofing felts, insulation, ceiling tiles, fire-resistant drywall, and acoustical products.

- **Asbestos-Containing Material.** Any material containing more than 1 percent asbestos, per 29 CFR 1926.1101.
- **Category I Non-friable ACM.** Asbestos-containing packings, gaskets, resilient floor covering, and asphalt roofing products containing more than 1 percent asbestos, per 40 CFR 61, Subpart M.
- **Category II Non-friable ACM.** Any material, excluding Category I non-friable ACM, containing more than 1 percent asbestos that, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure, per 40 CFR 61, Subpart M.
- **Demolition.** The wrecking or removal of any load-bearing walls or structure with any related handling operations.
- **Friable.** Any ACM that, when dry, can be crumbled, pulverized, or reduced to powder by hand pressure (may include damaged ACM that was previously identified as non-friable), per 40 CFR 763.
- **Glove Bag.** A sealed compartment with attached inner gloves that is used for handling ACM. Glove bags provide a small work area enclosure typically used for small-scale asbestos stripping operations.

- **Presumed Asbestos-Containing Material (PACM).** Thermal system insulation (TSI) and surfacing material found in buildings constructed no later than 1980, per 29 CFR 1926.1101.
- **Regulated Asbestos-Containing Material (RACM).** Includes friable ACM, Category I non-friable ACM that has become friable, Category I non-friable ACM that has been sanded, ground, cut, etc., and Category II non-friable ACM that has a high probability of becoming crumbled, pulverized, or reduced to powder during demolition or renovation, per 40 CFR 61, Subpart M.
- **Removal.** Stripping, chipping, sanding, sawing, drilling, scraping, sucking, and other methods of separating material from its installed location in a building.
- **Renovation.** Altering a facility or its components in any way, including stripping or removal of RACM, per 40 CFR 61, Subpart M.

8.1.2. Key Concepts

- **Demolition Notification.** North Carolina law requires notification for all demolition, regardless of whether asbestos is present, 10 working days prior to starting demolition.
- **Disposal.** ACM waste can be accepted at the MCB Camp Lejeune Sanitary Landfill. Work with the ROICC or Contract Representative to coordinate the disposal through the MCB Camp Lejeune Sanitary

Landfill. Asbestos waste is only accepted on Mondays through Thursdays from 0700 to 1000.

- **Removal Requirements.** Permits for asbestos removal or demolition must be obtained when the ACM present exceeds 260 linear feet, 160 square feet, or 35 cubic feet. Additionally, proper work practice procedures must be followed during demolition or renovation operations.
- **Renovation Notification.** If ACM is present within a structure, North Carolina law requires notification of renovation 10 working days prior to starting renovation.

8.1.3. Environmental Management System

Contractor practices associated with asbestos management include the following:

- Building operation/maintenance/repair
- Construction/demolition/renovation
- Equipment operation/maintenance/disposal
- HW transportation
- Parts replacement

The potential impacts of these activities on the environment include soil contamination, degradation of water quality and air quality, and the potential exposure of installation occupants.

8.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard the installation must be aware of and adhere to all applicable regulations and requirements regarding ACM, which include but may not be limited to the following:

- **Asbestos General Standard, 29 CFR 1910.1001 – Asbestos.** Applies to all occupational exposures to asbestos in all industries covered by the Occupational Safety and Health Administration (OSHA).
- **Asbestos Hazard and Emergency Response Act (AHERA), 1986.** AHERA was written primarily to provide officials in schools, grades K-12, with rules and guidance for the management of ACM.
- **Asbestos School Hazard Abatement Reauthorization Act, 1992.** This act extended AHERA regulations to cover public and commercial buildings.
- **National Emission Standards for Hazardous Air Pollutants (NESHAP), Subpart A, General Provisions, and 40 CFR 61 – Subpart M – National Emission Standard for Asbestos.** Includes standards for asbestos demolition, renovation, and disposal, and administrative requirements.
- **Naval Facilities Engineering Service Center, Facilities Management Guide for Asbestos and Lead.** Summarizes asbestos and lead requirements

that routinely affect facilities operations, to protect workers, building occupants, and the environment.

- **Naval Facilities Guide Specifications and Engineering Control of Asbestos Materials.** Covers the requirements for safety procedures and requirements for the demolition, removal, encapsulation, enclosure, repair, and disposal of ACM.
- **North Carolina Asbestos Hazard Management Program, NC General Statutes, Chapter 130A, Article 19; 10A NCAC 41C.0601–.0608 and .0611.** Incorporates 40 CFR 763 and 29 CFR 1926.1101 by reference and outlines criteria for asbestos exposures in public areas, accreditation of persons conducting asbestos management activities, and asbestos permitting and fee requirements.
- **Safety and Health Regulations for Construction, Asbestos, 29 CFR 1926.1101.** Regulates asbestos in the construction, demolition, alteration, repair, maintenance, or renovation of structures that contain asbestos.

8.3. RESPONSIBILITIES BEFORE A DEMOLITION OR RENOVATION PROJECT

Prior to starting a demolition or renovation project, contractors must:

- Determine whether ACM, PACM, and/or RACM are present in the buildings involved in the project.
- Complete the necessary notifications to the State of North Carolina and obtain any necessary permits for the removal of ACM, PACM, and/or RACM.
- Understand what actions to take if ACM, PACM, and/or RACM are unexpectedly encountered during project execution.
- Remove all non-friable and friable ACM in accordance with all Federal, State, and local regulations, prior to demolition activities.
- Know how to properly dispose of ACM, and provide any waste disposal manifests generated for disposal.

The ROICC or Contract Representative is required to notify Camp Lejeune's Asbestos Program Manager of all work involving asbestos removals, including glove bag projects.

8.3.1. Identification of ACM and PACM

Form DHHS 3768 *must* be posted onsite during all permitted projects.

Contract documents will identify the presence of known ACM, PACM, and RACM. Contact the ROICC or Contract Representative with questions regarding the presence of these materials as identified in the contract documents. An inspection conducted by a Health Hazards

Control Unit (HHCU)-licensed asbestos inspector may be necessary to confirm the location and quantities of any ACM, PACM, and/or RACM and determine if any previously unidentified materials are present.

8.3.2. Notification

To maintain accurate files and records, the ROICC or Contract Representative is required to notify the Asbestos Program Manager, who is part of the Installations and Environment Department, of all work involving asbestos removals, including glove bag projects.

A demolition/ renovation notification form, DHHS 3768, must be submitted to the NC HHCU 10 working days before demolition activities, regardless of whether asbestos is present.

The North Carolina Department of Health and Human Services (DHHS) Form 3768, *Asbestos Permit Application and Notification for Demolition and Renovation*, must be submitted to the North Carolina HHCU 10 working days in advance of demolition activities, regardless of whether asbestos is present. This form must be posted onsite during the entire duration of the project. Have the ROICC or Contract Representative contact the Asbestos Program Manager with questions or concerns about requirements for notification of demolition or renovation.

8.3.3. Removal

Any ACM, PACM, and/or RACM present must be removed before the area is disturbed during renovation or demolition

activities (except in certain rare instances). Certification and handling requirements for asbestos removal are provided in 10A NCAC 41C and the Asbestos NESHAP. Refer to these regulations for detailed requirements.

8.3.4. Training

North Carolina regulations require that all persons who perform asbestos management activities in the State of North Carolina must be accredited by the North Carolina HHCU under the appropriate accreditation category (i.e., Building Inspector, Project Supervisor, and/or Abatement Worker). Training documentation should be available upon request.

8.4. RESPONSIBILITIES DURING A DEMOLITION OR RENOVATION PROJECT

North Carolina regulations require that DHHS Form 3768, *Asbestos Permit Application and Notification for Demolition and Renovation*, be acquired by the contractor and posted onsite during all permitted projects. Contractors must post this form when the project will remove the following: at least 260 linear feet, 160 square feet, or 35 cubic feet of RACM or asbestos that might become regulated as a result of handling. The form must also be posted for nonscheduled asbestos removal that will exceed these numbers in a calendar year.

During a renovation or demolition project, if the contractor suspects the presence of additional ACM (other than the materials identified in contract documents), the contractor

must immediately report the suspected area to the ROICC or Contract Representative. Before proceeding, the facility must be inspected by an asbestos inspector licensed by the North Carolina HHCU. The individual performing the asbestos survey will coordinate with the ROICC or Contract Representative throughout the process. A legible copy of the building inspection report must be provided to the North Carolina HHCU prior to each demolition and upon request for renovations; a building inspection report will be acceptable only if the inspection was performed during the 3 years prior to the demolition. A copy of the report should also be forwarded to the Asbestos Program Manager.

During a renovation or demolition project, a contractor who suspects additional ACM is present must immediately report the suspected area to the ROICC or Contract Representative.

For specific work procedures and requirements for glove bag projects, refer to 29 CFR 1926.1101.

8.5. DISPOSAL OF ACM WASTE

Contractors can dispose of ACM waste at the MCB Camp Lejeune Sanitary Landfill after first coordinating with the MCB Camp Lejeune Landfill office through the ROICC or Contract Representative. The contractor must provide the MCB Camp Lejeune Landfill with Form DHHS 3787, *North Carolina Health Hazards Control Unit's Asbestos*

Waste Shipment Record. The contractor must submit this form to the North Carolina HHCU for all permitted asbestos removal projects.

PAGE INTENTIONALLY BLANK

9.0 LEAD-BASED PAINT

Lead was used in paint for its color and water-resistant properties until it was banned in 1978 for its highly toxic properties that may cause a range of health problems, especially in young children. Improper removal of lead-based paint (LBP) may result in paint chips and dust, which may contaminate a structure inside and out. The North Carolina DHHS regulations require any person who performs an inspection, risk assessment, or abatement to be certified. North Carolina DHHS also requires a person to obtain a permit for conducting an abatement of a child-occupied facility or target housing.

9.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with LBP activities. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate Environmental Department or Safety Representative if additional clarification is necessary.

9.1.1. Key Definitions

- **Abatement.** The permanent removal or elimination of all LBP hazards.
- **Demolition.** The removal of any load-bearing walls or structure.

- **Inspection.** A surface-by-surface investigation to determine the presence of LBP, and a report explaining the results of the investigation.
- **Lead-Based Paint.** Surface coatings that contain lead in amounts equal to or in excess of 1.0 milligram per square centimeter, as measured by X-ray fluorescence (XRF) or laboratory analysis, or more than 0.5 percent by weight, per 40 CFR 745.
- **Lead-Containing Paint.** Surface coatings that contain lead in any amount greater than the laboratory reporting limit but less than 1.0 milligram per square centimeter, or less than 0.5 percent by weight, per 29 CFR 1926.62 and 29 CFR 1910.1025 (also contained in 40 CFR 745 Subpart L, and adopted by the State of North Carolina under North Carolina General Statute Chapter 130A, Article 19A).
- **Renovation.** Alteration of a facility or its components in any way.
- **Target Housing.** Any housing constructed before 1978, with the exception of housing for the elderly and persons with disabilities (unless a child under the age of 6 lives there) and residential dwellings where the living areas are not separated from the sleeping areas (efficiencies, studio apartments, dormitories, etc.).

9.1.2. Key Concepts

- **Disposal.** Analysis is required to determine proper disposal of waste (non-hazardous or hazardous). A Toxic Characteristic Leaching Procedure (TCLP) analysis must be conducted to determine whether lead levels have exceeded 5 parts per million (ppm), which is the RCRA threshold for HW determination.
- **LBP Survey.** A LBP survey is required prior to disturbing painted surfaces, to determine whether the paint meets the criteria of lead containing over 1.0 milligram per square centimeter or over 0.5 percent by weight.
- **Training.** LBP training requirements set forth by the OSHA must be followed by all personnel involved in all LBP removal activities. MCB Camp Lejeune Base Safety tracks this training for contract staff, as the Safety Office houses the Lead Program Manager.

9.1.3. Environmental Management System

Contractor practices associated with LBP include the following:

- Construction/demolition/renovation
- HW transportation
- Paint removal

The potential impacts of these activities on the environment include the potential degradation of soil, water, and air

environments, and the potential exposure of installation occupants.

9.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard the installation must be aware of and adhere to all applicable Federal, State, and local regulations and requirements regarding LBP activities, which include but may not be limited to the following:

- **Naval Facilities Engineering Service Center, Facilities Management Guide for Asbestos and Lead.** Summarizes asbestos and lead requirements that routinely impact facilities operations, in order to protect workers, building occupants, and the environment.
- **Lead-Based Paint Hazard Management Program, NC General Statutes, Chapter 130A, Article 19A. Section 130A-453.01 through 453.11.** Requires a person who performs an inspection, risk assessment, abatement, or abatement design work in a child-occupied facility (daycare center, pre-school, etc.) or housing built before 1978 to be certified and establishes the requirements for certification, including the oversight of required training. It also requires a person who conducts an abatement of a child-occupied facility or target housing to obtain a permit for the abatement; establishes work practice standards for LBP abatement activities; and has adopted requirements included in 40 CFR Part 745, Subpart L and 40 CFR Part 745, Subpart D.

- **Lead-Based Paint Hazard Management Program for Renovation, Repair, and Painting (RRP), 10A NCAC 41C.0900.** Common renovation activities may create hazardous lead dust and chips by disturbing LBP, which may be harmful to adults and children. This article requires that dust sampling technicians, firms, and individuals performing renovation, repair, and painting projects for compensation that disturb LBP in housing and child-occupied facilities built before 1978 be certified and follow specific work practices to prevent lead contamination. Child-occupied facilities include, but are not limited to, child care facilities and schools (with children under the age of 6) that were built before 1978.

- **10A NCAC 41C.0800, Lead-Based Paint Hazard Management Program.** Requires (1) all individuals and firms involved in LBP activities to be certified and (2) all LBP activities to be carried out in accordance with 40 CFR 745.

- **29 CFR 1926, Safety and Health Regulations for Construction.** Contains the OSHA requirements for construction activities where workers may come into contact with lead.

- **40 CFR Part 745, Lead-Based Paint Poisoning Prevention in Certain Residential Structures.** Ensures that (1) LBP abatement professionals, including workers, supervisors, inspectors, risk assessors, and project designers, are well trained in conducting LBP activities; and (2) inspections for the

identification of LBP, risk assessments for the evaluation of LBP hazards, and abatements for the permanent elimination of LBP hazards are conducted safely, effectively, and reliably by requiring certification of professionals.

9.3. RESPONSIBILITIES BEFORE RENOVATION OR DEMOLITION

Buildings constructed prior to 1978 are assumed to contain LBP.

Ordinary renovation and maintenance activities may create dust that contains lead, but following lead-safe work practices may help mitigate or prevent lead hazards. The North Carolina RRP Program (10A NCAC 41C.0900) mandates that contractors, property managers, and others working for compensation in homes and child-occupied facilities built before 1978 be trained in and use lead-safe work practices. In addition, it mandates that contractors provide the owner and occupants with *The Lead-Safe Certified Guide to Renovate Right* information pamphlet, which is found at the following website: http://epi.publichealth.nc.gov/lead/pdf/RenovateRight.pdf

Individuals must be certified by the State of North Carolina to perform RRP activities for compensation in housing and child-occupied facilities built before 1978. A firm engaged in regulated renovation activities (such as RRP that disturbs more than 6 square feet of interior painted surfaces or 20 square feet of exterior painted surfaces, or dust sampling after renovation) must be a certified renovation firm.

To address the hazards associated with the improper abatement or removal of LBP, any person who performs an inspection, risk assessment, abatement, or abatement design work in a child-occupied facility (child development centers, preschools, etc.) or housing built before 1978 must be certified by the State of North Carolina. Any person who conducts an abatement of a child-occupied facility or target housing must also obtain a permit for the abatement. Individuals conducting LBP abatement activities in North Carolina, such as inspections, risk assessments, LBP hazards abatement, clearance testing, or abatement project design in housing and child-occupied facilities built before 1978, must be certified by the State of North Carolina. A firm engaged in abatement activities must be a certified lead abatement firm.

Prior to any renovation or demolition aboard the installation that involves the disturbance of painted surfaces, a LBP survey must be completed by an inspector certified in North Carolina, retained through the ROICC or Public Works Division (PWD). Certain projects will use PWD staff to conduct the sampling, and other projects will use contracted personnel. Buildings constructed prior to 1978 are assumed to contain LBP; therefore, no LBP survey is necessary. The LBP survey (through sampling and analysis) will determine whether painted surfaces meet the criteria of LBP (lead content equal to or greater than 1.0 milligram per square centimeter as measured by XRF or lab analysis, or 0.5 percent by weight). Naval Facilities Guide Specifications and contract documents must be implemented for contracts where LBP is to be abated/removed prior to demolition or renovation.

If the area is to be reoccupied, final clearance must be conducted, including a visual inspection and sample collection, prior to reoccupation. Clearance on all projects involving abatement must be provided by a certified risk assessor or a certified LBP inspector. Clearance for RRP projects may be conducted by a certified risk assessor, certified LBP inspector, or certified dust sampling technician.

9.4. PERMITS

Contractors must obtain a North Carolina LBP Abatement Permit from North Carolina DHHS when lead paint is removed from targeted structures (child-occupied facilities or housing built prior to 1978).

9.5. DISPOSAL

If the LBP survey determines that LBP will be abated as part of a renovation or demolition project, analytical samples must be taken to determine whether the material is hazardous.

If the LBP survey determines that LBP will be abated as part of a renovation or demolition project, the contractor must take analytical samples to determine whether the waste material is hazardous. Usually, a TCLP sample is collected from a "representative" sample of the material removed. The laboratory conducting the sample analysis must be accredited by the Environmental Lead Laboratory Accreditation Program. A list of these accredited labs is available by contacting (703) 849-8888 or visiting

http://apps.aiha.org/qms_aiha/public/pages/reports/publicScopeView.aspx?ProgramCode=37&Version=2.

If the LBP is removed from the underlying building material, then the paint is the waste stream. If the LBP is removed with the building material, then both materials are considered the waste stream.

If the lead content is below HW regulatory disposal levels, consult the ROICC or Contract Representative to determine whether if the contract allows for the disposal of the material in the MCB Camp Lejeune Sanitary Landfill. Lead waste is only accepted on Mondays through Thursdays from 0700 to 1000.

If the abated LBP is above HW regulatory levels, refer to Section 7.0 of this guide for information on HW management and disposal requirements.

9.6. TRAINING

Before the project begins, workers who are subject to lead exposure during abatement or removal activities must be trained according to the OSHA regulations in 29 CFR 1926.62 concerning lead exposure in construction, and they must receive all training and certification specified by 10A NCAC 41C.0800 and 10A NCAC 41C.0900. The contractor is responsible for providing this training before initiating any work aboard MCB Camp Lejeune.

PAGE INTENTIONALLY BLANK

10.0 NATURAL RESOURCES

The installation has stewardship and recovery responsibilities over the natural resources on the installation. These responsibilities are regulated under numerous laws described in this section. The installation ensures compliance with these laws through an interdisciplinary process of review and coordination of all activities occurring on the installation.

Contractors working on the installation are responsible for complying with conditions and measures imposed on their work as a result of this process; these responsibilities include preserving the natural resources within the project boundaries and outside the limits of permanent work, restoring work sites to an equivalent or improved condition after the work is complete, and confining construction activities to the limits of the work indicated or specified. The contractor is advised that the installation is subject to strict compliance with Federal, State, and local wildlife laws and regulations. The contractor must not disturb wildlife (birds, nesting birds, mammals, reptiles, amphibians, and fish) or the native habitat adjacent to the project area except when indicated or specified.

10.1. KEY DEFINITIONS AND CONCEPTS

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

The following key definitions and concepts are associated with natural resources management. If you have any questions or concerns

about the information in this section or require assistance regarding any wildlife matters (snakes, nesting birds, nuisance wildlife, etc.) on the site or within the project area, please consult the ROICC or Contract Representative, who will contact the Environmental Conservation Branch.

10.1.1. Key Definitions

- **Conservation.** The planned management, use, and protection of natural resources to provide their sustained use and continued benefit to present and future generations.
- **Ecosystem.** A dynamic, natural complex of living organisms interacting with each other and with their associated nonliving environment.
- **Habitat.** An area where a plant or animal species lives, grows, and reproduces, and the environment that satisfies its life requirements.
- **Natural Resource.** Soil, water, air, plants, and animals, according to the Natural Resources Conservation Service.
- **Endangered or Threatened Species.** Federally listed taxon that is "in danger of extinction throughout all or a significant portion of its range" or "likely to become endangered within the foreseeable future throughout all or a significant portion of its range."
- **Riparian Buffer.** Vegetated area bordering a body of water, such as a stream, lake, or pond.

- **Wetland.** Areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, bogs and similar areas, per the EPA.

10.1.2. Key Concepts

- **Coastal Zone Management Act (CZMA) of 1972.** Requires each installation to ensure that its operations, activities, projects, and programs affecting the coastal zone in or on coastal lands or waters are consistent with the federally approved Coastal Zone Management Plan of the State.

- **Ecosystem Management.** A goal-driven approach to managing natural and cultural resources that supports present and future mission requirements; preserves ecosystem integrity; is at a scale compatible with natural processes; is cognizant of natural processes' time scales; recognizes social and economic viability within functioning ecosystems; is adaptable to complex, changing requirements; and is realized through effective partnerships among private, local, State, tribal, and Federal interests. Ecosystem management is a process that considers the environment as a complex system functioning as a whole, not as a collection of parts, and recognizes that people and their social and economic needs are a part of the whole.

- **Integrated Natural Resources Management Plan (INRMP).** A planning document using ecosystem management principles to direct the management and conservation of installation natural resources, which includes all elements of natural resources management applicable to the installation.
- **National Environmental Policy Act.** Requires Federal agencies, including the USMC, to consider the environmental impacts of projects prior to implementation. All projects that support military training, minor and major military construction, maintenance, and natural resources management actions are reviewed for potential environmental impacts. Contractors must obtain and review any NEPA documentation associated with their projects. All NEPA documentation can be obtained from the ROICC or Contract Representative.
- **Threatened and Endangered Species.** Specific requirements regarding protected areas on the installation apply to contractor activities. Eight federally threatened and endangered species are currently managed at MCB Camp Lejeune – red-cockaded woodpecker, green sea turtle, loggerhead sea turtle, rough-leaved loosestrife, seabeach amaranth, piping plover, red knot, and American alligator. In addition, as of March 25, 2015, the U.S. Fish and Wildlife Service lists six species as threatened and nine as endangered for Onslow County, NC. Consult the ROICC or Contract Representative to determine if there are any project

requirements regarding threatened or endangered species.

- **Timber.** Contractors must ensure that the ROICC or Contract Representative notify the EMD's Forest Management Program prior to conducting site work. Timber will not be released to contractors without the approval of the Forest Management Program.
- **Waters of the United States.** All waters that are currently used, were used in the past, or may be susceptible to use in interstate or foreign commerce; interstate waters; the territorial seas; impoundments; tributaries; adjacent waters including wetlands, ponds, lakes, oxbows, and impoundments; waters determined to have a significant nexus; Carolina bays; Pocosins; and waters within the 100-year floodplain or within 4,000 feet of the high tide line or ordinary high water mark; per 33 U.S.C. 1251 *et seq*. Section 328.3.
- **Wetlands.** Any work in installation waters or wetlands requires a permit prior to the start of an activity.

10.1.3. Environmental Management System

Contractor practices associated with natural resources include the following:

- Erosion/runoff control
- Fish stocking
- Habitat management

- Land clearing
- Live fire range operations
- Road construction and maintenance
- Soil excavation/grading
- Timber management
- Urban wildlife management

The potential impacts of these activities on the environment include air emissions, sedimentation, eutrophication of surface waters (addition of nutrients that stimulate aquatic plant growth and depletes oxygen), degradation of habitat, impacts to marine mammals, damage to commercial and noncommercial timber, impacts to endangered species and natural resources, and degradation of soil quality.

10.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard the installation must be aware of and adhere to all applicable regulations and requirements regarding natural resources, which include but may not be limited to the following:

- **Bald and Golden Eagle Protection Act of 1940, as Amended (16 USC 688 *et seq.*).** Prohibits taking, possessing, and transporting bald eagles and golden eagles and importing and exporting their parts, nests, or eggs. The definition of “take” includes pursue, shoot, shoot at, poison, wound, capture, trap, collect, molest, or disturb.

- **BO 5090.11A, Protected Species Program.** Sets forth regulations and establishes responsibilities to ensure the conservation of threatened and endangered species and species at risk aboard MCB Camp Lejeune.
- **BO 5090.12, Environmental Impact Review Procedures.** Implements NEPA 1969 and NEPA policy and guidance in Chapter 12 of MCO P5090.2A.
- **Clean Water Act of 1972.** Establishes the basic structure for regulating wastewater discharges and placing fill materials into the waters of the United States.
- **CZMA of 1972 (16 USC 1451 *et seq.*).** Requires that Federal actions affecting any land/water use or coastal zone natural resource be implemented consistent with the enforceable policies of an approved State coastal management program. Requires concurrence from the State before taking an action affecting the use of land, water, or natural resources of the coastal zone.
- **Endangered Species Act of 1973 (16 USC 1531 *et seq.*).** Requires all Federal agencies to carry out programs to conserve federally listed endangered and threatened species of plants and wildlife.
- **EO 11990, Protection of Wetlands, 24 May 1977.** Addresses Federal agency actions required to identify and protect wetlands, minimize the risk of wetlands destruction or modification, and preserve

and enhance the natural and beneficial values of wetlands.

- **EO 13186, Responsibilities of Federal Agencies to Protect Migratory Birds, 10 January 2001.** Requires each Federal agency taking actions that have, or are likely to have, a measurable negative effect on migratory bird populations to develop and implement a plan to promote the conservation of migratory bird populations.

- **Marine Mammal Protection Act of 1972 (MMPA), as Amended (16 USC 1361 *et seq.*).** Mandates a moratorium on the killing, capturing, harming, and importing of marine mammals and marine mammal products. The MMPA also prohibits the taking of any marine mammal, including to harass, hunt, capture, collect, or kill any marine mammal, including any of the following: collection of dead animals or their parts, restraint or detention of a marine mammal, tagging a marine mammal, the negligent or intentional operation of an aircraft or vessel, or any other negligent or intentional act that results in disturbing or molesting a marine mammal.

- **Migratory Bird Treaty Act of 1918, as Amended (16 USC 703 *et seq.*).** Protects migratory birds (listed in 50 CFR 10.13) and their nests and eggs and establishes a permitting process for the taking of migratory birds by establishing a Federal prohibition to "pursue, hunt, take, capture, kill, attempt to take, capture or kill, possess, offer for sale, sell, offer to purchase, purchase, deliver for shipment, ship, cause

to be shipped, deliver for transportation, transport, cause to be transported, carry, or cause to be carried by any means whatever, receive for shipment, transportation or carriage, or export, at any time, or in any manner, any migratory bird or any part, nest, or egg of any such bird."

- **MCO P5090.2A, Environmental Compliance and Protection Manual.** Provides guidance and instruction to installations to ensure the protection, conservation, and management of watersheds, wetlands, natural landscapes, soils, forests, fish and wildlife, and other natural resources as vital USMC assets.
- **NEPA 1969 (42 U.S.C. 4321 *et seq*.).** Requires Federal agencies, including the USMC, to consider the environmental impacts of projects before the decisionmaker proceeds with the implementation. All projects that support military training, major and minor military construction, maintenance, and natural resources management actions are reviewed for potential environmental impacts.
- **Rivers and Harbors Act of 1899.** Prohibits the excavation, filling, or alteration of the course, condition, or capacity of any port, harbor, or channel without prior approval from the Chief of Engineers.
- **Sikes Act of 1960, as Amended (16 USC 670 *et seq*.).** Requires military installations to manage natural resources for multipurpose uses and public access appropriate for those uses, as well as ensuring no net loss to training, testing or other defined

missions of the installation through the development and implementation of an INRMP.

- **Neuse River Basin Riparian Buffer Rules (15A NCAC 02B.0233).** Require a 50-foot riparian buffer that is divided into two zones. The 30 feet closest to the water (Zone 1) must remain undisturbed. The outer 20 feet (Zone 2) may include managed vegetation, such as lawns or shrubbery. The riparian buffer rules also require diffuse flow of stormwater runoff. The buffers apply to intermittent streams, perennial streams, lakes, ponds, estuaries, and modified natural streams that are depicted on the most recent printed version of the soil survey map prepared by the Natural Resources Conservation Service or the 1:24,000 scale quadrangle topographic map prepared by the U.S. Geologic Survey.

10.3. NATIONAL ENVIRONMENTAL POLICY ACT

Staff specialists from various installation departments participate in the NEPA process, which coordinates the review of projects and documents environmental impacts (or lack thereof) for projects before implementation.

The documentation of this review process occasionally includes mandatory conditions affecting the design and construction/ implementation of the project. The documentation, when completed, is provided to the action proponent, who is expected to provide it to the ROICC or Contract Representative.

Consult the ROICC or Contract Representative to obtain or review any NEPA documentation associated with the project. The documentation marks the end of the NEPA review process; it does not constitute approval for the proponent of the action to implement the action. Some contracts may include stipulations from the NEPA document that must be implemented prior to the onset of work to prevent environmental impacts and violations of Federal or State rules and regulations. Stipulations could include replacing monitoring wells if damages occur from contractor operations, stopping work if contamination is encountered, notification that a wetlands permit is required, seasonal restrictions, etc.

Consult the ROICC or Contract Representative to obtain or review any NEPA documentation associated with the project.

10.4. TIMBER

Potential timber resources are identified during the NEPA process. The contractor is responsible for advising the ROICC or Contract Representative to notify EMD's Forest Management Program prior to beginning site work. Additionally, the ROICC or Contract Representative and/or contractor is required to notify the Forest Management Program if the contract has been amended with modifications to the site location.

MCB Camp Lejeune manages its forest in accordance with the installation INRMP. The Forest Management Program

maintains first right of refusal for all timber products on construction projects and will determine whether the Government will harvest the timber or release it to the contractor. The Government retains exclusive rights to all forest products on construction projects. If the Government elects to harvest the timber, only merchantable timber will be removed.

Contractors must adhere to the following requirements when performing site work that may impact timber resources:

Protect existing trees that are to remain in place and that may be injured, bruised, defaced, or otherwise damaged by construction operations.

- Do not remove, cut, deface, injure, or destroy trees or shrubs without authorization from the ROICC or Contract Representative.
- Do not fasten or attach ropes, cables, or guy wires to nearby trees for anchorages without authorization from the ROICC or Contract Representative. (If these actions are authorized, the contractor is responsible for any resultant damage.)
- Protect trees that are to remain in place and that may be injured, bruised, defaced, or otherwise damaged by construction operations.
- With the ROICC or Contract Representative's approval, use approved methods of excavation to

remove trees with 30 percent or more of their root systems destroyed.

- With the ROICC or Contract Representative's approval, remove trees and other landscape features scarred or damaged by equipment operations, and replace with equivalent, undamaged trees and landscape features.

Please refer to Section 12.0 for disposal information for land-clearing debris.

10.5. THREATENED AND ENDANGERED SPECIES

Entry into a threatened or endangered species site or shorebird nesting area marked with signs and/or white paint is prohibited without written permission from installation personnel.

With the exception of improved roadways, entry into a threatened or endangered species site or shorebird nesting area marked with signs and/or white paint is prohibited without written permission from installation personnel. BO 5090.11A lists threatened and endangered species that may be encountered at the installation. The following restrictions apply on the installation unless written permission is explicitly provided:

- Work on Onslow Beach or Brown's Island is not permitted between April 1 and October 31. Traffic

on the beaches should be limited to below the high tide line.

- Vehicles and lighting are prohibited on the beaches overnight between May 1 and October 31.
- Construction activities are prohibited within 1,500 feet of a bald eagle's nest (JD, MC, and IF Training area).
- Cutting or damaging pine trees is not permitted.
- Altering hydrology through excavation, ditching, etc., is prohibited.
- Fish and wildlife must not be disturbed.
- Water flows may not be altered; the native habitat adjacent to the project and critical to the survival of fish and wildlife may not be significantly disturbed, except as indicated or specified.

10.6. WETLANDS

10.6.1. Avoidance

Contractors must incorporate avoidance and minimization measures to comply with the national policy to permit no overall net loss of wetlands.

In accordance with MCO P5090.2A, all facilities and operational actions must avoid, to the maximum degree feasible, wetlands destruction or degradation, regardless of the wetlands size or legal necessity for a permit. Prior to the onset of

construction, coordination with the Environmental Conservation Branch of EMD should have taken place during project design to ensure CWA permitting issues are addressed by the contractor at the earliest opportunity. Contractors must incorporate avoidance and minimization measures to comply with the national policy to permit no overall net loss of wetlands, as well as meeting concept design criteria while incorporating avoidance and minimization measures to protect wetlands, streams, and waters of the United States. Any proposed action that would significantly affect wetlands must be coordinated with the CG of MCB Camp Lejeune.

The contractor must ensure that construction of all buildings, facilities, and related amenities, including earthwork, grading, landscaping, drainage, stormwater management, parking lot and paved roadway, sidewalks, site excavation, sanitary sewer system extensions, and domestic water extensions, avoids, to the maximum degree feasible, wetlands destruction or degradation.

Identified and mapped boundaries of the legally defined wetlands on all USMC lands within the project area will be distributed to the ROICC or Contract Representative for use (if available) and included in all design products, including drawings, plans, and figures.

10.6.2. Permits

All unavoidable potential impacts to wetlands or waters of the United States require prior coordination as described in this section. Failure to acquire written authorization for

If work in wetlands is required, know who is responsible for obtaining permits, and what the terms and conditions of the permits require.

impacts to wetlands and/or waters of the United States may result in significant project delays or design modifications.

No discharge of fill material, mechanized land clearing, or any other activity is allowed in jurisdictional wetlands or waters of the United States without the proper approvals. The contractor may be responsible for obtaining the following permits (including pre-permit coordination, preparation, and submission of all permit applications after review and concurrence by the installation) and complying with all regulations and requirements stipulated by the State of North Carolina as conditions upon issuance of the permits:

- U. S. Army Corps of Engineers (USACE), Section 404 Permit (individual or applicable nationwide permit); CWA of 1977, as Amended (Public Law 95-217, 33 U. S. C. 1251 et seq.)
- North Carolina Division of Water Resources (NCDWR), Section 401 Water Quality Certification – (15A NCAC 02H) NCDEQ; CWA of 1977, as Amended (Public Law 95-217, 33 U. S. C. 1251 et seq.)
- North Carolina Division of Coastal Management (NCDCM), Federal Consistency Determination (15A NCAC 07) NCDEQ; CZMA of 1972 (16 USC 1451 et seq.)

Two types of activities generally require a permit from the USACE:

- **Activities within navigable waters.** Activities such as dredging, constructing docks and bulkheads, and placing navigation aids require review under Section 10 of the Rivers and Harbors Act of 1899 to ensure that they will not cause an obstruction to navigation.
- **Activities in wetlands and waters of the United States (regulated by Section 404 of the CWA of 1972).** A major aspect of the regulatory program under Section 404 of the CWA is determining which areas qualify for protection as wetlands. Contractors should contact the USACE, the NCDWR, or the NCDCM if there is any question about whether activities could impact wetlands, streams, or protected buffers.

Contractors working on the installation will not perform any work in waters of the United States or wetlands without an approved permit (even if the work is temporary).

Contractors working on the installation will not perform any work in waters of the United States or wetlands without an approved permit (even if the work is temporary). Examples of temporary discharges include dewatering of dredged material prior to final disposal and temporary fills for access roadways, cofferdams, storage, and work areas.

10.6.3. Impacts

Any disturbance to the soil or substrate (bottom material) of a wetland or water body, including a stream bed or protected buffer, is an impact and may adversely affect the hydrology of an area. Discharges of fill material generally include the following, without limitation:

- Placement of fill material that is necessary for the construction of any structure or impoundment requiring rock, sand, dirt, or other material for its construction; site-development fills for recreational, industrial, commercial, residential, and other uses; and causeways or road fills
- Dams and dikes
- Artificial islands
- Property protection or reclamation devices such as riprap, groins, seawalls, breakwaters, revetments, and beach nourishment
- Levees
- Fill for intake and outfall pipes and subaqueous utility lines
- Fill associated with the creation of ponds
- Any other work involving the discharge of fill or dredged material

10.6.4. Mitigation

Any facility requirement that cannot be sited to avoid wetlands must be designed to minimize wetlands degradation and must include compensatory mitigation as required by wetland regulatory agencies (USACE and NCDWR) in all phases of project planning, programming, and budgeting.

The contractor may be required to develop onsite mitigation, consisting of wetland/stream restoration or creation, for all unavoidable wetland and stream impacts, whenever possible and feasible.

The contractor may be required to develop onsite mitigation, if appropriate, consisting of wetland/stream/buffer restoration or creation, for all unavoidable wetland, stream, and buffer impacts, whenever possible and feasible. Use of USMC lands and lands of other entities may be permissible for mitigation purposes for USMC projects when consistent with EPA and USACE guidelines or permit provisions. Land within the project area suitable for establishment of mitigation may be evaluated by the contractor and used for mitigation where compatible with mission requirements and approved by the CG. Proposals for permanent resource areas must be approved by the Assistant Secretary of the Navy (Installations and Environment) or his/her designee.

Offsite mitigation is preferred and should be coordinated through the North Carolina Division of Mitigation Services or an approved private mitigation bank.

10.7. TEMPORARY CONSTRUCTION

Traces of temporary construction facilities, such as haul roads, work areas, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other signs of construction, should be removed upon completion of a contract or project. Temporary roads, parking areas, and similar temporarily used areas should be graded to conform to surrounding contours and the area restored, to the degree practical, to its state prior to any disturbing activities.

11.0 STORMWATER

MCB Camp Lejeune is responsible for stormwater permits associated with construction, industrial, or municipal activities that discharge to outfalls leading to receiving waters. The most applicable permit for contractors is the construction permit, since the majority of the contractor activities are affiliated with construction/renovation.

However, the contractor is also responsible for adhering to the requirements of the industrial and municipal permits held by MCB Camp Lejeune for all of the contractor activities on the installation. In essence, all contractors for the installation need to know and implement the necessary measures to prevent stormwater runoff and pollution runoff from land-disturbing activities (LDAs) and associated construction permit requirements, as well as industrial and municipal activities. The general requirements for each area, as they apply to contractors, are discussed in the following subsections.

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

11.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with stormwater. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the

appropriate environmental office if additional clarification is necessary.

11.1.1. Key Definitions

- **Best Management Practices.** Schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the pollution of waters of the United States. BMPs include structural and nonstructural stormwater controls, operation and maintenance procedures, treatment requirements, and practices to control site runoff (e.g., sediment, spillage or leaks, sludge or waste disposal, or drainage from material storage). See the following website for more information: http://deq.nc.gov/about/divisions/energy-mineral-land-resources/stormwater
- **Certificate of Stormwater Compliance.** A document providing approval for development activities that meet the requirements for coverage under a stormwater general permit.
- **Discharge (Pollutant).** The addition of any pollutant or combination of pollutants to waters of the United States from any point source, including, but not limited to, any spilling, leaking, pumping, pouring, emitting, emptying, or dumping of any pollutant; this excludes discharges in compliance with a National Pollution Discharge Elimination System (NPDES) permit.

- **Erosion and Sedimentation Control Plan.** Any plan, amended plan, or revision to an approved plan submitted to the North Carolina Division of Land Resources or its delegated authority in accordance with North Carolina General Statute 113A-57. Erosion and Sedimentation Control Plans show the devices and practices that are required to retain sediment generated by the land-disturbing activity within the boundaries of the tract during construction and upon development of the tract. *Note that in North Carolina, the Erosion and Sedimentation Control Plan and the NCG010000 Construction General Permit are considered the Stormwater Pollution Prevention Plan (SWPPP, or SPPP) for a construction site.* See the following website for more information:
  http://deq.nc.gov/about/divisions/energy-mineral-land-resources/stormwater

- **Land Disturbance.** Areas that are subject to clearing, excavating, grading, stockpiling, and placement/removal of earth material.

- **Nonpoint Source Discharge.** All discharges from stormwater runoff that cannot be attributed to a discernible, confined, and discrete conveyance. *(See also point source discharge, below.)*

- **Point Source Discharge.** Any discernible, confined, and discrete conveyance, including but specifically not limited to, any pipe, ditch, channel, tunnel conduit, well, discrete fissure, container, rolling stock, or concentrated animal feeding operation from

which pollutants are or may be discharged to waters of the State. *(See also nonpoint source discharge, above.)*

- **Stormwater (Runoff).** The portion of precipitation (rain and/or snowmelt) that does not naturally infiltrate into the ground or evaporate but flows via overland flows, channels, or pipes into a defined surface-water channel or stormwater system during and immediately following a storm event. As the runoff flows over the land or impervious surfaces (such as streets, parking lots, and building rooftops), it accumulates sediment and/or other pollutants that could pollute receiving streams.
- **Stormwater Associated with Construction Activities.** The discharge of stormwater from construction activities, including clearing, grading, and excavating, that result in a land disturbance of equal to or greater than 1 acre, per 40 CFR 122.
- **Stormwater Associated with Industrial Activities.** The discharge from any conveyance that is used for collecting and conveying stormwater and which is directly related to manufacturing, processing, or raw materials storage areas from an applicable industrial plant or activity, per 40 CFR 122.
- **Stormwater Associated with Municipal Activities.** The discharge of stormwater from municipal activities, including public works shops, vehicle maintenance shops, and other municipal activities, with the potential to cause stormwater pollution.

11.1.2. Key Concepts

- **Energy Independence and Security Act (EISA).** In December 2007, Section 438 of EISA was issued. This section requires that Federal facility projects over 5,000 square feet must "maintain or restore, to the maximum extent technically feasible, the predevelopment hydrology of the property with regard to temperature, rate, volume, and duration of flow." In January 2010, the DoD Policy of Implementing Section 438 of the EISA was issued; this document includes a flowchart with implementation steps.
- **Good Housekeeping.** Good housekeeping practices refer to the maintenance of a clean and orderly facility to prevent potential pollution sources from coming into contact with stormwater. The practices include procedures to reduce the possibility of mishandling materials or equipment. Good housekeeping practices benefit stormwater quality and also provide for a clean, safe place for employees and clients. *Note that good housekeeping is one of the six minimum control measures (MCMs) of the MS4 permit requirements.*
- **Low Impact Development (LID).** LID is a holistic approach that incorporates site-specific ecosystem and watershed-based considerations for planning and design. The goal of LID is to mimic a site's predevelopment hydrology by using design techniques that infiltrate, filter, store, evaporate, and detain runoff close to the source. LID seeks to control

non-point source pollutants "nature's way," through the application of plant-soil-water mechanisms that maintain and protect the ecological and biological integrity of receiving waters and wetlands.

- **National Pollution Discharge Elimination System.** The national program for issuing, modifying, revoking, reissuing, terminating, monitoring, and enforcing permits. The NPDES stormwater program regulates stormwater discharges from three potential stormwater sources, as follows:
    - **Construction Activities.** LDAs that disturb 1 or more acres need an NPDES permit. At a minimum, these permits require the development of a site-specific Erosion and Sedimentation Control Plan to address sediment controls during construction and upon development of the tract. As previously noted, the Erosion and Sedimentation Control Plan and the NCG010000 Construction General Permit are considered the SWPPP for a construction site in North Carolina. In the applicable areas of the installation, a State Stormwater Management Permit and coverage under the Construction General Permit may be required. *Note that construction site runoff control is also one of the six MCMs of the Municipal Separate Storm Sewer Systems (MS4) permit requirements.*
    - **Industrial Activities.** Owners and operators of industrial facilities that fall into any of the 30 industrial sectors identified by EPA stormwater

regulations need an NPDES Phase I permit if stormwater is discharged directly into surface water (or MS4). The permit regulations specify steps that facility operators must take prior to becoming eligible for permit coverage and actions that must be taken to continue coverage under an existing permit. These steps and actions include, but are not limited to, effluent limits, monitoring, inspection, sampling, reporting, and corrective action requirements.

- **Municipal Separate Storm Sewer Systems.** Owners and operators of MS4s need an NPDES Phase II permit. An MS4 is a system of pipes and drainage ditches within an urbanized area used to collect storm runoff and convey it to receiving waters. Polluted runoff is commonly transported through MS4s, from which it is often discharged untreated into local waterbodies.

- **Operational Requirements.** Equipment, discharge, and material use requirements that apply to all construction and industrial activities.

- **Post-Construction Requirements.** The management of stormwater generated on a stable, established site after the construction process is complete. The State Stormwater Management Program sets forth requirements for post-construction stormwater runoff control. *Note that post construction is one of the six MCMs of the MS4 permit requirements.*

- **Stormwater Pollution Prevention Plan.** A plan required by permits provided under NPDES that provides guidance to prevent stormwater pollution from construction, industrial, or municipal activities. *Note that the terminology for this plan (and associated acronym) varies somewhat from State to State.*

11.1.3. Environmental Management System

Contractor practices associated with stormwater include the following:

- Boat, ramp, dock cleaning
- Channel dredging
- Composting
- Construction/demolition/renovation
- Erosion/runoff control
- Fueling and fuel management/storage
- HM storage
- Land clearing
- Laundry
- Landscaping
- Livestock operations
- Pesticide/herbicide management and application
- Range residue clearance

- Road construction and maintenance
- Sewers
- Sidewalk and road deicing
- Soil excavation/grading
- Stormwater collection/conveyance
- Surface washing
- Vehicle parking
- Wash rack

Other activities that contractors could be involved in that may cause stormwater pollution include:

- Grounds maintenance (herbicide, pesticides, fertilizer, etc.)
- Outdoor material storage
- Building/roof repairs
- Industrial activities

The potential impacts of these activities on the environment include degradation of water quality and damage to public and private property due to flooding.

11.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard the installation must be aware of and adhere to all applicable regulations and requirements regarding potential stormwater contamination, which include but may not be limited to:

- **Clean Water Act of 1972.** Establishes the basic structure for regulating discharges of pollutants into the waters of the United States. The CWA establishes that no oil or hazardous substances should be discharged into or upon the navigable waters of the United States or adjoining shorelines, which may affect natural resources under the management of the United States through the following goals: (1) eliminate the introduction of pollutants into waters of the United States, and (2) develop water quality, which protects and propagates fish, shellfish, and wildlife and provides for recreation in and on the water.

- **40 CFR 122, National Pollutant Discharge Elimination System.** Requires industrial, construction, and municipal stormwater permits for the discharge of pollutants from any point source into waters of the United States.

- **15A NCAC Chapter 4.** Requires all persons conducting a land-disturbing activity to take all reasonable measures to protect all public and private property from damage caused by the release of sediments from the activity. The primary tool used to accomplish the objective is the development of an Erosion and Sedimentation Control Plan.
    - Identify critical areas
    - Limit exposure areas
    - Limit time of exposure
    - Control surface water

- Control sedimentation
- Manage stormwater runoff

More information can be found at:

http://reports.oah.state.nc.us/ncac.asp?folderName=\Title%2015A%20-%20Environmental%20Quality\Chapter%2004%20-%20Sedimentation%20Control

- **15A NCAC 02H.1000 Stormwater Management.** The State Stormwater Management Program requires all persons conducting LDAs that (1) require a Coastal Area Management Act (CAMA) Major Development Permit or an Erosion and Sedimentation Control Plan, and (2) are located within coastal counties or drain to specific classifications of water bodies, to protect surface waters and highly productive aquatic resources from the adverse impacts of uncontrolled high-density development or the potential failure of stormwater control measures. To receive permit approval, projects must limit the density of development, reduce the use of conventional collection systems in favor of vegetative systems, and incorporate post-construction, structural BMPs.

11.3. PRIOR TO SITE WORK

Contractors are required to address the following in the below section prior to beginning site work.

11.3.1. Construction Notifications

Any project involving LDAs aboard the installation must be reviewed by the installation's NEPA Review Board prior to the onset of work so that potential impacts of the project and associated mitigation measures (if necessary) can be determined. Documentation of this review should have been provided to the ROICC or Contract Representative and may include mandatory conditions affecting the construction/implementation of the project. Consult the ROICC or Contract Representative to obtain or review any NEPA documentation associated with the project in the contract.

Any project involving LDAs aboard the installation must be reviewed by the installation's NEPA Review Board prior to the onset of work.

11.3.2. Familiarity with the Stormwater Phase I Industrial Permit

Discharges of industrial stormwater have the potential to contain contaminants from industrial activity. Because of this, MCB Camp Lejeune holds a Stormwater Phase I industrial permit. This type of discharge is defined and regulated in 40 CFR 122, the EPA final rule regarding NPDES stormwater permitting.

Contractors are responsible for preparing project-specific permit applications and related plans and for coordinating the permit review schedule with the ROICC or Contract Representative.

Daily industrial operations discharging stormwater aboard MCB Camp Lejeune and MCAS New River are covered under an individual NPDES permit. In accordance with the permit, the installation maintains an industrial SWPPP that identifies potential sources of pollution that may affect the water quality of stormwater discharges associated with an industrial activity. Refer to Section 11.4 for more information on contractor responsibilities associated with this permit.

11.3.3. Familiarity with the Stormwater Phase II Municipal Permit

Discharges of municipal stormwater have the potential to contain contaminants from municipal activity. Because of this, MCB Camp Lejeune holds a Stormwater Phase II municipal permit. This type of discharge is defined and regulated in 40 CFR 122, the EPA final rule regarding NPDES stormwater permitting.

Daily municipal operations discharging stormwater aboard MCB Camp Lejeune and MCAS New River are covered under an NPDES permit. In accordance with the permit, the installation maintains a municipal Stormwater Plan to address the six MCMs of the permit, as well as other requirements. Refer to Section 11.4 for more information on contractor responsibilities associated with this permit.

11.3.4. Project-Specific Construction Permits

Contractors are responsible for preparing all project-specific stormwater permit applications and related plans and for coordinating the permit review schedule with the ROICC or

Contract Representative. MCB Camp Lejeune is the responsible party for all project-specific stormwater permits located outside of Public-Private Venture (PPV) housing. All permit-required plans and applications must be submitted to the appropriate MCB Camp Lejeune organization to go through internal approval prior to submission to the appropriate State agency. The permit review schedule should allow adequate time for internal review prior to State submission deadlines. Adequate review time fluctuates and is based on the type of permit application. Stormwater compliance should be coordinated with the appropriate PPV partner for housing-related projects outside the jurisdiction of MCB Camp Lejeune.

All permit-required plans and applications must go through internal approval before being submitted to the appropriate State agency.

Permit coverage is required under the North Carolina General Permit No. NCG010000 (General Permit) for construction activities that disturb 1 acre or more of land. Three copies of a proposed Erosion and Sedimentation Control Plan must be prepared and submitted to the NCDEQ Sedimentation Control Commission (or to an approved local program) at least 30 days prior to beginning construction activity to obtain coverage under the General Permit. A copy of the plan will be kept on file at the job site at all times while the site is active. **Coverage under the permit becomes effective when a plan approval is issued. No LDAs may take place prior to receiving the plan approval.** The

approved plan is considered a requirement or condition of the General Permit; deviation from the approved plan will constitute a violation of the terms and conditions of the permit unless prior approval for the deviations has been obtained.

A State Stormwater Management Permit, issued in accordance with 15A NCAC 02H.1000, is required for all development activities that require a CAMA Major Development Permit or an Erosion and Sedimentation Control Plan and that meet any of the following criteria:

- Development within the 20 coastal counties
- Development within 1 mile of and draining to any waters classified as High Quality Water (HQW) and rated "excellent" based on biological and physical/ chemical characteristics through the NCDWR monitoring or special studies, primary nursery areas designated by the Marine Fisheries Commission, and other functional nursery areas designated by the Marine Fisheries Commission
- Development that drains to an Outstanding Resource Water, which is a subset of HQW that is intended to protect unique and special waters having excellent water quality and being of exceptional ecological or recreational significance to the State or Nation

A State Stormwater Management Permit is required for all activities that will disturb 1 acre or more of land.

Because the installation is in a coastal county, any project that disturbs greater than 1 acre of land (requiring coverage under the General Permit for construction activity) will also require a State Stormwater Management Permit. A State Stormwater Management Permit application must be submitted and filed with the NCDEQ, Division of Water Quality, after the construction plans and specifications are complete and before construction activities begin. Additional information is available on the NCDEQ website:

http://deq.nc.gov/about/divisions/energy-mineral-land-resources/stormwater

State Stormwater Management Permits typically specify design standards for conveyance systems and structural BMPs, a schedule of compliance, and general conditions to which the permittee must adhere.

11.4. RESPONSIBILITIES DURING SITE WORK

The contractor is responsible for maintaining the quality of the stormwater runoff and preventing pollution of stormwater at the construction/job site. The job site may be inspected by installation environmental personnel to ensure compliance with the contractor's construction and/or the installation's industrial SWPPP, municipal stormwater plan, and applicable permits. The following requirements apply to all projects at the installation that have the potential to impact water quality:

- Any changes to the project area that do not comply with the approved Erosion and Sedimentation Control Plan, alter the approved post-construction stormwater conveyance system, or could otherwise significantly change the nature or increase the quantity of pollutants discharged should be immediately communicated to the ROICC or Contract Representative.
- All permitted erosion and sedimentation control projects will be inspected by the contractor at least once every 7 calendar days (unless discharges to a 303(d)-listed water body are occurring) and within 24 hours after any storm event greater than 0.5 inch of rain per 24-hour period, as required by the North Carolina General Permit No. NCG010000. Inspection results shall be maintained by the designated contractor throughout the duration of an active construction project.
- Equipment used during the project activities must be operated and maintained in such a manner as to prevent the potential or actual pollution of the surface or ground waters of the State.
- No POL products (e.g. fuels, lubricants, hydraulic fluids), coolants (e.g., antifreeze), or any other substance shall be discharged onto the ground, into surface waters, or down storm drains (to include leaking vehicles, heavy equipment, pumps, and/or structurally deficient containers of hazardous materials).

- Spent fluids shall be disposed of in a manner so as not to enter surface or ground waters of the State, or storm drains. Disposal of spent fluids is outlined in Section 7.0.
- Implement spill prevention measures, clean up all spills immediately, and follow the spill reporting requirements presented in Section 5.0. Any spilled fluids shall be cleaned up to the extent practicable and disposed of in a manner so as not to allow their entry into the water (surface or ground) of the State. Refer to Section 5.0 for emergency and spill response procedures.
- Herbicide, pesticide, and fertilizer use shall be consistent with the Federal Insecticide, Fungicide, and Rodenticide Act and shall be used in accordance with label restrictions. Refer to Section 7.0 for additional information on Hazardous Material/Hazardous Waste Management.
- Particular care must be used when storing materials outside. Materials and equipment stored outside that could potentially affect the quality of stormwater runoff include, but are not limited to, garbage dumpsters, vehicles, miscellaneous metals, chemical storage, fuels storage, wood products, and empty storage drums. These materials should be stored under cover whenever practicable. Contact the ROICC or Contract Representative with any questions about whether an outdoor storage practice is acceptable.

- Use good housekeeping practices to maintain clean and orderly work areas, paying particular attention to those areas that may contribute pollutants to stormwater. For industrial activities, refer to the link below for more information on best management practices to prevent stormwater pollution. EPA Industrial Fact Sheet Series for Activities Covered by EPA's multi-sector general stormwater permit: http://www.epa.gov/npdes

PAGE INTENTIONALLY BLANK

12.0 SOLID WASTE, RECYCLING, AND POLLUTION PREVENTION (P2)

Contractors should minimize the amount of solid waste requiring disposal in a landfill.

The installation has a proactive P2 and recycling program, and contractors should minimize the amount of solid waste requiring disposal in a landfill. This section addresses solid waste, including both municipal solid waste (MSW) and construction and demolition (C&D) waste. HM and HW are discussed in Section 7.0 of this guide. Contractors are required to comply with all Federal, State, and local laws and regulations for proper disposal and recycling of all solid wastes.

12.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with solid waste, recycling, and pollution prevention. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

12.1.1. Key Definitions

- **Construction and Demolition Debris.** Inert materials generated during the construction, renovation, and demolition of buildings, roads, and bridges. C&D waste often contains bulky, heavy materials such as concrete, lumber (from buildings), asphalt (from roads and roofing shingles), gypsum (the main component of drywall), and glass (from windows).
- **Green Procurement (GP).** The purchase of products and services that are environmentally preferable, when compared with competing products that serve the same purpose, in accordance with federally mandated "green" procurement preference programs. GP is intended to have a lesser or reduced negative effect on human health and the environment, and to permit fulfilling the social, economic, and other requirements of present and future generations.
- **Pollution Prevention.** Reducing the amount of pollution entering waste streams or otherwise released to the environment through source reduction and process efficiencies.
- **Recycling.** Activities that may include collection, separation, and processing, by which products or other materials are recovered from the solid waste stream for use as raw materials in the manufacturing of new products. Recycling also includes using, reusing, or reclaiming materials, as well as processes

that regenerate a material or recover a usable product from it.

- **Municipal Solid Waste.** Any solid materials discarded, including garbage, construction debris, commercial refuse, non-hazardous materials, non-recyclable wood, or other non-recyclable material per BO 11350.1, Refuse Disposal Procedures.

12.1.2. Key Concepts

- **Pollution Prevention/Green Procurement.** Installation contractors are strongly encouraged to use P2 and GP practices.
- **Qualified Recycling Program (QRP).** An organized operation that diverts or recovers scrap or waste streams and that identifies, segregates, and maintains the integrity of the recyclable materials in order to maintain or enhance the marketability of the materials.
- **Recycling.** Recycling is required on the installation. The MCB Camp Lejeune Landfill (Base Landfill) Recycling Center accepts specified recyclables according to the schedule in Table 12-1. Call (910) 451-4214 prior to a bulk turn-in.
- **Solid Waste.** Solid waste is disposed of in accordance with contract specifications (off the installation or at the Base Landfill). Data related to disposal off the installation (to include C&D waste) must be provided to the ROICC or Contract Representative on a monthly basis.

- **Source Reduction.** Any practice that reduces the amount of any HM, pollutant, or contaminant entering any waste stream or released into the environment prior to recycling, treatment, and disposal that could reduce the hazard to public health and the environment. Source reduction may include equipment or technology modification; process or procedure modification; reformulation or redesign of products; substitution of raw materials; and improvements in housekeeping, maintenance, training, or inventory control.

12.1.3. Environmental Management System

Contractor practices associated with solid waste, recycling, and P2 include the following:

- Battery management
- Building operation/maintenance/repair
- Composting
- Construction/demolition/renovation
- Equipment operation/maintenance/disposal
- Grease traps
- HW disposal offsite transport
- Land clearing
- Livestock operations
- Metal working
- Packaging/unpackaging

- Paint removal
- Painting
- Parts replacement
- Polishing
- Range residue clearance
- Recreational facilities operation
- Road construction maintenance
- Rock crushing operations
- Solid waste collection/transportation
- Storage tank management
- Urban wildlife management
- Vehicle maintenance

The potential impacts of these activities on the environment include soil degradation, surface water quality degradation, depletion of landfill space, and depletion of nonrenewable resources.

12.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard the installation must be aware of and adhere to all applicable regulations and requirements regarding solid waste disposal, recycling, and P2, which include but may not be limited to the following:

- **BO 5090.17, Solid Waste Reduction – Qualified Recycling Program.** Provides guidance for solid

waste reduction, P2, and management of recyclable materials.

- **BO 11350.2D, Refuse Disposal Procedures.** Establishes procedures for the separation, collection, and disposal of refuse and the disposal of waste wood products.
- **DoD Instruction 4715.4, Pollution Prevention.** Establishes the DoD requirement for installation QRPs and calls for GP.
- **EO 13423, Strengthening Federal Environmental, Energy and Transportation Management.** Integrates prior practices, strategies, and requirements to further enhance the environmental and energy performance and compliance requirements. The EO sets goals in several environmental areas, including recycling.
- **EO 13514, Federal Leadership in Environmental, Energy, and Economic Performance.** Expands on the environmental performance requirements for Federal agencies, to include setting goals for solid waste diversion.
- **Pollution Prevention Act of 1990 (42 USC 13101 et seq.).** Establishes the national policy that "pollution should be prevented or reduced at the source whenever feasible," and establishes the following hierarchy: source reduction, recycling, treatment, and disposal.
- **Resource Conservation and Recovery Act of 1976.** Governs the disposal of solid waste and establishes

Federal waste disposal standards and requirements for State and regional authorities. The objectives of Subtitle D are to assist in developing and encouraging methods for the disposal of solid waste that are environmentally sound and that maximize the utilization of valuable resources recoverable from solid waste.

- **Solid Waste Disposal Act (SWDA) of 1965.** Requires Federal facilities to comply with all Federal, State, interstate, and local requirements concerning the disposal and management of solid wastes, including permitting, licensing, and reporting requirements. The SWDA encourages the reuse of waste through recycling and requires the procurement of products that contain recycled materials.

12.3. SOLID WASTE REQUIREMENTS

Contractors must follow all Federal, State, and local requirements regarding the collection, storage, and disposal of solid waste. Contact the ROICC or Contract Representative for additional information regarding solid waste requirements.

At a minimum, the following actions are required for all contractors:

1. Prior to performing work that will or may generate solid waste at the installation, all contractors must provide their ROICC or Contract Representative with a copy of their Solid Waste Disposal Permit

unless the use of the Base Landfill is authorized for disposal. If the Base Landfill is authorized, the contractor must contact the Base Landfill Operations Clerk to ensure the contract is registered in the Landfill Tracking System. Recycling should be coordinated with the ROICC or Contract Representative and the Landfill Manager.

2. Provide the weight of ALL waste, both MSW and C&D, that is either disposed of or recycled, to the ROICC or Contract Representative, with a copy to the Landfill Manager. This requirement does not apply if the landfill/recycling facility picks up or accepts materials directly from the contractor. If contractors transport waste offsite for disposal, it is mandatory that they track the material weight and provide that information to their ROICC or Contract Representative for input into the annual Pollution Prevention Annual Data Summary.

In addition, contractors producing solid waste on the installation are required to take these steps:

- Pick up solid waste, separate it according to material type, and place it in covered containers of the correct type that are regularly emptied for recycling or landfilling.
- Verify that the solid waste contains no HM or HW.
- Prevent contamination of the site and the surrounding areas when handling and disposing of waste.

- Leave the project site clean upon completion of a project.

12.3.1. MCB Camp Lejeune Landfill Acceptable Waste Streams

To dispose of waste at the Base Landfill, contractors must be authorized with a valid construction pass and placard representing the related contract. Contractors must also contact the Landfill Operator prior to unloading refuse. Contact the ROICC or Contract Representative with any questions regarding use of the landfill or to coordinate disposal.

The Base Landfill accepts certain types of solid waste under the conditions specified in Table 12-1. Base Landfill hours of operation are 0730 to 1530, Monday through Friday, but ACM waste must be delivered between 0700 and 1000, Monday through Thursday. Each material must be separated into different loads.

PAGE INTENTIONALLY BLANK

Table 12-1. Base Landfill Requirements

No Personal Property/ Off-Base Trash Accepted
Landfill Operating Hours
0700-1500 Monday – Thursday 0700-1400 Friday
Wood Products
The following products may be mixed together and delivered to the landfill: • Scrap lumber (unpainted) • Embark boxes (broken down) • Pallets (broken/untreated) The following products must be separated and delivered to the landfill: • Trees (cut to 10 feet or less and free of soil) • Leaves and scrubs Serviceable pallets
Lead Based Painted Wood Products
• Delivered before 1400 Monday – Thursday • Not accepted on Friday • Cut in less than 8-foot lengths Wrapped in 6-millimeter plastic bags/sealed
Asbestos (all types)
• Appointment needed (910-451-5011 / 2946) • Delivered by 1000 (Mon – Thurs.) • Not accepted on Friday • Double wrapped in 6-millimeter plastic bags

• Sealed with duct tape Labeled and manifested prior to delivery
Organic Products
• Leaves, pine straw, grass, and shrub clippings • No bags or containers allowed • No twigs or limbs over 2 inches in diameter • Less than 6-foot lengths
Concrete
• Delivered separately from other items • Wire and rebar must be cut off flush with exposed surfaces • Concrete and culverts • Bricks and blocks • Mortar products
Soil
Non-contaminated soil accepted
Recyclable Products (Must be separated and dropped off at a designated recycling drop-off point or at a Recycling Center)
• Wood pallets (delivered separately) • White paper (mixed flat or shredded) • Newspaper • Magazines • Military publications (binders removed) • Phone books • Plastic and glass (containers or bottles) • Toner cartridges • Cardboard (delivered separately if in bulk)

• Vinyl siding (delivered separately, in less than 6-foot lengths) • Asphalt shingles (delivered separately) Scrap metals
Other Related Information
Asphalt may be accepted in small quantities, as needed, at the discretion of the Landfill Manager (large quantities of asphalt must be taken off the installation).
All furniture must be accompanied by a DD Form 1348, with a classification of rejected by the Base Property Office **AND** downgraded to scrap by Defense Logistics Agency Disposition Services (DLADS).
All other Base or USMC property must be accompanied by a DD Form 1348 and downgraded to scrap by DLADS.
Scrap materials related to **ordinance, ammunition or dangerous items**, including containers, tubes, and packing, must also be accompanied by Ammunition, Explosives, and Other Dangerous Articles (AEDA) certifications and copies of the certifier and verifier's appointment letters.
Phone Numbers: (area code 910) • Landfill Manager 451-4998 • Recycling Manager 451-4214 • Landfill Fax 451-9935 • Landfill Clerk 451-2946 • EMD 451-5837 • EOD 451-0558

Unacceptable Items
• Hazardous Waste • Liquid Waste • Useable Appliances • Paint and Paint Cans • Appliances • Electronics • Computer Equipment • Batteries • Wire (Communication/Barbed/ Concertina) • Oyster Shells • Contaminated Soil • Tires • 55-Gallon Drums • Oil Filters • Petroleum Containers • Regulated Medical Waste • PCBs or PCB containers • Demilitarized Waste • Construction and Demolition Debris (unless specified in the contract)

12.4. RECYCLING REQUIREMENTS

The installation's QRP is managed by the EMD in collaboration with the Public Works Division. Reducing solid waste saves money and helps protect the environment by conserving natural resources. Additionally, USMC facilities are mandated to recycle, and the installation must meet solid waste diversion goals specified in EO 13514, the

DoD Strategic Sustainability Performance Plan, and the EMS.

12.4.1. Recycling Center

The MCB Camp Lejeune Recycling Center, Building 982, is co-located with the Base Landfill on Piney Green Road. Normal working hours are Monday through Thursday, 0700–1500, and Friday, 0700-1400. All materials should be brought to the Recycling Center. Have the ROICC or Contract Representative contact the Recycling Center at (910) 451-4214 for additional details. Call Recycling Coordinator at (910) 451-4214 for specific types and categories of materials accepted.

The following types and categories of materials are accepted for recycling but must be delivered to the Recycling Center on Piney Green Road:

- Scrap metal
- Steel (high temperature, corrosion resistant)
- Brass (includes spent/fired munitions, but excludes brass casings above .50 caliber; please call the Recycling Coordinator at (901) 451-4214 for details and documentation requirements)
- Copper and copper wire
- Aluminum (plate, sheet, scrap) and aluminum cans
- Paper (white, news, magazine)
- Cardboard

- Glass bottles (no window, windshields, or drinking glass)
- Plastic bottles
- Toner cartridges

Special arrangements may be made for other materials (C&D waste) or larger volumes of commonly recycled materials from events such as C&D. Regulations set forth in BO 11350.1 must be followed.

12.4.2. Other Recyclables

- **Asphalt Pavement.** Asphalt must be removed and delivered to an asphalt recycling facility. Contractors must provide a record of the total tons of asphalt recycled and the corporate name and location of the recycling facility to their ROICC or Contract Representative, with a copy to the Landfill Manager.
- **Empty Metal Paint Cans.** Take empty metal paint cans to Building S-962 for recycling. Turn in all HM cans or HM containers that are generated from MCB Camp Lejeune or MEF contracts to Building S-962 on Michael Road on the scheduled contractor turn-in day. Have the ROICC or Contract Representative contact EMD for more information. Any waste generated from this process must be managed appropriately.
- **Other Metals.** Take other metals to the DLADS disposal area in Lot 201, following the guidelines of BO 5090.17.

- **Red Rag Recycling.** Contractors should seek a red rag program to supply and launder shop rags. This service supplies clean rags and picks them up after use. The rags are laundered offsite and returned.
- **Universal Waste.** See Section 7.0 of this guide for management procedures.
- **Unused Hazardous Materials.** Turn in these materials to the HM Free Issue Point, Building 977 on Michael Road. Have the ROICC or Contract Representative contact the Free Issue Point at (910) 451-1482.
- **White Rag Recycling.** White rags are used in painting (these have no dye and thus do not interfere with these types of operations) and may be laundered offsite in a program analogous to the red rag recycling service.

12.5. POLLUTION PREVENTION AND GREEN PROCURMENT

MCB Camp Lejeune is subject to GP requirements. GP implements environmentally protective principles in the procurement arena and includes preferential use of the following:

- Products made from recovered materials
- Biobased products
- Water- and energy-efficient products
- Alternatives to ozone-depleting substances

- Non-toxic and less-toxic products
- Electronics that meet Electronic Product Environmental Assessment Tool standards
- Products that do not contain toxic chemicals, hazardous substances, or other pollutants targeted for reduction and elimination by the DoD
- Products with alternative fuel use/increased fuel efficiency
- Environmentally preferable purchasing practices

Contractors are encouraged to employ GP practices whenever feasible.

13.0 POTENTIAL DISCOVERY OF UNDOCUMENTED CONTAMINATED SITES

MCB Camp Lejeune was placed on the EPA National Priorities List, effective November 4, 1989. To ensure the protection of human health and the environment, a proactive Installation Restoration Program has been established to assess and remediate various sites on the installation. Numerous investigations have been performed to ensure that all of the installation's contaminated sites have been found, but additional contaminated areas may still exist. It is the contractor's responsibility to notify the ROICC or Contract Representative of any unforeseen site conditions while on the installation. It is recommended that any contractors performing intrusive activities on the installation be properly trained in accordance with the OSHA standards in 29 CFR 1910.120(e). If intrusive activities are planned for known contaminated areas, all required environmental training should be completed *prior* to working at MCB Camp Lejeune. Copies of training records should be available upon request by Federal or State regulators.

Contact the ROICC or Contract Representative with questions or concerns about the information in this section.

13.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with unforeseen site conditions. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

13.1.1. Key Definitions

- **Free Product.** A discharged HM/HW, POL, or environmental pollutant that is present in the environment as a floating or sinking non-aqueous phase liquid that exists in its free state (i.e., exceeds the solubility limit of liquids or saturation limit of soil/solids).
- **National Priorities List.** List of sites of national priority among the known releases or threatened releases of hazardous substances, pollutants, or contaminants.
- **Petroleum, Oil, and Lubricants.** A broad term that includes all petroleum and associated products or oil of any kind or in any form, including, but not limited to, petroleum, fuel oil, vegetable oil, animal oil, sludge, oil refuse, and oil mixed with wastes.
- **Unforeseen Site Condition.** A potentially hazardous or unanticipated site condition encountered on a job site.

- **Munitions and Explosives of Concern.** Military munitions that may pose explosives safety risks, including MEC, UXO, DMM, and munitions constituents present in a high enough concentration to present an explosives hazard.

13.1.2. Key Concepts

- **Notification.** Contractors must notify the ROICC or Contract Representative, in writing, of any unforeseen site conditions prior to disturbing them.
- **Response.** Contractors must stop working and evacuate work areas if unforeseen site contaminants, HM, or MEC/DMM/UXO are suspected to be present.

13.1.3. Environmental Management System

Unforeseen site conditions are potentially applicable to all EMS practices conducted aboard MCB Camp Lejeune.

13.2. OVERVIEW OF REQUIREMENTS

Contractors operating aboard the installation must be aware of and adhere to all applicable regulations and requirements regarding unforeseen site conditions, which include but may not be limited to the following:

- **CERCLA of 1980 and Superfund Amendments & Reauthorization Act (SARA) of 1986.** Establishes the Nation's HW site cleanup program.

- **Occupational Safety and Health Standards, 29 CFR 1910.** Federal standards that govern occupational health and safety to ensure the protection of employees from recognized hazards, such as exposure to toxic chemicals, excessive noise levels, mechanical dangers, heat or cold stress, or unsanitary conditions. The standards include provisions for many facets of employee safety and health, including, but not limited to, employee training, personal protective equipment, HM communication, medical surveillance, and emergency planning.

13.3. UNFORESEEN SITE CONDITION PROCEDURES

Contractors must promptly, before the conditions are disturbed, give a written notice to the ROICC or Contract Representative of (1) any subsurface or latent physical conditions at the site that differ materially from those indicated in the contract, or (2) any unknown physical conditions at the site, of an unusual nature, that differ materially from those ordinarily encountered.

The ROICC or Contract Representative will investigate the site conditions promptly after receiving the notice.

The most common unforeseen conditions at MCB Camp Lejeune typically relate to POL contamination and MEC/DMM/UXO. Procedures for these scenarios are provided in the following sections.

13.3.1. Petroleum, Oil, and Lubricants

The most frequently encountered condition that requires EMD assistance is the presence of a POL odor while excavating. If an odor or any free product is encountered during construction or excavation activities, take the following actions:

- Stop work.
- Immediately clear the area of all personnel to a safe distance upwind of the suspected area.
- Call the Fire and Emergency Services Division (911) immediately if personnel are affected or injured by the suspected contaminant.
- Call the Fire and Emergency Services Division to properly secure the area.
- Notify the ROICC or Contract Representative so that the EMD Spill Response Team will be contacted to determine the appropriate course of action.

If there is an odor, stop work and immediately clear the area of all personnel to a safe distance upwind of the suspected area.

Please note that if contaminated soil is removed during excavation activities, the soil will have to be characterized prior to disposition. While it is staged and awaiting characterization sampling results, contaminated soil is to be placed within a bermed area on an impervious surface or barrier and securely covered with plastic or appropriate

material. Sample results and characterization will determine the ultimate disposition of the soil. In accordance with installation policy, contaminated soil is not permitted to be reintroduced into excavations.

Recognize

Retreat

Report

13.3.2. Munitions and Ordnance

MCB Camp Lejeune has been in operation as a military training installation since the early 1940s. As such, munitions or an ordnance item may be encountered during site excavation or construction activities. MEC, DMM, or UXO at MCB Camp Lejeune and its outlying areas typically include flares, mines, grenades, rockets, artillery projectiles, bulk explosives, fuses, or blasting caps. These items may vary in condition from very good/easily recognizable to unrecognizable, fragmented, or corroded scrap metal. MEC, DMM, or UXO may be encountered on the ground surface, partially buried, or completely buried.

Contractors operating aboard the installation should follow the "3R" concept if a possible munitions or ordnance item is discovered: **"Recognize, Retreat, and Report."**

Recognize

Retreat

Report

- **Recognize.** Contractors with the potential to encounter any possible MEC, DMM, or UXO should have a basic knowledge of these items. The item does not have to

be specifically recognized or identified, but it is important for personnel to recognize the potential hazard.

- **Retreat.** If a suspected MEC, DMM, or UXO item is encountered, leave the immediate area and DO NOT DISTURB the item. If possible, note the general size and shape of the item, any markings, and the location.
- **Report.** Report all occurrences to the appropriate authority, including any observations (e.g., size, shape, markings, and location).

Stop work immediately if a project unearths a hazardous material, such as MEC/DMM/UXO, and report the situation to the ROICC or Contract Representative.

If a project unearths any potential MEC/DMM/UXO, recognize the potential hazard. Stop work immediately, and have all personnel clear the immediate area. Report the situation and any observations to the ROICC or Contract Representative, who will then report the item to Range Control and Explosive Ordnance Disposal (EOD). The following link is to a 6-minute "UXO Safety" awareness training video that provides additional guidance.

http://www.lejeune.marines.mil/OfficesStaff/ExplosivesSafety/ %20trainingandguides.aspx

For other emergency response procedures, please refer to Section 5.0 of this guide.

PAGE INTENTIONALLY BLANK

14.0 PERMITTING

Contractors operating aboard the installation must ensure that all relevant environmental permits are obtained before work commences onsite. Contractors must work with their ROICC or Contract Representative to determine permitting responsibilities prior to beginning work. Contractors must adhere to all permit conditions. Examples of permits related to the environment are provided in Section 14.3.

14.1. KEY DEFINITIONS AND CONCEPTS

The following key definitions and concepts are associated with contractor permitting requirements. If you have any questions or concerns about the information in this section, please consult the ROICC or Contract Representative, who will contact the appropriate environmental office if additional clarification is necessary.

Please consult the ROICC or Contract Representative with any questions or concerns about the information in this section.

14.1.1. Key Definitions

- **Major Source.** Any source that emits or has the potential to emit 100 tons per year or more of any criteria air pollutant in accordance with Title V of the CAA.

- **Permit.** A legally enforceable document required by statutory regulation for potential sources of pollution that is required for operations that may have an environmental impact. Permits may be administered at the Federal, State, or local level.
- **Target Housing.** Any housing constructed before 1978, with the exception of housing for the elderly and persons with disabilities (unless a child under the age of 6 lives or is expected to live there) and residential dwellings where the living areas are not separated from the sleeping areas (efficiencies, studio apartments, dormitories, etc.).

14.1.2. Key Concepts

- **Permits.** Prior to beginning work aboard the installation, consult applicable permit requirements and ensure that they are met before work begins. Copies of all applicable permits/authorizations should be retained onsite for the life of the project. Additional information on North Carolina permits is found on the following webpage: http://deq.nc.gov/about/divisions/environmental-assistance-customer-service/deacs-permit-guidance/environmental-permit-assistance

Consult the ROICC or Contract Representative for additional information concerning the contract's permit requirements. The contractor is responsible for ensuring that all required permits are acquired prior to any work aboard MCB Camp Lejeune.

14.1.3. Environmental Management System

Currently, no practices are associated with permitting under the EMS.

14.2. OVERVIEW OF REQUIREMENTS

Please refer to the individual sections of this Guide for applicable permitting regulations and requirements for each environmental media. Many permits have specific timetables for submittal prior to project initiation. Contractors must consult the permit requirements and ensure that all pertaining permits are obtained in the required timeframe.

14.3. PROJECT PERMITS AND APPROVALS

The NCDEQ website (http://deq.nc.gov/) is a useful reference for determining required permits and obtaining necessary forms.

Prior to work being awarded, EMD's NEPA Section should have performed an environmental review of the installation-associated action proponent to comply with NEPA 1969. The outcome of this review would be either a Decision Memorandum or an Environmental Assessment. Contractors must refer to their contract and the requirements outlined in the NEPA documentation for specific permitting requirements. EMD Program Managers are available for

guidance; however, if the contractor is tasked with preparing permit applications, the contractor is expected to have the capability and expertise required to complete the submittals in accordance with the guidance provided by the regulatory agency that issues the permit. In addition, EMD must be provided with copies of all permits submitted to the NCDEQ. In some cases, EMD must submit the permit application. Please direct questions to the ROICC or Contract Representative.

Some permits that may be required are discussed in applicable sections of this Guide. The following list of permits is not meant to be all-inclusive; please be aware that other permits may also be required. The NCDEQ website (http://deq.nc.gov/) is a useful reference for determining required permits and obtaining necessary forms. In addition, any inspection and/or data collection required by the permits must be retained onsite for review upon request.

14.3.1. Stormwater (Section 11.0)

- **NPDES Stormwater Discharge Permit for Construction Activities (also referred to as General Permit No. NCG010000).** Required for all LDAs that exceed 1 acre; also requires an accompanying Erosion and Sedimentation Control Plan.
- **General Permit SWG050000.** Required for residential development activities within the 20 coastal counties (including Onslow County) located within 1/2 mile and draining to class SA waters (waters classified as SA are tidal salt waters that are

used for commercial shellfishing or marketing purposes) that disturb less than 1 acre if adding more than 10,000 square feet of built-upon area that will result in a built-upon area greater than 12 percent of the total project area.

- **High-Density Stormwater Permit.** Required when (1) the LDA exceeds 1 acre and impervious surfaces are greater than or equal to 25 percent of the total project area adjacent to non-SA waters or greater than or equal to 12 percent of the total project area adjacent to SA water; or (2) total development exceeds 10,000 square feet of impervious surface.
- **Low-Density Stormwater Permit.** Required when the LDA exceeds 1 acre and impervious surfaces are less than 25 percent of the total project area when adjacent to non-SA waters or less than 12 percent of the total project area when adjacent to SA waters.

14.3.2. Asbestos (Section 8.0)

- **Asbestos Permit Application and Notification for Demolition/Renovation.** DHHS Form 3768, available at the following website (under *Forms & Applications*):

  http://epi.publichealth.nc.gov/asbestos/ahmp.html

14.3.3. Lead-Based Paint (Section 9.0)

- **North Carolina Lead-Based Paint Abatement Permit Application.** Any person or firm conducting an abatement of a child-occupied facility or target

housing is required to obtain a Lead Hazard Management Plan Permit. The application is available at the following website: http://epi.publichealth.nc.gov/lead/pdf/LeadAbatePermit08-07.pdf

14.3.4. Air Quality (Section 4.0)

- **Construction Permits.** Construction permits are required for all new stationary sources and all existing stationary sources that are added to or are modified with new equipment that may emit air pollutants. Permits may be required for the construction or modification of the following types of emission sources:
  - Boilers
  - Generators
  - Engine test stands
  - Surface coating/painting operations
  - Refrigerant recovery and recycling operations for other ozone-depleting substances, such as industrial chillers, refrigerators, air conditioning compressors, or cleaning agents.
  - Chemical or mechanical paint removal, abrasive blasting, grinding, or other surface preparation activities
  - Fuel storage and fuel dispensing
  - Woodworking shops

- Welding shops
- Bulk chemical or flammables storage
- Open burning
- Fire training
- Rock crushing or other dust-causing activities

- **New Source Review Permit.** A New Source Review permit is a pre-construction permit that authorizes the construction of new major sources of air pollution or major modifications of existing sources.

14.3.5. Wetlands (Section 10.6)

- **Section 404 Clean Water Act Permit.** Contractors working aboard the installation will not perform any work in waters of the United States or wetlands (see definition below) without an approved permit (even if the work is temporary). Unavoidable impacts to wetlands or waters of the United States will require coordination and written approval from the USACE for a Section 404 CWA permit (individual or applicable nationwide permit), the NCDWR for a Section 401c Water Quality certification, and the NCDCM for a Federal Consistency Determination. Failure to acquire written authorization for making impacts to wetlands and/or waters of the United States may result in significant project delays or design modifications. See the following website for more information:

  http://www.epa.gov/laws-regulations

14.3.6. Drinking Water/Wastewater

- **Approval of Engineering Plans and Specifications for Water Supply Systems.** Applicants must submit engineering plans and specifications at least 30 days prior to the date upon which the Authorization to Construct is desired. Authorization to Construct must be obtained prior to onset of work.
- **Wastewater Extension Permit.** NCDEQ Form FTA 02/03 – Rev. 3 04/05. Applicants submitting Form FTA 02/03 should plan to allow the State approximately 90 days to issue the permit. The Wastewater Extension Permit must be obtained prior to onset of work.