# SURVEY FINDINGS Building: HP504

## Friable ACM identified

| DESCRIPTION | LOCATION | Date | Quantity |
|---|---|---|---|

**No friable ACM records found in database**


## Non-friable ACM identified

| DESCRIPTION | LOCATION | Date | Quantity |
|---|---|---|---|
| ROOFING SEALANT, BLACK | ROOF CENTERLINE VENTS AND PARAPET WALL FLASHING | 3/28/2006 | 650 SF |
| ROOFING SEALANT, BLACK | ROOF CENTERLINE VENTS ONLY; PARAPET WALL FLASHING TESTED NON ACM (SEE ALSO HM40) | 9/22/2014 | 60 SF |
| ROOFING SEALANT, BLACK | ROOF CENTERLINE VENTS AND PARAPET WALL FLASHING | 7/16/2009 | 650 SF |
| ROOFING SEALANT, BLACK | ROOF CENTERLINE VENTS AND PARAPET WALL FLASHING | 9/5/2012 | 650 SF |

## Tested Non ACM or REMOVED Materials


| DESCRIPTION | LOCATION | Date | Quantity |
|---|---|---|---|
| 2'x2' CEILING TILE, | CENTRAL LOUNGES | 3/28/2006 | |
| 12" BEIGE FLOOR TILE AND ADHESIVE | CENTER HALLS, LAUNDRY | 3/28/2006 | |
| 12" GRAY FLOOR TILE AND ADHESIVE | DORM ROOMS AND COMMON AREAS THROUGHOUT | 3/28/2006 | |
| DUCT SEALANT, WHITE | CENTRAL PIPE CHASE DUCTS BETWEEN FLOOR PENETRATIONS | 7/16/2009 | |
| INTERIOR CAULKING, | PIPE CHASE CMU/ BLOCK EXPANSION JOINTS | 7/16/2009 | |
| ADHESIVE | CENTER HALLS, LAUNDRY | 3/28/2006 | |
| DUCT SEALANT, GRAY | PIPE CHASES, MECHANICAL ROOMS, AND STUB DUCT INTO DORM ROOMS | 3/28/2006 | |
| DRYWALL AND JOINT MATERIAL | DORM ROOMS AND COMMON AREAS THROUGHOUT | 3/28/2006 | |
| MISCELLANEOUS SEALANT | CEMENTITIOUS PACKING AT WASTE DRAIN PIPING IN PIPE CHASES | 3/28/2006 | |
| TEXTURED CEILING MATERIAL | DORM ROOMS AND COMMON AREAS THROUGHOUT | 3/28/2006 | |

| | | |
|---|---|---|
| MISCELLANEOUS SEALANT | PIPE CHASES AT SEWER AND VENT LINE WALL PENETRATION | 7/16/2009 |
| MISCELLANEOUS SEALANT | PIPE CHASES, MECHANICAL ROOMS WALL CABLE/CONDUIT PENETRATIONS | 3/28/2006 |
| EXTERIOR CAULKING, | WINDOWS | 3/28/2006 |
| CLOTH EXPANSION JOINT MATERIAL, THIN | MECHANICAL ROOM HVAC UNITS | 7/16/2009 |
| FOIL BACKED TAPE | MECHANICAL ROOM HVAC UNITS AND DUCTS | 7/16/2009 |
| HVAC DUCT INSULATION | MECHANICAL ROOM HVAC UNITS AND DUCTS | 7/16/2009 |
| INTERIOR CAULKING, | VANITY SINKS AND DORM ROOM DOORS | 7/16/2009 |
| PIPE INSULATION | MECHANICAL ROOMS AND PIPE CHASES THROUGHOUT | 7/16/2009 |
| FIBERGLASS INSULATION SEALANT | MECHANICAL ROOMS AND PIPE CHASES ON FIBERGLASS INSULATION THROUGHOUT | 7/16/2009 |
| FIBERGLASS INSULATION SEALANT | PIPE CHASES, FIBERGLASS PIPING END CAPS | 7/16/2009 |
| INTERIOR CAULKING, | RESIDUAL MATERIAL, SECOND FLOOR HALL (WATER SCUTTLEBUTT REMOVED) | 7/16/2009 |
| VINYL THRESHOLD MATERIAL | CENTER HALL DOORWAYS (TILE TO CONCRETE TRANSITIONS) | 7/16/2009 |
| EXTERIOR CAULKING, | BRICK FACING EXPANSION JOINTS | 7/16/2009 |
| ROOFING SEALANT, GRAY | ROOFING SYSTEM PERIMETER FLASHING AT SEAMS (SEE ALSO HM07) | 9/22/2014 |
| PITCH POCKET TAR | ROOFING SYSTEM CABLE/ CONDUIT PENETRATIONS | 7/16/2009 |
| BUILT-UP ROOFING | MAIN ROOFING SYSTEM MEMBRANE (NOT A CORE SAMPLE) | 7/16/2009 |
| ROOFING MATERIAL, | MAIN ROOFING SYSTEM MEMBRANE (NOT A CORE SAMPLE) | 7/16/2009 |
| ADHESIVE | CENTER HALLS, LAUNDRY, DORM ROOMS | 7/16/2009 |
| DUCT SEALANT, GRAY | PIPE CHASES, MECHANICAL ROOMS, AND STUB DUCT INTO DORM ROOMS | 7/16/2009 |
| 12" GRAY FLOOR TILE AND ADHESIVE | DORM ROOMS AND COMMON AREAS THROUGHOUT | 7/16/2009 |
| DRYWALL AND JOINT MATERIAL | DORM ROOMS AND COMMON AREAS THROUGHOUT | 7/16/2009 |
| TEXTURED CEILING MATERIAL | DORM ROOMS AND COMMON AREAS THROUGHOUT | 7/16/2009 |
| EXTERIOR CAULKING, | WINDOWS AND DOORS | 7/16/2009 |




AN ASBESTOS NOTIFICATION
ELECTRICAL PANEL
IP INFORMATION PACKET
MR MECHANICAL ROOM

SAMPLE LEGEND ID




**NO ACM IDENTIFIED**

BUILDING HP504
FIRST FLOOR

15' 0' 15' 30' 60'

REVISIONS


| DWG | DESCRIPTION | DATE | APPROVED |
|---|---|---|---|

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
HP504-01
MCB CAMP LEJEUENE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: SEPTEMBER 2014
SHEET 1 OF 4




MR MECHANICAL ROOM

SAMPLE LEGEND ID

01-01 (+,-)

SAMPLE IDENTIFICATION

POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS

HOMOGENOUS MATERIAL

**NO ACM IDENTIFIED**

BUILDING HP504

SECOND FLOOR

15' 0' 15' 30' 60'

REVISIONS


| SYM | DESCRIPTION | DATE | APPROVED |
|---|---|---|---|

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
HP504-02
MCB CAMP LEJEUENE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: SEPTEMBER 2014
SHEET 1 OF 1




MR MECHANICAL ROOM

SAMPLE LEGEND ID

01-01 (+,-)

- SAMPLE IDENTIFICATION
- POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS
- HOMOGENOUS MATERIAL

**NO ACM IDENTIFIED**

BUILDING HP504

THIRD FLOOR

15' 0' 15' 30' 60'

REVISIONS


| NO. | DESCRIPTION | DATE | APPROVED |
|---|---|---|---|

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
HP504-03
MCB CAMP LEJEUENE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: SEPTEMBER 2014
SHEET 3 OF 4




A ATTIC ACCESS

SAMPLE LEGEND ID

01-01 (+,-)

- SAMPLE IDENTIFICATION
- POSITIVE (+), NEGATIVE (-), OR TRACE (TR) FOR THE PRESENCE OF ASBESTOS
- HOMOGENOUS MATERIAL

BUILDING HP504
ROOF

15' 0' 15' 30' 60'

ACM LEGEND

ROOF MATERIAL, TAR [HM07]

REVISIONS

| SYM | DESCRIPTION | DATE | APPROVED |
|---|---|---|---|

AH Environmental Consultants

MCB CAMP LEJEUNE, NC

CY2014 ASBESTOS INSPECTION
HP504-R
MCB CAMP LEJEUENE, NC

CHECKED BY: DD
DRAWN BY: ARD
SCALE: GRAPHIC
DATE: SEPTEMBER 2014
SHEET 4 OF 4